

**Himachal Pradesh
Public Works Department**

No-PW/Ksli/CB/Tender /2026-27- 4401-4408
To

Dated:- 09/07/2026


✓ The Executive Engineer, (I.T. cell)
HPPWD, Nirman Bhwan, Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on departmental site.

Sir,

Enclosed please find herewith the tender notice of works as given in the Notice inviting Tenders for uploading on departmental web site as per Notification of the Pr. Secretary (PW) to the Govt. of H.P. No. PBW-(B)A((3)1/2024 dated 03.01.2024 & PWD-B-A)(3)/8/2025-300858 dated 09.10.2025 as the work mentioned in the tender notice are urgent in nature and public interest.

DA:- As Above.


Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

Copy to Superintending Engineer, 3rd Circle, HPPWD, Solan for information
please.

Copy to All the AE working under this Division for information .
Copy to AB/DB of this office for information.


Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

**Himachal Pradesh
Public Works Department
"Notice Inviting Tenders"**

The Executive Engineer HPPWD Kasauli Distt solan HP on behalf of Governor
of HP invites the tender on the form 6 for below mentioned work from the eligible and approved contractors/Firms
registered with HPPWD Department.

Job No.	Name of Work	Tentative Cost	Earnest Money	Time allowed	Cost of Form
1	R/R damages on Kharyana to Ranopul road in Km. 0/00 to 27/400.(SH:- C/O R/Wall at Rds. 1/800 to 1/816.50) Under PDNA.	4,98,959/-	10000/-	Two Months	350/-
2	R/R damages on Kharyana to Ranopul road in Km. 0/00 to 2/400.(SH:- C/O R/Wall in Wire Crate at Rds. 0/200 to 0/213.75) Under PDNA.	4,76,819/-	9500/-	Two Months	350/-
3	R/R damages on Link road to Village Radiyana in Km. 0/00 to 2/500.(SH:- Providing and Laying interlocking Tiles Pavements at Rds. 1/200 to 1/243) Under PDNA.	2,89,996/-	5800/-	Two Months	350/-
4	R/R Damges on Parwanoo Kasauli Dharampur Subathu Solan road in Km. 0/00 to 58/100.(SH:- P/L Interlocking Tiles Pavements at Rds. 45/150 to 45/215) Under PDNA.	4,87,842/-	9800/-	Two Months	350/-
5	R/R damages Parwanoo Kasauli Dharampur Subathu Solan road in Km. 0/00 to 58/100.(SH:- P/L Interlocking Tiles Pavements at Rds. 45/215 to 45/279)Under PDNA	4,96,586/-	9900/-	Two Months	350/-
6	A/R & M/O to various roads under Subathu Sub-Division.(SH:- Supplying and Stacking of stone aggregate of size 63mm to 45mm size at site under Subathu Section)	99,298/-	2000/-	One Months	350/-
7	R/R damages to Trashari to Perri road and Kharayana to Rano Pul road under Subathu Sub-Division.(SH:- Hiring of Excavator Cum loader for removal of slips, Clearance of road side drain, and Preparation of road side berms and hiring of Tipper for shifting of earth, debris etc. in Km. 0/00 to 1/600 & 0/00 to 2/400)Under PDNA.	4,98,400/-	10000/-	Two Months	350/-
8	R/R damages to link road to Village Arla in Km. 0/00 to 3/500.(SH:- C/O PCC U-shape drain between Km. 1/030 to 1/457)DC Deposit.	4,81,776/-	9600/-	Two Months	350/-
9	C/O 18.75 mtr single lane span RCC T-Beam bridge across Katal Ki Nali on Chandi Ghyan road at Rd. 5/085.(SH:- C/O PCC B/Wall at Rd. 5/540 to 5/560 & 5/570 to 5/590)Under SCDP.	4,67,732/-	9400/-	Two Months	350/-
10	R/R damages to Parwanoo Kasauli Dharampur Subathu Solan road in Km. 0/00 to 57/100.(SH:- Hiring of Excavator Cum loader for removal of slips and Clearance of road side drain and hiring of Tipper for Shifting of earth, debris etc. in Km. 50/00 to 57/100) Under PDNA.	2,98,400/-	6000/-	Two Months	350/-
11	R/R damages to Garkhal Subathu road in Km. 0/00 to 17/500.(SH:- Hiring of Excavator Cum loader for removal of slips and clearance of road side drain and hiring of Tipper for shifting of earth, debris etc. in Km. 12/00 to 17/500) Under PDNA.	99,900/-	2000/-	One Months	350/-
12	R/R damages to Jadli Grownghatti Badorighatti road in Km. 0/00 to 9/160.(SH:- Hiring of Excavator Cum loader for removal of slips and Clearance of road side drain and hiring of Tipper for shifting of earth, debris etc. in Km. 5/00 to 9/160)Under PDNA.	99,500/-	2000/-	One Months	350/-
13	R/R damages on Chandi Ghyan road in Km. 0/00 to 5/600.(SH:- C/O HPC Toe wall & Wing Wall at Various Rds. & C/O U-Shape drain at Rds. 0/080 to 0/200)	4,99,421/-	10000/-	Two Months	350/-
14	R/R damages on Banalgi Chandi Bhatt Ki Hatti road in Km. 0/00 to 12/300.(SH:- C/O R/Wall at Various Rds)	4,89,872/-	10000/-	Two Months	350/-
15	R/R damages on Chandi Ghyan road in Km. 0/00 to 5/600.(SH:- Repair of damaged portion by P/L 80mm thick interlocking Paver block at Rds. 2/400 to 2/475)Under PDNA.	4,15,159/-	8300/-	Two Months	350/-

16	R/R damages on Joharji Mallah road Km. 0/00 to 27/465.(SH:- C/O R/Wall at Rd. 4/296 to 4/301 and 16/810 to 16/823)Under PDNA.	4,94,730/-	9895/-	Two Months	350/-
17	R/R of rain damages on Patta Joharji road in Km. 0/00 to 8/00.(SH:- Hiring of Excavator Cum loader alongwith rock Breaker and Tipper for removal of slips /Landslide, C/O unlined drain & Dressing of berms in Km. 0/00 to 8/00)	99,700/-	2000/-	One Months	350/-
18	R/R damages on Patta Beja Masoolkhana Km. 3/00 to 9/500.(SH:- C/O R/Wall at Rd. 3/330 to 3/340 and 4/060 to 4/068 and 4/075 to 4/087)Under PDNA.	4,94,674/-	9895/-	Two Months	350/-
19	R/R damages on Bhojnagar Banaser Khadeen Parwanoo road Km. 0/00 to 12/720. (SH:- C/O R/Wall at Rd. 0/190 to 0/205)Under PDNA.	4,47,353/-	8950/-	Two Months	350/-
20	R/R damages on Joharji Mallah road Km. 0/00 to 27/465.(SH:- C/O R/Wall at Rd. 24/530 to 24/535 and 23/580 to 23/857))Under PDNA	3,47,807/-	6960/-	Two Months	350/-

Date and time of receipt of application for tender form:- 16.07.2026 . up to 3.00 PM
 Issue of tender form 17.07.2026 up to 5.00 PM
 Date and time receipt of tender :- 18.07.2026 up to 10.30 AM
 Date and time opening of tender:- 18.07.2026 11.30APM

Executive Engineer,
 Kasauli Division,
 HPPWD Kasauli
 (On behalf of the Governor of HP

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost :-		498959.00
		Earnest Money :-		10000.00
		Time :-		Two Months
Name of Work :- R/R Damages on Kharyana to Ranopul road in km 0/00 to 2/400 (SH:- C/O R/Wall at RDs 1/800 to 1/816.50) Under PDNA				
Sr. No	Description of work	Qty	Unit	Rate in Figures Words Amount
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	54.95	Per Cubic Metre	312.20 Rupees Three Hundred & Twelve - Paise Twenty Only17155.00
2	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded stone aggregate 40mm (forty millimeters) nominal size) mechanically mixed, vibrated, curing complete and including cost of form work in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) as per MORD specifications including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	35.64	Per Cubic Metre	5474.10 Rupees Five Thousand Four Hundred & Seventy Four - Paise Ten Only195097.00
3	Providing and laying plain Cement concrete in 1:4:8 (one cement isto four sand isto eight graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	54.45	Per Cubic Metre	4713.65 Rupees Four Thousand Seven Hundred & Thirteen - Paise Sixty Five Only256658.00

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	44.00	Each	307.30	Rupees Three Hundred & Seven - Paise Thirty Only	13521.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	13.86	Per Cubic Metre	1192.50	Rupees One Thousand One Hundred & Ninety Two - Paise Fifty Only	16528.00
Total:-						498959.00

Rupees Four Lakh Ninety Eight Thousand Nine Hundred & Fifty Nine Only

T/S No. for the year 2026-2027
Sr. No. 167 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost:- 476819.00				
		Earnest Money:- 9500.00				
		Time:- Two Months				
Name of Work :- R/R Damages on Kharyana to Ranopul road in km 0/00 to 2/400 (SH:- C/O R/Wall in wire crate at RDs 0/200 to 0/213.75) Under PDNA						
Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	39.53	Per Cubic Metre	312.20	Rupees Three Hundred & Twelve - Paise Twenty Only	12341.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm(four millimeter) dia GI wire conforming to IS:280 (two huded eighty) and IS:4826 (four thousand eight hundred twenty six) in 100 mm x 100 mm(one hundred into one hundred millimeter) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301.(one thousand three hundred one) including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	128.91	Per Cubic Metre	3549.65	Rupees Three Thousand Five Hundred & Forty Nine - Paise Sixty Five Only	457585.00

3	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight), including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	5.78	Per Cubic Metre	1192.50	Rupees One Thousand One Hundred & Ninety Two - Paise Fifty Only	6893.00
Total:-						476819.00
Rupees Four Lakh Seventy Six Thousand Eight Hundred & Nineteen Only						

T/S No. for the year 2026-2027
Sr. No. 108 for the year 2026-2027


Executive Engineer
B&R Division, HP.PWD. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost :-		Earnest Money :-		Time :-	
		289996.00		5800.00		Two Months	
Name of Work :- R/R Damages on Link road to village Radiana in km 0/00 to 2/500 (SH:- Providing and laying Interlocking Tiles Pavements at RDS 1/200 to 1/243) Under PDNA							
Sr. No	Description of work	Qty	Unit	Rate in		Amount	
				Figures	Words		
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4 or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	178.45	Per Square Metre	15.00	Rupees Fifteen Only	2677.00	
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	15.27	Per Cubic Metre	4215.95	Rupees Four Thousand Two Hundred & Fifteen - Paise Ninety Five Only	64378.00	
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. as per HP.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One),including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	152.65	Per Square Metre	1256.00	Rupees One Thousand Two Hundred & Fifty Six Only	191728.00	

4	Providing and laying plain concrete i.e. P.C.C. grade M 20 (twenty) Nominal mix 1:2:4 (one isto two isto four graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	5.16	Per Cubic Metre	6049.00	Rupees Six Thousand & Fourty Nine Only	31213.00
Total:-						289996.00
Rupees Two Lakh Eighty Nine Thousand Nine Hundred & Ninety Six Only						

T/S No. for the year 2026-2027
Sr. No. 109 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD. Kasauli

4

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost:-		487842.00		
		Earnest Money:-		9800.00		
		Time:-		Two Months		
Name of Work :- R/R Damages on Parwano Kasauli Dharampur Subathu Solan road in km 0/00 to 58/100 (SH:- Providing and laying Interlocking Tiles Pavements at RDs 45/150 to 45/215) Under PDNA						
Sr.No	Description of work	Qty	Unit	Rate in	Amount	
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4 or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	299.00	Per Square Metre	15.00	Rupees Fifteen Only	4485.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	26.00	Per Cubic Metre	4215.95	Rupees Four Thousand Two Hundred & Fifteen - Paise Ninety Five Only	109615.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. as per H.P.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One),including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	260.00	Per Square Metre	1256.00	Rupees One Thousand Two Hundred & Fifty Six Only	326560.00

4	Providing and laying plain concrete i.e. P.C.C. grade M 20 (twenty) Nominal mix 1:2:4 (one isto two isto four graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	7.80	Per Cubic Metre	6049.00	Rupees Six Thousand & Fourty Nine Only	47182.00
	Total:-					487842.00
Rupees Four Lakh Eighty Seven Thousand Eight Hundred & Fourty Two Only						

T/S No. for the year 2026-2027
Sr. No. 110 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost :-		496586.00		
		Earnest Money :-		9900.00		
		Time :-		Two Months		
Name of Work :- R/R Damages on Parwano Kasauli Dharampur Subathu Solan road in km 0/00 to 58/100 (SH:- Providing and laying Interlocking Tiles Pavements at RDS 45/215 to 45/279) Under PDNA						
Sl. No	Description of work	Qty	Unit	Rate in	Amount	
				Figures	Words	
1	Scarifying the existing bituminous road surface to a depth of 150 mm and disposal of scarified material with a lift upto 3 m and lead upto 1000 m as per Technical Specification Clause 301.4 or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	304.00	Per Square Metre	15.00	Rupees Fifteen Only	4560.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plinths for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	26.56	Per Cubic Metre	4215.95	Rupees Four Thousand Two Hundred & Fifteen - Paise Ninety Five Only	111976.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. as per HP.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One),including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	265.60	Per Square Metre	1256.00	Rupees One Thousand Two Hundred & Fifty Six Only	333594.00

4	Providing and laying plain concrete i.e. P.C.C. grade M 20 (twenty) Nominal mix 1:2:4 (one isto two isto four graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	7.68	Per Cubic Metre	6049.00	Rupees Six Thousand & Fourty Nine Only	46456.00
	Total:-					496586.00
Rupees Four Lakh Ninety Six Thousand Five Hundred & Eighty Six Only						

T/S No. for the year 2026-2027
Sr. No. 111 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD. Kasauli

DRAFT SCHEDULE OF QUANTITY

6

Estimated Cost:-	99298.00
Earnest Money:-	2000.00
Time limit :-	One Month

Name of Work :- A/R & M/O to various roads under Subathu Sub Division. (SH:- Supplying and stacking of stone aggregate of size 63mm to 45mm size at site under Subathu Section).

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Supplying and stacking of stone and hand breaking into coarse aggregate to Grading-II (63mm to 45mm) at site as per table 400.8 of technical specifications. The aggregate should be free from harmful materials/foreign materials such as alkalis, vegetable matter and other deleterious substances, neausea shells or similar laminated materials in such quantities as to effect adversely its strength if tested through appropriate test. Clay, fine silt and fine dust shall not exceeded by more than 1% by weight. It shall also be free from soft friable, elongated pieces and shall be roughly conical in shape The crushing value of aggregate should confirm to the Indian standard. The materials should be stacked in such a way as it does not effect the normal flow of traffic in any way. The stacks should be made as per general specifications of HP.PWD. and instructions of Engineer-in-Charge at site.	73.000	m ³ Per cubic meter	1360.25	Rupees One Thousand Three Hundred & Sixty - Paise Twenty Five Only	99298.00
in words. Rupees Ninety Nine Thousand Two Hundred & Ninety Eight Only						99298.00
% quoted in figure:-						
% quoted in words:-						

T/S No. for the year 2026-27
Sr. No. 11/2 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 99298.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.



DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-	498400.00
Earnest Money:-	10000.00
Time limit:-	Two Month

Name of Work :- R/R damages to Trashari to Perri road and Kharayana to Rano pul road under Subabhu Sub Division. (SH: Hiring of excavator cum loader for removal of slips, clearance of road side drain, and preparation of road side berms and hiring of tipper for shifting of earth, debris etc. in Km. 0/00 to 1/600 & 0/00 to 2/400). Under PDNA.

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	344.00 Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	378400.00
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. and as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	30.00 Day	Per Day	4000.00	Rupees Four Thousand Only	120000.00
Rupees Four Lakh Ninety Eight Thousand Four Hundred Only						
in words.						
% quoted in figure:-						
% quoted in words:-						

T/S No. for the year 2026-27
Sr. No. 113 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 498400.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

(2)

					Estimated Cost:-	481776.00
					Earnest Money:-	9600.00
					Time limit :-	Two Month
Name of Work :- R/R damages to link road to village Arla in Km. 0/00 to 3/500. (SH: C/o PCC U-shape drain between Km. 1/030 to 1/457). DC Deposit.						
Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	179.340 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	49767.00



2	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded stone aggregate 40mm (forty millimeters) nominal size) mechanically mixed, vibrated, curing complete and including cost of form work in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) as per MORD specifications including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	83.27 m ³	Per Cubic Meter	5188.05	Rupees Five Thousand One Hundred & Eighty Eight - Paise Five Only	432009.00
						481776.00

in words.

Rupees Four Lakh Eighty One Thousand Seven Hundred & Seventy Six Only

% quoted in figure:-
% quoted in words:-

T/S No. for the year 2026-27

Sr. No. 114 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 481776.00 only


Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/o 18.75 mtr single lane span RCC T-Beam bridge across Katal Ki Nali on Chandhi Ghyran road at Rd 5/085.
(SH:- C/o PCC B/Wall at Rd 5/540 to 5/560 & 5/570 to 5/590). Under SCDD.

Estimated Cost :-	467732.00
Earnest Money :-	9400.00
Time limit :-	Two Month

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	63.600 m ³	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	17649.00
2	Providing and Laying concrete 1:4:8 (one cement isto four sand isto eight Graded stoe aggregate 40 mm (forty millimeters) nominal size for plain reinforced concrete mechanically mixed and viberated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge.	94.90 m ³	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	430580.00

3	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) as per MORD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	64.000 Nos	Each	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	19503.00
						467732.00

in words.

Rupees Four Lakh Sixty Seven Thousand Seven Hundred & Thirty Two Only

% quoted in figure:-	
% quoted in words:-	

T/S No. for the year 2026-27
Sr. No. 115 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 467732.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.



DRAFT SCHEDULE OF QUANTITY

(10)

Name of Work :- Name of Work :- R/R damages to Parwanoo Kasauli Dharampur Subathu Solan road in Km. 0/00 to 57/100. (SH: Hiring of excavator cum loader for removal of slips and clearance of road side drain and hiring of tipper for shifting of earth, debris etc. in Km. 50/00 to 57/100). Under PDNA.

				Estimated Cost:-	298400.00		
				Earnest Money:-	6000.00		
				Time limit :-	Two Month		
Name of Work :- Name of Work :- R/R damages to Parwanoo Kasauli Dharampur Subathu Solan road in Km. 0/00 to 57/100. (SH:3)							
Hiring of excavator cum loader for removal of slips and clearance of road side drain and hiring of tipper for shifting of earth, debris etc. in Km. 50/00 to 57/100). Under PDNA.							
Sr. No	Description of work	Qty.	Unit	Rate in	Amount		
				Figures	Words.		
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	184.00	Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	202400.00
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. and as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	24.00	Day	Per Day	4000.00	Rupees Four Thousand Only	96000.00
						298400.00	

in words.

Rupees Two Lakh Ninety Eight Thousand Four Hundred Only

% quoted in figure:-

% quoted in words:-

T/S No. for the year 2026-27
Sr. No. 16 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 298400.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-	99900.00
Earnest Money:-	2000.00
Time limit :-	One Month

Name of Work :- R/R damages to Garkhal Subathu road in Km. 0/00 to 17/500. (SH: Hiring of excavator cum loader for removal of slips and clearance of road side drain and hiring of tipper for shifting of earth, debris etc. in Km. 12/00 to 17/500). Under PDNA.

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	69.00	Hr	Per Hour	1100.00 Rupees One Thousand One Hundred Only	75900.00
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. and as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	6.00	Day	Per Day	4000.00 Rupees Four Thousand Only	24000.00
						99900.00

in words. Rupees Ninety Nine Thousand Nine Hundred Only

% quoted in figure:-	
% quoted in words:-	

T/S No. for the year 2026-27
Sr. No. 117 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 99900.00 only

Executive Engineer
B&R Division, HP, PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-	99500.00
Earnest Money:-	2000.00
Time limit :-	One Month

Name of Work :- R/R damages to Jadhli Grownghatti Badorighatti road in Km. 0/00 to 9/160. (SH: Hiring of excavator cum loader for removal of slips and clearance of road side drain and hiring of tipper for shifting of earth, debris etc. in Km. 5/00 to 9/160). Under PDNA.

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer In-Charge.	65.00 Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	71500.00
2	Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. and as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	7.00 Day	Per Day	4000.00	Rupees Four Thousand Only	28000.00
in words. Rupees Ninety Nine Thousand Five Hundred Only						99500.00
% quoted in figure:-						
% quoted in words:-						

T/S No. for the year 2026-27
Sr. No. 118 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 99500.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost:- 499421.00

Earnest Money:- 10000.00

Time:- Two Months

Name of Work :- R/R damages on Chandi Chyan road in km 0/00 to 5/600 (SH:- C/O HPC Toe wall & wing wall at various RDS & C/O U-Shape drain at RDS 0/080 to 0/200)

Sr.No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chisling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	46.80	Per Cubic Metre	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	12987.00
2	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6. (one cement isto three sand isto six graded stone aggregate 40mm (forty millimeters) nominal size) mechanically mixed, vibrated, curing complete and including cost of form work in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) as per MORD specifications including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	62.49	Per Cubic Metre	5297.65	Rupees Five Thousand Two Hundred & Ninety Seven - Paise Sixty Five Only	331050.00
3	Providing and laying plain Cement concrete in 1:4:8 (one cement isto four sand isto eight graded crushed hard stone aggregate 40mm (forty millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	31.14	Per Cubic Metre	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	141288.00

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	14.00	Each	304.75	Rupees Three Hundred & Four - Paise Seventy Five Only	4267.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	8.88	Per Cubic Metre	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	9829.00
Total:-						499421.00
Rupees Four Lakh Ninety Nine Thousand Four Hundred & Twenty One Only						

T/S No. 38 for the year 2026-27
Sr. No. 54 for the year 2026-27


Executive Engineer
B&R Division, HP.PWD. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost :-	489872.00
Earnest Money :-	10000.00
Time :-	Two Months

Name of Work :- R/R damages on Banalgi Chandi Bhatt Ki Hatti road in km 0/00 to 12/300 (SH:- C/O R/Wall at various RDS)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	26.17	Per Cubic Metre	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	7262.00
2	Providing and laying concrete for P.C.C. grade M-10 (ten) nominal mix 1:3:6 (one cement isto three sand isto six graded stone aggregate 40mm (forty millimeters) nominal size) mechanically mixed, vibrated, curing complete and including cost of form work in open foundations complete as per drawings and technical specifications clause 802, 803, 1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) as per MORD specifications including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	39.11	Per Cubic Meter	5297.65	Rupees Five Thousand Two Hundred & Ninety Seven - Paise Sixty Five Only	207191.00
3	Providing and laying plain Cement concrete in 1:4:8 (one cement isto four sand isto eight graded crushed hard stone aggregate 40mm (forty millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	54.73	Per Cubic Metre	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	248321.00



4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	34.00	Each	304.75	Rupees Three Hundred & Four - Paise Seventy Five Only	10362.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	15.12	Per Cubic Metre	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	16736.00
Total:-						489872.00

Rupees Four Lakh Eighty Nine Thousand Eight Hundred & Seventy Two Only

T/S No. 48 for the year 2026-27
Sr. No. 60 for the year 2026-27

Executive Engineer
B&R Division, HP.PWD. Kasauli



DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost :-	415159.00
Earnest Money:-	8300.00
Time:-	Two Months

Name of Work :- R/R Damages on Chandi Ghyana road in km 0/00 to 5/600 (SH:- Repair of damaged portion by P/L 80mm thick Interlocking paver block at RDS 2/400 to 2/475) Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	31.88	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	8847.00
2	Providing, laying, spreading and compacting graded stone aggregate to Wet Mix Macadam specification including premixing the material with water at OMC in mechanical mixer (Pug Mill), carriage of mixed material by tipper to site, laying in uniform layers in sub-base/base course on a well prepared sub-base and compacting with smooth wheel roller of 80 to 100kN weight to achieve the desired density including lighting, barricading and maintenance of diversion, etc as per Tables 400.11 & 400.12 and Technical Specification Clause 406.as per direction of Engineer-in-Charge including carriage of all labour, equipment and material to various location through all modes of transportation in all lead, lift and all incidental charges.	23.91	Per Cubic Meter	2433.40	Rupees Two Thousand Four Hundred & Thirty Three - Paise Forty Only	58183.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm as per drawings and Technical Specification Clause 1504. as per HP.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One),including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	247.50	Per Square Meter	1246.40	Rupees One Thousand Two Hundred & Fourty Six - Paise Fourty Only	308484.00

4	Providing and laying plain concrete i.e. P.C.C. grade M 20 (twenty) Nominal mix 1:2:4 (one isto two isto four graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	6.75	Per Cubic Meter	5873.40	Rupees Five Thousand Eight Hundred & Seventy Three - Paise Fourty Only	39645.00
Total:-						415159.00
Rupees Four Lakh Fifteen Thousand One Hundred & Fifty Nine Only						

T/S No. 35 for the year 2026-2027
Sr. No. 51 for the year 2026-2027

Executive Engineer
B&R Division, H.R. P.W.D. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost :-		494730.00		
		Earnest Money:-		9895.00		
		Time:-		Two Months		
Name of Work :- R/R Damages on Joharij Mallah Road Km 0/00 to 27/465 (SH:- C/O R/wall at Rd 4/296 to 4/301 and 16/810 to 16/823 Under PDNA						
Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the	73.51	Per Cubic Metre	312.20	Rupees Three Hundred & Twelve - Paise Twenty Only	22949.00
2	Providing and laying plain Cement concrete in 1:6:12 (one cement is to six sand isto twelve graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	10.10	Per Cubic Meter	4215.95	Rupees Four Thousand Two Hundred & Fifteen - Paise Ninety Five Only	42590.00
3	Providing and laying plain Cement concrete in 1:4:8 (one cement isto four sand isto eight graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	84.90	Per Cubic Metre	4713.60	Rupees Four Thousand Seven Hundred & Thirteen - Paise Sixty Only	400185.00

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	42.00	Each	307.31	Rupees Three Hundred & Seven - Paise Thirty One Only	12907.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	13.50	Per Cubic Metre	1192.50	Rupees One Thousand One Hundred & Ninety Two - Paise Fifty Only	16099.00
Total:-						494730.00
Rupees Four Lakh Ninety Four Thousand Seven Hundred & Thirty Only						

T/S No. for the year 2026-2027
Sr. No. | 03 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD. Kasauli



Draft SCHEDULE OF QUANTITY

Estimated Cost: -	AMOUNT
99700.00	
Earnest Money: -	2000.00
Time Limit: -	One month.

Name of work:-R/R of Rain Damages on Patta Johari road km 0/00 to 8/00 (SH:-Hiring of Exacavator cum loader along with rock Breaker and tipper for Removal of slips/Landslide, Construction of unlined drain and dressing of berms in km 0/00 to 8/00)

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
1	Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999. quantity of excavated / removed material should not be less than 28 cum / per hour.	47.00	Per hour.	1100.00	Rupees One Thousand One Hundred Only	51700.00
2	Hiring of Rock breaker for breaking of Boulders Hire Charges should include expenses on account of establishment POL Major and Minor repairs/over Hauling and replacement of Tyres and batteries if Required. It should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, also include all local or out side taxes including of the road tax , entry tax and other taxes if any. The rock breaker has to perform not less than the prescribed in the norms of HP.PWD and as per the direction of Engineer in Charge, including carriage of all labour equipments and material to various locations through all modes of transportation in all leads and lifts and lifts and all incidental charges.	32.00	Per hour.	1500.00	Rupees One Thousand Five Hundred Only	48000.00
	Total :-					99700.00

Total in Words Rupees Ninety Nine Thousand Seven Hundred Only
Draft Schedule of Quantity Recommended for approval for Rs. 99700.00 only.

Draft Schedule of Quantity approved for Rs. 99700.00

only.

Assistant Engineer,
B&R Sub Division, HP.PWD, Chandl
Sr. No. 673 for the year 25-26
Executive Engineer
B&R Division, HP.PWD, Kasauli.

DRAFT SCHEDULE OF QUANTITY

Job No.		Estimated Cost :-		Earnest Money :-		Time :-	
		494674.00		9895.00		Two Months	
Name of Work :- R/R Damages on Patta Beja Masoolkhana 3/00 to 9/500 (SH:- C/O R/wall at Rd 3/330 to 3/340 and 4/060 to 4/068 and 4/075 to 4/087 Under PDNA							
Sl. No	Description of work	Qty	Unit	Rate in		Amount	
				Figures	Words		
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the	36.58	Per Cubic Metre	312.20	Rupees Three Hundred & Twelve - Paise Twenty Only .	11420.00	
2	Providing and laying plain Cement concrete in 1:6:12 (one cement is to six sand isto twelve graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	13.50	Per Cubic Meter	4215.95	Rupees Four Thousand Two Hundred & Fifteen - Paise Ninety Five Only	56915.00	
3	Providing and laying plain Cement concrete in 1:4:8 (one cement isto four sand isto eight graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	81.00	Per Cubic Metre	4713.60	Rupees Four Thousand Seven Hundred & Thirteen - Paise Sixty Only	381802.00	

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	49.00	Each	307.31	Rupees Three Hundred & Seven - Paise Thirty One Only	15058.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	24.72	Per Cubic Metre	1192.50	Rupees One Thousand One Hundred & Ninety Two - Paise Fifty Only	29479.00
Total:-						
Rupees Four Lakh Ninety Four Thousand Six Hundred & Seventy Four Only						
494674.00						

T/S No. for the year 2026-2027
Sr. No. 104 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD. Kasauli

DRAFT SCHEDULE OF QUANTITY

(19)

Job No.

Estimated Cost :-	447353.00
Earnest Money :-	8950.00
Time :-	Two Months

Name of Work :- R/R Damages on Bhojnagar Banaser Khadeen Parwano road Km 0/0 to 12/720 (SH:- C/O R/wall at Rd 0/190 to 0/205 Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	40.05	Per Cubic Metre	312.20	Rupees Three Hundred & Twelve - Paise Twenty Only	12504.00
2	Providing and laying plain Cement concrete in 1:6:12 (one cement is to six sand isto twelve graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	9.30	Per Cubic Meter	4215.95	Rupees Four Thousand Two Hundred & Fifteen - Paise Ninety Five Only	39208.00
3	Providing and laying plain Cement concrete in 1:4:8 (one cement isto four sand isto eight graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	76.50	Per Cubic Metre	4713.60	Rupees Four Thousand Seven Hundred & Thirteen - Paise Sixty Only	360590.00

4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	25.00	Each	307.31	Rupees Three Hundred & Seven - Paise Thirty One Only	7683.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	22.95	Per Cubic Metre	1192.50	Rupees One Thousand One Hundred & Ninety Two - Paise Fifty Only	27368.00
Total:-						447353.00
Rupees Four Lakh Fourty Seven Thousand Three Hundred & Fifty Three Only						

T/S No. for the year 2026-2027
Sr. No. 165 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost :-	347807.00
Earnest Money :-	6960.00
Time :-	Two Months

Name of Work :- R/R Damages on Johari Mallah Road Km 0/00 to 27/465 (SH:- C/O R/wall at Rd 24/530 to 24/535 and 23/580 to 23/857 Under PDNA

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	31.85	Per Cubic Metre	312.20	Rupees Three Hundred & Twelve - Paise Twenty Only	9944.00
2	Providing and laying plain Cement concrete in 1:6:12 (one cement is to six sand isto twelve graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	7.27	Per Cubic Meter	4215.95	Rupees Four Thousand Two Hundred & Fifteen - Paise Ninety Five Only	30650.00
3	Providing and laying plain Cement concrete in 1:4:8 (one cement isto four sand isto eight graded crushed hard stone aggregate 40mm (forty) millimeter nominal size) mechanically mixed, vibrated and curing complete in open foundation and plinth for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	60.56	Per Cubic Metre	4713.60	Rupees Four Thousand Seven Hundred & Thirteen - Paise Sixty Only	285456.00



4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and MORD technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) or as directed by the Engineer-in-Charge including cartiage of materials with in all leads and lifts and other incidentals.	24.00	Each	307.31	Rupees Three Hundred & Seven - Paise Thirty One Only	7375.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including cartiage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	12.06	Per Cubic Metre	1192.50	Rupees One Thousand One Hundred & Ninety Two - Paise Fifty Only	14382.00
Total:-						347807.00
Rupees Three Lakh Fourty Seven Thousand Eight Hundred & Seven Only						

T/S No. for the year 2026-2027
Sr. No. 106 for the year 2026-2027


Executive Engineer
B&R Division, HP.PWD. Kasauli