

**Himachal Pradesh
Public Works Department**

No-PW/Ksli/CB/Tender /2026-27-
To

4593-4602

Dated:- 16/07/2026

The Executive Engineer, (I.T. cell)
HPPWD, Nirman Bhwan, Nigam Vihar,
Shimla-2.

Subject:- Publication of Tender Notice on departmental site.

Sir,


Enclosed please find herewith the tender notice of works as given in the Notice inviting Tenders for uploading on departmental web site as per Notification of the Pr. Secretary (PW) to the Govt. of H.P. No. PBW-(B)A((3)1/2024 dated 03.01.2024 & PWD-B-A)(3)/8/2025-300858 dated 09.10.2025 as the work mentioned in the tender notice are urgent in nature and public interest.

DA:- As Above.


Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

Copy to Superintending Engineer, 3rd Circle, HPPWD, Solan for information
please.

Copy to All the AE working under this Division for information .
Copy to AB/DB of this office for information.


Executive Engineer,
Kasauli Division, HPPWD,
Kasauli.

**Himachal Pradesh
Public Works Department
" Notice Inviting Tenders"**

The Executive Engineer HPPWD Kasauli Distt solan HP on behalf of Governor of HP invites the tender on the form 6 for below mentioned work from the eligible and approved contractors/Firms registered with HPPWD Department.

Job No.	Name of Work	Tentative Cost	Earnest Money	Time allowed	Cost of Form
1	C/O link road to Village-Nara in Km. 0/00 to 0/480 under Chandi Sub-Division.(SH:- Preparation of Digital Map, Topo sheet of projects and CA site with collecting data from site with preparation of FCA Case..	95,000/-	2000/-	Six Month	350/-
2	C/O Link road Karah Ka Nala Chayani Bughrat to Primary School Bughrat road in Km. 0/00 to 1/500 Under Chandi Sub-Division.(SH:- Preparation of Digital Map, Topo Sheet of Project and CA site with collecting data from site with Preparation of FCA Case.	95000/-	2000/-	Two Month	350/-
3	R/R damages to Patta Goela Chhachi road in Km. 0/00 to 22/00.(SH:- C/O R/Wall in Wire Crates at Rds. 13/435 to 13/442.50)	99,945/-	2000/-	Two Month	350/-
4	A/R & M/O to HPPWD Rest House at Parwanoo.(SH:- Painting in dormitory, Supplying Single bed, Mattress, Pillow and Blanket for dormitory)	93,260/-	2000/-	One Month	350/-
5	R/R damages to link road to Gharsi Brahmana in Km. 0/00 to 1/300.(SH:- c/O R/Wall at Rd. 0/678 to 0/682.30)	99,783/-	2000/-	Two Months	350/-
6	R/R of Rain damages on Link Jagtawn to Roper road in Km. 0/00 to 1/300.(SH:- Hiring of excavator Cum loader alongwith rock Brekar and Tipper for removal of Slips/landslide, C/o unlined drain and dressing of berms in Km. 0/00 to 1/300)	99,100/-	2000/-	Two Months	350/-
7	R/R damages on Link road to Village-Banjani in Km. 0/00 to 1/250.(SH:- P/L Interlocking Tiles Pavement 80mm thick at Rds. 1/180 at junction point)Under PDNA.	99,847/-	2000/-	Two Months	350/-
8	C/O road Nichala Mandhyana to Reli Rugh (SH:- Hiring of Excavator Cum loader along with Tipper for executing ROFD Work)Under VKVNY Deposit)	99,500/-	2000/-	One Months	350/-
9	C/O Additional Accomodation in GSSS building at Ganol.(SH:- Site Development)Job No-1.Deposit Work.	96,529/-	1900/-	Two Months	350/-
10	C/O Additional Accomodation in GSSS building at Ganol.(SH:- Site Development)Job No-2.Deposit Work	94,872/-	1900/-	Two Months	350/-
11	A/R & M/O to Circuit House & Rest House under Parwanoo Sub-Division.(SH:- Refilling of fire extinguishers and Providing & Fixing of 2HP submersible Pump)	82,266/-	1600/-	One Months	350/-
12	A/R & M/O to Joharji Mallah road in Km. 0/00 to 27/465.(SH:- Trimming of grass in Km. 13/00 to 20/00)	98,968/-	2000/-	One Months	350/-
13	A/R & M/O to Joharji to Mallah road in Km. 0/00 to 27/465.(SH:- White Washing of Parapets, guide stone, nreast wall strips & tree trunks etc. in Km. 13/00 to 20/00)	99,385/-	2000/-	One Months	350/-
14	Repair of damaged road portion (due to laying of underground IPH pipeline) on Dharampur Kasauli (MDR-10) road in Km. 0/00 to 10/835.(SH:- P/L thermoplastic edge line)Job No-01. Deposit.	95,980/-	2000/-	Two Months	350/-
15	R/R damages to Barotiwala Gunai road in Km. 0/00 to 19/120.(SH:- Hiring of excavator cum loader along with tractor trolly for removal of slips and clearance of road side drain in Km. 6/00 to 12/00)Under Patta Section.	98,300/-	2000/-	One Months	350/-
16	R/R damages to Barotiwala Gunai road in Km. 0/00 to 19/120.(SH:- Hiring of excavator cum loader along with tractor trolly for removal of slips and clearance of road side drain in Km. 0/00 to 6/00)Under Patta Section	98,300/-	2000/-	One Months	350/-

17	A/R & M/O Circuit house building at Parwanoo.(SH:- P/F Steel Work, Exterior Paint etc)	99,746/-	2000/-	Two Months	350/-
18	R/R damages to link road to Gharsi Brahmana in Km. 0/00 to 1/300.(SH:- C/O CC Pavement at Rd. 0/945 to 0/970)	99,384/-	2000/-	Two Months	350/-
19	R/R damages to link road to Village Arla in Km. 0/00 to 3/500.(SH:- Hiring of excavator Cum loader for removal of slips and clearance of road side drain and hiring of Tipper for shifting of earth, debris etc in Km. 0/00 to 3/500)Under Subathu Section.	98,100/-	2000/-	One Months	350/-
20	A/R & M/O various roads under Kasauli Sub-Division.(SH:- Providing and supplying printed Stationery items etc.	99,762/-	2000/-	Two Months	350/-
21	R/O to rain damages on SAKB road Km. 37/00 to 70/00.(SH:- Hiring of JCB/loader Cum-Excavator for removal of slips & clearance of and hiring of Tipper for shifting of earth etc in km. 52/00 to 55/00)Under PDNA.	99,900/-	2000/-	One Months	350/-

Date and time of receipt of application for tender form:- 22.07.2026. up to 3.00 PM
 Issue of tender form 23.07.2026 up to 5.00 PM
 Date and time receipt of tender :- 24.07.2026 up to 11.00 PM
 Date and time opening of tender:- 24.07.2026 11.30PM

Executive Engineer,
 Kasauli Division,
 HPPWD Kasauli

(On behalf of the Governor of HP

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost :-	95000.00
Earnest Money :-	2000.00
Time limit :-	Six Month

Name of Work:- C/o link road to village Nara in Km. 0/00 to 0/480 under Chandi Sub Division. (SH: Preparation of Digital Map, Topo sheet of project and CA side with collecting data from site with preparation of FCA case).

Sr.No	Description of work	Qty.	Unit	Rate in		Amount	
				Figures	Words		
1	Preparation and processing of complete FCA Case as per the guidelines of MoEF by performing following tasks: 1. Working out detail of forest land(forest compartment wise). 2.GPS Survey of the project area with G.P.S. Coordinates @ 100 meter interval as per the direction of Engineer in charge. 3.Mapping of project area showing forest boundary and land use on Survey of India Toposheet.. 4.Preparation of Digital Map/KML file/SHP File of project area. 5.Working out the land identified for Compulsary Afforestation(CA) & preparation of CA Maps. 6.Uploading main application form (Part I/ Form A) as per FCA Rules on MoEF portal Parivesh complete in all respect. 7. Assistance to HPPWD to attend all queries & Clarification sought by MoEF/GoHP. 8.Assistance to HPPWD in submission of Stage I compliance report for obtaining Stage II approval. 9.Assistance to HPPWD to make presentation for REC Meeting as required by	1.00	No	Each	95000.00	Rupees Ninety Five Thousand Only	95000.00
Total :-							95000.00
1 in Words % above/below to the DNT amount i.e. Rs. Rupees Ninety Five Thousand Only							
SCHEDULE OF PAYMENT							
i	On successful submission of Case to Divisional Forest Office in Hard Copy.				40%		
ii	On successful submission of Case to from Nodal office to Regional Forest Office.				25%		
iii	On receipt of In principal Approval				35%		

Draft Schedule of Quantity approved for Rs. 95000.00 only

TS No. 69 for the year 2025-26
DNT No. 52 for the year 2025-26

Executive Engineer
B&R Division, HP PWD.

Signature

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost :-	95000.00
Earnest Money :-	2000.00
Time limit :-	Six Month

Name of Work:- C/O Link road Karah ka Nala Chayavni Bughrat to Primary school Bughrat road in Km. 0/00 to 1/500 under FCA case).
Division (SH: Preparation of Digital Map, Topo sheet of project and CA site with collecting data from site with preparation of FCA case).

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Preparation and processing of complete FCA Case as per the guidelines of MoEF by performing following tasks:- 1. Working out detail of forest land/forest compartment wise). 2. GPS Survey of the project area with G.P.S. Coordinates @ 100 meter interval as per the direction of Engineer in charge. 3. Mapping of project area showing forest boundary and land use on Survey of India Toposheet.. 4. Preparation of Digital Map/KML file/SHP File of project area. 5. Working out the land identified for Compulsary Afforestation(CA) & preparation of CA Maps. 6. Uploading main application form (Part I Form A) as per FCA Rules on MoEF portal Parivesh complete in all respect. 7. Assistance to HPPWD to attend all queries & Clarification sought by MoEF/GoHP. 8. Assistance to HPPWD in submission of Stage I compliance report for obtaining Stage II approval. 9. Assistance to HPPWD to make presentation for REC Meeting as required by	1.00 No	Each	95000.00	Rupees Ninety Five Thousand Only	95000.00
Total :-						95000.00
Rupees Ninety Five Thousand Only						
1 in Words						
% above/below to the DNT amount i.e. Rs.						
SCHEDULE OF PAYMENT						
i	On successful submission of Case to Divisional Forest Office in Hard Copy.			40%		
ii	On successful submission of Case to from Nodal office to Regional Forest Office.			25%		
iii	On receipt of In principal Approval			35%		

Draft Schedule of Quantity approved for Rs. 95000.00 only

TS No. 50 for the year 2025-26
DNIT No. 53 for the year 2025-26

Executive Engineer
R&R Division, HP PWD.
Misauli



DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost: - 99945.00

Earnest Money: - 2000.00

Time: - Two Months

Name of Work :- R/R Damages to Patta Goela Chhachhi road in km 0/00 to 22/00 (SH:- C/O R/Wall in wire crates at RDS 13/435 to 13/442.50)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimesions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	12.15	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	3372.00
2	Providing and laying of boulder apron laid in wire crates with 4 mm(four millimeter) dia GI wire conforming to IS:280 (two hundred eighty) and IS:4826 (four thousand eight hundred twenty six) in 100 mm x 100 mm(one hundred into one hundred millimeter) mesh (woven diagonally) including 10(ten) per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogramme) each as per drawing and technical specifications Clause 1301,(one thousand three hundred one) including carriage of all labour equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	26.90	Per Cubic Meter	3516.02	Rupees Three Thousand Five Hundred & Sixteen - Paise Two Only	94581.00

3	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight) , including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	1.80	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six Paise Eighty Five Only	1992.00
	Total:-					99945.00
Rupees Ninety Nine Thousand Nine Hundred & Fourty Five Only						

T/S No. 10 for the year 2026-2027
Sr. No. 10 for the year 2026-2027

Executive Engineer
B&R Division, HPWD, Kasauli



4

DRAFT SCHEDULE OF QUANTITY

Job No.	Name of Work :- A/R & M/O to HPPWD Rest House at Parwanoo (SH:- painting in doormitory, Supplying single bed, mattress, Pillow and Blanket for doormitory)	Estimated Cost :-		Earnest Money :-	
		93260.00		2000.00	
Sr. No	Description of work	Qty	Unit	Time :-	
				Figures	Amount
				Rate in Words	
1	Supplying single bed having size 1.89mx 0.91m made up of 40mm Hollow square pipe painted white/black and high density MDF board having weighing capacity 300 kg in all respect as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkhana, Toll tax, goods service tax, labour cess or other taxes imposed by the Government.	6.00	Each	Rupees Six Thousand Five Hundred Only	39000.00
2	Supplying of single bed (72x36 inches) mattress 100mm thickness in all respect as per the entire satisfaction and directions of Engineer-in-Charge. The rates are inclusive of octroi, royalty, Malkhana, Toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.00	Each	Rupees Two Thousand Two Hundred & Fifty Only	22500.00
3	Supplying of Pillow with cover including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each	Rupees Three Hundred Only	2400.00
4	Supplying of Blanket single including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate includes octroi, royalty, malkhana, toll tax, Goods Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	Each	Rupees One Thousand Only	8000.00
5	Wall painting with plastic emulsion paint of approved brand and manufacture to give an even shade: One or more coats on old work complete as per the direction of Engineer-in-Charge including carriage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	160.00	Per Square Meter	Rupees One Hundred & Thirty Three - Paise Fifty Only	21360.00
Total:-					93260.00
Rupees Ninety Three Thousand Two Hundred & Sixty Only					

T/S No. for the year 2025-2026
Sr. No. 737 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli



DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost :- 99783.00

Earnest Money :- 2000.00

Time limit :- Two Month

Name of Work :- R/R damages to link road to Gharsi Brahmana in Km. 0/00 to 1/300. (SH:- C/o PCC R/Wall at Rd 0/678 to 0/682.30).

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is probeted) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil. erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	9.83 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven Paise Fifty Only	2728.00
2	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed and vibrated for plain concrete in open foundations and plinths for all type of structure including the cost of form work complete as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidentals.	0.96 m3	Per cubic meter	4039.45	Rupees Four Thousand & Thirty Nine Paise Fourty Five Only	3878.00

	Providing and Laying concrete 1:4:8 (one cement isto four sand isto eight graded stoe aggregate 40 mm (fourty millimeters) nominal size for plain reinforced concrete mechanically mixed and viberated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge	18.95 m ³	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	85980.00
4	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structure with slope of 1:20 (One verticle isto twenty horizontal) towards drawing face complete as per drawing and technical specification clause 614, 709, 1204.3.7(six hundred fourteen, seven hundred nine, one thousand two hundred four point three point seven) as per MORD specification including carriage of all labour, equipment and material to various location through all modes of transportation in all leads lifts and all incidental charges.	8.00 No.	Each.	304.74	Rupees Three Hundred & Four - Paise Seventy Four Only	2438.00
5	Backfilling of Granular material behind abutment, wing wall and return wall, breast walls, retaining walls and parapets up to all heights, depths and levels complete as per drawings and MORD technical specification clause 1204.3.8 (one thousand two hundred four point three point eight), including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	4.30 m ³	Per Cubic Meter	1106.85	Rupees One Thousand One Hundred & Six - Paise Eighty Five Only	4759.00
Rupees Ninety Nine Thousand Seven Hundred & Eighty Three Only						
99783.0						
% above/below to the DNT amount i.e. Rs.						

T/S No. 676 for the year 2025-26
DNT No. 708 for the year 2025-26

Draft Schedule of Quantity approved for Rs. 99783.0 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

Draft SCHEDULE OF QUANTITY

Estimated Cost:-	99100.00
Earnest Money:-	7500.00
Time Limit:-	Two months.

Removal of slips/Landslide, Construction of unlined drain and dressing of berms in km 0/00 to 1/300 (SH:-Hiring of Excavator cum loader along with rock Breaker and tipper

Sl. No.	Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
				Figures	Words	
1	Hiring of JCB / loader cum-excavator.					
	Terms and Conditions :-					
1	Hire charges should include expenses on account of establishment POL Major and minor repairs /over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999. quantity of excavated / removed material should not be less than 28 cum / per hour.	61.00	Per hour.	1100.00	Ruppes One Thousand One Hundred Only	67100.00
2	Hiring of Rock breaker for breaking of Boulders Hire Charges should include expenses on account of establishment POL Majhor and Minor repairs/over Hauling and replacement of Tyres and batteries if Required. It should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, also include all local or out side taxes including of the road tax, entry tax and other taxes if any. The rock breaker has to perform not less than the prescribed in the norms of HP.PWD and as per the direction of Engineer in Charge, including carriage of all labour equipments and material to various locations through all modes of transportation in all leads and lifts and lifts and all incidental charges	8.00	Per hour.	1500.00	Ruppes One Thousand Five Hundred Only	12000.00
3	Hiring of tipper which shall include all expenses on account of establishment POL repair and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per direction of Engineer in charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	5.00	Per day	4000.00	Ruppes two thousands two hundred and sixteen only	20000.00
Total :-						99100.00

Total in Words Rupees Ninety Nine Thousand One Hundred Only
Draft Schedule of Quantity Recommended for approval for Rs. 99100.00 only.

Draft Schedule of Quantity approved for Rs. 99100.00 only.

Assistant Engineer,
B&R Sub Division, HP.PWD, Chandī
Sr. No. 737 for the year 25-26
Sr. No. 741 for the year 25-26
Executive Engineer
B&R Division, HP.PWD, Kasauli.

DRAFT SCHEDULE OF QUANTITY

Job No.	Name of Work :- R/R Damages on Link road to village Banjani in km 0/00 to 1/250 (SH:- P/L Interlocking tiles pavement 80mm thick at RDS 1/180 at Junction point) Under PDNA	Estimated Cost :-		Earnest Money :-		Time :-	
		99847.00		2000.00		Two Months	
Sr. No	Description of work	Qty	Unit	Rate in		Amount	
				Figures	Words		
1	Providing and laying Plain Cement Concrete nominal mix 1:6:12 (one cement isto six sand isto twelve graded stone aggregate 40mm (fourty millimeters) nominal size) Mechanically mixed, vibrated and curing complete in open foundations and plintds for all type of structure including the cost of form work as per drawing and MORD Technical Specification clause 802, 803, 1202 and 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	4.74	Per Cubic Meter	4039.45	Rupees Four Thousand & Thirty Nine - Paise Fourty Five Only	19147.00	
2	Providing and Laying of Interlocking Concrete Block Pavements M-40 having thickness 80 mm as per drawings and Technical Specification Clause 1504, as per HP.PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour equipment and material to various location through all modes of transportation in all leads and lifts, including all incidental charges and as per direction of engineer in charge.	59.28	Per Square Meter	1246.40	Rupees One Thousand Two Hundred & Fourty Six - Paise Fourty Only	73887.00	
3	Providing and laying plain concrete i.e. P.C.C. grade M 20 (twenty) Nominal mix 1:2:4 (one isto two isto four graded crushed hard stone aggregate 20mm (twenty millimetre) nominal size) mechanically mixed, vibrated and curing complete including the cost of formwork in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 (Eight hundred two, eight hundred three, one thousand two hundred two and one thousand two hundred three) and as per direction of Engineer in Charge and as per MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all leads lifts and all incidental charges.	1.16	Per Cubic Meter	5873.40	Rupees Five Thousand Eight Hundred & Seventy Three - Paise Fourty Only	6813.00	
Total:-						99847.00	
Rupees Ninety Nine Thousand Eight Hundred & Fourty Seven Only							

T/S No. 04 for the year 2025-2026
Sr. No. 04 for the year 2025-2026

Executive Engineer
B&R Division, HP.PWD. Kasauli

D.N.I.T

Name of work :- C/o road Nichala Mandhyana to Reli Rugh (SH: Hiring of Excavator cum loader along with tipper for executing ROFD work) under VK VNY deposit

Estimated cost :- Rs. 99,500/- only
Earnest Money :- Rs. 2000 /- only
Time limit :- One Month

S.No	Sub heads and items of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic metre) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibility of the contractor. The work shall be executed as per the MORTH specification and the direction of Engineer-in-Charge.	65.00	Per hour	1100.00	Rupees One thousand one hundred only	71500.00
2	Hiring of tipper which shall include all expenses on a/c establishment, POL, repair, and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per directions of Engineer in charge including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges	7.00	per day	4000.00	Rupees four thousand only	28000.00
Total=						99500.00

T. S No. 03 for the year 2024-27
DNJTN. 03 for the year 2024-27

[Signature]
Assistant Engineer
Kasauli Sub- Division (B&R)
HPPWD Kasauli

[Signature]
Executive Engineer
Kasauli Division (B&R)
HPPWD Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost :- 96529.00
Earnest Money :- 1900.00
Time :- Two Months

Name of Work :- Construction of Additional Accomodation in GSSS Building at Ganol (SH:- Site Development) Job No.1

Deposit work

Sr. No.	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mts. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. (one six zero three point one) and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc. and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited) All earth work in excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and safe disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other cases, it shall be removed by the suitable diversion, bailing out or dewatering as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	723.880	Per Cubic Meter	133.35	Rupees One Hundred & Thirty Three - Paise Thirty Five Only	96529.00
Total:-						96529.00

Rupees Ninety Six Thousand Five Hundred & Twenty Nine Only

T/S No. 29 for the year 2026-2027
Sr. No. 43 for the year 2026-2027

Executive Engineer
B&R Division, H.R. P.O. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.

Name of Work :- Construction of Additional Accomodation in GSSS Building at Ganol (SH:- Site Development) Job No.2
Deposit work

Sr. No.	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with a lift upto 1.50mts. And a lead upto 20.00 mtr. as per technical specification Clause 1603.1. (one six zero three point one) and MORD specification including carriage of all labour equipment and materials to various location of site through all modes of transportations in all lead, lift and all incidental charges. all work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc. and to protect stability of hill side rock work shall be executed with chiseling, wedging out rock, where blasting is prohibited) All earth work in excavation including rock excavation shall be carried out true to lines, grades, side slopes, width, camber super elevations and levels as shown on the drawing or as directed by the Engineer-in-Charge. Stacking of materials useful for construction at suitable site and safe disposal of unserviceable cut material in specified manners, trimming, filling of unevenness blindages and finishing of the road to specified dimensions as directed by the Engineer-in-Charge. If the foundation of the structure is in an area with stagnant water or water is met with in the excavation due to spring seepage rain and other cases, it shall be removed by the suitable diversion, bailing out or dewatering as directed and the area of the foundation or embankment shall be kept dry. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	711.450	Per Cubic Meter	133.35	Rupees One Hundred & Thirty Three - Paise Thirty Five Only	94872.00
Total:-						94872.00
Rupees Ninety Four Thousand Eight Hundred & Seventy Two Only						

Estimated Cost :- 94872.00
Earnest Money :- 1900.00
Time :- Two Months

T/S No. 30 for the year 2026-2027
Sr. No. 44 for the year 2026-2027

Executive Engineer
B&R Division, R.P.W.D. Kasauli

DRAFT SCHEDULE OF QUANTITY

Job No.

Estimated Cost:- 98968.00

Earnest Money:- 2000.00

Time:- One Month

Name of Work :- A/R & M/O to Johari Mallah road in km 0/00 to 27/465 (SH:- Trimming of grass in km 13/00 to 20/00)

Sr. No	Description of work	Qty	Unit	Rate in		Amount
				Figures	Words	
1	Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914 as per H.P. PWD. specification 1990 (One thousand Nine hundred Ninety) Volume-1 (One), including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	22240	Per Square Metre	4.45	Rupees Four - Paise Fourty Five Only	98968.00
Total:-						98968.00

Rupees Ninety Eight Thousand Nine Hundred & Sixty Eight Only

T/S No. 43 for the year 2026-27
Sr. No. 59 for the year 2026-27

Executive Engineer
B&R Division, H.P. PWD. Kasauli

(13)

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY

Job No. :-

Estimated Cost :-

99385.00

Earnest Money :-

2000.00

Time limit :-

One Days

Name of Work :- A/R & M/O to Johari to Mallah road in Km. 0/00 to 27/465. (SH:- White washing of parapets, guide stone, breast wall strips & tree trunks etc. in Km. 13/00 to 20/00).

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Trimming of grass and weeds from the shoulder/berms and disposing of the same to suitable location including all leads, lifts and carriage of materials as per technical specifications and as per direction of Engineer in Charge including carriage of all labour, equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	2803.53	m2 Per Sqm.	35.45	Rupees Thirty Five - Paise Forty Five Only	99385.00
Total :-						99385.00
In Words		Rupees Ninety Nine Thousand Three Hundred & Eighty Five Only				
		% above/below to the DNT amount i.e. Rs.				

15

T/S No. 42 for the year 2026-27
DNT/No. 58 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 99385.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli

DRAFT SCHEDULE OF QUANTITY

Estimated Cost :-	95980.00
Earnest Money :-	2000.00
Time limit :-	Two Month

Name of Work :- Repair of damaged road portion (due to laying of underground IPH pipeline) on Dharampur Kasauli (MDR-10) road in Km. 0/00 to 10/850. (SH:- P/I thermoplastic edge line). Job No-01. Deposit.

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing and laying of hot applied thermoplastic compound 2.5 mm (two point five millimeters) thick and 0.10 (point one zero) meter wide strip in Center line / Edge line including reflectorising glass beads @ 250 gms (two fifty grammes) per square meter area, thickness of 2.5 mm (two point five millimeters) is exclusive of surface applied glass beads as per IRC:35 (thirty five) in accordance with Ministry of Road Transport Specification (Latest revision) and IRC Code. The finished surface to be level, uniform and free from streaks and holes including carriage of all labour, equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges	200.00	Per Square meter.	479.90	Rupees Four Hundred & Seventy Nine Paise Ninety Only	95980.00
Rupees Ninety Five Thousand Nine Hundred & Eighty Only						
in words.						
% quoted in figure:-						
% quoted in words:-						

T/S No. 66 for the year 2026-27
Sr. No. 87 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 95980.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

(15)

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY							Estimated Cost:-		98300.00
							Earnest Money:-		2000.00
							Time limit :-		One Month
Name of Work :- R/R damages to Barotiwala Gunai road in Km. 0/00 to 19/120. (SH: Hiring of excavator cum loader along along with tractor trolley for removal of slips and clearance of road side drain in Km. 6/00 to 12/00). Under Patta Section.									
Sr. No	Description of work	Qty.	Unit	Rate in		Amount			
				Figures	Words				
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	69.00 Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	75900.00			
2	Hiring of Tractor-Trolley with handraulic jack, minimum 8 (Eight) working hours per day, which shall include all expenses on AC of establishment, POL, repair & other overhead charges including insurance of machinery/vehicles. All useful material i.e. stones etc. shall belongs to department, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	8.00 Day	Per Day	2800.00	Rupees Two Thousand Eight Hundred Only	22400.00			
						98300.00			
Rupees Ninety Eight Thousand Three Hundred Only									

in words.

% quoted in figure:-	
% quoted in words:-	

T/S No. for the year 2026-27
Sr. No. 65 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 98300.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

Estimated Cost:-	98300.00
Earnest Money:-	2000.00
Time limit :-	One Month

Name of Work :- R/R damages to Barotiwalwa Gunai road in Km. 0/00 to 19/120. (SH: Hiring of excavator cum loader along along with tractor trolley for removal of slips and clearance of road side drain in Km. 0/00 to 6/00). Under Patta Section.

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Hiring of Excavator cum loader for excavation, removal of slips, removal of ships, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	69.00	Hr	Per Hour	1100.00 Rupees One Thousand One Hundred Only	75900.00
2	Hiring of Tractor-Trolley with handrautic jack, minimum 8 (Eight) working hours per day, which shall include all expenses on A/C of establishment, POL, repair & other overhead charges including insurance of machinery/vehicles. All useful material i.e. stones etc. shall belongs to department. maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.	8.00	Day	Per Day	2800.00 Rupees Two Thousand Eight Hundred Only	22400.00
Rupees Ninety Eight Thousand Three Hundred Only						98300.00

in words.

% quoted in figure:-	
% quoted in words:-	

T/S No. for the year 2026-27
Sr. No. 66 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 98300.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

(17)

Job No :-

Estimated Cost :-	99746.00
Earnest Money :-	2000.00
Time :-	Two Month

Name of Work :- A/R & M/O Circuit House Building at Parwanoo . (SH:- P/F Steel work, Exterior Paint etc.)

Sr.No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Providing and fixing 0.47mm thick prepainted steel sheet Tata/Duroshine in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge. including carriage of materials with in all leads and lifts and other incidental charges.	30.50	Per Square Meter	1492.45	Rupees One Thousand Four Hundred & Ninety Two - Paise Fourty Five Only	45520.00
2	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished welded type tubes complete as per the direction of Engineer-in-charge including carriage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	200.00	Kg	136.50	Rupees One Hundred & Thirty Six - Paise Fifty Only	27300.00
3	Providing and fixing wooden moulded beading to door and window frames with iron screws, plugs and priming coat on unexposed surface etc. complete :50 x 20 mm or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	38.00	Per RMT	237.45	Rupees Two Hundred & Thirty Seven - Paise Fourty Five Only	9023.00
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete or as directed by the Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental charges.	50.00	Per Square Meter	121.65	Rupees One Hundred & Twenty One - Paise Sixty Five Only	6083.00



5	Finishing walls with textured exterior paint of required shade :New work (Two or more coat applied @ 3.28 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)complete as per the direction of Engineer-in-Charge including cartiage of all labour equipments and materials to various location through all modes of transportation in all leads lifts and all incidental charges.	50.00	Per Square Meter	236.40	Rupees Two Hundred & Thirty Six - Paise Fourty Only	11820.00
Total:-		Rupees Ninety Nine Thousand Seven Hundred & Fourty Six Only				99746.00

T/S No. for the year 2026-2027
Sr. No. 93 for the year 2026-2027

Executive Engineer
B&R Division, HP.PWD.
Kasauli

DRAFT SCHEDULE OF QUANTITY

Estimated Cost: -	99384.00
Earnest Money: -	2000.00
Time limit: -	Two Month

Name of Work :- R/R damages to link road to Gharsi Brahmana in Km. 0/00 to 1/300. (SH:- C/o CC pavement at Rd 0/945 to 0/970).

Sr. No	Description of work	Qty.	Unit	Rate in		Amount
				Figures	Words	
1	Earthwork in excavation for all type of road structures such as retaining wall, breast wall and parapets etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiesling / wedging out rocks (where blasting is prohibited) as per drawing and technical specification true to lines and grades. Dimensions and other particulars as per drawing and Technical Specification Clause 305.1(Three hundred Five point One) including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and stacking of materials useful for construction at suitable sites and safe disposal of unserviceable excavated materials in specified manners to dumping site (to be arranged by the contractor) including trimming, dressing of sides and bottom, filling of unevenness blindages, backfilling in trenches with excavated suitable material and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge. All work of excavation by blasting shall be carried out by taking all necessary precautions against soil erosions, damage to hill side, water pollutions etc., and to protect stability of hill side rock. Any loss to the public or private property during the course of execution shall be the sole responsibility of the contractor, which shall have to be duly compensated by him at his own cost of all cases.	15.250 m3	Per Cubic Meter	277.50	Rupees Two Hundred & Seventy Seven - Paise Fifty Only	4232.00
2	Providing and Laying concrete 1:1:8 (one cement isto four sand isto eight graded stoe aggregate 40 mm (forty millimeters) nominal size for plain reinforced concrete mechanically mixed and vibrated in open foundations including the cost of form work complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 (eight hundred two, eight hundred three, one thousand two hundred two & one thousand two hundred three) including carriage of all labour equipments and material to various location through all modes of transportation in all leads and lifts as per the direction of the Engineer-in-charge.	11.44 m3	Per Cubic Meter	4537.20	Rupees Four Thousand Five Hundred & Thirty Seven - Paise Twenty Only	51906.00

18



3	Providing and laying cement concrete work 1:2:4 (one cement two sand four graded crust hard stone aggregate twenty millimetre nominal size/mechanically mixed and vibrated for compacting concrete required strength and curing complete including cost of form work and reinforcement for reinforced cement concrete work as per HPPWD specification 1990 (one thousand Nine hundred Ninety) volume-I including carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge. Foundations, and plinth in all depths and levels.	7.630 m ³	Per cubic meter	5667.90	Rupees Five Thousand Six Hundred & Sixty Seven Paise Ninety Only	43246.00
Rupees Ninety Nine Thousand Three Hundred & Eighty Four Only						
in words.						
	% quoted in figure:-					
	% quoted in words:-					99384.00

T/S No. 65 for the year 2026-27
Sr. No. 85 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 99384.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

(19)

DRAFT SCHEDULE OF QUANTITIES									
						Estimated Cost:-		98100.00	
						Earnest Money:-		2000.00	
						Time limit:-		One Month	
Name of Work :- R/R damages to link road to village Arla in Km. 0/00 to 3/500. (SH: Hiring of excavator cum loader for removal of slips and clearance of road side drain and hiring of tipper for shifting of earth, debris etc. in Km. 0/00 to 3/500). Under Subathu Section.									
Sr. No		Description of work		Qty.	Unit	Rate in		Amount	
						Figures	Words		
1		Hiring of Excavator cum loader for excavation, removal of slips, removal of slips, removal of debris & dressing of berms with a minimum capacity of 28.00 (Twenty Eight cubic meter) per hour minimum six hour per day including pay of operators, POL charges, maintenance or any minor or major accidents and other damages to private and Govt. property is the whole responsibilities of the contractor. The work shall be executed as per the MORT&H specification and the direction of Engineer-In-Charge.		71.00 Hr	Per Hour	1100.00	Rupees One Thousand One Hundred Only	78100.00	
2		Hiring of Tipper which shall include all expenses on A/C of establishment, POL, repair & other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HP. PWD. and as per direction of Engineer in Charge, including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.		5.00 Day	Per Day	4000.00	Rupees Four Thousand Only	20000.00	
						Rupees Ninety Eight Thousand One Hundred Only			
in words.									
% quoted in figure:-									
% quoted in words:-									
						T/S No.		for the year 2026-27	

T/S No. for the year 2026-27
Sr. No. 92 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 98100.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli.

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITIES						Estimated Cost :-	99762.00
						Earnest Money :-	2000.00
						Time limit :-	Two Month
Name of Work :- A/R & M/O various roads under Kasauli Sub Division. (SH:- Providing and supplying printed Stationery items etc.)							
Sr. No	Description of work	Qty.	Unit	Rate in		Amount	
				Figures	Words		
1	Providing & Supplying the printing item/articles of the following items as Per PWD Specification and up to date amendments with the satisfaction of Engineer-In-Charge. The rates includes carriage of material with in all leads and lifts, GST, any other tax, in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.						
1.1	Form No-6	1000.00 Nos	Each	8.26	Rupees Eight Paise Twenty Six Only	8260.00	
1.2	Tender form No 7/8	480.00 Nos	Each	94.40	Rupees Ninety Four Paise Fourty Only	45312.00	
1.3	Agreement file cover (Printed)	300.00 Nos	Each	34.50	Rupees Thirty Four Paise Fifty Only	10350.00	

14	Photostate paper (A4)	100.00	Nos	Each	358.40	Rupees Three Hundred & Fifty Eight Paise Fourty Only	35840.00
Rupees Ninety Nine Thousand Seven Hundred & Sixty Two Only							
in words.							
% quoted in figure:-							
% quoted in words:-							
							99762.00

T/S No. 72 for the year 2026-27
Sr. No. 160 for the year 2026-27

Draft Schedule of Quantity approved for Rs. 99762.00 only

Executive Engineer
B&R Division, HP.PWD.
Kasauli

Draft SCHEDULE OF QUANTITY

(21)

AMOUNT	
Estimated Cost: -	99900.00
Earnest Money: -	2000.00
Time Limit: -	One months.

Work:- Restoration to rain damages on SAKB Road km 37/00 to 70/00(SH:- Hiring of JCB/loader cum-excavator for Removal of slips & clearance of and hiring of Tipper for shifting of earth etc in km 52/00 to 55/00) Under PDNA

Description of work	Qty.	Unit	RATE In		AMOUNT Rs.
			Figures	Words	
Hiring of JCB / loader cum-excavator.					
Terms and Conditions :-					
Hire charges should include expenses on account of establishment POL Major and minor repairs / over hauling and replacement of tyres and batteries if reqd. Hire charges should also include insurance of machinery/vehicles and establishment and the department shall not be responsible for any fatal/non fatal accidents, The bucket and loader capacity of JCB cum-excavator should not be less than 0.24 cum and one, The machinery should be of latest modal not older than 1999 . quantity of excavated / removed material should not be less than 28 cum / per hour.	69.00	Per hour.	1100.00	Rupees One Thousand One Hundred Only	75900.00
Hiring of tipper which shall include all expenses on account of establishment POL repair and other overhead charges etc. The tipper has to perform not less than as prescribed in the norms of HPPWD and as per direction of Engineer in charge , including carriage of all labour equipment and material to various locations through all modes of transportation in all leads and lifts and all incidental charges.	6.00	Per day	4000.00	Rupees two thousands two hundred and sixteen only	24000.00
Total :-					99900.00

Rupees Ninety Nine Thousand Nine Hundred Only
Draft Schedule of Quantity Recommended for approval for Rs. 99900.00 only.

Assistant Engineer,
B&R Sub Division, HP.PWD. Chandni

Sr. No. for the year 26-27
Draft Schedule of Quantity approved for Rs. 99900.00 only.

Executive Engineer
B&R Division, HP.PWD. Kasauli.

Shand