

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-AD-EA-I-Tender-2026-27

4719-28

Dated: 24/07/26

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220204

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **01.08.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **31.07.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **31.07.2026 up to 5:00 PM**.


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Restoration of Rain damages on Chmakripul to Dhundan road km. 0/0 to 5/0 (SH:- C/o R/wall in km. 0/600 to 0/620)PDNA	1,33,480/-	2,700/-	2 Months	350/-
2.	Restoration of Rain damages on Chmakripul to Dhundan road km. 0/0 to 5/0 (SH:- C/o R/wall in km. 0/400 to 0/420) Under PDNA	1,33,480/-	2,700/-	2 Months	350/-
3	Balance work of C/o Culvert/Cause way in link road from Bhalag to Sehnali km 0/0 to 4/555(SH:- C/o R/wall at Rds 3/735 to 3/740, 3/585 to 3/620 and Bed Cutting in km. 0/465 to 0/525)DMFT	4,99,905/-	10,000/-	1 Month	350/-
4	Construction of R/wall G.M.S Kotla Play Ground G.P Hanuman Badog (SH:- VKVNY (MLA LAD).	97,056/-	2,000/-	1 Month	350/-

5	Construction of R/wall G.M.S Kotla Play Ground G.P. Hanuman Badog (D.D. Deposit).	98,039/-	2000/-	1 Month	350/-
6	Restoration of rain damages on Nawin Karyah road k. 0/0 to 2/0(SH:-C/o R/wall at RD 1/465 to 1/472)	82,925/-	1700/-	1 Month	350/-
7	C/o link road Animal Husbandary Darla to Kotla Numhal Kotla Pujaria Datti Shiv Nagar road km. 0/0 to 4/500(SH:-C/o R/wall at Rds 0/060 to 0/063)DMFT	99,554/-	2000/-	1 Month	350/-
8	Restoration of rain damages in Darla Sub-Division(SH:-Hiring of Tipper for reoval of slips in Darla Section various Roads)Job No.1	97,500/-	2000/-	Fifteen days	350/-
9	Restoration of rain damages in Darla Sub-Division(SH:-Hiring of Tipper for reoval of slips in Navgaon section various roads)Job No.1)	97,500/-	2000/-	Fifteen days	350/-
10	Restoration of rain damages on Darla Sub-Division(SH:-Hiring of JCB for removal of slips in Navgaon section various roads)Job No.2	99,000/-	2000/-	Fifteen days	350/-
11	Balance work of C/o Culvert/Cause way in link road from Bhalag to Sehnali km 0/0 to 4/555(SH:-P/L Kharnja Soling C.C. Pavement 1:4:8 & 1:2:4 in Km. 3/525 to 3/555 & 3/580 to 3/650)DMFT	3,62,409/-	7300/-	1 Month	350/-
12	C/o Culvert /Causeway in link road from Bhalag to Sehnali km. 0/0 to 4/555(SH:-P/L C.C. Pavement 1:4:8 & 1:2:4 & Cause way at Rds 3/0, 3/045, 3/105 and 3/210)DMFT	4,99,988/-	10,000/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2026-27- 4719-28

Dated:- 24/07/2026

Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3rd Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.



Executive Engineer

Arki Division

H.P.W.D. Arki

Certificate

Certified that the tenders called vide this notice inviting tender for 12(Twelve) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer

Arki Division

H.P.W.D. Arki

Job No-1

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Chamakharipul to Dhundan road km 0/000 to 5/000 (SH:- C/o R/ wall in km 0/600 to 0/620) PDNA

Estimated Cost: -Rs 1,33,480/- only

Earnest Money : Rs 2700/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.	Rate	Unit	Amount
1	2	3	In figure In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.52 Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre 1632.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	29.28 Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre 128557.00
3	Providing and laying weepholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through full width of the structures with slop of 1:20 1(vertical);20 (Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,,709,1204.3.7.	12.00 Rmt	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five Only	Each per running metre 3291.00
				Total	133480.00

Quoted Rate Percentage in Figure :-

Quoted Rate Percentage in Words :-

Executive Engineer
Arki Division,
HPPWD, Arki

Job No. 2

SCHEDULE OF QUANTITY

Name of work: - Restoration of Rain damages on Chamakharipul to Dhundan road km 0/000 to 5/000 (SH:- C/o R/ wall in km 0/400 to 0/420) PDNA

Estimated Cost: -Rs 1,33,480/- only

Earnest Money : Rs 2700/-Only

Time -Two Months

S.N o.	Sub head and items of work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.52	Cum	171.40	Rupees One Hundred Seventy One and Paise Forty Only	Per cubic metre	1632.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts. (i) 1:5:10(40mm)	29.28	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Paise Sixty Only	Per cubic metre	128557.00
3	Providing and laying weepholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)millimetre dia PVC pipe extending through full width of the structures with slop of 1:20 1(vertical);20 (Horizontal) towards drawing face complete as per drawings and technical specifications MORD clause 614,,709,1204.3.7.	12.00	Rmt	274.25	Rupees Two Hundred Seventy Four and Paise Twenty Five Only	Each per running metre	3291.00
						Total	133480.00

Quoted Rate Percentage in Figure:-
Quoted Rate Percentage in Word:-

**Executive Engineer
Arki Division,
HPPWD, Arki**

100 DINO 3

SCHEDULE OF QUANTITY

Name of Work:-C/o R/wall on G.M.S. Kotla Play Ground Mohal G.P. Hanuman Barog (VKVNY (MLA LAD))

Estimated Cost: -Rs97056/- only

Earnest Money :-Rs2000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	7.32	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1255
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	21.27	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	93388
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	8.80	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	2413
					Total	97056

Quoted Rate Percentage in Figure:-

Quoted Rate Percentage in words:-

Executive Engineer
Arki Division,
HPPWD, Arki

Job No- 4

SCHEDULE OF QUANTITY						Estimated Cost: -Rs98039/- only	
Name of Work:-C/o R/wall on G.M.S. Kotla Play Ground G.P. Hanuman Barog (DC Deposit)						Earnest Money :-Rs2000/-only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
1	2		Figure	Words			
1		3	4	5	6		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	7.32	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.		1255
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	21.52	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.		94486
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	8.38	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt		2298
					Total		98039

Quoted Rate Percentage in Figure:-
Quoted Rate Percentage in Words:-

Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs82925/- only	
Name of Work:- Restoration of Rain Damages on Nawin Karyah road km 0/00 to 2/00 {SH:- C/O R/Wall at RD 1/465 to /1/472}					Earnest Money :-Rs1700/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	9.66	171.40	Rupees one hundred seventy one and paise fourty only	P.Cum.	1656
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	16.73	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	73455
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	5.04	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	6065
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	6.38	274.25	Rupees two hundred seventy four and paise twenty five only	Rmt	1750
					Total	82925

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99,554/- only	
Name of Work:-C/o Link Road Animal Husbandry Darla to Kotla Numhal Kotla Pujaria Datti Shiv Nagar Road Km 0/00 to 4/500.(Sh:- C/o R/wall at Rds 0/060 to 0/063.) DMFT Deposit						Earnest Money :-Rs2,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
			Figure	Words			
1	2	3	4	5	6		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	10.50	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1800	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	20.85	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	91544	
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	4.50	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	5415	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	2.90	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	795	
					Total	99554	

Quoted Rate Percentage in Figure


Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs97,500/- only	
Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Darla Section Various Roads.) (Job No- 1)						Earnest Money :-Rs2000/-Only	
						Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4		5	6
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expension of P.O.L. charges , repair of machineries . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred fifty and paise nil only	P.Hour.	97500
						Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY							Estimated Cost: -Rs97,500/- only		
Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Navgaoun Section Various Roads.) (Job No- 1)							Earnest Money :-Rs2000/-Only		
							Time :-Fifteen Days		
S. No.	Sub head and items of work			Qty.		Rate In		Unit	Amount
1	2					Figure	Words		
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expension of P.O.L. charges , repair of machineries . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.			150.00	Hour	650.00	Rupees six hundred fifty and paise nil only	P.Hour.	97500
								Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY							Estimated Cost: -Rs99000/- only	
Name of Work:-Restoration of Rain Damages of Darla Sub Division . (SH:-Hiring of JCB for removal of Slips in Navgaoun Section Verious Roads) Job No-2							Earnest Money :-Rs2000/-Only	
							Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount	
				Figure	Words			
1	2	3		4		5	6	
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000	
						Total	99000	

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY				Estimated Cost: -Rs4,99,905/- only		
Name of Work:- Balance Work of C/o Culvert /Cause way in Link Raod from Bhalag to Sehnali KM 0/00 to 4/555.(SH:-C/o R/wall at Rds 3/735 to 3/740, 3/585 to 3/620 and Bed Cutting in Km 0/465 to 0/525.) DMFT				Earnest Money :-Rs10,000/-Only		
				Time :-One Month		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	38.10	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	6530
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	82.55	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	362444
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	27.30	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	32850
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	46.50	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	12753
5	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, . The recovery of useful stone that is 77.50 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	232.50	367.00	Rupees three hundred sixty seven and paise zero only	P.Cum.	85328
					Total	499905

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs3,62,409/- only	
Name of Work:- Balance Work of C/o Culvert /Cause way in Link Raod from Bhalag to Sehnali KM 0/00 to 4/555.(SH:-P/L Kharnja Soling C.C. Pavement 1:4:8. & 1:2:4 in Km 3/525 to 3/555 & 3/580 to 3/650.) DMFT					Earnest Money :-Rs7300/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil complete as per H.P.PWD. Specifications and as per direction of Engineer-in-Charge.	350.00	1.60	Rupees one and paise sixty only	P.Sqm	560.00
2	Consolidation of sub-grade with power road roller of 8 to 12 (Eight to Twelve) tonns including making the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade till the soil is evenly the densely consolidated and be have as elastic mass complete to make the surface for laying of soling and as per direction of the Engineer-in-Charge as per technical specification MORD 800,1600,300 including carriage of materials with in all leads and lifts and as per	350.00	1.85	Rupees one and paise eighty five only	P.Sqm	647.50
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	52.50	1425.25	Rupees one thousand four hundred twenty five and paise twenty five only	P.Cum.	74825.63
4	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 20mm (Twenty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and as directed by Engineer-In- Charge	26.25	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	130074.00
5	Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compecting with vibrator and curing complete including the cost of centering and shuttering - All work up to plinth level carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	26.25	5954.35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	156301.69
					Total	362409

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,99,988/- only	
Name of Work:- C/o Culvert /Cause way in Link Raod from Bhalag to Sehnaali KM 0/00 to 4/555.(SH:-P/L C.C. Pavement 1:4:8. & 1:2:4 & Cause way at Rds 3/00,3/045,3/105,3/210.) DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and	126.00	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	21596
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	63.00	1425.25	Rupees one thousand four hundred twenty five and paise twenty five only	P.Cum.	89791
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 20mm (Twenty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and as directed by Engineer-In- Charge	31.50	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	156089
4	Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compecting with vibrator and curing complete including the cost of centering and shuttering - All work up to plinth level carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	31.50	5954.35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	187562
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials within all leads lifts and other incidentals as per the direction of Engineer-in-charge.	487.00	92.30	Rupees ninety two and paise thirty only	P.Kg	44950
					Total	499988

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki /