

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2026-27 3895-3903

Dated:- 07/07/2026

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **17.07.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **16.07.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **16.07.2026 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips etc)Job No.1	99,000/-	2000/-	1 Month	350/-
2.	Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips etc)Job No.2	99,000/-	2000/-	1 Month	350/-
3	Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips etc)Job No.3	99,000/-	2000/-	1 Month	350/-
4	Restoration of rain damages on various roads under Kunihar Sub-Division under mann section(SH:-Hiring of JCB for removal of slips etc)Job No.1	49,000/-	1000/-	1 Month	350/-
5.	Restoration of rain damages on various roads under Kunihar Sub-Division under Kunihar section(SH:-Hiring of JCB for removal of slips	99,000/-	2000/-	1 Month	350/-

	etc)Job No.1				
6	Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips etc)Job No.6	99,000/-	2000/-	1 Month	350/-
7	Restoration of rain damages on various roads under Kunihar Sub-Division under Jainagar section(SH:-Hiring of JCB for removal of slips etc)Job No.7	99,000/-	2000/-	1 Month	350/-
8	C/o Ambulance road from Badal Kotalu Chakhar k. 0/0 to 1/500(SH:-C/o R/wall at Rds 0/675 to 0/693)DMFT	4,71,537/-	9500/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2026-27- 3895-3903

Dated:- 07/07/2026

Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 8 (Eight) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

DRAFT SCHEDULE OF QUANTITY							
Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job No.					Estimated Cost :- Rs 99,000.00		
					Earnest money :- Rs 2,000.00		
					Time: One month		
Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paisenil Only	Per Hours	99000.00
						Total	99000.00

Percentage Rate Quated in figure
Percentage Rate Quated in words

Executive Engineer
Arki Division (B&R)
HP, PWD. Arki.

DRAFT SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job No. 2

Estimated Cost :- Rs 99,000.00


Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paise Nil Only	Per Hours	99000.00
						Total	99000.00

Percentage Rate Quoted in figure

Percentage Rate Quoted in words


 Executive Engineer
 Arki Division (B&R)
 HP PWD. Arki.

DRAFT SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job No. **3**

Estimated Cost :- Rs 99,000.00


Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paise nil Only	Per Hours	99000.00
						Total	99000.00

Percentage Rate Quoted in figure

Percentage Rate Quoted in words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar Sub Division under Mann Section.(Sh :Hiring of JCB for removal of slips in various roads) Job No.1

Estimated Cost :- Rs 49,000.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	49.00	Hours	1000.00	Rupees One thousand and paise nil Only	Per Hours	49000.00
						Total	49000.00

Percentage Rate Quated in figure

Percentage Rate Quated in words

Executive Engineer

Arki Division (B&R)

HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar Sub Division under Kunihar Section.(Sh :Hiring of JCB for removal of slips in various roads) Job No.1

Estimated Cost :- Rs 99,000.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paise nil Only	Per Hours	99000.00
						Total	99000.00

Percentage Rate Quated in figure

Percentage Rate Quated in words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job No.6					Estimated Cost :- Rs 99,000.00		
					Earnest money :- Rs 2,000.00		
					Time: One month		
Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paisenil Only	Per Hours	99000.00
						Total	99000.00


Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under kunihar sub division under Jainagar section.(Sh-Hiring of JCB for removal of slips etc.) Job No. 7

Estimated Cost :- Rs 99,000.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paise Nil Only	Per Hours	99000.00
						Total	99000.00


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY					Estimated Cost. -Rs4,71,537/- only	
Name of Work:-C/o Ambulance Road From Badal Kotalu Chakhar Km 0/00to 1/500.(SH:- C/o R/wall at Rd,s 0/675 to 0/693.) DMFT					Earnest Money :-Rs9,500/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	47.52	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	8145
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	93.96	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	412541
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	31.32	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	37687
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	48.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	13164
					Total	471537

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki