

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-AD-EA-I-Tender-2026-27 6515-23

Dated:- 29/08/2026

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.


Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A(3)I/2024 dated shimla-2 the 03.01.2024 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714 

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714 

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **07.09.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **06.09.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **06.09.2026 up to 5:00 PM**.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1.	Construction of link road from Khalighati to Kaldwar Falodan road km. 0/00 to 6/200 (SH:- Construction of R/wall at RD's 6/070 to 6/081, B/wall at RD's 6/050 to 6/064) DMFT	4,90,069/-	10,000/-	1 Month	350/-
2.	Special Repair to Veterinary Dispensary at Bainj Ki Hatti Tehsil Arki, Distt. Solan (HP). DMFT Deposit.	4,99,543/-	10,000/-	Fifteen days	350/-
3.	Construction of Protection wall behind Cow Shed at Daseran (Sukhed Khad) G.P Daseran Tehsil Arki, Distt. Solan (HP) (SH:- C/o Protection wall at RD 0/00 to 0/016.75 (DMFT Deposit).	1,79,814/-	3,600/-	1 Month	350/-
4.	Restoration of rain damages on Darla Sub Division (SH:- Hiring of JCB for removal of slips in Darla Section various roads) Job No.2	99,000/-	2,000/-	Fifteen days	350/-

	Balance work of C/o Rooms on First Floor of GMS Sera Education Block Dhundan Tehsil Arki Distt. Solan (SH:- Plaster, Paint & Finishing work etc.) DMFT.	1,77,174/-	3,600/-	2 Months	350/-
6	Restoration of rain damages on various roads under Kunihar Sub-Division under Diggall section, HP, PWD, Digal (SH:- Hiring of Tipper for carriage of slips Materials in various roads/locations etc.) Job No.5	99,450/-	2,000/-	1 Months	350/-
7	Restoration of rain damages on various roads under Kunihar Sub-Division under Diggall section, HP, PWD, Digal (SH:- Hiring of Tipper for carriage of slips Materials in various roads/locations etc.) Job No.6	99,450/-	2,000/-	1 Months	350/-
8	Restoration of rain damages on various roads under Kunihar Sub-Division under Diggall section, HP, PWD, Digal (SH:- Hiring of Tipper for carriage of slips Materials in various roads/locations etc.) Job No.7	99,450/-	2,000/-	1 Months	350/-
9	Construction of Sahid Ram Rattan link road to village Banli Brahmana km. 0/0 to 0/640 Job No.2) (SH:- Providing and laying 20mm thick precast carpet and Seal coat in km. 0/0 to 0/640) Under DMFT (PMKKKY)	4,99,712/-	10,000/-	1 Months	350/-
10	C/o link road from Khalighatti to Kaldwar Falodan Road km. 0/0 to 6/900 (SH:- C/o R/wall at Rds 3/800 to 3/818) DMFT	4,94,475/-	10,000/-	1 Months	350/-
11	Construction of Sahid Ram Rattan link road to village Banli Brahmana km. 0/0 to 0/640 Job No.1) (SH:- Providing and laying WBM Grade-II and Primer coat, Tack coat in km. 0/0 to 0/640) Under DMFT (PMKKKY)	4,16,573/-	9,000/-	1 Months	350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

Dated:- 29/08/2026

No: PW-AD-EA-I-Tender-2026-27- 6515-23

Copy forwarded for the following for information and necessary action to:-

- The Superintending Engineer 3rd Circle HPPWD Solan.
- The all Assistant Engineer working under this division for information and necessary action.
- All the heads of the branches in this office.
- Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 11 (Eleven) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,90,069/- only	
Name of Work:- C/o Link Road from Khalighati to Kaldwar Falodan Road Km 0/00 to 6/200. (SH:-C/o R/wall at Rds 6/070 to 6/081,B/wall at Rds 6/050 to 6/064.) DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	63.06	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	10808
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	100.400	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	440816
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	56.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	15413
4	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	19.14	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	23031
					Total	490069

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs 4,99,543/- only
Name of Work:-Special Repair to Veterinary Dispensary at Bainj Ki Hatti Tehsil Arki Distt. Solan (HP). DMFT Deposit						Earnest Money :-Rs10,000/-Only
						Time :-One Month
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within all lead & lift and as per direction of Engineer - in- charge.	9.16	1465.35	Rupees one thousand four hundred sixty five and paise thirty five only	P.Cum.	13423
2(i)	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, piinth beams, girders, bressumers and cantilevers within all lead& lift and as per direction of Engineer - in- charge.	21.42	387.15	Rupees three hundred eighty seven and paise fifteen only	P.Sqm	8293
(ii)	Suspended floors, roofs, landings, balconies and access platform	91.61	468.30	Rupees four hundred sixty eight and paise thirty only	P.Sqm	42901
(iii)	Edges of slabs and breaks in floors and walls under 20 Cm wide.	40.80	131.50	Rupees one hundred thirty one and paise fifty only	Rmt	5365
3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size). including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	14.68	7835.75	Rupees seven thousand eight hundred thirty five and paise seventy five only	P.Cum.	115029
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials within all leads lifts and other incidentals as per the direction of Engineer-in-charge.	1908.40	92.30	Rupees ninety two and paise thirty only	P.Kg	176145
5	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood	0.022	95763.05	Rupees Ninety five thousand seven hundred sixty three and paise five only	P.Cum.	2107
6	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in charge. (35 mm thick shutters)	10.26	3122.60	Rupees three thousand one hundred twenty two and paise sixty only	P.Sqm	32038
7	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws. Second class teak wood	8.64	3669.30	Rupees three thousand six hundred sixty nine and paise thirty only	P.Sqm	31703
8	6mm Cement plaster to ceiling In Cement mortar 1:3 (1 Cement:3 Sand) as per the direction of Engineer-In- Charge	95.03	142.35	Rupees one hundred fourty two and paise thirty five only	P.Sqm	13528

SCHEDULE OF QUANTITY

Name of Work:-Special Repair to Veterinary Dispensary at Bainj Ki Hatti Tehsil Arki Distt. Solan (HP). DMFT Deposit						Estimated Cost: -Rs 4,99,543/- only	
						Earnest Money :-Rs10,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
1	2	3	Figure	Words	5	6	
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within all lead & lift and as per direction of Engineer - in- charge.	9.16	1465.35	Rupees one thousand four hundred sixty five and paise thirty five only	P.Cum.	13423	
2(i)	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers within all lead& lift and as per direction of Engineer - in- charge.	21.42	387.15	Rupees three hundred eighty seven and paise fifteen only	P.Sqm	8293	
(ii)	Suspended floors, roofs, landings, balconies and access platform	91.61	468.30	Rupees four hundred sixty eight and paise thirty only	P.Sqm	42901	
(iii)	Edges of slabs and breaks in floors and walls under 20 Cm wide.	40.80	131.50	Rupees one hundred thirty one and paise fifty only	Rmt	5365	
3	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand) : 3 graded stone aggregate 20 mm nominal size). including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	14.68	7835.75	Rupees seven thousand eight hundred thirty five and paise seventy five only	P.Cum.	115029	
4	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials within all leads lifts and other incidentals as per the direction of Engineer-in-charge.	1908.40	92.30	Rupees ninety two and paise thirty only	P.Kg	176145	
5	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Sal wood	0.022	95763.05	Rupees Ninety five thousand seven hundred sixty three and paise five only	P.Cum.	2107	
6	Providing and fixing panelled or panelled and glazed shutters for doors, windows and clerestory windows fixing with butt hinges of required size with necessary screws, excluding panelling which will be paid for separately, all complete as per direction of Engineer-in charge. (35 mm thick shutters)	10.26	3122.60	Rupees three thousand one hundred twenty two and paise sixty only	P.Sqm	32038	
7	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws .Second class teak wood	8.64	3669.30	Rupees three thousand six hundred sixty nine and paise thirty only	P.Sqm	31703	
8	6mm Cement plaster to ceiling In Cement mortar 1:3 (1 Cement:3 Sand) as per the direction of Engineer-In- Charge	95.03	142.35	Rupees one hundred forty two and paise thirty five only	P.Sqm	13528	

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
9	15mm Cement plaster in single coat on the rough side and fair side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. including all leads , lifts & carriage of material. (Cement Mortar 1:6 (one Cement isto six Sand).	15.40	185.40	Rupees One hundred eighty five one and paise forty only	P.Sqm	2855
10	Providing and applying white cement based putty of average thickness 1mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	110.43	85.10	Rupees eighty five and paise ten only	P.Sqm.	9398
11	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	110.43	37.40	Rupees thirty seven and paise forty only	P.Sqm.	4130
12	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	110.43	106.25	Rupees one hundred six and paise twenty five only	P.Sqm.	11733
13	Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.75 ltr / 10 sqm of approved brand and manufacture.	21.59	94.30	Rupees ninety four and paise thirty only	P.Sqm.	2036
14	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge	4.32	89.90	Rupees eighty nine and paise ninty only	P.Sqm.	388
15	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC10 as per IS:1868) transparent or dyed to required colour or shade, with necessary screws etc. complete (250x10 mm)	4.00	99.20	Rupees ninety nine and paise twenty only	Each	397
16 (i)	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125mm	2	57.55	Rupees fifty seven and paise fifty five only	Each	115
(ii)	100mm	4.00	50.75	Rupees fifty and paise seventy five only	Each	203
17	Providing and fixing aluminium hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. complete. Twin rubber stopper	2.00	61.00	Rupees sixty one and paise zero only	Each	122
18	Providing and fixing bright finished brass casement stays (straight peg type) with necessary screws etc. complete 300 mm weighing not less than 330 gms	4.00	182.70	Rupees one hundred eighty two and paise seventy only.	Each	731

S No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
19	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete (300x16mm)	5.00	239.60	Rupees two hundred thirty nine and paise sixty only.	Each	1198
20	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete (Size of Tile 600x600 mm)	12.90	1360.70	Rupees one thousand three hundred sixty and paise seventy only	P.Sqm	17553
21	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 550x400 mm with a pair of 15 mm C.P.	1.00	2402.95	Rupees two thousand four hundred two and paise ninety five only	Each	2403
22	Providing and fixing white vitreous pedestal for wash basin completely recessed at the back for the reception of pipes and fittings complete and as per direction of Engineer-in-charge	1.00	1420.15	Rupees one thousand four hundred twenty and paise fifteen only	Each	1420
23	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid	1.00	4330.20	Rupees four thousand three hundred thirty and paise twenty only	Each	4330
					Total	499543

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs1,79,814/- only	
Name of Work:- C/o Protection wall behind Cow Shed at Daseran (Sukhed Khad) G.P.Daseran Tehsil Arki Distt. Solan (H.P.) (SH:- C/o Protection wall at Rd 0/00 to 0/016.75(DMFT Deposit)					Earnest Money :-Rs3,600/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	45.22	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	7751
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	37.690	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	165482
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	24.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	6582
					Total	179814


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Estimated Cost: -Rs99000/- only

Name of Work:-Restoration of Rain Damages of Darla Sub Division . (SH:-Hiring of JCB for removal of Slips in Darla Section Verious Roads) Job No-2

Earnest Money :-Rs2000/-Only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4	5	6	
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

Schedule of Quantity					Estimated cost Rs. :-1,77,174/- only.	
NAME OF WORK:- Balance work of C/o Rooms on First Floor of GMS Sera Education Block Dhundan Tehsil Arki Distt. Solan (SH:- Plaster , Paint & Finishing work etc.) (DMFT)					Earnest Money Rs.:-3,600/-only.	
					Time: - Two Month.	
Sr. No.	SCHEDULE OF WORKS	Qty.	Unit	RATE In		AMOUNT
				Figures	Words	
1	2	3	4	5	6	8
1	Providing and fixing M.S. tube hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer. as per HP. PWD. specifications of 1990 volume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge.	194.00	Kg	136.55	Rupees One Hundred & Thirty Six - Paise Fifty Five Only	26491
2	6 mm cement plaster 1:3 (1 cement : 3 fine sand) finished with a floating coat of neat cement and thick coat of Lime wash on top of walls when dry for bearing of R.C.C. slabs and beams. including carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge.	111.59	Sqm	191.05	Rupees One Hundred & Ninety One - Paise Five Only	21319
3	15mm Cement plaster in single coat on the rough side and fair side of brick/ concrete/stone walls for interior plastering upto floor two level including arrises, internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. including all leads, lifts & carriage of material. (	217.30	Sqm	196.45	Rupees One Hundred & Ninety Six - Paise Fourty Five Only	42689
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete. and as per the direction of Engineer-in-Charge.	328.89	Sqm	85.10	Rupees Eighty Five - Paise Ten Only	27989
5	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	120.08	Sqm	132.50	Rupees One Hundred & Thirty Two - Paise Fifty Only	15911
6	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm) and as per the direction of Engineer-in-Charge.	328.89	Sqm	125.20	Rupees One Hundred & Twenty Five - Paise Twenty Only	41177
7	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade, with nuts and screws etc. complete : (300x16 mm) and as per the direction of Engineer-in-Charge.	4.00	Each	239.60	Rupees Two Hundred & Thirty Nine - Paise Sixty Only	958
8	Providing and fixing ISI marked oxidised aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS:1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : complete (150x10 mm) and as per the direction of Engineer-in-Charge	4.00	Each	72.20	Rupees Seventy Two - Paise Twenty Only	289
9	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125mm	4.00	Each	57.55	Rupees Fifty Seven - Paise Fifty Five Only	230
10	Providing and fixing hanging floor door stopper, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour and shade, with necessary screws etc. Complete (Twin rubber stopper)	2.00	Each	61.00	Rupees Sixty One Only	122
					Total	177174

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words

Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar sub division under Diggal Section HP,PWD Diggal.(Sh :Hiring of Tipper for carriage of slips Materials in various Roads/locations etc.) Job No.5

Estimated Cost :- Rs 99,450.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
		3		In figure	In words	6	7
1	2						
1.00	Hiring of tipper for carriage of land slide/debris with minimum capacity of 5.50 cum per trip and minimum working six hours per day.The contractor/ owner of the tipper shall bear the expences of POL charges, repair of tipper.Any accident and other damages to the govt and private property occured during the working hours will be responsibility of the contractor and debris disposed with in all leads and lifts and as per the direction of Engineer in charge.	153.00	Hours	650.00	Rupees Six hundred fifty and paise zero Only	Per Hours	99450.00
						Total	99450.00

Percentage Rates Quated in figure

Percentage Rates Quated in words

Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar sub division under Diggal Section HP,PWD Diggal.(Sh :Hiring of Tipper for carriage of slips Materials in various Roads/locations etc.) Job No.6

Estimated Cost :- Rs 99,450.00


Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of tipper for carriage of land slide/debris with minimum capacity of 5.50 cum per trip and minimum working six hours per day.The contractor/ owner of the tipper shall bear the expences of POL charges, repair of tipper.Any accident and other damages to the govt and private property occured during the working hours will be responsibility of the contractor and debris disposed with in all leads and lifts and as per the direction of Engineer in charge.	153.00	Hours	650.00	Rupees Six hundred fifty and paise zero Only	Per Hours	99450.00
						Total	99450.00

Percentage Rates Quated in figure

Percentage Rates Quated in words


Executive Engineer
Arki Division (B&R)
H.R. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar sub division
under Diggal Section HP,PWD Diggal.(Sh :Hiring of Tipper for carriage of slips Materials in
various Roads/locations etc.) Job No.7

Estimated Cost :- Rs 99,450.00


Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of tipper for carriage of land slide/debris with minimum capacity of 5.50 cum per trip and minimum working six hours per day.The contractor/ owner of the tipper shall bear the expences of POL charges, repair of tipper.Any accident and other damages to the govt and private property occured during the working hours will be responsibility of the contractor and debris disposed with in all leads and lifts and as per the direction of Engineer in charge.	153.00	Hours	650.00	Rupees Six hundred fifty and paise zero Only	Per Hours	99450.00
						Total	99450.00

Percentage Rates Quated in figure

Percentage Rates Quated in words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Sahid Ram Rattan Link road to Village Banli Brahmana km 0/00 to 0/640 Job no.2.(SH:-Providing and laying 20 mm thick premix carpet and Seal coat in km 0/00 to 0/640) Under DMFT (PMKKKY) *Balance work.*

Estimated Cost :- Rs 4,99,712.00

Earnest money :- Rs 10,000.00

Time: One month

Sr.N o.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Providing, laying and rolling open graded premix carpet of 20 mm (Twenty millimeters) completed thickness composed of 13.20 mm. to 5.6 mm. (Thirteen point Two millimeters to Five point Six millimeters) course stone aggregate at the rate 0.27cum(Zero point two seven) cubic metre mixed with 14.6 Kg (fourteen point six) kilogram per 10 sqm(ten) bitumen VG-10(viscosting grade ten) to required line, grade and level to serve as wearing course on a previously prepared base, including mixing and heating binder and aggregate in a suitable hot mix plant 30/40(thrity oblic forty) tonne per hour capacity transporting mixed material and laying with paver finisher and rolling with a three wheel 80-100 kN capacity static road roller, finished to required level and grades to be followed by seal coat of Type -B- as per MORD Technical Specification Clause 508 (Five hundred Eight), and entire stasification of Engineer-In- Charge including carriage of materials in all leads and lifts.	1952.00	Sqm	186.50	Rupees One hundred eighty six and Paise fifty only	Per square metre	364048.00
2.00	Providing and laying seal coat for sealing the voids in a bituminous surface laid to the specified levels, grade and cross fall using Type-B as per MORD Technical Specification Clause 510 (Five hundred Ten) using VG-10 (viscosting grade-10) at the rate 6.80 Kg (Six point eight kilogram) premixed with 0.06 (Zero point zero six) cubic metre of crushed sand defiendas as passing 2.36 mm rieve and retained on 180 micron sieve per10(ten) squaremetre by mechanical means and rolling with power road roller 8-10 (eight to ten) tonne capacity including carriage of materials, labour and equipments to various location of site of work through all modes of transportation By Mechanical Means including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge.	1952.00	Sqm	69.50	Rupees Sixty nine and Paise fifty only	Per square metre	135664.00
						Total	499712.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.(ii) The btumen will be procured by the contractor himself from the refinery.

Percentage Rates Quated in figure

Percentage Rates Quated in words

Verd
Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,94,475/- only	
Name of Work:- C/o Link Road from Khalighati to Kaldwar Falodan Road Km 0/00 to 6/900. (SH:-C/o R/wall at Rds 3/800 to 3/818.) DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
					Unit	Amount
S. No.	Sub head and items of work	Qty.	Rate In			
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	57.97	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	9936
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	101.92	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	447490
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	16.83	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	20252
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	61.25	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	16798
					Total	494475

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words

Leifad
Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Sahid Ram Rattan Link road to Village Banli Brahmana km 0/00 to 0/640. Job no.1.(SH:-Providing and laying WBM Grade-II and Primer coat ,Tack coat in km 0/00 to 0/640) Under DMFT (PMKKKY)

Estimated Cost :- Rs 4,16,573.00

Earnest money :- Rs 9,000.00

Time: One months

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Providing, laying, spreading and compacting stone aggregates of specific sizes 63mm to 45mm(sixty three millimetre to forty five millimetre) grading- II 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to hundred) static roller in stages to proper grade and camber, applying and brooming, crushable screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.20 cum.(Zero point twenty cubic metre) and binding materials at the rate 0.06cum. (zero point zero six cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density Grading as per MORD Technical Specification Clause 405.. By mechanical means and as per intire satisfaction direction by the Engineer-In-Charge. including carriage of materials all leads and lifts	153.60	cum	1625.50	Rupees One thousand six Hundred twenty five and paise fifty Only	Per cubic metre	249677.00
2.00	Providing and applying primer coat with bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface and spraying primer at the rate of 0.70-1.0 kg/sqm using mechanical means as per Technical Specification Clause 502 Low porosity including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge	1952.00	Sqm	63.85	Rupees Two thousand zero Hundred twenty seven and paise eighty five Only	Per Square metre	124635.00
3.00	Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.27% (Zero point two seven five kilogram) per square metre on the prepared granular surfaces treated with primer and cleaned with hydraulic broom as per MORD technical specification Clause 503 (Five hundred three) including carriage of materials with in all leads and lifts as per the direction of Engineer-In- Charge.	1952.00	Sqm	21.65	Rupees Two thousand two Hundred forty one and paise ninety five Only	Per Square metre	42261.00
						Total	416573.00

Conditions:- i) All the material will be procured by the contractor himself and bills will be submitted.

Percentage Rates Quoted in figure

Percentage Rates Quoted in words

Executive Engineer
Arki Division (B&R)
HP, PWD, Arki.