



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

No. PWD/BWD/TA/NIT/ 2026-27-

5134-43 Dated:- 27/08/26

To

The Chief Engineer (KZ),
HPPWD Dharamshala.

Subject:-

Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders along with schedule of quantities for uploading on departmental website as per directions received through e-mail dated 25.06.2026 from Worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla.

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ As Above


Executive Engineer
Bhawarna Division
HP.PWD Bhawarna

Copy along with copy of tender Notice is forwarded to the following for information.

1. The Superintending Engineer, 5th Circle, HPPWD Palampur.
2. All Assistant Engineers working under this division.
3. The Drawing/ Accounts Branch in this office.
4. Notice Board.


Executive Engineer
Bhawarna Division
HP.PWD Bhawarna



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

"NOTICE INVITING TENDERS"


Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **07-09-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 05-09-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 05-09-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Time Limit	Cost of Tender form
1	A/R & M/O AE HPPWD officat Dheera (SH:- Providing and fixing PVC wall panelling, painting work and other Minor Repair work)	99,573/-	2000/-	Three Month	350/-
2	Construction of Childran Park at Dain Dheera (SH:- C/O Prepainted Steel sheet roof shed)	99,726/-	2000/-	Two Month	350/-
3	Restoration of rain damages on Kiarwan Panahar road km. 0/0 to 3/0 (SH:- C/O Edge wall at RD. 1/800 to 1/829.40)	99,982/-	2000/-	Three Month	350/-
4	Restoration of rain damages on Pantehar Garla Dai road km. 0/0 to 2/300, Rada Mat Badain road km. 0/0 to 2/0, Bod Mandap Kural road km. 0/0 to 2/0 (Sullah Section) (SH:- Painting and writing on Bridges, Bridges Pedestal, Rain Shelter, Boards and Kilometre stones etc)	98,876/-	2000/-	Three Month	350/-
5	Restoration of rain damages on Hamirpur Sujampur Thural Maranda road (SH:- C/O Edge wall at RD. 40/240 to 40/258)	99,882/-	2000/-	Three Month	350/-
6	Restoration of rain damages on Marhogn Kural Akshaina road km. 0/0 to 8/0 & Sullah Kakrain road km. 0/0 to 3/0 (SH:- Painting and writing on Bridges, Bridges Pedestal, Rain Shelter, Boards and Kilometre stones etc)	98,842/-	2000/-	Three Month	350/-
7	Restoration of rain damages on Duhak to Gharthoon road & Bhadroon Kona Lahru road (Bhagolu da Ghatta Section) (SH:- C/O Unlined drain & maintenance of earthen shoulder)	78,750/-	1600/-	Three Month	350/-

Terms & Conditions:-

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


Executive Engineer
Bhawarna Division
HPPWD Bhawarna.

On behalf of Governor of Himachal Pradesh



Himachal Pradesh
Public Works Department
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works being called are of emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2026-27/- 5134-43 dated.27/08/2026


Executive Engineer,
Bhawarna Division,
HPPWD. Bhawarna.

Draft Schedule of Quantity

Name of Work :- A/R & M/O AE HP PWD Office at Dheera. (SH:- Providing and fixing PVC Wall Panelling, Painting Work and other Minor Repair works).

Estimate Cost :- Rs. 99,573/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S.No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing and fixing 4mm (Four millimetre) thick Plain Glass panes with putty and nails including removal of broken glass panes complete as per the Architectural Drawings approved specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	2.16	900.00	Rupees Nineteen point five zero only	Per Square metre	1944.00
2	Providing and fixing 30 mm thick (Thirty millimetre) Second class deodar wood wire gauge shutters using galvanised M.S. wire gauge of 1.S. gauge designation 85 G (Eighty five gauge) with wire of dia 0.56 mm (zero decimal five six millimetre) for doors windows and clerestorey windows including bright finished black enamelled iron hinges with necessary screws. The rate is inclusive of octroi, royalty, malkana, sales tax, toll tax, GST or all type of other taxes imposed by the Government.	3.78	3500.00	Rupees Nineteen point five zero only	Per Square metre	13230.00
3	Providing and fixing approved quality rigid PVC Wall Panelling of minimum 81x111 (mm) thick and approved shade, fixed directly over the finished plastered wall with approved construction adhesive and suitable PVC screws with wall plugs wherever required, including PVC edge trims, corner profiles, cutting, making openings for electrical fixtures, finishing and cleaning complete in all respects as directed by the Engineer-in-Charge. Rate inclusive toll tax GST and any other taxes imposed by the government.	28.98	1000.00	Rupees Nineteen point five zero only	Per Square metre	28980.00
4	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture for interior grade on undecorated concrete/stone/plastered wall surfaces to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth including applying of putty a required for mending the surface within all leads lifts and other incidentals as per the direction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	44.68	90.00	Rupees Nineteen point five zero only	Per Square metre	4021.00
5	Painting two coats (excluding priming coat) on new wood and wood based surfaces with enamel paint brushing to give an any shade including cleaning the surfaces of all dirt, dust and other foreign matters sand papering and stopping as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	38.54	60.00	Rupees Nineteen point five zero only	Per Square metre	2312.00
6	Painting two coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	23.22	70.00	Rupees Nineteen point five zero only	Per Square metre	1625.00

work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, welding and applying a priming coat of Hot finished welded type tubes of approved steel primer, including materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.					
8	Providing and fixing 0.60mm (sixty millimetre) thick prepared steel sheet (IS marked Z-120) of TATA Durashine/ (RMP) organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with prepared iron J or L hooks, bolts and nuts 6mm (six millimetre) diameters with prepared limpet and rubber washers complete with all accessories as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	137.21	100.00	Rupees Nineteen point five zero only	Per Kilogram
9	Providing and supplying M.S. Steel Almirah, of standard size approximately 1800 mm height x 800 mm width x 500 mm depth, fabricated from high quality CRCAM.S. steel sheets, having two hinged doors, internal shelves, hanging rod, locker with lock and key arrangement, handles and all necessary fittings and accessories, finished with approved shade powder coating, complete with all accessories as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	17.16	1500.00	Rupees Nineteen point five zero only	Per Square metre
		1.00	8000.00	Rupees Nineteen point five zero only	Each
Total :-					99573.00

Drift Schedule of Quantity approved for Rs. 99573 only

Executive Engineer
Bhawarna Division
HP PWD Bhawarna

Draft Schedule of Quantity

Name of Work :- Construction of Children Park at Dain Dheera, (SH- C/o Pre-painted Steel sheet roof Shed) (Deposit work).

Estimate Cost :- Rs. 99,726/-
Earnest Money :- Rs. 2000/-
Time Limit :- Two Months

S. No	Description of item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in foundation, trenches etcetera in earth work involving all classification of soil such as pick work, pick jumper work, blasting work, soft or hard rocks including chiselling/wedging out of rocks where blasting work is prohibited or any other mixed variety of intermediate soil, dewatering and removal of slush if arisen during course of construction and lifts upto all heights including stacking the excavated soil not more than three meters clear from the edge of the excavation and then returning the stacked soil in 15 cm (fifteen centimeters) thick layers when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming and watering and then disposing of all surplus excavation earth within all leads, lifts by any mode of transportation and other incidental, as per the direction and entire satisfaction of Engineer-in-Charge. Any loss to the private and public property during course of construction shall be absolute responsibility of the contractor. Rate inclusive royalty, Malkana, toll tax, GST and other taxes imposed by the government.	0.55	250.00	Rupees Two Hundred Fifty Only	Per cubic metre	138.00
2	Providing and laying cement concrete 1:3:6 (One cement isto three sand isto six aggregate) graded crushed stone aggregate 40mm (forty millimeter) nominal size mechanically mixed and curing complete, excluding cost of form work in foundation and plinth as per approved specification, drawing including entire carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	0.55	4950.00	Rupees Four Thousand Nine Hundred Fifty Only	Per cubic metre	2723.00
3	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of Hot finished welded type tubes of approved steel primer, including welding and bolting with special shaped washers etc. complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	350.48	100.00	Rupees One Hundred Only	Per Kilogram	35048.00
4	Charge Rate inclusive toll tax, GST and any other taxes imposed by the government. Providing and fixing 0.60mm (sixty millimeter) thick pre-painted steel sheet (IS marked Z-120) of TATA Durashine/ RMP organic coating of 20 (Twenty) microns over 5 (Five) microns primer coating of back coat of polyester of 5 (Five) microns over 5 (Five) microns primer coating including fixing with pre-painted iron J or L hooks, bolts and nuts 6mm (six millimeter) diameters with pre-painted limpet and rubber washers complete with all accessories as required as per specification, drawing and design including carriage of materials with in all leads, lifts and other incidentals as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	36.30	1500.00	Rupees One Thousand Five Hundred Only	Per Square metre	54450.00
5	Providing ridges or nips 0.63 mm thick (zero decimal six three millimeter) over all in plain G.I. sheet with galvanised iron J or L hooks, bolts and nuts 8mm dia G.I. Limpet and bitumen washers complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	8.25	750.00	Rupees Seven Hundred Fifty Only	Per Running meter	6188.00

6	Painting two coats(excluding priming costs) on new steel and other metal surfaces with enamel paint to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters complete as per PWD Specification. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	19.65	60.00	Rupees Sixty Only	Per Square metre	1179.00
	Quoted rates percentage in figures			Total :-		99726.00
	Quoted rates percentage in words					

Draft schedule of Quantity approved for Rs. 99726/- only

Executive Engineer
Bhawana Division
HP PWD Bhawana

[Signature]

Draft Schedule of Quantity

Name of Work :- Restoration of rain damage on Kiarwan Panhar road Km 0/00 to 3/000 (SH:- C/O Edge Wall at Rd 1/800 to 1/829.40).

Estimated Cost :-Rs. 99,982/-
Earnest Money :-Rs. 2000/-

Time Limit :- Three Months

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.23	250.00	Rupees Nineteen point five zero only	Per Cubic metre	3308.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and M.O.R.D. technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.52	4950.00	Rupees Nineteen point five zero only	Per Cubic metre	91674.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- In-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	20.00	250.00	Rupees Nineteen point five zero only	Each	5000.00
Total :-						99982.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Draft schedule of quantity approved for B. 99982/- fully.

Executive Engineer
Bhawanji Division
HP PWD Bhawanji

Schedule of quantity.

Name of Work :- Restoration of rain damage on Panthehar Garla Dal road Km. 0/000 to 2/300 & Rada Mat Badain Road Km. 0/000 to 2/000 Boda
Mandap Nural road Km. 0/000 to 2/000. (Sulih Section). (SW. - Painting & Writing on Bridges, Bridges Pedestal, Rain Shelter, Boards, and
Alometer stones etc.)

Estimated Cost :- Rs. 98,876/-
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	143.99	6.00	Rupees Nineteen point five zero only	Per Square Metre	864.00
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	28.08	60.00	Rupees Nineteen point five zero only	Per Square Metre	1625.00
3	Applying priming coat on new concrete/ masonry/ asbestos cement plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand appearing as required with ready mixed primer including carriage of materials within all leads, lifts, and other incidentals as per the direction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	115.91	50.00	Rupees Nineteen point five zero only	Per Square Metre	5736.00
4	Finishing wall with weather proof exterior emulsion of Asian paint/ Nerolac Suraksha paint/ Berger paint/Dulux paint of approved brand and manufacture and of required shade on undecorated wall surfaces. (Two or more coats) to give an even shade after thoroughly brushing the surface to remove all dirt, dust and remains of loose powdered material including cost and carriage of material with in all leads, lifts and other incidentals as per specifications, approved drawing as per the direction and entire satisfaction of Engineer-In-Charge. Rate is inclusive of sale tax, toll tax, GST and any other taxes imposed by the government.	115.91	95.00	Rupees Nineteen point five zero only	Per Square Metre	11011.00
5	Writing letters or figures on any surface with black japan paint (stops, commas, hyphens and the like not to be measured and paid separately) as per the direction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	28400.00	2.80	Rupees Nineteen point five zero only	Per letter per centimetre height	79520.00
Total :-						98876.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Draft Schedule of Quantity appeared for Rs. 98876/- only

Executive Engineer
Bhawana Division
HP PWD Bhawana

Draft Schedule of Quantity

Estimate of work for the construction of the structure for the purpose of the draft schedule of quantity. The draft schedule of quantity is for the purpose of the draft schedule of quantity. The draft schedule of quantity is for the purpose of the draft schedule of quantity.

Estimated Cost Rs. 99,882/-
 Earnest Money Rs. 20,000/-
 Time Limit - Three Months

Description of Work	Quantity	In Figure		Rate		Unit	Amount
		In Figure	In Words	In Words	In Words		
1. Excavation of the structure for the purpose of the draft schedule of quantity. The draft schedule of quantity is for the purpose of the draft schedule of quantity. The draft schedule of quantity is for the purpose of the draft schedule of quantity.	18.36	5200.00	Rupees Nineteen point five zero only	Per Cubic metre	35472.00		
2. Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V) 20 (H) (one vertical twenty horizontal) towards draining face complete as per drawing and M.O.F.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and sanction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Mahatma toll tax, GST or other taxes imposed by the Government.	9.00	250.00	Rupees Nineteen point five zero only	Each	2250.00		99882.00

Total :-
 Draft Schedule of Quantity approved for Rs. 99,882/- only

Executive Engineer
 Bhawana Division
 HP PWD Bhawana

Schedule of quantity.

Name of Work :- Restoration of rain damage on Marthog Kural Akshaina Mandir road Km. 0/000 to 8/000 & Sulah Kakrain road Km. 0/000 to 3/000. Estimated Cost :- Rs. 98,842/-
(South Section). (SW :- Painting & Writing on Bridges, Bridges Pedestal, Rain Shelter, Boards, and Kilometer stones etc.).
Earnest Money :- Rs. 2000/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	274.72	6.00	Rupees Nineteen point five zero only	Per Square Metre	1648.00
2	Painting two coats (excluding priming coats) on new steel and other metal surfaces with enamel paint brushing to give and even shade including cleaning the surfaces of all dirt dust and other foreign matter enamel paint other than white including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.36	60.00	Rupees Nineteen point five zero only	Per Square Metre	1102.00
3	Applying priming coat on new concrete masonry/ asbestos cement plastered surfaces after and including preparing the surface by thoroughly cleaning oil, grease dirt and other foreign matter sand appearing as required with ready mixed primer including carriage of materials within all leads, lifts, and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	256.36	50.00	Rupees Nineteen point five zero only	Per Square Metre	12818.00
4	Finishing wall with weather proof exterior emulsion of Asian paint/ Nerolac Suraksha paint/ Berger paint/Dulux paint of approved brand and manufacture and of required shade on undecorated wall surfaces (Two or more coats) to give an even shade after thoroughly brushing the surface to remove all dirt, dust and remains of loose powdered material including cost and carriage of material with in all leads, lifts and other incidentals as per specifications, approved drawing as per the direction and entire satisfaction of Engineer-in-Charge. Rate is inclusive of sale tax, toll tax GST and any other taxes imposed by the government.	256.36	95.00	Rupees Nineteen point five zero only	Per Square Metre	24354.00
5	Writing letters or figures on any surface with black Japan paint (stops, commas, hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	21400.00	2.80	Rupees Nineteen point five zero only	Per letter per centimetre height	59920.00
1	Indian (letters/figures)	21400.00	2.80	Rupees Nineteen point five zero only	Per letter per centimetre height	59920.00
Total :-						99842.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Draft Schedule of Quantity approved for B. 99842/20m

Executive Engineer
Bhawanra Division
HP PWD Bhawanra

Schedule of Quantity

Name of Work :- Restoration of rain damages on Duhak to Garhnoon & Badhnoon Kona Lahru road, (Bhagolu da-Ghalla Section), (SW.- C/O Unlined drain & Maintenance of Earthen Shoulder).

Estimate Cost :-Rs. 78,750/-
Earnest Money :-1600 /-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	750.00	42.00	Rupees Forty Two Only	Per Running metre	31500.00
2	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. Rate inclusive toll tax, GST and any other taxes imposed by the government.	1050.00	45.00	Rupees Forty Five Only	Per Square metre	47250.00
Total :-						78750.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Self schedule of quantity approved for Rs. 78750/- only.

Executive Engineer
Bhawarna Division
HP PWD Bhawarna