



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Telephone No:-01782-240075
e-mail:-ee-kum-hp@nic.in

No. PW-KMS-AB-NIT/2026-27- 3869-71

Dated: - 26/08/26

To

✓ The Executive Engineer (IT Cell),
HP, PWD, Shimla-2

Subject: -

Publication of Tender Notice

Enclosed please find herewith the tender of works as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)1/2020 dated 16.07.2021 as the works mentioned in the tender notice are urgent in nature and public interest.

Encl: - Notice Inviting tender &
Schedule of Quantity and certificate.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

Copy to the Superintending Engineer, 11th Circle,
HP.PWD., Rampur Bsr. for information please.

Copy to Drawing Branch in this office.

✓
Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS
CALLED VIDE THIS OFFICE LETTER NO. PW-KMS-AB-NIT/ 2026-
27 3819-68 DATED 26/08/26 ARE URGENT NATURE AND
PUBLIC INTEREST.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed percentage rate tenders are hereby invited by the Executive Engineer, Kumarsain Division, and HP.PWD. Kumarsain from the experienced contractors enlisted with PWD for B&R works, so as to reach in this office on or before **8.09.2026** up to **12:00 PM** and will be opened on same day at **02:00 PM**. in the presence of intending contractors or their authorized representatives who may wish to be present.

The application for issue of tender form shall be received on **7.09.2026** up to **1:00 PM**. The tender form can be had from this office against cash payment (Non-refundable) on **7.09.2026** upto **5:00 PM**.

The earnest money in the shape of National saving certificate/Time deposit receipt of any recognized Bank in H.P. duly pledged in the name of XEN must accompany with each application for obtaining the tender form. The Executive Engineer reserves the right to reject the tenders without assigning any reasons.

- 1 **Name of work:-**R/O R/D on NH-22 Thumb Kandyali Jimmu road Km.0/000 to 8/756 (under PDNA) (SH:-Hiring of Tipper for carriage of removal slips / debries).Estimated Cost:-2,51,640/-(Excluding GST) Earnest Money: 5,050/- Time allowed: -Two Months.
- 2 **Name of work:-**R/O R/D on Slapper Tattapani Suni Luri road Km.103/800 to 120/800 (under PDNA) (SH:-Hiring of Tipper for carriage of removal slips / debries).Estimated Cost:-2,79,600/-(Excluding GST) Earnest Money: 5,600/- Time allowed: -Two Months.
- 3 **Name of work:-**R/O R/D on Kiara Reog road Km.0/000 to 5/360 (under PDNA) (SH:- Hiring of JCB front end loader for removal of slips between Km.0/000 to 5/360).Estimated Cost:-2,34,600/- Earnest Money: 4,700/- Time allowed: -One Month.
- 4 **Name of work:-**R/O R/D on NH-22 Thumb Kandyali Jimmu road Km.0/000 to 8/756 (under PDNA) (SH:- Hiring of JCB front end loader for removal of slips between Km.0/000 to 8/756).Estimated Cost:-2,44,800/-(Excluding GST) Earnest Money: 4,900/- Time allowed: -One Month.
- 5 **Name of work:** R/O R/D on Dudhlidhar to Dakolu road Km.0/000 to 5/435 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 5/435).Estimated Cost:-2,,19,300/-(Excluding GST) Earnest Money: 4,400/- Time allowed: -One Month.
- 6 **Name of work:** R/O R/D on Slapper Tattapani Suni Luri road Km.103/800 to 120/800 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips between Km.103/800 to 120/800). Estimated Cost:-2,14,200/-(Excluding GST) Earnest Money: 4,300/- Time allowed: -One Month.
- 7 **Name of work:** R/O R/D on Kepu Kirti road Km.0/000 to 7/000 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 7/000). Estimated Cost:-2,19,300/-(Excluding GST) Earnest Money: 4,400/- Time allowed: -One Month.
- 8 **Name of work:** R/O R/D on Thanedhar Bhutti Banot Nallah road Km.0/000 to 9/375 under PDNA) (SH:-Hiring of Tipper for carriage of removal slips / debries).Estimated Cost:-2,46,980/-(Excluding GST) Earnest Money: 4,950/- Time allowed: -Two Months.
- 9 **Name of work:** R/O R/D on Oddi Khaneti Kotgarh road Km.0/000 to 21/000 (under PDNA) (SH:- Hiring of JCB front end loader for removal of slips between Km.0/000 to 21/000).Estimated Cost:-2,29,500/-(Excluding GST) Earnest Money: 4,600/- Time allowed: -One Month.
- 10 **Name of work:** R/O R/D on Thanedhar Bhutti Banot Nallah road Km.0/000 to 9/375 under PDNA)(SH:- Hiring of JCB front end loader for removal of slips between Km.0/000 to 9/375).Estimated Cost:-2,24,400/-(Excluding GST) Earnest Money: 4,500/- Time allowed: -One Month.
- 11 **Name of work:-**R/O R/D on Tikkar Aldi Baza road Km.0/000 to 5/090 (under PDNA) (SH: Hiring of JCB front end loader for removal of slips between Km.0/000 to 5/090).Estimated Cost:-2,14,200/-(Excluding GST) Earnest Money: 4,300/- Time allowed: -One Month.
- 12 **Name of work:-**R/O R/D on Nog Kirti road Km.0/000 to 9/165 (under PDNA) (SH: Hiring of JCB front end loader for removal of slips between Km.0/000 to 9/165).Estimated Cost:-3,06,000/-(Excluding GST) Earnest Money: 6,150/- Time allowed: -One Month.
- 13 **Name of work:-**R/O R/D on Kumarsain Pharal road Km.0/000 to 7/645 (under PDNA)(SH:- Hiring of JCB front end loader for removal of slips between Km.0/000 to 7/645).Estimated Cost:-3,06,000/-(Excluding GST) Earnest Money: 6,150/- Time allowed: -One Month.
- 14 **Name of work:-**R/O R/D on link road from Aur to Kalmu Galani Km.0/000 to 2/300(SH:- C/O PCC R/Wall at Rd.0/232.50 to 0/240). Estimated Cost:-2,24,029/-(Excluding GST) Earnest Money: 4,500/- Time allowed: -One Month.

- 15 **Name of work:-**R/O R/D on link road from NH-5 Bhora Gang Hut to Banu Km.0/000 to 0/750 (SH:- C/O PCC R/Wall at Rd.0/528.50 to 0/543.50).Estimated Cost:-3,87,097/- (Excluding GST) Earnest Money: 7,750/- Time allowed: -One Month.
- 16 **Name of work:-**R/O R/D on Tipri to Dhinguli via Chiya Khaltu Harabag Shantibag in GP Zar Km.0/000 to 3/855 (SH:- C/O PCC B/Wall at Rd.2/722 to 2/752).Estimated Cost:-3,49,344/- (Excluding GST) Earnest Money: 7,000/- Time allowed: -One Month.
- 17 **Name of work:** R/O R/D on Thanedhar Bhutti Banot Nallah road Km.0/000 to 9/375 under PDNA) (SH:- ROFD between Km.0/920 to 9/995). Estimated Cost:-3,94,977/- (Excluding GST) Earnest Money: 7900/- Time allowed: -One Month
- 18 **Name of work:-**R/O R/D on Oddi to Upper Ghareothi Km.0/000 to 1/200 (SH:- C/O PCC R/Wall at Rd.0/310 to 0/323).Estimated Cost:-3,01,319/- (Excluding GST) Earnest Money: 6,050/- Time allowed: -One Month.
- 19 **Name of work:-** Restoration of rain damages on Narkanda Thandhar Kotgarh Bithal road Km.0/000 to 44/000 (SH:-Construction of P.C.C Retaining wall at RD. 18/836 to 18/841, 18/857 to 18/861 & P.C.C Breast wall at Rd. 18/655 to 18/668). Estimated Cost:-4,43,718/- (Excluding GST) Earnest Money: 8,900/- Time allowed: -One Month.
- 20 **Name of work:-** Restoration of rain damages on Bharara Kumarsain road Km.0/000 to 1/165 (SH:-Construction of P.C.C Retaining wall at RD. 0/530 to 0/540.80) Under PDNA. Estimated Cost:-4,19,828/- (Excluding GST) Earnest Money: 8,400/- Time allowed: -One Month.
- 21 **Name of work:-**Restoration of rain damages on link road from Malendi to Pichli Ghetti Km. 0/000 to 0/600 (SH:-Construction of P.C.C Retaining wall at RD. 0/305 to 0/316.80).Under PDNA Estimated Cost:-4,31,379/- (Excluding GST) Earnest Money:-8650/- Time allowed:-One Month.

Terms and conditions:-

1. The contractors shall produce their latest registration/renewal of their registration/GST No/EPF No./ PAN No. along with their application.
2. The single/conditional tender will be rejected.
3. The offer shall remain valid up to 75 days.
4. The amount should be within the 5% above.
5. The work should be started within fifteen days from the opening of tender.

Note:- Since the work involves mass concrete. Hence ⁴⁰20mm dia needle vibrator is mandatory at site during concrete pouring

Executive Engineer,
Kumarsain Division
HP.PWD, Kumarsain

No.PW-KMS-AB-N.I.T/2026-27-

3819-68

Dated:-

26/08/20

Copy to the Engineer-in-Chief, HP.PWD., Shimla-2.
Copy to the Deputy Commissioner Shimla, District Shimla (H.P.)
Copy to the Sub-Divisional Officer © Kumarsain, Distt. Shimla (H.P.)
Copy to the Superintending Engineer, XIth Circle, HP.PWD., Rampur.
Copy to Block Development office, Narkanda Distt. Shimla, (H.P.)
Copy to all Assistant Engineers under this Division for information & n.a.
Copy to various contractors for information.
Copy to Notice Board of this office.

Executive Engineer,
Kumarsain Division,
HP.PWD. Kumarsain

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.251640/-

Earnest money:-Rs.5050/-

Time allowed:-Two Months.

Name of work:-Restoration of rain damages on NH-22 Thumb Kandyali Jimmu road Km.0/000 to 8/756 (under PDNA)(SH:-Hiring of Tipper for carriage of removal slips/debries)

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of tipper for carriage of slips/muck including boulders etc. in all leads and lifts as direction of Engineer-in-Charge.	54 Days	4660.00	(Rupees four thousand six hundred sixty only).	Per Day.	251640.00
	Total:-					251640.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
Rs. 2,51,640/- only


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.279600/-

Earnest money:-Rs.5600/-

Time allowed:-Two Months.

Name of work:-Restoration of rain damages on Slapper Tatapani Sunni Luhri road Km.103/800 to 120/800 (under PDNA)(SH:-Hiring of Tipper for carriage of removal slips/debries)

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of tipper for carriage of slips/muck including boulders etc. in all leads and lifts as direction of Engineer-in-Charge.	60 Days	4660.00	(Rupees four thousand six hundred sixty only).	Per Day.	279600.00
	Total:-					279600.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Baragaon Sub-Division,
HP.PWD., Baragaon.

**Draft schedule of quantity approved for
Rs. 2,79,600/- only**

**Executive Engineer,
Kumarsain Division,
HP.PWD Kumarsain.**

DRAFT SCHEDULE OF QUANTITY

26

Estimated cost:-Rs.234600/-

Earnest money:-Rs.4700/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages (in PDNA) on Kiara Reog road Km.0/000 to 5/360 (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 5/360).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compensated to the full extent by him in all respect and in all cases .	230.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	234600.00
	Total:-					234600.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
2,34,600/- only

Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

21

Estimated cost:-Rs.244800/-

Earnest money:-Rs.4900/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages (in PDNA) on NH-22 Thumb Kandyali Jimmu road Km.0/000 to 8/756 (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 8/756).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compensated to the full extent by him in all respect and in all cases .	240.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	244800.00
	Total:-					244800.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
Rs. 2,44,800/- only

Executive Engineer,
Kumarsain Division,
HP.PWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

22

Estimated cost:-Rs.219300/-

Earnest money:-Rs.4400/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on Dudlidhar to Dakolu road Km.0/000 to 5/435 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 5/435).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compensated to the full extent by him in all respect and in all cases .	215.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	219300.00
Total:-						219300.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Baragaon Sub-Division,
HP.PWD., Baragaon.

Draft schedule of quantity approved for
Rs. 2,19,300/- only

Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

23

Estimated cost:-Rs.214200/-

Earnest money:-Rs.4300/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on Slapper Tatanani Sunni Luhri road Km.103/800 to 120/800 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips between Km.103/800 to 120/800).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compansated to the full extent by him in all respect and in all cases .	210.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	214200.00
	Total:-					214200.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Baragaon Sub-Division,
HP.PWD., Baragaon.

Draft schedule of quantity approved for
Rs. 2,14,200/- only


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

24

Estimated cost:-Rs.219300/-

Earnest money:-Rs.4400/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages (in PDNA) on Kepu Kirti road Km.0/000 to 7/000 (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 7/000).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of seviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compensasated to the full extent by him in all respect and in all cases .	215.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	219300.00
Total:-						219300.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
Rs. 2,19,300/- only


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.246980/-

Earnest money:-Rs.4950/-

Time allowed:-Two Months.

Name of work:-Restoration of rain damages on Thanedhar Bhutti Banot Nallah road Km.0/000 to 9/375 (under PDNA)(SH:-Hiring of Tipper for carriage of removal slips/debries)

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of tipper for carriage of slips/muck including boulders etc. in all leads and lifts as direction of Engineer-in-Charge.	53 Days	4660.00	(Rupees four thousand six hundred sixty only).	Per Day.	246980.00
	Total:-					246980.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
Rs. 2,46,980/- only

Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.229500/-

Earnest money:-Rs.4600/-

Time allowed:-One Month.

25

Name of work:-Restoration of rain damages (in PDNA) on Oddi Khaneti Kotgarh road Km.0/000 to 21/000 (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 21/000).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compensasated to the full extent by him in all respect and in all cases .	225.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	229500.00
Total:-						229500.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
Rs. 2,29,500/- only

Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

(26)

Estimated cost:-Rs.224400/-

Earnest money:-Rs.4500/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages (in PDNA) on Thanedhar Bhutti Banot Nallah road Km.0/000 to 9/375 (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 9/375).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compensated to the full extent by him in all respect and in all cases .	220.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	224400.00
	Total:-					224400.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
Rs. 224400/- only

Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

27

Estimated cost:-Rs.214200/-

Earnest money:-Rs.4300/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages (in PDNA) on Tikker Aldi Baza road Km.0/000 to 5/090 (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 5/090).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compensated to the full extent by him in all respect and in all cases .	210.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	214200.00
Total:-						214200.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Assistant Engineer,
Thanedhar Sub-Division,
HP.PWD., Thanedhar.

Draft schedule of quantity approved for
Rs. 2,14,200/- only

Executive Engineer,
Kumarsain Division,
HP.PWD Kumarsain.

DRAFT SCHEDULE OF QUANTITY

28

Estimated cost:-Rs.306000/-

Earnest money:-Rs.6150/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages (in PDNA) on Nog Kirti road Km.0/000 to 9/165 (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 9/165).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of execution and disposal of serviceable / unserviceable material shall be the absolute responsibility of the contractor which shall also be duly compensated to the full extent by him in all respect and in all cases .	300.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	306000.00
Total:-						306000.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.


Assistant Engineer,
Kumarsain Sub-Division,
HP.PWD., Kumarsain.

Draft schedule of quantity approved for
Rs. 3,06,000/- only

Executive Engineer,
Kumarsain Division,
HP.PWD Kumarsain.

29

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.306000/-

Earnest money:-Rs.61500/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on Kumarsain Pharal road Km.0/000 to 7/645 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips between Km.0/000 to 7/645).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the absolute responsibility of the contractor which shall also be duly compensated to the full extent by him in all respect and in all cases .	300.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	306000.00
	Total:-					306000.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.


Assistant Engineer,
Kumarsain Sub-Division,
HP.PWD., Kumarsain.

Draft schedule of quantity approved for
Rs. 3,06,000/- only

Executive Engineer,
Kumarsain Division,
HP.PWD Kumarsain.

30

DRAFT SCHEDULE OF QUANTITY**Estimated cost:-Rs.224029/-****Earnest money:-4500/-****Time allowed:-One month.****Name of work:-Restoration of rain damages on Link road from Aur to Kalmu Galani Km. 0/000 to 2/300 (SH:-Construction of P.C.C. Retaining wall at RD. 0/232.50 to 0/240).**

S. No.	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	15.39 m3	160.00	(Rupees one hundred sixty only).	Per cubic metre.	2462.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	22.95 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	5049.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	51.00 m3	4070.00	(Rupees four thousand seventy only).	Per cubic metre.	207570.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	23 Nos.	270.00	(Rupees two hundred seventy only).	Each.	6210.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	3.38 m3	810.00	(Rupees eight hundred ten only).	Per cubic metre.	2738.00
Total:-						224029.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for
Rs. 2,24,02,91/- only

 Executive Engineer,
 Kumarsain Division,
 H.P.RWD., Kumarsain.

(31)

DRAFT SCHEDULE OF QUANTITY**Estimated cost:-Rs.387097/-****Earnest money:-7750/-****Time allowed:-One month.**

Name of work:-Restoration of rain damages on Link road from NH-5 Bhora Gang Hut to Banu Km. 0/000 to 0/750 (SH:-Construction of P.C.C. Retaining wall at RD. 0/528.50 to 0/543.50).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	31.80 m3	160.00	(Rupees one hundred sixty only).	Per cubic metre.	5088.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	5.25 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	1155.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	88.65 m3	4070.00	(Rupees four thousand seventy only).	Per cubic metre.	360806.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	45 Nos.	270.00	(Rupees two hundred seventy only).	Each.	12150.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	9.75 m3	810.00	(Rupees eight hundred ten only).	Per cubic metre.	7898.00
Total:-						387097.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for Rs. 387097/- only

Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.349344/-

Earnest money:-Rs.7000/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Tipri to Dhinguli Via Chiya Khaltu Harabag Shantibag in G.P. Zar road Km.0/0000 to 3/855 (SH:-Construction of P.C.C. Breast wall at RD. 2/722 to 2/752).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	65.10 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	14322.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	78.60 m3	4070.00	(Rupees four thousand seventy only).	Per cubic metre.	319902.00
3	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	56 Nos	270.00	(Rupees two hundred seventy only).	Each.	15120.00
Total:-						349344.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for Rs. 3,49,344/- only


Executive Engineer,
Kumarsain Division,
H.P.W.D., Kumarsain.

5

DRAFT SCHEDULE OF QUANTITY.

Estimated Cost:-Rs.394977/-

Earnest money:-7900/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Thanedhar Bhutti Banot Nalla road Km.0/000 to 9/375 (SH:-ROFD at RD.0/920 to 0/995) (PDNA).

S.No.	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	5/7 meters wide (5 meters wide in straight and 7 meters on curves) Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth in all height and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock where blasting is prohibited and their intermediate classification of soils including dewatering wherever required, setting out true to the required lines, grades, side, slopes, trimming of bottom and levels as shown on the drawing and as directed by the Engineer.-in Charge. at site according to the HP.PWD specification of 1990 volume-I and sorting out useful and un-useful material and stacking the same in all leads and lifts and transportation of the un serviceable materials for filling in roadways, embankment s for grade improvement and leveling to required grades and then disposing of all surplus excavated materials in acquired width of the road or on approved dumping site /sites through all labours machineries materials, tools, equipments and safety measures and other incidental necessary to complete the work by mechanical means and or labour if any required. The recovery for stones, whether useful or not for 195.45 (One hundred ninety five point forty five) Cubic Meter in all cases at the rate of Rupees 300/- only (Rupees three hundred only) per cubic meter shall be effected on pro rata basis in all circumstances. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1790.71 m3	220.57	(Rupees two hundred twenty and paise fifty seven only).	Per cubic metre.	394977.00
G.Total:-						394977.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

The following materials will be issued from P.W.D Store at Kumarsain.

- | | | |
|---|-----------------------------|------------------------|
| 1 | Gelatine @ Rs.88.53/Per Kg. | } +3% storage charges. |
| 2 | Detonator @ Rs.3.39/Each. | |
| 3 | S.F coil @ Rs.31/Coil | |

Draft schedule of quantity approved for Rs. 3,94,977/- only

Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

33

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.301319/-

Earnest money:-6050/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Link road from Oddi to Upper Ghareothi Km. 0/000 to 1/210 (SH:-Construction of P.C.C. Retaining wall at RD. 0/310 to 0/323).

S. No.	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	20.93 m3	160.00	(Rupees one hundred sixty only).	Per cubic metre.	3349.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	27.82 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	6120.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	68.77 m3	4070.00	(Rupees four thousand seventy only).	Per cubic metre.	279894.00
4	Providing weapholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	24 Nos.	270.00	(Rupees two hundred seventy only).	Each.	6480.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	6.76 m3	810.00	(Rupees eight hundred ten only).	Per cubic metre.	5476.00
Total:-						301319.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves masonry concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for Rs. 3,01,319/- only

Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.443718/-

Earnest money:-8900/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Narkanda Thanedhar Kotgarh Bithal road Km. 0/000 to 44/000 (SH:-Construction of P.C.C. Retaining wall at RD. 18/836 to 18/841, 18/857 to 18/861 & P.C.C. Breast wall at RD. 18/655 to 18/668). PDNA

S. No.	Sub-Head/Items of work.	Quantity.	Rate (excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	15.29 m3	160.00	(Rupees one hundred sixty only).	Per cubic metre.	2446.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	37.81 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	8318.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 P.C.C. Grade M-10 Nominal mix 1:4:8 (1 Cement : 4 Sand : 8 Aggregate) 40mm size crushed stone aggregate complete including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	94.00 m3	4400.00	(Rupees four thousand four hundred only).	Per cubic metre.	413600.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia Finolex or equivalent PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	46 Nos.	270.00	(Rupees two hundred seventy only).	Each.	12420.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	8.56 m3	810.00	(Rupees eight hundred ten only).	Per cubic metre.	6934.00
Total:-						443718.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involved mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for
Rs. 4,43,718/- only

Executive Engineer,
 Kumarsain Division,
 HP PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.419828/-

Earnest money:-8400/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on Bharara Kumarsain road Km. 0/000 to 1/165 (SH:-Construction of P.C.C. Retaining wall at RD. 0/530 to 0/540.80).

S. No.	Sub-Head/Items of work.	Quantity.	Rate (excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	24.08 m3	160.00	(Rupees one hundred sixty only).	Per cubic metre.	3853.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	46.55 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	10241.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 P.C.C. Grade M-10 Nominal mix 1:4:8 (1 Cement : 4 Sand : 8 Aggregate) 40mm size crushed stone aggregate complete including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	89.64 m3	4400.00	(Rupees four thousand four hundred only).	Per cubic metre.	394416.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia Finolex or equivalent PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	28 Nos.	270.00	(Rupees two hundred seventy only).	Each.	7560.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	4.64 m3	810.00	(Rupees eight hundred ten only).	Per cubic metre.	3758.00
Total:-						419828.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for
Rs. 4,19,828/- only


Executive Engineer,
Kumarsain Division,
H.P.W.D., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.431379/-

Earnest money:-8650/-

Time allowed:-One month.

Name of work:-Restoration of rain damages on link road from Malendi to Pichli Ghatti Km. 0/000 to 0/600 (SH:-Construction of P.C.C. Retaining wall at RD. 0/305 to 0/316.80).

S. No.	Sub-Head/Items of work.	Quantity.	Rate (excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	26.55 m3	160.00	(Rupees one hundred sixty only).	Per cubic metre.	4248.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	30.80 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	6776.00
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203) P.C.C nominal mix 1:5:10 (40mm aggregates) including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	96.29 m3	4070.00	(Rupees four thousand seventy only).	Per cubic metre.	391900.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia Finolex or equivalent PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	30 Nos.	270.00	(Rupees two hundred seventy only).	Each.	8100.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	25.13 m3	810.00	(Rupees eight hundred ten only).	Per cubic metre.	20355.00
Total:-						431379.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for Rs. 4,31,379/- only

Executive Engineer,
Kumarsain Division,
HP PWD., Kumarsain.