

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO-PW-KMS-AB-NIT/-2026-

3995-97

Dated:-

27/09/26

To

The Executive Engineer(IT Cell),
HP.PWD., Shimla-2..

Subject: -

Public of Tender Notice.

Enclosed please find herewith the tender of works as given in the Notice inviting tender for uploading on department website as per notification Pr. Secy.(PW) to the Govt. of Himachal Pradesh letter No.PBW(B)1/2020 dated-16-07-2021 as the works mentioned in the tender notice are urgent in nature and public interest.

Enal:-Notice Inviting tender &

Schedule of Quantity and certificate.


Executive Engineer,
Kumarsain Division,
HPPWD, Kumarsain.

Bsr. For information please.

Copy to the Superintending Engineer, 11th Circle, HPPWD., Rampur

Copy to D/B in this office for information.


Executive Engineer,
Kumarsain Division
HPPWD, Kumarsain

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS CALLED VIDE THIS
OFFICE LETTER NO.PW-KMS-AB-NIT/2026-27 2945-96 DATED
27/1/26 ARE URGENT NATURE AND PUBLIC INTEREST.


Executive Engineer,
Kumarsain Division
HPPWD, Kumarsain

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed percentage rate tenders are hereby invited by the Executive Engineer, Kumarsain Division, and HP.PWD, Kumarsain from the experienced contractors enlisted with PWD for B&R works, so as to reach in this office on or before **07.09.2026** up to **12:00 PM** and will be opened on same day at **02:00 PM**, in the presence of intending contractors or their authorized representatives who may wish to be present.

The application for issue of tender form shall be received on **31.8.2026** up to **1:00 PM**. The tender form can be had from this office against cash payment (Non-refundable) on **31.8.2026** upto **5:00 PM**.


The earnest money in the shape of National saving certificate/Time deposit receipt of any recognized Bank in H.P. duly pledged in the name of XEN must accompany with each application for obtaining the tender form. The Executive Engineer reserves the right to reject the tenders without assigning any reasons.

1. **Name of work:-** Restoration of rain damages on Narkanda Thandhar Kotgarh Bithal road Km 0/000 to 44/000 (SH:- Construction of P.C.C. Retaining wall at Rd. 8/165 to 8/185) PDNA Estimated Cost:-430084/- (Excluding GST) Earnest Money: 8650/- Time allowed: -One Month.
2. **Name of work:-** Construction of link road from Rohanda to Bantiper Km. 0/000 to 3/200 (SH:- Formation cutting 5/7mtr. Wide road in Km. 0/180 to 0/285) Estimated Cost:-422934/- (Excluding GST) Earnest Money:-8500/- Time allowed:-One month..

Terms and conditions:-

1. The contractors shall produce their latest registration/renewal of their registration/GST No/EPF No./ PAN No. along with their application.
2. The single/conditional tender will be rejected.
3. The offer shall remain valid up to 75 days.
4. The amount should be within the 5% above.
5. The work should be started within fifteen days from the opening of tender.

Note:- Since the work involves mass concrete. Hence 40mm dia needle vibrator is mandatory at site during concrete pouring


Executive Engineer,
Kumarsain Division
HP.PWD, Kumarsain


No.PW-KMS-AB-N.I.T/2026-27-

3945-3994

Dated:-

27/08/26

Copy to the Engineer-in-Chief, HP.PWD., Shimla-2.
Copy to the Deputy Commissioner Shimla, District Shimla (H.P.)
Copy to the Sub-Divisional Officer © Kumarsain, Distt. Shimla (H.P.)
Copy to the Superintending Engineer, XIth Circle, HP.PWD., Rampur.
Copy to Block Development office, Narkanda Distt. Shimla, (H.P.)
Copy to all Assistant Engineers under this Division for information & n.a.
Copy to various contractors for information.
Copy to Notice Board of this office.


Executive Engineer,
Kumarsain Division,
HP.PWD, Kumarsain

43

DRAFT SCHEDULE OF QUANTITY**Estimated cost:-Rs.430084/-****Earnest money:-8650/-****Time allowed:-One month.****Name of work:-Restoration of rain damages on Narkanda Thanedhar Kotgarh Bithal road Km. 0/000 to 44/000 (SH:-Construction of P.C.C. Retaining wall at RD. 8/165 to 8/185). PDNA**

S. No.	Sub-Head/Items of work.	Quantity.	Rate (excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Excavation in soil in hill area by manual means/mechanical means including cutting and trimming of side slope and disposing of excavated earth with in all leads and lifts as per drawing and technical specification clause 1603.10 as per direction of the Engineer-in-charge.	12.80 m3	160.00	(Rupees one hundred sixty only).	Per cubic metre.	2048.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	54.80 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	12056.00
3	Providing and laying concrete for plain/reinforced concrete in open foundation complete as per drawing and technical specification clauses 802,803,1202 and 1203 P.C.C. Grade M-10 Nominal mix 1:4:8 (1 Cement : 4 Sand : 8 Aggregate) 40mm size crushed stone aggregate complete including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	90.00 m3	4400.00	(Rupees four thousand four hundred only).	Per cubic metre.	396000.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100mm dia Finolex or equivalent PVC pipe extending through the full width of the structures with slop of 1 (v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	38 Nos.	270.00	(Rupees two hundred seventy only).	Each.	10260.00
5	Back filling behind abutment, retaining wall/breast wall including entire carriage of materials through all modes of transportation with in all leads and lifts as per direction of the Engineer-in-Charge.	12.00 m3	810.00	(Rupees eight hundred ten only).	Per cubic metre.	9720.00
Total:-						430084.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for
430,084/- only


 Executive Engineer,
 Kumarsain Division,
 HP PWD., Kumarsain.

45

DRAFT SCHEDULE OF QUANTITY.

Estimated Cost:-Rs.422934/-

Earnest money:-8500/-

Time allowed:-One month.

Name of work:-Construction of link road from Rohanda to Buntipper Km.0/000 to 3/200 (SH:-Formation cutting 5/7 mtr. wide road in Km.0/180 to 0/285)

S.No.	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	5/7 meters wide (5 meters wide in straight and 7 meters on curves) Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth in all height and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock where blasting is prohibited and their intermediate classification of soils including dewatering wherever required, setting out true to the required lines, grades, side, slopes, trimming of bottom and levels as shown on the drawing and as directed by the Engineer.-in Charge. at site according to the HP.PWD specification of 1990 volume-I and sorting out useful and un-useful material and stacking the same in all leads and lifts and transportation of the un serviceable materials for filling in roadways, embankment s for grade improvement and leveling to required grades and then disposing of all surplus excavated materials in acquired width of the road or on approved dumping site /sites through all labours machineries materials, tools, equipments and safety measures and other incidental necessary to complete the work by mechanical means and or labour if any required. The recovery for stones, whether useful or not for 194.74 (One hundred ninety four point seventy four) Cubic Meter in all cases at the rate of Rupees 300/- only (Rupees three hundred only) per cubic meter shall be effected on pro rata basis in all circumstances. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	2028.75 m3	208.47	(Rupees two hundred eight and paise forty seven only).	Per cubic metre.	422934.00
G.Total:-						422934.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

-The following materials will be issued

from P.W.D Store at Kumarsain.

- | | | |
|---|-----------------------------|------------------------|
| 1 | Gelatine @ Rs.88.53/Per Kg. | } +3% storage charges. |
| 2 | Detonator @ Rs.3.39/Each. | |
| 3 | S.F coil @ Rs.31/Coil | |

Draft schedule of quantity approved for
Rs. 4,22,934/- only

Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.