

Himachal Pradesh  
Public Works Department

No. PWP/Agr. Asstt./Tender/2026/ 7936-51

Dated/ 27-8-26

To

The Chief Engineer (KZ),  
HP.PWD Dharamshala.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per directions received through e-mail dated 22.05.2026 of worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer  
Palampur Division  
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer  
Palampur Division  
HPPWD Palampur

## CERTIFICATE

Certified that the tenders invited vide this office  
NIT No. PWP/ Agr. Asstt/ NIT/ 2026/- 7936-51  
Dated 27/08/26 are urgent in nature and in public interest.

Executive Engineer  
Palampur Division  
HPPWD Palampur

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
'NOTICE INVITING TENDERS'**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **03.09.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 02.09.2026 up to 4.00 P.M and the application for issue of tender form shall be received 01.09.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

| S. No. | Name of work.                                                                                                                                                           | Estimated Cost. | Earnest Money | Time Limit   |
|--------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------|---------------|--------------|
| 1      | Restoration of rain damages on link road to Topo Basti Km 0/00 to 0/350 (SW:- P/L CC Pavement work at RD 0/00 to 0/110 (PDNA-2025)                                      | Rs 4,16,696.00  | Rs. 8,300.00  | Three Months |
| 2      | Restoration of rain damages on link road to Topo Basti Km 0/00 to 0/350 (SW:- P/L CC Pavement work at RD 0/130 to 0/190 & C/o R/Wall at RD 0/00 to 0/012.80 (PDNA-2025) | Rs. 4,20,321.00 | Rs. 8,400.00  | Three Months |
| 3      | Restoration of rain damages on Dharaman Sungal Jadiyara Chatardhar Sagur road Km 0/00 to 4/00 (SW:- P/L WBM G-III and CC Pavement at RD 1/200 to 1/310 (PDNA-2025)      | Rs. 4,20,269.00 | Rs. 8,400.00  | Three Months |
| 4      | Restoration of rain damages on Dharaman Sungal Jadiyara Chatardhar Sagur road Km 0/00 to 4/00 (SW:- P/L WBM G-III and CC Pavement at RD 1/420 to 1/530 (PDNA-2025)      | Rs. 4,19,893.00 | Rs. 8,400.00  | Three Months |
| 5      | Restoration of rain damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- C/o Breast Wall at RD 36/250 to 36/270 (PDNA-2025)            | Rs. 3,99,868.00 | Rs. 8,000.00  | Three Months |
| 6      | Restoration of rain damages damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- C/o Hume Pipe culvert at RD 39/300 (PDNA-2025)        | Rs. 4,22,080.00 | Rs. 8,400.00  | Three Months |

|   |                                                                                                                             |                 |              |              |
|---|-----------------------------------------------------------------------------------------------------------------------------|-----------------|--------------|--------------|
| 7 | Restoration of rain damages on Spedu to Gorat road Km 0/00 to 2/00 (SW:- C/o R/Wall at RD 1/410 to 1/430 (PDNA-2025)        | Rs. 4,22,290.00 | Rs. 8,400.00 | Three Months |
| 8 | Restoration of rain damages on Spedu to Gorat road Km 0/00 to 2/00 (SW:- C/o U-shape drain at RD 1/625 to 1/680 (PDNA-2023) | Rs. 4,23,321.00 | Rs.8,500.00  | Three Months |

**Terms & Conditions-**

**Following documents should accompany the application for tenders.**

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer  
Palampur Division  
HPPWD Palampur

## Schedule of Quantity

Name of work:- Restoration of rain damages on link road to topo Basti Km 0/00 to 0/350 (SH:- P/L CC Pavement work at RD 0/00 to 0/110) (PDNA-2025)

Estimated Cost :- Rs. 4,16,696/-  
Earnest Money :- Rs. 8300/-

Time Limit :- Three Months

| S. No                                     | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity | Rate      |                                                                    | Unit            | Amount<br>Rs.    |
|-------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|--------------------------------------------------------------------|-----------------|------------------|
|                                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          | In figure | In Words                                                           |                 |                  |
| 1                                         | Providing, laying, Wearing 53 to 22.4mm ( Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.                                                                                                                                    | 33.00    | 1949.15   | Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only | Per Cubic metre | 64322.00         |
| 2                                         | Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 66.00    | 5339.00   | Rupees Five Thousand Three Hundred Thirty Nine Only                | Per Cubic metre | 352374.00        |
| <b>Total :-</b>                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |           |                                                                    |                 | <b>416696.00</b> |
| <b>Quoted rates percentage in figures</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |           |                                                                    |                 |                  |
| <b>Quoted rates percentage in words</b>   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |          |           |                                                                    |                 |                  |

Executive Engineer  
Palampur Division  
HP PWD Palampur

## Schedule of Quantity

Estimated Cost :- Rs. 4,20,321/-  
Earnest Money :- Rs. 8400/-  
Time Limit :- Three Months

Name of work:- Restoration of rain damages on link road to topo Basti Km 0/00 to 0/350 (SH:- P/L CC Pavement work at RD 0/130 to 0/190 & C/o R/wall at RD 0/00 to 0/012.80) (PDNA-2025)

| S. No | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Quantity | Rate      |                                                                    | Unit             | Amount<br>Rs. |
|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|--------------------------------------------------------------------|------------------|---------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |          | In figure | In Words                                                           |                  |               |
| 1     | Providing, laying, Wearing 53 to 22.4mm ( Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | 15.75    | 1949.15   | Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only | Per Cubic metre  | 30699.00      |
| 2     | Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                      | 31.50    | 5339.00   | Rupees Five Thousand Three Hundred Thirty Nine Only                | Per Cubic metre  | 168179.00     |
| 3     | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 28.03    | 228.80    | Rupees Two Hundred Twenty Eight And Paise Eighty Only              | Per cubic metre. | 6413.00       |

|          |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |         |                                                                        |                  |           |
|----------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---------|------------------------------------------------------------------------|------------------|-----------|
|          | Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 ( One cement : four sand : eight graded crushed/ broken stone aggregate 40mm ( forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, or other taxes imposed by the Government but excluding GST. | 52.61 | 3813.55 | Rupees Three Thousand Eight Hundred Thirteen And Paise Fifty Five Only | Per Cubic metre  | 200631.00 |
| 5        | Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                     | 24.00 | 220.30  | Rupees Two Hundred Twenty And Paise Thirty Only                        | Each             | 5287.00   |
| 6        | Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                   | 15.36 | 593.20  | Rupees Five Hundred Ninety Three And Paise Twenty Only                 | Per cubic metre. | 9112.00   |
| Total :- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |       |         |                                                                        |                  | 420321.00 |
|          | Quoted rates percentage in figures                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  |       |         |                                                                        |                  |           |
|          | Quoted rates percentage in words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    |       |         |                                                                        |                  |           |

Executive Engineer  
Palampur Division  
HP PWD Palampur

## Schedule of Quantity

Name of work:- Restoration of rain damages on Dhraman Sungal jadiayara chatardhar Sagur road Km 0/00 to 4/00 (SH:- P/L WBM G-III & CC Pavement at RD 1/200 to 1/310) (PDNA-2025)

Estimated Cost :- Rs. 4,20,269/-  
Earnest Money :- Rs. 8400/-  
Time Limit :- Three Months

| S. No                              | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Quantity | Rate      |                                                                         | Unit            | Amount<br>Rs. |
|------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-------------------------------------------------------------------------|-----------------|---------------|
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          | In figure | In Words                                                                |                 |               |
| 1                                  | Providing, laying, Wearing 53 to 22.4mm ( Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 28.67    | 1949.15   | Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only      | Per Cubic metre | 55882.00      |
| 2                                  | Construction of un - reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 (forty three) grade cement or any other type as per Clause 1501 M 30 (thirty) (grade) design mix coarse and fine aggregates conforming to IS: 383 (three hundred eighty three) maximum size of coarse aggregate not exceeding 25 mm, (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing). spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge / culvert and construction joints, admixtures as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification clause 1501 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals.The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 57.33    | 6355.95   | Rupees Six Thousand Three Hundred Fifty Five And Paise Ninety Five Only | Per Cubic metre | 364387.00     |
| Total :-                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |           |                                                                         |                 | 420269.00     |
| Quoted rates percentage in figures |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |           |                                                                         |                 |               |
| Quoted rates percentage in words   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |          |           |                                                                         |                 |               |

Executive Engineer  
Palampur Division  
HP PWD Palampur

## Schedule of Quantity

Name of work:- Restoration of rain damages on Dhraman Sungal jadiayara chatardhar Sagur road Km 0/00 to 4/00 (SH:- P/L WBM G-III & CC Pavement at RD 1/420 to 1/530) (PDNA-2025)

Estimated Cost :- Rs. 4,19,893/-  
Earnest Money :- Rs. 8400/-

Time Limit :- Three Months

| S. No                              | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Quantity | Rate      |                                                                         | Unit            | Amount       |
|------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-------------------------------------------------------------------------|-----------------|--------------|
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          | In figure | In Words                                                                |                 |              |
| 1                                  | Providing, laying, Wearing 53 to 22.4mm ( Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | 28.64    | 1949.15   | Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only      | Per Cubic metre | Rs. 55824.00 |
| 2                                  | Construction of un - reinforced, dowel jointed at expansion and construction joint only, plain cement concrete pavement, thickness as per design, over a prepared sub base, with 43 (forty three) grade cement or any other type as per Clause 1501 M 30 (thirty) (grade) design mix coarse and fine aggregates conforming to IS: 383 (three hundred eighty three) maximum size of coarse aggregate not exceeding 25 mm, (twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 (one hundred twenty five) micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge / culvert and construction joints, admixtures as approved, curing of concrete slabs for 14 (fourteen) days using curing compound (where specified) and water finishing lines and grade as per drawing and MORD Technical specification clause 1501 and as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 57.28    | 6355.95   | Rupees Six Thousand Three Hundred Fifty Five And Paise Ninety Five Only | Per Cubic metre | 364069.00    |
| Total :-                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |           |                                                                         |                 | 419893.00    |
| Quoted rates percentage in figures |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |           |                                                                         |                 |              |
| Quoted rates percentage in words   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |          |           |                                                                         |                 |              |

Executive Engineer  
Palampur Division  
HP PWD Palampur

## Schedule of Quantity

Name of work:- Restoration of rain damages on Dharamshala Yol Dadh Holta Chadlar Sandhole road Km 33/00 to 40/500 (SH:- C/o Breast wall at RD 36/250 to 36/270) (PDNA-2025)

Estimated Cost :- Rs. 3,99,868/-  
Earnest Money :- Rs. 8000/-  
Time Limit :- Three Months

| S. No                              | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Quantity | Rate      |                                                       | Unit             | Amount<br>Rs.    |
|------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-------------------------------------------------------|------------------|------------------|
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          | In figure | In Words                                              |                  |                  |
| 1                                  | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 72.00    | 228.80    | Rupees Two Hundred Twenty Eight And Paise Eighty Only | Per cubic metre. | 16474.00         |
| 2                                  | Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 ( One cement : four sand : eight graded crushed/ broken stone aggregate 40mm ( forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                 | 96.00    | 3856.00   | Rupees Three Thousand Eight Hundred Fifty Six Only    | Per Cubic metre  | 370176.00        |
| 3                                  | Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 60.00    | 220.30    | Rupees Two Hundred Twenty And Paise Thirty Only       | Each             | 13218.00         |
| <b>Total :-</b>                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |           |                                                       |                  | <b>399868.00</b> |
| Quoted rates percentage in figures |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |           |                                                       |                  |                  |
| Quoted rates percentage in words   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |           |                                                       |                  |                  |

Executive Engineer  
Palampur Division  
HP PWD Palampur

## Schedule of Quantity

Name of work:- Restoration of rain damages on Dharamshala Yol Dadh Holta Chadiar Sandhole road Km 33/00 to 40/500 (SH:- C/o Hume pipe culvert at RD 39/300) (PDNA-2025)

Estimated Cost :- Rs. 4,22,080/-  
Earnest Money :- Rs. 8400/-  
Time Limit :- Three Months

| S. No                              | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Quantity | Rate      |                                                                     | Unit              | Amount<br>Rs. |
|------------------------------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|---------------------------------------------------------------------|-------------------|---------------|
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          | In figure | In Words                                                            |                   |               |
| 1                                  | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 144.00   | 228.80    | Rupees Two Hundred Twenty Eight And Paise Eighty Only               | Per cubic metre.  | 32947.00      |
| 2                                  | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 ( One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                         | 11.25    | 3983.00   | Rupees Three Thousand Nine Hundred Eighty Three Only                | Per Cubic metre   | 44809.00      |
| 3                                  | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1: 2 ½ : 5 ( One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetra and the like including the cost of form work as per drawings and M O R D. technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                           | 42.00    | 4745.80   | Rupees Four Thousand Seven Hundred Forty Five And Paise Eighty Only | Per Cubic metre   | 199324.00     |
| 4                                  | Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1: 2 ½ : 5 ( One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetra and the like including the cost of form work as per drawings and M O R D. technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                           | 25.00    | 5800.00   | Rupees Five Thousand Eight Hundred Only                             | Per Running metre | 145000.00     |
| Total :-                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |           |                                                                     |                   | 422080.00     |
| Quoted rates percentage in figures |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |           |                                                                     |                   |               |
| Quoted rates percentage in words   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |          |           |                                                                     |                   |               |

  
 Executive Engineer  
 Palampur Division  
 HP PWD Palampur

# **Schedule of Quantity**

Name of work:- Restoration of rain damages on Spedu to Gorat road Km 0/00 to 2/00 (SH:- C/o R/wall at RD 1/410 to 1/430 ) (PDNA-2026)

Estimated Cost :- Rs. 4,22,290/-  
 Earnest Money :- Rs. 8400/-  
 Time Limit :- Three Months

| S. No | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Quantity                                  | Rate      |                                                                        | Unit             | Amount Rs.       |
|-------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------|-----------|------------------------------------------------------------------------|------------------|------------------|
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                           | In figure | In Words                                                               |                  |                  |
| 1     | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 65.93                                     | 228.80    | Rupees Two Hundred Twenty Eight And Paise Eighty Only                  | Per cubic metre. | 15085.00         |
| 2     | Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 ( One cement : four sand : eight graded crushed/ broken stone aggregate 40mm ( forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                 | 99.79                                     | 3813.55   | Rupees Three Thousand Eight Hundred Thirteen And Paise Fifty Five Only | Per Cubic metre  | 380554.00        |
| 3     | Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | 57.00                                     | 220.30    | Rupees Two Hundred Twenty And Paise Thirty Only                        | Each             | 12557.00         |
| 4     | Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, or other taxes imposed by the Government but excluding GST. Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 23.76                                     | 593.20    | Rupees Five Hundred Ninety Three And Paise Twenty Only                 | Per cubic metre. | 14094.00         |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <b>Total :-</b>                           |           |                                                                        |                  | <b>422290.00</b> |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <b>Quoted rates percentage in figures</b> |           |                                                                        |                  |                  |
|       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | <b>Quoted rates percentage in words</b>   |           |                                                                        |                  |                  |

Executive Engineer  
 Palampur Division  
 HP PWD Palampur

## Schedule of Quantity

Item of work:- Balance work of Restoration of rain damages on Spedu to Gorat road Km 0/00 to 2/00 (SH:- C/O U-shape drain at RD 1/625 to 1/680)  
(PDNA-2023)

Estimated Cost :- Rs. 4,23,321/-  
Earnest Money :- Rs. 8500/-  
Time Limit :- Three Months

| S. No                              | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Quantity | Rate      |                                                        | Unit              | Amount<br>Rs. |
|------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|--------------------------------------------------------|-------------------|---------------|
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          | In figure | In Words                                               |                   |               |
| 1                                  | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST. | 25.03    | 237.30    | Rupees Two Hundred Thirty Seven And Paise Thirty Only  | Per cubic metre.  | 5940.00       |
| 2                                  | Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 ( One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                   | 15.40    | 3983.00   | Rupees Three Thousand Nine Hundred Eighty Three Only   | Per Cubic metre   | 61338.00      |
| 3                                  | Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m ( Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | 1040.00  | 50.85     | Rupees Fifty And Paise Eighty Five Only                | Per Running metre | 52884.00      |
| 4                                  | Construction of embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not exceeding 200mm (Two hundred millimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K.N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per Drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevant clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                          | 603.20   | 228.80    | Rupees Two Hundred Twenty Eight And Paise Eighty Only  | Per Cubic metre   | 138012.00     |
| 5                                  | Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   | 278.40   | 593.20    | Rupees Five Hundred Ninety Three And Paise Twenty Only | Per cubic metre.  | 165147.00     |
| Total :-                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |           |                                                        |                   | 423321.00     |
| Quoted rates percentage in figures |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |           |                                                        |                   |               |
| Quoted rates percentage in words   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |          |           |                                                        |                   |               |

Executive Engineer  
Palampur Division  
HP PWD Palampur