

**Himachal Pradesh
Public Works Department**

PW-SNR-EA-I-Tender/2026-

5727-28

Dated 22.08.2026

To

The Chief Engineer(MZ),
HPPWD, Mandi, Distt. Mandi H.P.

Subject :- Regarding publication of Tender on departmental site.

With reference to the notification No. PWD/ICT Wing/Website dated 22.05.2026 enclosed please find here with the Notice Inviting Tender for publishing in the departmental site.

“Certified that the works mentioned in the Tender Notice are urgent in nature.”

Encl:- As above.


Executive Engineer
Sunder Nagar Division,
HPPWD Sunder Nagar.

Copies forwarded to the following for information, please.

1. The Superintending Engineer, 1st Circle, HP PWD Sunder-Nagar.


Executive Engineer
Sunder Nagar Division,
HPPWD Sunder Nagar.

Himachal Pradesh
Public Works Department

NOTICE INVITING TENDER

Sealed percentage rate tenders on form no. 6 & 8 on behalf of the Governor of H.P. are hereby invited by the Executive Engineer HPPWD Division Sunder Nagar for the works as per details given below from the contractors of appropriately registered in HP PWD and Income Tax Department duly renewed supported with documentary proof so as to reach in this office on 02.09.2026 up to 10-30AM and the same shall be opened on the same day at 11-30AM in the presence of interested contractors or their authorized agents who may be present. The tender form can be had from this office against cash payment (non refundable) up to 01.09.2026 before 11:00 AM. The tender form shall accompany earnest money in the form of time deposit account or saving account at any post-office, bank duly pledged in favor of undersigned.

Telegraphic & conditional tenders without earnest money will not be entertained. The undersigned reserve the right to accept/reject the tender without assigning any reason. The offer to the tender remains valid for 75 days from the date of opening the tender.

Sr. No.	Name of work	Estimated Cost	Earnest money	Time	Cost of Form
1	2	3	4	5	6
1	RRD on Batadi to Kamail road KM 0/0 to 3/200(SH:- ROFD between KM 0/0 to 0/405). Under PDNA.	485317	10000	Three Months	350
2	RRD on Batadi to Kamail road KM 0/0 to 3/200(SH:- ROFD between KM 0/425 to 0/836). Under PDNA.	497313	10000	Three Months	350
3	RRD on Sunder Maloh road Km 0/0 to 5/565(Sh:- P/L Gr.III for correction layer & repair of Pot holes in KM 2/00 to 2/500). Under PDNA.	499223	10000	Two months	350
4.	Balance work on Sehli School to Chahri road KM 0/0 to 15/330(SH:- Earth filling at RD 2/698 to 2/734, C/O Wire crate B/Wall at RD 2/727 to 2/742, 2/707 to 2/732, C/O U-Shape drain at RD 2/745 to 2/775 and P/L WBM-G-I at RD 2/732 to 2/757).	497182	10000	Two Months	350


Executive Engineer
Sunder Nagar Division,
HPPWD Sunder Nagar.

No. PW-SSD/Tender/2026-

5729-5737

Dated 22.08.2026

Copies forwarded to the following for information & necessary action, please.

1. All the Assistant Engineers under Sunder-Nagar Division.
2. Supdt/ Gr.II, DAO, DHD.
3. Notice Board.


Executive Engineer
Sunder Nagar Division,
HPPWD Sunder Nagar.

SCHEDULE OF QUANTITY

Percentage BOQ

Estimate Cost :Rs. 4,85,317/-only

Earnest Money: Rs 10,000/- only

Time : Three Months

Name of work : RRD on Batadi to Kamail road km 0/0 to 3/200 (SH :- ROFD between km 0/00 to 0/405) Under PDNA

S.N.	Sub Head and item of work	Quantity	Rate in		Unit	Amount
			Figure	words		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Enginner-in charge at site according to MORTH technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of trasportation including head load animal load or machnical means alongwith its leveling fine dressing and all labour, machinaries , materials , tools equipments and sefety measures and incidentals necessary to complete the work by all means (if any required) recovery for usefull stone of 195.60 cubic mete @ Rs. 300.00 per cubic mete amounting to Rs. 58,680/- only shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of excution shall be the absolute responsibility of the contrator , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Enginer in charge .	2347.02 cum	206.78	Rupees Two Hundred Six And Paise Seventy Eight Only	Per cubic metre	485317.00
					Total	485317.00

Quoted Percentage in Figure

Quoted Percentage in Words


 Executive Engineer
 Sunder Nagar Division
 HBPWD Sunder Nagar

SCHEDULE OF QUANTITY

Percentage BOQ

Estimate Cost :Rs. 4,97,313/-only

Earnest Money: Rs 10,000/- only

Time : Three Months

Name of work :- RRD on Batadi to Kamail road km 0/0 to 3/200 (SH :- ROFD between km 0/425 to 0/836) Under PDNA

S.N	Sub Head and item of work	Quantity	Rate in		Unit	Amount
			Figure	words		
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required settingout to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Enginner-in charge at site according to MORTH technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of trasportation including head load animal load or machnical means alongwith its leveling fine dressing and all labour, machinaries , materials , tools equipments and sefety measures and incidentals necesary to complete the work by all means (if any required) recovery for usefull stone of 198.48 cubic mete @ Rs. 300.00 per cubic mete amounting to Rs. 59,545/- only shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of excution shall be the absolute responsibility of the contrator , which shall have to be duly compensated by him in all respect including all leada and lifts and materials and as per direction of Engineer in charge .	2412.50 cum	206.14	Rupees Two Hundred Six And Paise Fourteen Only	Per cubic metre	497313.00
					Total	497313.00

Quoted Percentage in Figure

Quoted Percentage in Words

Executive Engineer
Sunder Nagar Division
HPPWD Sunder Nagar

SCHEDULE OF QUANTITY

Percentage BOQ

Estimated Cost: Rs.4,99,223/- only

Earnest Money Rs.10,000/- Only

Time : Two Months

Name of work :- RRD on Sundernagar Maloh km 0/0 to 5/565 (SH:- P/L Gr.-III for correction layer and Repair of Pot holes in km 2/00 to 2/500) UNDER PDNA

S.No	Description of items	Quantity	Rate		Unit	Amount
			in figure	in word		
1	Providing and laying spreading and compacting crushed stone aggregate of specific sizes to water bound macadam specification including spreading and rolling with smooth wheel roller 80-100 KN in stages to proper grade and camber applying /binding materials to fill up the interstices of course aggregate watering and compacting to the required density grading III as per technical specification clause 405. including all leads , lifts of material and other incidentals .	12.39	2750.00	Rupees Two Thousand Seven Hundred Fifty Only	Per cubic metre	34073.00
2	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2,503 and 508.1. including all leads , lifts of material and other incidentals .	1500.00	310.10	Rupees Three Hundred Ten And Paise Ten Only	Per Square metre	465150.00
					Total	499223.00
Quoted Percentage in Figure						
Quoted Percentage in Words						

Executive Engineer

Sunder Nagar Division

HPPWD Sunder Nagar

Ar

4

SCHEDULE OF QUANTITY

Percentage BOQ

Estimate Cost: Rs. 4,97,182/- only

Earnest Money: Rs 10,000/- only

Time : Two Month

Name of Work:- Balance work on Sehli school to Chahri road km 0/0 to 15/330 (SH:- Earth filling at RD. 2/698 to 2/734 ,C/o wire crate B/wall at RD. 2/727 to 2/742, 2/707 to 2/732, C/o U-shape drain at 2/745 to 2/775 and P/L WBM - G-1 at RD. 2/732 to 2/757) PDNA

S. No.	Sub Head and item of work	Qyt.	Rate in		Unit	Amount
			Figure	Word		
1	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for road work within all leads , lifts and carriage of materials and other incidentals .	22.65	280.20	Rupees Two Hundred Eighty And Paise Twenty Only	per Cubic metre	6347.00
2	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of any kilometre also including ramming and watering of the earth in layers not exceeding any centimetre in trenches, plinth, sides of foundation etc. complete within all leads , lifts and carriage of materials and other incidentals .	373.68	385.10	Rupees Three Hundred Eighty Five And Paise Ten Only	per Cubic metre	143904.00
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter dia) G.I wire conforming to IS: 280 and IS: 4826 in 100mm x 100 (one hundred in to one hundred millimeters) in mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilo gram) each as per drawing including all leads , lifts of material and technical specification clause 1301. within all leads , lifts and carriage of materials and other incidentals .	100.80	2950.10	Rupees Two Thousand Nine Hundred Fifty And Paise Ten Only	per Cubic metre	297370.00
4	Plain cement concrete 1:3:6 (one cement : three coarse sand :six graded stone aggregate 20 mm (twenty millimetre) nominal size) nominal mix in foundation with crushed stone aggregate 40 mm nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days.including carriage of materials with in all leads, lifts and other incidentals.	5.94	4610.15	Rupees Four Thousand Six Hundred Ten And Paise Fifteen Only	per Cubic metre	27384.00

5	Providing , Laying , spreading and compacting stone aggregates of specific sizes 90 to 40 mm (ninety three to forty millimetre) to water bound macadam specification including spreading in uniform thickness, hand packing , rolling with three wheel 80-100 kN static roller in stages to proper grade and camber , applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate , watering and compacting to the required density Grading -I as per Technical specification Clause 405 (By manual , means .) including all leads , lifts of material and other incidentals.	8.80	2520.10	Rupees Two Thousand Five Hundred Twenty And Paise Ten Only	per Cubic metre	22177.00
					Total	497182.00

Quoted Percentage in Figure

Quoted Percentage in Words