

OFFICE OF THE EXECUTIVE ENGINEER
BANGANA DIVISION HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT BANGANA

No:- PW-BGN-CB/T-1/2026-27-
To

4570-78

Dated:- 25-08-26

The Chief Engineer (HZ),
HPPWD, Hamirpur
ce-ham-hp@nic.in.

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender. As per Notification Pr. Secy (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)A(3)1/2020 dated Shimla-2 the 16th July, 2021 as the works mentioned in the tender Notice are of urgent nature and in public interest, the same may be uploaded on the departmental website.

DA/- Notice Inviting Tender/Scheduled of Quantity
And "A" Certificate.


Executive Engineer
Bangana Division
HPPWD Bangana.

Copy forwarded with its enclosures for information to:-

1. The Engineer-in-Chief, H.P.P.W.D., Shimla-2.
2. The Superintending Engineer, 15th Circle, HPPWD, Una.
3. The Assistant Engineer, Sub Division, HPPWD Bangana and Basal.
4. Drawing Branch in this office.
5. Accounts Branch in this office.
6. Supdt of C Branch in this office.
7. Notice Board.


Executive Engineer
Bangana Division
HPPWD Bangana.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

CERTIFICATE.

Certified that the works are of urgent in nature and for larger public interest so there is exigencies/emergency in calling these tenders without press vide this office letter No. PW-BGN/CB/T-1/2026-

27- 4570-78 dated 25/08/2026



Executive Engineer
Bangana Division
HPPWD Bangana

**OFFICE OF THE EXECUTIVE ENGINEER BANGANA DIVISION HIMACHAL
PRADESH PUBLIC WORKS DEPARTMENT BANGANA**

NOTICE INVITING TENDER.

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Bangana Division HPPWD Bangana on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **01.09.2026 up to 10.30 A.M** and same will be opened on the same day at **11.00 AM** in presence of the interested contractors or their authorized representative. The application will be received in this office on at **29.08.2026 upto 03.00 PM**. The tender form can be had from the office of Executive Engineer Bangana Division HPPWD Bangana on cash payment (Non-refundable) on **31.08.2026** during office Hours **up to 4.00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Bangana Division HPPWD Bangana cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The tender document fee shall also be deposited by the applicant/ contractor with at the time of application in the shape of Demand Draft or Cash (Non-Refundable) otherwise tender documents/ Forms shall not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions. **The contractor should be registered as dealer under GST Act, Valid copy of Registration as required, Copy of PAN Card, EPF failing which no tender form will be issued to him.**

Work/Job No.	Name of Work	Estimated Cost	Earnest Money	Time Period	Eligible of Class
1	R.R.D. on Link Road to Village Jarola Km. 0/000 to 0/090. (Sub Head:- Construction of C.C. Pavement from RD. 0/025 to 0/046)	Rs. 99827.00	Rs. 2000.00	One Month	D
2	R.R.D. on Link Road Village Gehra Kothi Via Garib.Nath Temple Km. 0/000 to 9/920. (SH:- C/O R/Wall in Wire Crate Km. 9/635 to 9/640)	Rs. 95591.00	Rs. 2000.00	One Month	D
3	R.R.D. Various Road in Section Bangana-I under HPPWD Sub Division Bangana. (SH:- Making up Loss Material on Shoulder & C/O Unlined Drain) (Under OFC Head).	Rs. 99965.00	Rs. 2000.00	One Month	D
4	R.R.D. on Link Road to Village Jarola Km. 0/000 to 0/090. (SH:- C/O B/Wall from RD. 0/085 to 0/092.50)	Rs. 99718.00	Rs. 2000.00	One Month	D
5	R.R.D. Various Road in Section Bangana-II Under HPPWD Sub Division Bangana. (SH:- Making up Loss Material on Shoulder & C/O Unlined Drain) Under OFC Head.	Rs. 99897.00	Rs. 2000.00	One Month	D
6	R.R.D. Various Road in Section- Lathiani Under HPPWD Sub Division Bangana. (SH:- Making up Loss Material on Shoulder & C/O Unlined Drain) (Under OFC Head)	Rs. 99948.00	Rs. 2000.00	One Month	D

7	Construction of Link Road to Village Nanawin Abadi Mohmadan from Km. 0/000 to Km. 2/000 Under PMGSY-IV. (SH:- Preparation of Detailed Project Report and CBR Test)	Rs. 92000.00	Rs. 2000.00	One Month	D
8	R.R.D. on Link Road to Village Jarola KM. 0/000 to 0/090. (SH:- C/O C.C. Pavement from RD. 0/046 to 0/068)	Rs. 99768.00	Rs. 2000.00	One Month	D
9	R.R.D. on Link Road Village Gehra Kothi Via Garib Nath Temple Km. 0/000 to 9/920. (SH:- C/O R/Wall in Wire Crate Km. 9/630 to 9/635)	Rs. 95591.00	Rs. 2000.00	One Month	D
10	R.R.D. on Link Road to Village Jarola KM. 0/000 to 0/090. (SH:- C/O C.C. Pavement from RD. 0/068 to 0/090)	Rs. 99925.00	Rs. 2000.00	One Month	D
11	R.R.D. on Link Road Village Gehra Kothi Via Garib Nath Temple Km. 0/000 to 9/920. (SH:- C/O R/Wall in Wire Crate Km. 9/640 to 9/645)	Rs. 95591.00	Rs. 2000.00	One Month	D
12	R.R.D. on Link Road Badoli to Batuhi upto Mohalla Dharwal. (SH:- C/O Embankment in Km. 0/800 to 0/860)	Rs. 99984.00	Rs. 2000.00	One Month	D
13	R.R.D. on Link Road Village Gehra Kothi Via Garib Nath Temple Km. 0/000 to 9/920. (SH:- C/O R/Wall in Wire Crate Km. 9/6450 to 9/650)	Rs. 95591.00	Rs. 2000.00	One Month	D
14	R.R.D. on Link Road Badoli to Batuhi upto Mohalla Dharwal. (SH:- C/O Embankment in Km. 0/860 to 0/900)	Rs. 99590.00	Rs. 2000.00	One Month	D
15	R.R.D. on Una Aghar Mandi Road Km. 19/000 to 39/700. (SH:- C/O U-Shape Drain from RD. 31/900 to 31/915) Under OFC Head.	Rs. 97484.00	Rs. 2000.00	One Month	D
16	R.R.D. Various Road in Section- Bihru Under HPPWD Sub Division Bangana. (SH:- Making up Loss Material on Shoulder & C/O Unlined Drain) Under OFC Head.	Rs. 99940.00	Rs. 2000.00	One Month	D

HIM SUCHANA AVAM JAN SAMPARK.


 Executive Engineer
 Bangana Division
 HPPWD Bangana.
 On behalf of Governor of Himachal Pradesh.

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana					Estimated Cost Rs	99827.00
Name of work:- R.R.D. on link road to Village Jarola km 0/000 to 0/090 (SH: C/o C.C. Pavement from Rd 0/25 to 0/046)					Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-					Time Limit:	One Month
PRICE SCHEDULE						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	22.680	Per cubic metre	93.30	2116.00	Rupees Two Thousand One Hundred & Sixteen Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.030	Per Cubic metre.	3840.00	42355.00	Rupees Forty Two Thousand Three Hundred & Fifty Five Only
3.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.55	Per cubic metre	5247.00	55356.00	Rupees Fifty Five Thousand Three Hundred & Fifty Six Only
Total in Figures					99827.00	Rupees Ninety Nine Thousand Eight Hundred & Twenty Seven Only
Excess (+)						
Less (-)						
Quoted Rate in Figures						

Fuller
 Executive Engineer
 Bangana Division
 HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D. on link road Village Gehra Kothi via Grib Nath Temple Km 0/000 to 9/920 (SH: C/o R/wall in wire crate km 9/635 to 9/640)

Estimated Cost
Rs 95591.00

Earnest Money
Rs 2000.00

Time Limit: One Month

Name of Bidder/ Bidding Firm/ Company :-

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.68	Per cubic metre	332.00	3214.00	Rupees Three Thousand Two Hundred & Fourteen Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	28.45	Per cubic metre	3247.00	92377.00	Rupees Ninety Two Thousand Three Hundred & Seventy Seven Only
Total in Figures					95591.00	Rupees Ninety Five Thousand Five Hundred & Ninety One Only
Excess (+)						
Less (-)						
Quoted Rate in Figures						

Amal Chandra
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Estimated Cost
Rs 99965.00

Name of work:- R.R.D. various road in section-Bangana-I under HPPWD Sub-Division Bangana (SH: Making up loss material on shoulder & C/o unlined drain) Under O.F.C. Head

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	750.00	Per Square Metre	45.00	33750.00	Rupees Thirty Three Thousand Seven Hundred & Fifty Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.40 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	480.00	Per Running Metre	119.00	57120.00	Rupees Fifty Seven Thousand One Hundred & Twenty Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	535.00	Per Square Metre	17.00	9095.00	Rupees Nine Thousand & Ninety Five Only
Total in Figures					99965.00	Rupees Ninety Nine Thousand Nine Hundred & Sixty Five Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Amal Kumar
 Executive Engineer
 Bangana Division
 HP.PWD.Bangana


Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	99718.00
Name of work:- R.R.D. on link road to Village Jarola km 0/000 to 0/090 (SH: C/o B/wall from Rd 0/085 to 0/092.50)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M O R D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	5 22	Per cubic metre	333.00	1738.00	Rupees One Thousand Seven Hundred & Thirty Eight Only
	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802 803 1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government.	22 83	Per Cubic metre.	4133.00	94356.00	Rupees Ninety Four Thousand Three Hundred & Fifty Six Only
2.00	Providing weepholes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeters) dia PVC pipe of make D-PLAST/POLY having working pressure of 4.0 kg (four kilogramme) per square centimeter extending through the full width of the structures with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and MORD 2014 technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer-in-charge including carriage of materials with in all leads and lifts including other incidentals. The rate including octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	12 00	Each	302.00	3624.00	Rupees Three Thousand Six Hundred & Twenty Four Only
Total in Figures					99718.00	Rupees Ninety Nine Thousand Seven Hundred & Eighteen Only
Quoted Rate in Figures					Excess (+)	
					Less (-)	



 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana				Estimated Cost Rs	99897.00
Name of work:- R.R.D. various road in section-Bangana-II under HPPWD Sub-Division Bangana (SH: Making up loss material on shoulder & C/o unlined drain) Under O.F.C Head				Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-				Time Limit:	One Month

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	750.00	Per Square Metre	45.00	33750.00	Rupees Thirty Three Thousand Seven Hundred & Fifty Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.40 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	483.00	Per Running Metre	119.00	57477.00	Rupees Fifty Seven Thousand Four Hundred & Seventy Seven Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	510.00	Per Square Metre	17.00	8670.00	Rupees Eight Thousand Six Hundred & Seventy Only
Total in Figures					99897.00	Rupees Ninety Nine Thousand Eight Hundred & Ninety Seven Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana						Estimated Cost Rs	99948.00
Name of work:- R.R.D. various road in section-Lathiani under HPPWD Sub-Division Bangana (SH: Making up loss material on shoulder & C/o unlined drain) Under O.F.C Head						Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-						Time Limit:	One Month
PRICE SCHEDULE							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words	
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	750.00	Per Square Metre	45.00	33750.00	Rupees Thirty Three Thousand Seven Hundred & Fifty Only	
2.00	Construction of unlined surface drain of average cross-sectional area 0.40 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	482.00	Per Runnin g Metre	119.00	57358.00	Rupees Fifty Seven Thousand Three Hundred & Fifty Eight Only	
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	520.00	Per Square Metre	17.00	8840.00	Rupees Eight Thousand Eight Hundred & Fourty Only	
Total in Figures					99948.00	Rupees Ninety Nine Thousand Nine Hundred & Fourty Eight Only	
Qouted Rate in Figures					Excess (+)		
					Less (-)		


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana		Estimated Cost Rs	9200.00
Name of work:- Construction of Link Road to Village Nanawin Abadi Mohmadan from Km. 0/00 to Km. 2/000 under PMGSY-IV. (SH: Preparation of Detailed Project Report and CBR Test.)		Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-		Time Limit:	One Month

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Preparation of detailed project report which include the following provision as given below:- 1.1 - (a) Topography survey by digital total station with two second accuracy, showing all features on survey plan like trees, culverts, bridges, electric poles, telephone poles, hand pumps, schools, Haditants villages etc., b) Draw cross-sections at 15m (fifteen meter) intervals, L-section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable. c) Preparation of survey plan showing all provision and preparation of detailed project report as per NABARD Guidelines. 1.2 - Site mobilization including Inspection Report Preliminary Project Report including all testreports & coloured Photographs at every 100.00 mtr of road and at prominent points. Repots of 3 days traffic count survey along with soft copy as per the requirement of MoRD/NRIDA. 1.3 - Test Reports must include atleast following field test per km: (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii) Optimum Moisture Content (iv) Maximum Dry Density (v) Grain Size Analysis 1.4. Detailed Project Report and working drawings (Draft Final). 1.5. Technical Sanction as per Approved DPR. 1.6. Bid Documents with BOQ.	2.00	Per Kilometer	4600.00	9200.00	Rupees Nine Thousand Two Hundred Only
Total in Figures					9200.00	Rupees Nine Thousand Two Hundred Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Arslan
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana						Estimated Cost Rs	99768.00
Name of work:- R.R.D. on link road to Village Jarola km 0/000 to 0/090 (SH: C/o C.C. Pavement from Rd 0/46 to 0/068)						Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-						Time Limit:	One Month
PRICE SCHEDULE							
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words	
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax goods service tax, labour cess or other taxes imposed by the Government..	22.050	Per cubic metre	93.30	2057.00	Rupees Two Thousand & Fifty Seven Only	
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand:eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.030	Per Cubic metre.	3840.00	42355.00	Rupees Forty Two Thousand Three Hundred & Fifty Five Only	
3.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental, as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.55	Per cubic metre	5247.00	55356.00	Rupees Fifty Five Thousand Three Hundred & Fifty Six Only	
Total in Figures					99768.00	Rupees Ninety Nine Thousand Seven Hundred & Sixty Eight Only	
Quoted Rate in Figures		Excess (+)					
		Less (-)					

for E.E.
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Excecutive Engineer HPPWD Division Bangana	Estimated Cost Rs	95591.00
Name of work:- R.R.D. on link road Village Gehra Kothi via Grib Nath Temple Km 0/000 to 9/920 (SH: C/o R/wall in wire crate km 9/630 to 9/635)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.68	Per cubic metre	332.00	3214.00	Rupees Three Thousand Two Hundred & Fourteen Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetrr) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	28.45	Per cubic metre	3247.00	92377.00	Rupees Ninety Two Thousand Three Hundred & Seventy Seven Only
Total in Figures					95591.00	Rupees Ninety Five Thousand Five Hundred & Ninety One Only
Qouted Rate in Figures					Excess (+)	
					Less (-)	

And Chen
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Estimated Cost Rs 99925.00

Name of work:- R.R.D. on link road to Village Jarola km 0/000 to 0/090 (SH: C/o C.C. Pavement from Rd 0/60 to 0/090)

Earnest Money Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE						
Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Loosening of the ground upto a level of 300mm below the subgrade level, watered graded and compacted in layers to meet requirement of Tables 300.1 and 300.2 for subgrade construction as per technical Specification Clause 303.5.2 including carriage of materials with in all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, goods service tax, labour cess or other taxes imposed by the Government..	22.050	Per cubic metre	93.30	2057.00	Rupees Two Thousand & Fifty Seven Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete nominal mix 1:4:8 (One cement :four sand: eight graded crushed /broken stone aggregate 20mm (twenty Millimeter) nominal size in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	11.030	Per Cubic metre.	3840.00	42355.00	Rupees Fourty Two Thousand Three Hundred & Fifty Five Only
3.00	Providing and laying mechanically mixed and vibrated reinforced cement concrete of nominal mix 1 : 2 : 4 {one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetres)} nominal size grade M-20 (M-twenty) in substructure as per drawings and M.O.R.D. technical specification for Rural Roads Clauses 802,804,805,806,807,1202 and 1204 including the cost of form work but excluding the cost of reinforcement for reinforced concrete work in bed block , dirt wall and curing complete including hauling of materials in all kinds of leads, lifts and other incidental. as per the entire satisfaction and directions of Engineer-in-Charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	10.58	Per cubic metre	5247.00	55513.00	Rupees Fifty Five Thousand Five Hundred & Thirteen Only
Total in Figures					99925.00	Rupees Ninety Nine Thousand Nine Hundred & Twenty Five Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

And Gaur
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Estimated Cost
Rs 95591.00

Name of work:- R.R.D. on link road Village Gehra Kothi via Grib Nath Temple Km 0/000 to 9/920 (SH: C/o R/wall in wire crate km 9/640 to 9/645)

Earnest Money
Rs 2000.00

Name of Bidder/ Bidding Firm/ Company :-

Time Limit: One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.68	Per cubic metre	332.00	3214.00	Rupees Three Thousand Two Hundred & Fourteen Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	28.45	Per cubic metre	3247.00	92377.00	Rupees Ninety Two Thousand Three Hundred & Seventy Seven Only
Total in Figures					95591.00	Rupees Ninety Five Thousand Five Hundred & Ninety One Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


 Executive Engineer
 Executive Engineer
 Bangana Division
 H.P.P.W.D. Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D on link road Badoli to Batuhi upto Mohalla Dharwal (SH: C/o Embankment in Km 0/800 to 0/860)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost
Rs 99984.00

Earnest Money
Rs 2000.00

Time Limit: One Month

Sr. No.	Description of work	PRICE SCHEDULE					Total Amount in Rs. P.	Total Amount in Words
		Quantity	Unit	Estimated rate in Rs. P.				
1.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 or directions of the Engineer-in-charge including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water wherever required including handling of materials for construction of embankment within all leads and lifts. The rate shall include carriage of machineries, equipment, tolls and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	329.980	Per cubic metre	303.00			99984.00	Rupees Ninety Nine Thousand Nine Hundred & Eighty Four Only
Total in Figures							99984.00	Rupees Ninety Nine Thousand Nine Hundred & Eighty Four Only
Quoted Rate in Figures		Excess (+)						
		Less (-)						

Ad. Chav
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana	Estimated Cost Rs	95591.00
Name of work:- R.R.D. on link road Village Gehra Kothi via Grib Nath Temple Km 0/000 to 9/920 (SH: C/o R/wall in wire crate km 9/645 to 9/650)	Earnest Money Rs	2000.00
Name of Bidder/ Bidding Firm/ Company :-	Time Limit:	One Month

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be signed after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	9.68	Per cubic metre	332.00	3214.00	Rupees Three Thousand Two Hundred & Fourteen Only
2.00	Providing and laying of boulder apron laid in wire crates with 4mm (four millimetre) dia G.I. wire (Galvanized iron wire) confirming to IS:280 (IS : two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty Six) in 100mmx100mm (hundred millimetres into hundred millimetres) mesh (Woven diagonally) including 10% (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme) each and stone spalls as per drawing and M.O.R.D. 2014 technical specification Clause 1301 and as per directions of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals . The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	28.45	Per cubic metre	3247.00	92377.00	Rupees Ninety Two Thousand Three Hundred & Seventy Seven Only
Total in Figures					95591.00	Rupees Ninety Five Thousand Five Hundred & Ninety One Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D on link road Badoli to Batuhi upto Mohalla Dharwal (SH: C/o Embankment in Km 0/860 to 0/900)

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost
Rs 99590.00

Earnest Money
Rs 2000.00

Time Limit: One Month

Sr. No.	Description of work	PRICE SCHEDULE				
		Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Construction of embankment with approved material obtained from borrow pits with a lift upto 1.5 m, transporting to site, spreading, grading to required slope and compacting to meet requirement of Tables 300.1 and 300.2 with a lead upto 1000 m as per Technical Specification Clause 301.5 or directions of the Engineer-in-charge including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water wherever required including handling of materials for construction of embankment within all leads and lifts. The rate shall include carriage of machineries, equipment, tolls and materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-charge. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	328.680	Per cubic metre	303.00	99590.00	Rupees Ninety Nine Thousand Five Hundred & Ninety Only
Total in Figures					99590.00	Rupees Ninety Nine Thousand Five Hundred & Ninety Only
Qouted Rate in Figures		Excess (+)				
		Less (-)				

A. L. Chaur
Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D on Una Aghar Mandi road km 19/000 to 39/700 (SH: C/o U-shape drain from Rd 31/900 to 31/915) Under O.F.C Head

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs 97484.00

Earnest Money Rs 2000.00

Time Limit: One Month

Sr. No.	Description of work	PRICE SCHEDULE				
		Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts and drains etc. in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock, chiselling/wedging out rocks(where blasting is prohibited) as per drawings and M.O.R.D 2014 technical specification clause 305 and as per direction of the Engineer-in-charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts including dressing of sides, bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty milimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-charge including carriage of material within all leads and lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax, goods service tax, labour cess or other taxes imposed by the Government.	18.00	Per cubic metre	364.00	6552.00	Rupees Six Thousand Five Hundred & Fifty Two Only
2.00	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation/ for all type structure complete of plain cement concrete grade M-10 (M-Ten) in or under water and curing complete including pumping or bailing out water,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and technical specification Clause 802.803.1202 and 1203 as per the direction of the Engineer-in- charge including carriage of material with in all leads and lifts and other incidentals .The rate includes octroi, royalty,malkhana ,toll tax,GST,labour cess or other taxes imposed by the Government..	19.43	Per cubic metre	4680.00	90932.00	Rupees Ninety Thousand Nine Hundred & Thirty Two Only
Total in Figures					97484.00	Rupees Ninety Seven Thousand Four Hundred & Eighty Four Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				


Executive Engineer
Bangana Division
HP.PWD.Bangana

Percentage BOQ

Tender Inviting Authority:- Executive Engineer HPPWD Division Bangana

Name of work:- R.R.D. various road in section-Bihru under HPPWD Sub-Division Bangana (SH: Making up loss material on shoulder & C/o unlined drain) Under O.F.C. Head

Name of Bidder/ Bidding Firm/ Company :-

Estimated Cost Rs	99940.00
Earnest Money Rs	2000.00
Time Limit:	One Month

PRICE SCHEDULE

Sr. No.	Description of work	Quantity	Unit	Estimated rate in Rs. P.	Total Amount in Rs. P.	Total Amount in Words
1.00	Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto any lead as per technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	740.00	Per Square Metre	45.00	33300.00	Rupees Thirty Three Thousand Three Hundred Only
2.00	Construction of unlined surface drain of average cross-sectional area 0.40 sqm in Mechanical means ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site, including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	490.00	Per Running Metre	119.00	58310.00	Rupees Fifty Eight Thousand Three Hundred & Ten Only
3.00	Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and technical specification Clause 1903 Including carriage of material within all leads and lifts and other incidental. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	490.00	Per Square Metre	17.00	8330.00	Rupees Eight Thousand Three Hundred & Thirty Only
Total in Figures					99940.00	Rupees Ninety Nine Thousand Nine Hundred & Fourty Only
Quoted Rate in Figures		Excess (+)				
		Less (-)				

Sud Chandra
Executive Engineer
Bangana Division
HP.PWD.Bangana