

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER**

Sealed item rate / percentage rate tender are hereby invited on Form No. 6& 8 by the Executive Engineer, Bhoranj Division, HPPWD, Bhoranj on behalf of the Governor of Himachal Pradesh for the following works from the approved and eligible contractors/ firms of appropriate class enlisted in HPPWD (B&R) whose registration stood registered under the H.P. General Sales tax Act, 1968. As per latest instructions so as to reach and open in his office as per time schedule given below. The offer of the tender will be kept open for 20 days from the date of opening of the tenders. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

1. Date of receipt of Applications for tender form a/w requisite documents:- 01-09-2026 upto 10.00 AM to 11:00 AM.)
2. Date of issue/Sale of tender forms against Cash payment (Non- refundable) 01-09-2026 (3:00 PM to 5.00 PM)
3. Date of receipt of Tender: 02-09-2026 at 10.30 AM.
4. Date of opening of Tender: 02-09-2026 at 11.30 AM.

Sr. No.	Name of Road	Estimated Cost	Earnest Money	Time	Cost of Tender Form	Eligible class of Contractor
1	R/R damage to Kharwar- Mehal via Karah road km 0/00 to 5/00 (SDF/2023/485) (Deposit work) (SH:- C/O R/wall at RD 2/270 to 2/275)	99,563/-	2000/-	One Month	Rs. 350/-	Class-D
2	R/R damages to Residential colony of Police Thana Bhoranj (SDF/2023718) (SH:- C/O Protection wall at RD 0/015 to 0/020)	99,565/-	2000/-	One Month	Rs. 350/-	Class-D
3	Construction/ Repair of link road Dimple Shop Hour to Dohag road km 0/00 to 1/00 (SH:- P/L GSB & Cement concrete pavement at Km. 0/425 to 0/450) (MMGSY)	95,345/-	2000/-	One Month	Rs. 350/-	Class-D
4	R/R damages to Residential colony of Police Thana Bhoranj (SH:- C/O Protection wall at RD 0/10 to 0/015)	99,565/-	2000/-	One Month	Rs. 350/-	Class-D
5	R/R damages under Samirpur Sub Division on link road Amman Patwarian km 0/00 to 2/700 (SH:- Removal of slips, maintenance of earthen shoulder & C/O unlined surface drain at various RDs)	98,423/-	2000/-	One Month	Rs. 350/-	Class-D

6	Construction / Repair of link road Dimple shop Hour to Dohag road km 0/00 to 1/00 (SH:- P/L GSB & Cement concrete pavement at Km 0/450 to 0/475) (MMGSY)	95,345/-	2000/-	One Month	Rs. 350/-	Class-D
7	R/R damages under Samirpur Sub Division HPPWD Samirpur on link road Dimmi Jhamber road Km 0/00 to 2/255 (SH:- Removal of slips, maintenance of earthen shoulder & C/O unlined surface drain at various RDs)	98332/-	2000/-	One Month	Rs. 350/-	Class-D
8	C/O foot over bridge at Bassi Chowk on Hamirpur Jahu road (SH:- Conducting of soil investigation for foot over Bridge)	96,000/-	2000/-	One Month	Rs. 350/-	Class-D
9	R/R damages under Samirpur Sub Division HPPWD Samirpur on link road Chhoun to Dharyara km 0/00 to 2/705 (SH:- Repair and maintenance of earthen shoulder, unlined drain and removal of slips at various RDs)	99,197/-	2000/-	One Month	Rs. 350/-	Class-D
10	C/O foot over bridge at Bassi Chowk on Hamirpur Jahu road (SH:- Providing design for micropile system)	80,000/-	2000/-	One Month	Rs. 350/-	Class-D

The earnest money in the shape of National Saving Certificate/ Time Deposit/ saving account of any post office or FDR of Nationalized Bank duly pledged in the name of undersigned must be accompanied with each tender. The Conditional tender and tender not accompanying the earnest money in the proper mode of deposit with summarily be rejected.

The Tender documents to be sent should have invariably be waxed in sealed cover and in failure of that those will not be entertained.


The Copy of valid enlistment, GST Registration No. Income Tax PAN No. & EPF No. must be attached with application.

TERMS AND CONDITIONS:-

The tender form will be issued to those contractors who have relevant machinery and equipment, the list of which any be attached with their applications (The proof of ownership of machinery/ legal tie up arrangement).

The tender forms will not be issued to those contractors whose performance is not found satisfactory.

The tender form will not be issued to those contractors who have already two works in hand. The earnest money for the above work should be submitted with the application for the purchase of the tender forms. The application received without earnest money shall summarily be rejected.



The conditional/ ambiguous/ telephonic tenders or tender by fax shall not entertain considered in any case.

(i) No Violation of social distancing.

(ii) Mandatorily wearing of face cover by everyone.

(iii) It is further added that any violation of the National directives & guidelines of containment of pandemic Covid-19 is liable for prosecution under section of IPC 1860.

Certified that the above work is of emergent nature in exigency of Public interest.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

For and on behalf of Governor of HP.

No:-PW/BHD/TA/NIT/2025- 8176-8216

Dated:- 24-08-2026

Copy forwarded for information & necessary action to:-

1. The Engineer-in-Chief, Nirman Bhawan Nigam Vihar, HP:PWD., Shimla.
2. The Chief Engineer (HZ) HPPWD., Hamirpur.
3. The Superintending Engineer, 8th Circle HPPWD, Hamirpur.
4. All the Superintending Engineers/ Executive Engineers in HP.PWD.
5. The Deputy Commissioner, Hamirpur.
6. The Tehsildar, Bhoranj.
7. The B. D. O. Bhoranj.
8. The Municipal Committee, Bhoranj.
9. All the Assistant Engineers working under this Division.
10. Accounts Branch/ Drawing Branch/ Notice Board.
11. LokMitra, Bhoranj, Various Contractors/ Firms.

Executive Engineer
Bhoranj Division
HPPWD Bhoranj

SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages to Kharwar - Mehal via Karah road Km 0/00 to 5/00 (SDF/2023/485)(Deposit work)(SH:- C/o R/wall at Rd 2/270 to 2/275).

Sr No	Description of Items	Quantity	Unit	Rate	Time	one month
					Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.88	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.86	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.90	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HP PWD Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damage to Residential colony of Police Thana Bhoranj (SDF/2023 /718) (SH:- C/O Protection wall at Rd 0/015 to 0/020)					Estimated Cost	Rs. 99,565/-
					Earnest Money	Rs. 2000/-
					Time	one month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trendches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailing out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.88	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per directon of Engineer-in-Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.86	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lfts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.90	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.


Executive Engineer
Bhoranj Division
HP PWD Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:-Construction /Repair of Link road Dimple shop Hour to Dohag road km 0/00 to 1/00 (SH:- P/L GSB & cement concrete pavement at km 0/425 to 0/450)(MMGSY)					Estimated Cost	Rs.95,345/-
					Earnest Money	Rs. 2000/-
					Time	1 month
Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder stripping of excess soil formation shoulders surface to achieve the approval level and compacting with plate compactor at one as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	87.50	Per Square Meter			
2	Providing & laying of granular Sub-base by providing close graded material confirming to specification mixing in a mix plant at OMC carriage of mixed material by tipper to work sites for all leads and lift.Spreading in uniform layers of specified thickeners with material confirming to grade-1 and as per direction of Engineer-in-Charge.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Governme	7.62	Per cubic meter			
3	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	7.62	Per Cubic Meter			
4	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.72	Per Cubic Meter			
Total						
Terms and Condition:-						

1.Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 H.P.W.D Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damage to Residential colony of Police Thana Bhoranj (SDF/2023 /718) (SH:- C/O Protection wall at Rd 0/010 to 0/015)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	Rs. 99,565/-
					Earnest Money	Rs. 2000/-
					Time	one month
					Rates in Words	Amount
1	Earth work in excavation for all types of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil , ordinary rock , hard rock, chiseling/wedging out or rock (where blasting is prohibited) as per drawings and construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts includin dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimetre) compacted thickness including shoring an structting and pumping and bailling out water (surface and sub sol water) upto any depth and any quantum of water including cleaning of slush which arise out during dewatering as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	8.88	Per Cubic Meter			
2	Providing and laying mechanically mixed cement concrete 1:5:10 (one cement:five sand :ten graded crushed stone aggregate 40mm (forty millimetre nominal size) and curing complete including cost of form work with M.S. plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water compelete for all heights and depths. In retaining walls /breast walls complete as per drawings and technical specifications Clause 802, 803, 1200 and as per direclon of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	20.86	Per Cubic Meter			
3	Providing weep holes in brick/stone masonry/ plain/ reinforced concrete abutment, wing walls, return walls, retaining walls and breast wall with 110mm(one hundred ten millimeter) dia PVC pipe De-plast/finolex/ vectus pipe having pressure 4kg.per centimeter square. (four kilograme per centimeter square) extending through the full width of the structures with slopes of I(V): 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 as per direction of Engineer- in -Charge including entire carriage of material within all leads and lifts and other incidentals.The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	4.00	Each			
4	Backfilling behind abutment, wing wall and return wall complete as per drawing & technical specification clause 1204.3.8, and as per direction of Engineer-in-Charge. i) Granular material. including entire carriage of material within all leads and lifts and as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	6.90	Per Cubic Meter			
Total						
Terms and Condition:-						
1.Work shall be executed as per PWD specification.						

Executive Engineer
Bhoranj Division
HP PWD Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:- R/R Damages under Samirpur Sub Division HPPWD Samirpur on link road Amman Patwarian km 0/00 to 2/700 (SH:-Removal of Slips, Maintenance of earthen shoulders & C/O Unlined Surface drain at Various RDs).

Estimated Cost
Earnest Money
Time

Rs 98,423/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularity on shoulders to the design level by adding fresh approved soil and compacting leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	660.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Exacavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specifacation clause 307 as directed bythe engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	640.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming og slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per directon of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	196.50	Per cubic metre			
	Total					
	Terms and Condition:-					
	1.Work shall be executed as per PWD specification.					

Executive Engineer
Bhoranj Division
HR PWD Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:-Construction /Repair of Link road Dimple shop Hour to Dohag road km 0/00 to 1/00 (SH:- P/L GSB & cement concrete pavement at km 0/450 to 0/475)(MMGSY)				Estimated Cost	Rs.95,345/-
				Earnest Money	Rs. 2000/-
				Time	1 month
Sr No	Description of Items	Quantity	Unit	Rate	Amount
1	Maintenance of earthen shoulder stripping of excess soil formation shoulders surface to achieve the approval level and compacting with plate compactor at one as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	87.50	Per Square Meter		
2	Providing & laying of granular Sub-base by providing close graded material confirming to specification mixing in a mix plant at OMC carriage of mixed material by tipper to work sites for all leads and lift.Spreading in uniform layers of specified thickeners with material confirming to grade-1 and as per direction of Engineer-in-Charge.including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Governme	7.62	Per cubic meter		
3	Providing concrete for plain/ reinforced concrete in P.C.C. grade M-10(M- ten)nominal mix 1:3:6 (one cement : three sand : six graded crushed stone aggregate) 20mm(twenty millimeters) nominal size in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 as per the direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	7.62	Per Cubic Meter		
4	Providing and laying mechanically mixed cement concrete(M-20)(M-twenty) 1:2:4 one cement : two sand : four graded crushed stone aggregate) 20mm(twenty millimeters) for plain /reinforcement concrete in open foundation complete including cost of form work steel plate complete as per drawings and technical specification Clause 802, 803 1202 & 1204 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax,sale tax or other taxes imposed by the Government.	5.72	Per Cubic Meter		
Total					
Terms and Condition:-					

1.Work shall be executed as per PWD specification.

Executive Engineer
Bhoranj Division
R.PWD Bhoranj



SCHEDULE OF QUANTITY


NAME OF WORK:- R/R Damages under Samirpur Sub Division HPPWD Samirpur on link road Dimmi Jhamber road km 0/00 to 2/255 (SH:-Removal of Slips, Maintenance of earthen shoulders & C/O Unlined Surface drain at Various RDs).

Estimated Cost
Earnest Money
Time

Rs 98,332/-
Rs. 2000/-
2 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	783.00	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	700.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with a lift up to 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	99.60	Per cubic metre			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:- C/O foot over bridge at Bassi Chowk on Hamirpur Jahu road. (SH:- Conducting of soil investigation for foot over Bridge)

Estimated Cost
Earnest Money
Time

Rs 96,000/-
Rs. 2000/-
1 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Drilling of 4 Bores Through in Rock/ boulder/soil/SPT (IS 2131-1981). Total no. of Bore is 4 @ 8 m each bore including laboratory test (IS 2720 Part 4 and other): Modules of sub-grade reaction, modulus of elasticity and Poisson's ratio for horizontal and vertical (for analysis & design of raft foundations). Net safe bearing capacity & Suggested foundation levels for isolated & raft foundation on collected soil sample to obtain design soil classification, grain size distribution including hydrometric analysis, Direct shear test, Triaxial Test organic material content, dry density, optimum moisture content, total unit weight/relative density, atterberg limits, water content, undrained shear test, shear parameters (cohesion, angle of friction), a Adequate no. of soil sample shall be collected to perform the various laboratory tests. Settlement and unstart filling teetered including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Each			
Total						

Terms and Condition:-

1. Work shall be executed as per PWD specification.


Executive Engineer
Bhoranj Division
HP PWD Bhoranj



SCHEDULE OF QUANTITY

NAME OF WORK:- R/R damages under Samirpur Sub Division HPPWD Samirpur on Link road chhown to Dharyara km 0/00 to 2/705 (SH:-Repair and Maintenance of earthen shoulders, Unlined drain and removal of slips at various Rds.).

Estimated Cost
Earnest Money
Time

Rs 99,197/-
Rs. 2000/-
1 Months

Sr No	Description of Items	Quantity	Unit	Rate	Rates in Words	Amount
1	Maintenance of earthen shoulder filling with fresh selected soil/maintenance of earthen shoulder stripping of excess soil making up loss of material irregularities on shoulders to the design level by adding fresh approved soil and compacting with appropriate equipment as per technical specification clause no 1903 including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	517.50	Per square metre			
2	Construction of unlined surface drain of average cross sectional area 0.40 Sqm in soil to specified lines , grades, level and dimensions . Excavated material to be used in embankments with a lift up to 3 Mtr. and lead of 50 Mtr. (average lead 25 m) as per technical specification clause 307 as directed by the engineer in charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	1065.00	Per Running Mtr.			
3	Removal of land slide in hilly area in ordinary rock not required blasting by mechanical means including cutting and trimming of slope and disposal of cut material with in lift upto 1.50 mtr. (one point five zero meter) and leads up to 1000 mtr (one thousand meter) as per technical specification 302.3.5 and 1611 and as per direction of Engineer-in-Charge including entire carriage of material in all lead and lifts and other incidentals . The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	197.81	Per cubic metre			
Total						
Terms and Condition:-						

1. Work shall be executed as per PWD specification.


 Executive Engineer
 Bhoranj Division
 HPPWD Bhoranj



DRAFT SCHEDULE OF QUANTITY

NAME OF WORK:- C/O foot over bridge at Bassi Chowk on Hamirpur Jahu road. (SH:- Providing Design for micropile system)

Sr No	Description of Items	Quantity	Unit	Rate	Estimated Cost	Rs 80,000/-
					Earnest Money	Rs. 2000/-
1	Design of pile foundation suitable to site condition and competent with soil strata. Micropile system including entire carriage of material up to all leads and lifts including entire carriage of material within all leads and lifts and other incidentals . The rates are inclusive octrol, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	4.00	Each	20000.00	Time	1 Months
					Rates in Words	Amount
					Rupees Twenty thousand only	80000.00
Total						80000.00

Terms and Condition:-

1. Work shall be executed as per PWD specification.

DNIT . NO:- 208 for the year 2026- 27 duly approved for Rs 80,000/- (Rupees eighty thousand)only.

Executive Engineer
Bhoranj Division
HP PWD Bhoranj

