

Himachal Pradesh
Public Works Department
NO.PW- JDT-CB-EA-I- /Tender Notice/2026-27-2950-55 Dated:- 18/08/2026
To

✓
The Chief Engineer (HZ),
HPPWD Hamirpur (HP).

SUBJECT: - Publication of Tender Notice.

Sir,

Jai Hind!

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification of Secretary (PW) to the Govt. of HP vide Notification No. PBW (B)A(3)1/2024 Dated 03/01/2025 and further in compliance of the Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICT Wing/website dated 22/5/2026 as the matter is of urgent nature and in public interest, you are requested to kindly get it published on departmental website before 20/08/2026.

DA:-As above.


Executive Engineer,
Jhandutta, Division.
HPPWD, Jhandutta.

On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- As above.


Executive Engineer,
Jhandutta, Division.
HPPWD., Jhandutta.

On behalf of Governor of Himachal Pradesh

E-Mail ID - ecpwd-jha-bll@hp.gov.in**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT****"NOTICE INVITING TENDERS"**

Scaled Item / percentage rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to accept / reject any application / tender or all the tenders without assigning any reasons.

Date of receipt of application for tender form
Date of issue/sale of Tender forms
Date of opening of tender

25/08/2026 upto 12:00 PM
25/08/2026 from 02:00 PM to 04:00 PM
26/08/2026 at 11:00AM

The tender shall be received up to **10:30AM on 26/08/2026** and will be opened on the same day at **11:00AM** in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non-refundable) on **25/08/2026** from 02:00 PM to 04:00 PM.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tender and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to accept or reject the tender without assigning any reasons.

Sr. No	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	R/R Damages on Kathyuin Gujrehra Goacher road Km. 0/0 to 0/900 (SH: Removal of slips from Km. 0/330 to 0/370 and C/o Wire Crate B/wall between RD 0/352.50 to 0/370) Under PDNA 2023.	498660.00	9973.00	350.00	Two Month
2	R/R Damages on Kathyuin Gujrehra Goacher road Km. 0/0 to 0/900 (SH: Removal of slips from Km. 0/460 to 0/520 and C/o Wire Crate B/wall between RD 0/489 to 0/514) Under PDNA 2023.	498212.00	9964.00	350.00	Two Month
3	R/R Damages on Kathyuin Gujrehra Goacher road Km. 0/0 to 0/900 (SH: C/o Wire Crate B/wall and C.C. work between RD 0/515 to 0/535) Under PDNA 2023.	468367.00	9367.00	350.00	Two Month
4	R/R Damages on Kathyuin Gujrehra Goacher road Km. 0/0 to 0/900 (SH: C/o Wire Crate B/wall and C.C. work between RD 0/537 to 0/555) Under PDNA 2023.	482299.00	9646.00	350.00	Two Month
5	R/R Damages on Badgaon to Ree Radoh road Km. 0/0 to 4/0 (SH: C/o Hume Pipe Culvert at RD 3/685 a/w wing wall)	473088.00	9462.00	350.00	Three Month

Certificate:- Certified that tenders are being called for due to exigencies of works (landslide and road sinking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.



2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Jhandutta Division, HP.PWD, Jhandutta and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

... HIM SUCIINA AVAM JAN SAMPARK...


Executive Engineer,
Jhandutta Division,
HP.PWD, Jhandutta.

①

DRAFT SCHEDULE OF QUANTITY						
Name of Work :- R/R Damages on Kathyuin Gujrehra Gochar road km 0/00 to 0/900 (SH:- Removal of slips from km 0/330 to 0/370 and C/o wire crate B/wall between Rd 0/352.50 to 0/370) Under PDNA 2023			Estimated cost:- ₹ 498660.00			
			Earnest Money:- ₹ 9973.00			
			Time allowed:- Two Months			
Sr. No.	Description of iteams	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all left and land as per technical specification 302.3.5 and 1611 including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	1050.45	110.60	✓ INR One hundred ten and Paise six zero only	Per Cubic Meter	116180.00
2	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of materials and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	26.25	✓ 236.70	✓ INR Two hundred thirty six and Paise seven zero only	Per Cubic Meter	6213.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm (One hundred Millimeter) x 100 mm (One hundred Millimeter) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	109.38	3440.00	✓ INR Three thousand four hundred forty and Paise zero zero only	Per Cubic Meter	376267.00
Total:-						498660.00

Total:-

Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta

Estimate No. :- 69
DNIT No. :- 49
Head of account :-



(2)

DRAFT SCHEDULE OF QUANTITY						
Name of Work :- R/R Damages on Kathyuin Gujrehra Gochar road km 0/00 to 0/900 (SH:- Removal of slips from km 0/460 to 0/520 and C/o wire crate B/wall between Rd-0/460 to 0/485) Under PDNA 2023			Estimated cost:- ₹ 498212.00			
			Earnest Money:- ₹ 9964.00			
			Time allowed:- Two Months			
Sr. No.	Description of iteams	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all left and land as per technical specification 302.3.5 and 1611 including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	795.45	110.60	INR One hundred ten and Paise six zero only	Per Cubic Meter	87977.00
2	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of materials and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	30.00	236.70	INR Two hundred thirty six and Paise seven zero only	Per Cubic Meter	7101.00
3	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm (One hundred Millimeter) x 100 mm (One hundred Millimeter) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	117.19	3440.00	INR Three thousand four hundred forty and Paise zero zero only	Per Cubic Meter	403134.00
Total:-						498212.00

Estimate No. :- 50
 DNIT No. :- 50
 Head of account :-

Executive Engineer,
 Jhandutta Division,
 HP.PWD Jhandutta.

Draft Schedule of Quantity approved
 for Rs- 498212/only. Dtd. 25.06.24



3

DRAFT SCHEDULE OF QUANTITY						
Name of Work :- R/R Damages on Kathyuin Gujrehra Gochar road km 0/00 to 0/900 (SH:- C/o wire crate, B/wall and C.C. work between Rd 0/515 to 0/535) Under PDNA 2023			Estimated cost:- ₹ 468367.00			
			Earnest Money:- ₹ 9367.00			
			Time allowed:- Two Months			
Sr. No.	Description of iteams	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual /mechanical means including saturated soil comprising of ordinary soil , soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302,1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber ,embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor / firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and other incidentals necessary to complete the work by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials , within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties , royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 0 Cubic metre @ Rs.300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	650.00	180.25	INR One hundred eighty and Paise two five only	Per Cubic Meter	117163.00
2	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of materials and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	58.54	236.70	INR Two hundred thirty six and Paise seven zero only	Per Cubic Meter	13856.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement isto three coarse sand) isto six graded crushed stone aggregate 40 mm (fourty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax, Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	31.55	5375.00	INR Five Thousand three hundred seventy five and Paise zero zero only	Per Cubic Meter	169581.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm (one hundred millimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	20.00	325.00	INR Three hundred twenty five and Paise zero zero only	Each	6500.00



5	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm (One hundred Millimeter) x 100 mm (One hundred Millimeter) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	46.88	3440.00	INR Three thousand four hundred forty and Paise zero zero only	Per Cubic Meter	161267.00
Total:-						468367.00

*Draft schedule of quantity approved
for Rs. 468,367/- only for 2026-27*

Estimate No. :- 51
DNIT No. :- 51
Head of account :-

[Signature]
Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta.

4

DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/R Damages on Kathyuin Gujrehra Gochar road km 0/00 to 0/900
(SH:- C/o wire crate, B/wall and C.C. work between Rd 0/537 to 0/555) Under PDNA 2023

Estimated cost:- ₹1482399.00

Earnest Money:- ₹9646.00

Time allowed:- Two Months

Sr. No.	Description of items	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Excavation in hilly area in all heights and depths in all kinds of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rocks, hard rocks, chiselling/wedging out of rock (where blasting is prohibited) and other intermediate classification of soil, setting out true to the required line, grade width cutting and trimming of side slopes and level as shown on the drawing and as directed by the Engineer-in-Charge at site according to the M.O.R.D Technical Specification 2014 Clause 302,1603.1,1603.2, and sorting out useful material and stacking the same in all leads and lifts on acquired width of the road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus materials to the approved dumping sites, which shall be managed by the contractor/firm at their own, through all modes of transportation including head load or animals transport or mechanical means, alongwith its levelling fine dressing and carriage by mechanical means and/or labour if required. Any Loss to the public/private property during the execution shall be the absolute responsibility of the Contractor which shall have to be duly compensated by him in all cases including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. The rate including of Goods Service Tax but including labour cess, other levies / taxes, duties, royalties, sale tax, octry, Toll taxes of local bodies and authorities that the contractor will have to pay for the performance of this contract. A recovery of useful stones for 0 Cubic metre @ Rs.300/- per cubic metre shall be done on pro-rata basis from each running bill for this item.	585.00	180.25	INR One hundred eighty and Paise two five only	Per Cubic Meter	105446.00
2	Earth work in excavation for foundation of structures in all type of soil by Manual/mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of materials and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	57.49	236.70	INR Two hundred thirty six and Paise seven zero only	Per Cubic Meter	13608.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement isto three coarse sand) isto six graded crushed stone aggregate 40 mm (fourty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	41.01	5375.00	INR Five Thousand three hundred seventy five and Paise zero zero only	Per Cubic Meter	220429.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, Goods and Service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	26.00	325.00	INR Three hundred twenty five and Paise zero zero only	Each	8450.00

5	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm (One hundred Millimeter) x 100 mm (One hundred Millimeter) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	39.06	3440.00	INR Three thousand four hundred forty and Paise zero zero only	Per Cubic Meter	134366.00
Total:-						482299.00

*Do not schedule quantity approved
for Rs- 482,299/- only. Year 2026-27*

Estimate No. :- 52
DNIT No. :- 52
Head of account :-

[Signature]
Executive Engineer,
Jhandutta Division,
HP PWD Jhandutta.

DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/R Damages on Badgaon Rec-radoh road km 0/00 to 4/000 (SH:- C/o Hume pipe culvert at Rd 3/685 a/w wing wall)

Estimated cost:- ₹ 473088.00

Earnest Money:- ₹ 9462.00

Time allowed:- Three Months

Sr. No.	Description of iteams	Quantity	Rate in		Unit	Amount
			Figure	Words		
1	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of materials and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, Goods and service Tax, building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not entertain any claim whatsoever in this respect of the same.	94.87	236.70	INR Two hundred thirty six and Paise seven zero Only	Per Cubic Meter	22456.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 (one cement isto four coarse sand) isto eight graded crushed stone aggregate 40 mm (forty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	7.36	4838.00	INR four thousand eight hundred thirty eight and Paise zero zero Only	Per Cubic Meter	35608.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:6 (one Cement isto three coarse sand) isto six graded crushed stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax, Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	65.28	5350.20	INR Five thousand three hundredfifty and Paise two zero Only	Per Cubic Meter	349261.00
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	15.78	1230.00	INR One thousand two hundred thirty and paise zero zero only	Per Cubic Meter	19409.00

5	Providing and laying non-pressure NP2 class R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (one cement isto two fine sand) including testing of joints etc. complete : 900 mm (Nine hundred millimeter) dia. R.C.C. pipe including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	10.00	4050.40	INR four thousand fifty and Paise four zero Only	Per running Meter	40504.00
6	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm (one hundered milimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , Goods and Service Tax, building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.00	325.00	INR Three hundred twenty five and Paise zero zero Only	Each	5850.00
Total						473088.00

*Draft Schedule of quantities
approved for Rs. 473088/- only
year 2026-27.*

Estimate No. :- 42
DNIT No. :- 42
Head of account :-

[Signature]
Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta