

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NO.PW- GHD-EA-I- /Tender/2026-

5471-75 Dated:- 20-08-2026

The Chief Engiener (HZ),
HPPWD Hamirpur(HP).

SUBJECT: -

Publication of Tender Notice.

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 and further in compliance of Engineer-in-Chief,HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICTWing/website dt. 22/5/2026 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before 20.08.2026.

DA:-As above.

Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- One No.

Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

***NOTICE INVITING TENDER**

HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under O.the H.P General Sales Tax Act 1968 so as to reach in his office on or before 27-08-2026 up to 11.00 AM(if holiday then next working day), and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 26-08-2026 up to 4.00 P.M and the application for issue of tender form shall be received on 26-08-2026 up to 11.30 AM(if holiday then next working day). The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	Restoration of rain damages on Joginder Nagar Sarkaghat Ghumarwin (JNSG) road km 95/00 to 103/300 (SH:- Providing and laying of wire crates at RD 97/540 to 97/550.50) (Under PDNA Year 2023).	Rs.120921/-	Rs.2500/-	Rs.350/-	One Month
2.	Construction of link road from Dhiman Basti to Crimatorium in village Daloh G.P. Paplah (SH:-C/o Retaining wall at damage portion). (Under VKVNY).	Rs. 168667/-	Rs.3400/-	Rs.350/-	One Month
3.	Repair of Ambulance road from Ballu to Dadhol Kallan towards Harizan Basti in G.P. Dadhol (SH:- Providing and laying Cement concrete pavement at various damage reaches).(Under VKVNY).	Rs.253980/-	Rs.5100/-	Rs.350/-	One Month
4.	Construction of link road Mohra to Lower Mohra House of Jeet Ram Dhiman G.P. Plasla (SH:- Providing and laying Cement concrete pavement on existing metalled surface at various reaches).(Under VKVNY).	Rs.423622/-	Rs.8500/-	Rs.350/-	One Month
5.	Construction of Ambulance road in village Samloh from Hand Pump to Harizan Basti (towards Hill side of road) P.O. Kapahra Tehsil Ghumarwin distt. Bilaspur H.P.(SH:- Providing and laying Cement concrete pavement at RD 0/090 to 0/147.50).(Under VKVNY).	Rs.169471/-	Rs.3400/-	Rs.350/-	One Month
6.	Restoration of rain damages on link road Jol to Domehar km 0/00 to 3/270 (SH:-C/o Retaining wall at km 1/165 to 1/178). (Under PDNA Year 2023).	Rs.420017/-	Rs.8400/-	Rs.350/-	One Month
7.	Restoration of rain damages on link road Jol to Domehar km 0/00 to 3/270 (SH:-C/o Breast wall at km 0/615 to 0/645)(Under PDNA Year 2023).	Rs.422839/-	Rs.8500/-	Rs.350/-	One Month
8.	C/o Link road OBC Basti Amarpur GP Panol km 0/00 to 0/500 (SH: Providing and laying Cement concrete pavement at Various damaged RDs under SDP Deposit.	Rs.137661/-	Rs.2800/-	Rs.350/-	One Month

Certificate of Exigencies:- Certified that tenders are being called for due to exigencies of works (landslide and road singking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division, HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The Contractor/Firm shall quote the rate in percentage only, both in words and in figures. The percentage rate quoted shall be exclusive of GST. The contractor shall ensure that the rate quoted by him is inclusive of all other applicable costs, duties, royalties, labour cess, transportation, overheads, profits, etc., as applicable, but excluding GST.

Executive Engineer
Ghumarwin Division
HP.PWD, Ghumarwin

Draft Schedule of Quantity

Name of Work:- Restoration of rain damages on Joginder Nagar Sarkaghat Ghumarwin (JNSG) road km 95/00 to 103/300 (SH:- Providing and laying of wire crates at RD 97/540 to 97/550.50) .(Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead .All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	36.81	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	7799
1	Providing and laying of boulder apron laid in wire crates with 4 mm (four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 per cent (ten percent) extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and as per MORD technical Specification 2014 ,clause 1301 including carriage of materials with in all leads and other incidentals as per direction of Engineer-in-Charge.The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	40.63	Per cubic metre	2784.19	Rupees Two Thousand Seven Hundred Eighty Four and Nineteen Paise	113122
	Total					120921

Draft Schedule of Quantity No. 121 for the year 2026-27 approved for Rs. 1,20,921/- only

Executive Engineer
Ghumarwin Division
J.P.D. D. Ghumarwin

[Signature]

Draft Schedule of Quantity

Estimated Cost (Excluding GST):- Rs.	1,68,667.00
Earnest Money:- Rs.	3,400.00
Time :-	One month

Name of Work:- Construction of link road from Dhiman Basti to Crimatorium in village Daloh G.P. Paplah (SH:-C/o Retaining wall at damage portion). (Under VKVNY).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead .All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	22.61	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	4790
2	Providing and Laying cement concrete 1:5:10 nominal mix (One Cement is to five Sand is to Ten graded crushed stone aggregate.) 40mm (forty milimetre) nominal size with minimum cement contents 130 kg (One hundred thirty kilogram) per cubic metre and curring complete . including cost of form work for plain /reinforce concrete in retaining walls, breast wall as per drawing and MORD tecnical specification 2014 Clause 800 and 1200 including carriage of material with in all leads and lifts ,shoring and shuttering and curring complete including pumping or bailing out water (surface and sub soil water) up to all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of machinery, material ,tools equipment safety measures and including carriage of materials with in all leads lifts and other incidentals as per direction of Engineer-in-Charge.The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	37.48	Per cubic metre	3813.56	Rupees Three Thousand Eight Hundred Thirteen and Fifty Six Paise	142932
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	20.00	Each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	5508
4	Back filling with granular material behind retaining walls, abutment wing wall and return wall complete as per drawings and MORD technical specification 2014 Clause 1204.3.8 and as per direction of Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	11.04	Per cubic metre	1398.31	Rupees One Thousand Three Hundred Ninety Eight and Thirty One Paise	15437
Total						168667

Draft Schedule of Quantity No. 116 for the year 2026-27 approved for Rs. 1,68,667/- only.

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin

Draft Schedule of Quantity

Estimated Cost (Excluding GST):- Rs.	2,53,980.00
Earnest Money:- Rs.	5,100.00
Time :-	One Month

Name of Work:- Repair of Ambulance road from Ballu to Dadhol Kallan towards Harizan Basti in G.P. Dadhol (SH:- Providing and laying Cement concrete pavement at various damage reaches).(Under VKVNY).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm (fifteen centimetre) deep and disposal of rubbish, all lead and lift up to in All kinds of soil as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	262.91	Per square metre	16.95	Rupees Sixteen and Ninety Five Paise	4456
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre) spread thickness (finished work including materials and labour) as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	39.44	Per cubic metre	1313.56	Rupees One Thousand Three Hundred Thirteen and Fifty Six Paise	51807
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3 (One cement is to one point five coarse sand is to three graded crushed stone aggregate 20 mm (twenty milimetre) nominal size as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	32.86	Per cubic metre	6016.95	Rupees Six Thousand Sixteen and Ninety Five Paise	197717
Total:-						2,53,980.00

Draft Schedule of Quantity No 117. for the
year 2026-27 approved for Rs. 2,53,980/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.

✍

Draft Schedule of Quantity

Estimated Cost
(Excluding GST):- Rs. 4,23,622.00
Earnest Money:- Rs. 8,500.00
Time :- One Month

Name of Work:- Construction of link road Mohra to Lower Mohra House of Jeet Ram Dhiman G.P. Plasla (SH:- Providing and laying Cement concrete pavement on existing metalled surface at various reaches).(Under VKVNY).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Prepared surface of granular base including cleaning of road surface as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	560.40	Per cubic metre	3.81	Rupees Three and Eighty One Paise	2135
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3(One cement is to one point five coarse sand is to three graded crushed stone aggregate 20 mm (twenty milimetre) nominal sizes as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	70.05	Per cubic metre	6016.95	Rupees Six Thousand Sixteen and Ninety Five Paise	421487
Total:-						4,23,622.00

Draft Schedule of Quantity No. 115 for the year 2016-27 approved for Rs. 4,23,622/- only. [Four lakh twenty three thousands Six Hundred twenty two only].

Executive Engineer,
Ghumarwin Division,
H.B. PWD, Ghumarwin.



Draft Schedule of Quantity

Estimated Cost
(Excluding GST):- Rs. 1,69,471.00
Earnest Money:- Rs. 3,400.00
Time :- One Month

Name of Work:- Construction of Ambulance road in village Samloh from Hand Pump to Harizan Basti (towards Hill side of road) P.O. Kapahra Tehsil Ghumarwin distt. Bilaspur H.P.(SH:- Providing and laying Cement concrete pavement at RD 0/090 to 0/147.50).(Under VKVNY).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm (fifteen centimetre) deep and disposal of rubbish, all lead and lift up to in All kinds of soil as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	169.50	Per square metre	16.95	Rupees Sixteen and Ninety Five Paise	2873
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre)spread thickness (finished work including materials and labour)as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	26.33	Per cubic metre	1313.56	Rupees One Thousand Three Hundred Thirteen and Fifty Six Paise	34586
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3(One cement is to one point five coarse sand is to three graded crushed stone aggregate 20 mm (twenty milimetre) nominal sizes as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	21.94	Per cubic metre	6016.95	Rupees Six Thousand Sixteen and Ninety Five Paise	132012
Total:-						1,69,471.00

Draft Schedule of Quantity No. 114 for the year 2026-27 approved for Rs. 1,69,471/- only. [One Lakh Sixty Nine thousands Four Hundred Seventy one only].

Executive Engineer,
Ghumarwin Division,
H.P. PWD, Ghumarwin.

Draft Schedule of Quantity

Estimated Cost 4,20,017.00
(Excluding GST):- Rs.
Earnest Money:- Rs. 8,400.00
Time :- One month

Name of Work:- Restoration of rain damages on link road Iol to Domehar km 0/00 to 3/270 (SH:-C/o Retaining wall at km 1/165 to 1/178). (Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead .All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	33.77	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	7155
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate). 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	87.25	Per Cubic Metre	4237.29	Rupees Four Thousand Two Hundred Thirty Seven and Twenty Nine Paise	369704
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	48.00	Each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	13220
4	Back filling with granular material behind retaining walls, abutment wing wall and return wall complete as per drawings and MORD technical specification 2014 Clause 1204.3.8 and as per direction of Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	21.41	Per cubic metre	1398.31	Rupees One Thousand Three Hundred Ninety Eight and Thirty One Paise	29938
Total						420017

Draft Schedule of Quantity No. 109 for the year 2026-27 approved for Rs. 4,20,017/- only.

Executive Engineer
Chamravat Division
T. K. S. D. Chaudhary

Draft Schedule of Quantity

Draft Schedule of Quantity				Estimated Cost (Excluding GST):- Rs.		4,22,839.00
				Earnest Money:- Rs.		8,500.00
				Time :-		One month
Name of Work:- Restoration of rain damages on link road Iol to Domehar km 0/00 to 3/270 (SH:-C/o Breast wall at km 0/615 to 0/645)(Under PDNA Year 2023).						
Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST) In figure	In words	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead .All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	33.00	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	6991
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate) 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	94.50	Per Cubic Metre	4237.29	Rupees Four Thousand Two Hundred Thirty Seven and Twenty Nine Paise	400424
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614.709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	56.00	Each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	15424
Total						422839

Draft Schedule of Quantity No. 110 - for the year 2026-27 approved for Rs. 4,22,839/- only


 Executive Engineer
 CLERICAL DIVISION
 T.P. D. D. Chaurasia

Draft Schedule of Quantity

Estimated Cost (Excluding GST):- Rs.	1,37,661.00
Earnest Money:- Rs.	2,800.00
Time :-	One month

Item of Work:- Construction of link road OBC Basti Amarpur G.P. Panol km 0/00 to 0/500 (SH:- Providing and laying Cement concrete pavement at various damaged RD's). (Under SDP Deposit).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm (fifteen centimetre) deep and disposal of rubbish, all lead and lift up to in All kinds of soil as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	142.50	Per square metre	16.95	Rupees Sixteen and Ninety Five Paise	2415.00
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre) spread thickness (finished work including materials and labour) as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	21.38	Per cubic metre	1313.56	Rupees One Thousand Three Hundred Thirteen and Fifty Six Paise	28084.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering. All work up to plinth level. 1:1.5:3 (One cement is to one point five coarse sand is to three graded stone aggregate 20 mm (twenty milimetre) nominal size as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	17.81	Per cubic metre	6016.95	Rupees Six Thousand Sixteen and Ninety Five Paise	107162.00
Total						137661.00

Executive Engineer
Ghumarwin Division
HPPWD Ghumarwin