

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-AD-EA-I-Tender-2026-27

5713-23

Dated:- 14/8/26

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **24.08.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **22.08.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **22.08.2026 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1	Construction of link road Thyoda Pul to Jubbar km. 0/00 to 4/500 (SH:- Providing and laying WBM Grade-III and Interlocking Paver blocks tiles at Rd 0/150 to 0/250)Under DMFT/PMKKKY)Job No.2	3,33,738/-	7,000/-	1 Month	350/-
2.	Restoration of rain damages on Chandi Rudal Harsangdhar road km. 0/0 to 8/300(SH:-C/o R/wall at RD 5/930 to 5/945)Under PDNA	3,99,804/-	8,000/-	1 Month	350/-
3	C/o link road Pandal to Jokhati Nerli via Ram Nath Kaushal House to Dev Raja Mandir Km. 0/0 to 0/800(SH:-C/o V-shape drain 0/0 to 0/100, C/o R/wall at Rd 0/450 to 0/470 P/L G.I, G.II & Interlocking Tile at Rd 0/050 to 0/100)Under DMFT	4,99,827/-	10,000/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki.

No: PW-AD-EA-I-Tender-2026-27-

5713-23

Dated:-

14/8/26

Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D.Arki.

Certificate

Certified that the tenders called vide this notice inviting tender for 3(Three) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki.

SCHEDULE OF QUANTITY


Name of road:-C/O link road Thyoda Pul to Jubbar km 0/00 to 4/500 (SH:- Providing and Laying WBM Grade-III and Interlocking Paver blocks tiles at Rd 0/150 to 0/250) .(Under DMFT / PMKKKY) Job No.2						Estimated Cost :- Rs 3,33,738.00	
						Earnest money :- Rs 7,000.00	
						Time: One months	
Sr.No	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-III (G-III) as per Technical Specification Clause 405. including hauling / carriage of all labour equipments and materials to various locations through all modes of transporations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	31.00	cum	1795.30	Rupees One thousand seven Hundred Ninety five and thirty paise Only	Per cubic metre	55654.00
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-in-Charge . 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	310.00	Sqm	781.80	Rupees Seven Hundred seighty one and eighty paise Only	Per Square metre	242358.00
3	Providing and laying mechanically mixed and vibrated reinforced cement concrete nominal mix 1:2:4 (one cement:two : sand:four graded crushed stone aggregate grade M-20 (M-twenty) nominal size mix design to obtain the minimum compressive strength of grade M-20(twenty) open foundation including the cost of form work and reinforcement for reinforced concrete work in deck,slab,beams girders and bressumers etcetra per drawing and MORD technical specification for Roads clause-800,1205.4 & 1205.5 . including hauling / carriage of all labour equipments and materials to various locations through all modes of transporations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge	6.00	Cum	5954.35	Rupees Five thousand Nine Hundred fifty four and Thirty Five paise Only	Per cubic metre	35726.00
						Total	333738.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Percentage Rates Quated in figure

Percentage Rates Quated in words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

Job No 2

SCHEDULE OF QUANTITY					Estimated Cost: -Rs399804/- only	
Name of Work:- Restoration of Rain Damages on Chandi Rudal Harsangdhar road km 0/00 to 8/300 {SH:- C/O R/Wall at RD 5/930 to 5/945} PDNA					Earnest Money :-Rs8000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	39.60	171.40	Rupees one hundred seventy one and paise fourty only	P.Cum.	6787
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	78.30	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	343784
3	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	26.10	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	31406
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	65.00	274.25	Rupees two hundred seventy four and paise twenty five only	Rmt	17826
					Total	399804

Quoted Rate Percentage in Figure:-
Quoted Rate Percentage in Word:-

sd
Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY

Name of Work :- -C/o link road Pandal to Jokhati Nerli via Ram Nath Kaushal House to Dev Raja Mandir Km 0/00 to 0/800.(Sh:- C/O V-shape drain 0/000 to 0/100, C/O R/Wall at Rd 0/450 to 0/470 ,P/L G-I G-II & Interlocking Tile at Rd 0/050 to 0/100)(Under DMFT / PMKKKY	Estimated Cost :- Rs 4,99,827.00
	Earnest money :- Rs 10,000.00
	Time: One months

Sr.N	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1	Earthwork in excavation for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtr, dressing of sides and bottom and backfilling in trenches with excavated suitable material. Ordinary soil up to 3 mtr depth including carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads, lifts and all incidental charges	38.40	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	6582.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in foundation for all type of structure complete of plain concrete nominal mix 1:5:10 (one cement isto five sand isto ten graded stone agreegate 40 mm (forty millimetre) nominal size). including hauling / carriage of all labour equipments and materials to various locations through all modes of transporations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge	55.02	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	241571.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain concrete nominal mix 1:3:6 (one cement isto three sand isto six graded stone agreegate. including hauling / carriage of all labour equipments and materials to various locations through all modes of transporations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge	10.70	Cum	5291.95	Rupees Five thousand two Hundred Ninety one and Ninety Five paise Only	Per cubic metre	56624.00
4	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	6.60	Cum	1203.30	Rupees One thousand two Hundred three and Thirty paise Only	Per cubic metre	7942.00
5	Providing weep holes in brick masonry/stone masonry/plain reinforced concrete abutments, wing walls, return walls with 100 mm(One hundred millimeters) dia PVC pipe extending through the full width of wall/structure with slopes of 1(One) (v): 20(Twenty)(H) towards drawing and technical specification clause 614, 709,1204,3.7 as per the direction of the Engineer-in-charge including hauling / carriage of all labour equipments and materials to various locations through all modes of transporations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge	16.00	Rmt	274.25	Rupees Two Hundred seventy four and Twenty five paise Only	Per running metre	4388.00

6	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub-grade to be paid for separately depending upon the classification of soil complete as per H.P.PWD. Specifications and as per direction of Engineer-in-Charge.	155.00	Sqm	2.20	Rupees Two and twenty paise Only	Per Square metre	341.00
7	Consolidation of sub-grade with power road roller of 8 to 12 (Eight to Twelve) tonns including making the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade till the soil is evenly the densely consolidated and be have as elastic mass complete to make the surface for laying of soling and as per direction of the Engineer-in-Charge as per technical specification MORD 800,1600,300 including carriage of materials with in all leads and lifts and as per direction of Engineer-In-Charge	155.00	Sqm	2.50	Rupees Two and fifty paise Only	Per Square metre	388.00
8	WBM Grading -I :- Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming, stone screening /binding material to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading-1 as per Technical Specification Clause 405. by manual means using stone aggregate 90mm to 40mm (Ninety to forty milimeter size) including carriage of material with in all leads, lifts and as per the direction of Engineer-In-Charge.	15.25	cum	1503.15	Rupees One Hundred five hundred three and fifteen paise Only	Per cubic metre	22923.00
9	WBM Grading -II : Providing, laying, spreading and compacting stone aggregates of specific size to water bound macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100 kN static roller in stages to proper grade and camber, applying and brooming , stone screening /binding materials to fill-up the interstices coarse aggregate, watering and compacting to the required density Grading -II as per Technical Specification Clause 405.by manual means using stone aggregate 63mm to 45mm (Sixty three to forty five milimeter) size including carriage of materials, with in all leads, lifts and as per the direction of Engineer- In-Charge.	11.44	cum	1750.50	Rupees One thousand seven Hundred fifty and fifty paise Only	Per cubic metre	20026.00
10	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-inCharge . 80 mm thick C.C. paver block of M-30 grade with approved color design and pattern including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	155.00	Sqm	781.80	Rupees Seven Hundred seighty one and eighty paise Only	Per Square metre	121179.00

11	Providing and laying mechanically mixed and vibrated reinforced cement concrete nominal mix 1:2:4 (one cement:two : sand:four graded crushed stone aggregate grade M-20 (M-twenty) nominal size mix design to obtain the minimum compressive strength of grade M-20(twenty) open foundation including the cost of form work and reinforcement for reinforced concrete work in deck,slab,beams girders and bressumers etcetra per drawing and MORD technical specification for Roads clause-800,1205.4 & 1205.5 . including hauling / carriage of all labour equipments and materials to various locations through all modes of transporations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge	3.00	Cum	5954.35	Rupees Five thousand Nine Hundred fifty four and Thirty Five paise Only	Per cubic metre	17863.00
						Total	499827.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Percentage Rates Quated in figure

Percentage Rates Quated in words


Executive Engineer
Arki Division (B&R)
HP, PWD. Arki.