



Office of Executive Engineer, Banjar Division ,
Himachal Pradesh Public Works Department Banjar 175123
Phone No.01903-221031 Fax: 01903-221031
No.PW/BD/CB/TA/Ten.Not/2026-8133-72 Dated:- 20/08/2026

To

The Chief Engineer (MZ)
HPPWD. Mandi -175001.

Subject :- Publishing of Notice Inviting Tenders / Advertisement.

Enclosed please find herewith Copies of Notice Inviting Tender for the up-loading on department website as per Notification No. PBW(B) A (3) 8/2025-3000858 Dated 13.11.2025 as direction issued Vide Engineer-in-Chief, HPPWD., Shimla letter No. PWD/ICTWing/Website Dated-22.05.2026 as the works mentioned in the Notice are emergent nature and in the public interest.

Encl:- Notice

Executive Engineer,
Banjar Division ,
H.P.P.W.D. Banjar.

Copy forwarded to followings for information and necessary action.

The Engineer-in-Chief, HPPWD Shimla .
The Superintending Engineer 6th circle HPPWD Kullu.
All the Contractors enlisted in HPPWD.
The Superintendent, DAO ,HDM of this Office.
Notice Board

Executive Engineer,
Banjar Division,
H.P.P.W.D. Banjar

Himachal Pradesh
Public works Department
Notice Inviting Tender

Sealed Percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Banjar Division, HP,PWD, Banjar on behalf of Governor of H.P. from the eligible contractors enlisted in HP,PWD for the following works, so as to reach in this office on or before 02.09.2026 up to 11.00AM and the tender will be opened on the same day at 11.30 A.M in the presence of intending contractors or their authorized representatives. The tender forms can be had from this office against cash payment (non-refundable) up to 01.09.2026 at 4.00 PM. The application for issue of tender forms shall be received up-to 2.00 PM on 01.09.2026.

The Earnest money in the shape of FDR/National Saving Certificate/Time deposit/Saving Account in any of the post office/Saving Bank Account of Nationalized Bank in HP duly pledged in favour of Executive Engineer, Banjar Division, HPPWDBanjar must be accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The offer of tender shall remain open for 75 days from the date of opening. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

All the contractors will have to bring with them attested copy of enlistment/ renewal/ exemption in earnest money. Contractor will be issued the tender forms only when they fulfill the terms and condition of form No. 6 & 8. Contractors should be registered under HP, Sales Tax Act. 1968/EPF/GST.

Sr.No	Description of item	Estimated cost	EMD	Time	Cost of form
1	RRD on Neuli to Shansher road Km.0/0 to 14/00. (SH:- C/O Retaining wall at RD- 8/040 to 8/050) (under PDNA)	431097	8700	Three Months	350/-
2	RRD on Neuli to Shansher road Km.0/0 to 14/00. (SH:- C/O PCC Retaining wall at RD- 9/513 to 9/525) (under PDNA)	441434	8900	Three Months	350/-
3	RRD on Neuli to Shansher road Km.0/0 to 14/00. (SH:- C/O Retaining wall at RD- 8/515 to 8/525) (under PDNA)	431097	8700	Three Months	350/-
4	RRD on Khoraaage to Bhallan road Km.0/0 to 10/862. (SH:-C/O Breast wall at RD-10/660 to 10/670) (under PDNA)	449515	9000	Three Months	350/-
5	RRD on Larji to Sainj road Km.0/0 to 14/0. (SH:-C/OPCC Retaining wall at RD- 8/280 to 8/290) (under PDNA)	441596	8900	Three Months	350/-
6	RRD on Chilyani to Naghar road Km.0/0 to 4/500. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)	410328	8300	Three Months	350/-
7	RRD on Thatibir Sehuli Jouri road Km.0/0 to 9/00. (SH:- C/O WireCrated Retaining wall at RD- 6/880 to 6/908) (under PDNA)	498961	10000	Three Months	350/-
8	RRD on Thatibir Sehuli Jouri road Km.0/0 to 9/00. (SH:- C/O WireCrated Breast wall at RD- 9/220 to 9/245) (under PDNA)	267986	5400	Three Months	350/-
9	RRD on Ghiagi to Sajwad road Km.0/0 to 8/500. (SH:- C/O Breast wall at RD-4/165 to 4/180) (under PDNA)	314686	6300	Three Months	350/-
10	RRD on Thatibir Sehuli to Jouri road 0/0 to 9/500. (SH:- C/O Breast wall at RD-1/660 to 1/675) (under PDNA)	286504	5800	Three Months	350/-
11	RRD on Khundan to Shatyaugi road 0/0 to 6/500. (SH:- C/O Retaining wall at RD- 0/810 to 0/820) (under PDNA)	382418	7700	Three Months	350/-
12	RRD on Bhuinkapul to Kotla road Km.0/0 to 10/800. (SH:- Removal of slips / Land slide at RD-0/0 to 2/315) (under PDNA)	499560	10000	Three Months	350/-
13	RRD on Shalwar to Kanon road Km.0/0 to 5/880. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)	498023	10000	Three Months	350/-
14	RRD on Sainj to Dehuri road Km.0/0 to 7/00. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)(Job-1)	493724	10000	Three Months	350/-
15	RRD on Suchain to Shangar road Km.0/0 to 8/0. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)	499742	10000	Three Months	350/-
16	RRD on Larji to Sainj road Km.0/0 to 14/0. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)	493790	10000	Three Months	350/-
17	RRD on Suchain to Shangar road Km.0/0 to 8/0. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)(Job-1)	499499	10000	Three Months	350/-
18	RRD on Ghiyagi to Sajwar road 0/0 to 8/500. (SH:- C/O PCC Toe wall alongwith wire crated B/ wall at RD-0/185 to 0/200) (under PDNA)	310255	6300	Three Months	350/-

19	RRD on Banjar Bye Pass (Bhumar Nallah to Gheligad) road 0/0 to 1/945). (SH:-Providing and laying Kharanja Stone soling at various reaches) (under PDNA)	225901	4600	Three Months	350/-
20	RRD on Banjar Bye Pass (Bhumar Nallah to Gheligad) road 0/0 to 1/945). (SH:-C/O PCC Toe wall alongwith R/wall at RD-0/166 to 0/177) (under PDNA)	413562	8300	Three Months	350/-
21	RRD on Sidhwan to Godigad road Km. 0/0 to 8/0. (SH:-C/O Breast wall at RD-3/975 to 3/997.50) (under PDNA)	423607	8500	Three Months	350/-
22	RRD on Banjar Bye Pass (Bhumar Nallah to Gheligad) road 0/0 to 1/945). (SH:-Providing and laying Kharanja Stone soling at various reaches) (under PDNA) (Job No.2)	159681	3200	Three Months	350/-
23	RRD on Banjar Bye Pass (Bhumar Nallah to Gheligad) road 0/0 to 1/945). (SH:-C/O Hume Pipe Culvert 900mm dia at RD-1/731) (under PDNA)	366912	7400	Three Months	350/-
24	RRD on Suchain to Shangar road Km.0/0 to 8/0. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)(Job-2)	412455	8300	Three Months	350/-
25	RRD on Suchain to Shangar road Km.0/0 to 8/0. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)(Job-3)	479237	9600	Three Months	350/-
26	RRD on Suchain to Shangar road Km.0/0 to 8/0. (SH:- Removal of slips / Land slide at various reaches) (under PDNA)(Job-4)	480691	9700	Three Months	350/-
27	RRD on Ruar Gharat to Narol road Km. 0/0 to 4/300. (SH:-C/O PCC Breast wall at RD- 0/0 to 0/014) (under PDNA)	392310	8000	Three Months	350/-
28	RRD on Ruar Gharat to Narol road Km. 0/0 to 4/300. (SH:-C/O PCC Breast wall at RD- 0/015 to 0/030) (under PDNA)	395842	8000	Three Months	350/-
29	RRD on Manglore to Panihar road Km. 0/0 to 8/0. (SH:- C/O PCC Toe wall alongwith Retaining wall at RD- 6/135 to 6/148.50) (under PDNA)	429105	8600	Three Months	350/-
30	RRD on Chilladhar Bihar road Km. 0/0 to 4/00. (SH:- Construction of Breast wall at RD- 2/690 to 2/700) (under PDNA)	379582	7600	Three Months	350/-
31	RRD on Manglore to Panihar road Km. 0/0 to 8/0. (SH:- C/O Breast wall at RD- 6/080 to 6/097) (under PDNA)	416385	8400	Three Months	350/-
32	RRD on Thatibir Sehuli to Jouri road 0/0 to 9/500. (SH:- C/O PCC Toe wall alongwith Wire Crated Retaining wall at RD-2/005 to 2/020) (under PDNA)	452113	9100	Three Months	350/-
33	Hiring of Bolero Camper neo for Banjar sub division HPPWD Banjar under Head 2059-S/M	312000	6500	Six Months	350/-

TERMS AND CONDITIONS :-

The contractors/Bidders must quote their PAN/Income Tax Number/Sale Tax number(TIN number)/EPF No./GST No. on the tender along with the copy of the same be attached with the application. The contractor/Firms should attach copy of registration/Renewal with the application, Contractor/Bidder are advised to visit and examine the site where the work are to be carrying out and its surrounding. The contractors/Bidders should quote his rates Both in figure and words. Where there is any discrepancy between the rates in figure and in words. The rates in words will be governed. Contractors/Bidders must inspect the site to ascertain/familiar the site condition accessibility etc. Before quoting the bid/tender. Conditional and telegraphic tenders shall not be accepted and rejected straightway. Tenders received after due date and time will be rejected. Executive Engineer reserves the right to reject or all tenders without assigning any reason. Certified that tender of above works are being called for emergent nature in exigency and in the public interest.

Executive Engineer
Banjar Division,
HP,PWD, Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Neuli to Shensher road Km. 0/00 to 14/00.
(SH) - Construction of Retaining wall at RD.8/040 to 8/050). (Under PDNA).

Estimated Cost:- Rs.431097/- only.
Earnest Money :-Rs.8700/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	18.50	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	6173.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	32.25	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	17215.00
3	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	8.00	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	37972.00
4	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.20	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	25522.00
5	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	29.24	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	146851.00
6	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	42.64	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	179491.00
7	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.38 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	12.60	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	17873.00
Total in words :- Four lac thirty one thousand ninety seven only.							431097.00

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Neuli to Shensher road Km. 0/00 to 14/00.
(SH :-Construction of PCC Retaining wall at RD.9/513 to 9/525),(Under PDNA).

Estimated Cost:- Rs.441434/- only.
Earnest Money :-Rs.8900/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST	Unit		Amount
		3	4		Figures	Words	
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	16.00	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	5338.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects, including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	22.81	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	12176.00
3	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.75	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	22546.00
4	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	61.13	Cubic Metre.	6076.58	Rupees six thousand seven hundred fifty eight paise only.	Per cubic metre.	371461.00
5	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1% (V:20 H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	27.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	11288.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	13.13	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	18625.00
Total in words :-Four lac forty one thousand four hundred thirty four only.							Total:- 441434.00

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Neull to Shensher road Km. 0/00 to 14/00.
(SH :-Construction of Retaining wall at RD.B/515 to 8/525)(Under PDNA).

Estimated Cost:-Rs.431097/- only.
Earnest Money:-Rs.8700/- only.
Time :- Three Month.

Sr. No.	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	18.50	Cubic Metre.	333.65	Rupees three hundred thirty three paise six five only.	Per cubic metre.	6173.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	32.25	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	17215.00
3	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	8.00	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	37972.00
4	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.20	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	25522.00
5	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	29.24	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	146851.00
6	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/carryage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	42.64	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	179491.00
7	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/carryage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	12.60	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	17873.00
Total in words :- Four lac thirty one thousand ninety seven only.							431097.00

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Khora aage to Bhallan road Km. 0/00 to 10/862.
(SH :- Construction of Breast wall at RD.10/660 to 10/670).(Under PDNA).

Estimated Cost:- Rs.449515/- only.
Earnest Money :-Rs.9000/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST	Unit		Amount
		3	4	5	6	7	
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/ carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	547.34	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	182620.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other Incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/ carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	49.21	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	26269.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704, 1202 and 1204, including hauling/ carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	44.12	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	221582.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614.709, 1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	45.55	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	19044.00
		Total in words :- Four lac forty nine thousand five hundred fifteen only.		Total:-		449515.00	

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Larji to Sainj Road Km. 0/00 to 14/00.
(SH :- Construction of PCC Retaining wall at RD.8/280 to 8/290) (Under PDNA).

Estimated Cost:- Rs.441596/- only.
Earnest Money :- Rs.8900/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	12.60	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	4204.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, aggregate and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	24.50	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	13078.00
3	Providing and laying concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.30	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	20410.00
4	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	61.60	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	374317.00
5	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall/return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	27.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	11288.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.38 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	12.90	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	18299.00
						Total:-	441596.00

Total in words :- Four lac forty one thousand five hundred ninety six only.

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Chilyani to Naghar road Km. 0/00 to 4/500.
(SH :- Removal of slips / Land Slide at various reaches).(Under PDNA).

Estimated Cost:- Rs.410328/- only.
Earnest Money :-Rs.8300/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along,the road side as per direction of Engineer-in-Charge.	3092.15	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	8.00 410328.00
Total in words :-Four lac ten thousand three hundred twenty eight only.							410328.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Thatiber Sheuli Jouri road Km. 0/00 to 9/00.
(SH :-Construction of wire crated R/wall at RD. 6/880 to 6/908).(Under PDNA).

Estimated Cost:- Rs.498961/- only.
Earnest Money :-Rs.10000/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST	Unit	Amount
		3	4	Figures		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	65.52	Cubic Metre.	533.81	Per cubic metre.	34975,00
2	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-1 wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	150.20	Cubic Metre.	2843.20	Per cubic metre.	427049,00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/carriage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge.	26.04	Cubic Metre.	1418.49	Per cubic metre.	36937,00
Total in words :-Four lac ninety eight thousand nine hundred sixty one only.					Total:-	498961,00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Thatiber Sheuli Jouri road Km. 0/00 to 9/00.
(SH :- Construction of wire crated Breast wall at RD.9/220 to 9/245) (under PDNA).

Estimated Cost:- Rs.267986/- only.
Earnest Money :-Rs.5400/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	74.25	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	8.00 24774.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	24.19	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	12913.00
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	81.00	Cubic Metre.	2843.20	Rupees two thousand eight hundred forty three paise twenty only.	Per cubic metre.	230299.00
Total in words :- Two lac sixty seven thousand nine hundred eighty six only.							267986.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

Name of Work:-Restoration of rain damages on Ghiagi to Sajwad road Km. 0/00 to 8/500.
(SH:-Construction of Breast wall at RD.4/165 to 4/180).(under PDNA).

Estimated Cost:- Rs.314686/- only.
Earnest Money :-Rs.6300/- only.
Time :- Three Month

Sr. No	Description of Items	Quantity			Rate with all taxes Excluding GST		Unit	Amount
		3		4	Figures	Words		
		52.35	Cubic Metre.	5	Rupees three hundred thirty three paise sixty five only.	7		
1	Excavation soil in hilly area by mechanical means including cutting and trimming at side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	52.35	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	17467.00	
2	Excavation in rock work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles,agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	20.25	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	10810.00	
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	34.80	Cubic Metre.	5022.25	Rupees five thousand two hundred twenty two paise twenty five only.	Per cubic metre.	174774.00	
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	26.52	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	111635.00	
						Total:-	314686.00	

Total in words :-Three lac fourteen thousand six hundred eighty six only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ghiagi to Saiwad road Km. 0/00 to 8/500.
(SH :-Construction of Breast wall at RD.4/165 to 4/180),(under PDNA).

Estimated Cost:- Rs.314686/- only.
Earnest Money :-Rs.6300/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes Excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by mechanical means including cutting and trimming af side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	52.35	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	17467.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	20.25	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	10810.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	34.80	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	174774.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	26.52	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	111635.00
						Total:-	314686.00

Total in words :-Three lac fourteen thousand six hundred eighty six only.

Percentage %


Executive Engineer
Banjar Division
HPPWID Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Thatiber Sheuli to Jouri road Km. 0/00 to 9/500.
(SH :- Construction of Breast wall at RD.1/660 to 1/675).(Under PDNA).

Estimated Cost:- Rs.286504/- only.
Earnest Money :-Rs.5800/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	46.35	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	8.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	19.80	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	10569.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	30.75	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	154434.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	25.19	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	106036.00
Total in words :- Two lac sixty eight thousand five hundred four only.							Total:- 286504.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Khundan to Shatyangi road Km. 0/00 to 6/500.
(SH :-Construction of Retaining wall at RD.0/810 to 0/920).(Under PDNA).

Estimated Cost:- Rs.382418/- only.
Earnest Money :-Rs.7700/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST	Unit	Amount
		3	4	Figures Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, levelling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	31.85	Cubic Metre.	533.81 Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	17002.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.90	Cubic Metre.	4746.53 Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	23258.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	22.50	Cubic Metre.	6076.58 Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	136723.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	18.66	Cubic Metre.	5022.25 Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	93715.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	22.80	Cubic Metre.	4209.45 Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	95975.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	11.10	Cubic Metre.	1418.49 Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	15745.00
Total in words :-Three lac eighty two thousand four hundred eighteen only.						382418.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bhuinkapul to Kolla road Km. 0/00 to 10/800.
(SH :- Removal of slips / Land Slide at RD. 0/00 to 2/315) (Under PDNA).

Estimated Cost:- Rs.499560/- only.
Earnest Money :-Rs.10000/- only.
Time :- Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along the road side as per direction of Engineer-in-Charge.	3764.58	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	499560.00
Total in words :-Four lac ninety nine thousand five hundred sixty only.							Total:- 499560.00

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Shalwar to Kanon road Km. 0/00 to 5/880.
(SH :- Removal of slips / Land Slide at various reaches).(Under PDNA).

Estimated Cost:- Rs.498023/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along,the road side as per direction of Engineer-in-Charge.	3753.00	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	498023.00
Total in words :-Four lac ninety eight thousand twenty three only.							498023.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sainj to Deori road Km. 0/00 to 7/00.
(SH :- Removal of slips / Land Slide at various reachea).(Under PDNA).(Job No.1).

Estimated Cost:- Rs.493724/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge.	3720.60	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	8.00 493724.00
Total in words :-Four lac ninety three thousand seven hundred twenty four only.							Total:- 493724.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain to Shangher road Km. 0/00 to 8/00.
(SH :- Removal of slips / Land Slide at various reaches).(Under PDNA).(Job No.1)

Estimated Cost:- Rs.499742/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge.	3765.95	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	8.00 499742.00
Total in words :-Four lac ninety ninety nine thousand seven hundred forty two only.							Total:- 499742.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages-onLarji to Sainj road Km. 0/00 to 14/00.
(SH :- Removal of slips / Land Slide at various reachea).(Under PDNA).

Estimated Cost:- Rs.493790/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along,the road side as per direction of Engineer-in-Charge.	3721.10	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	8.00 493790.00
Total in words :-Four lac ninety three thousand seven hundred ninety only.							Total:- 493790.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain to Shangher road Km. 0/00 to 8/00.
(SH :- Removal of slips / Land Slide at various reaches).(Under PDNA).

Estimated Cost:- Rs.499499/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along the road side as per direction of Engineer-in-Charge.	3764.12	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	499499.00
Total in words :-Four lac ninety nine thousand four hundred ninety nine only.							Total:- 499499.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

18

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ghiyagi to Saiwad road Km. 0/00 to 8/500.
(SH :- Construction of PCC Toe wall alongwith wire crated Breast wall at RD. 0/185 to 0/200) (under PDNA).

Estimated Cost:- Rs.310255/- only.
Earnest Money :-Rs.6300/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST	Unit	Amount
		3	4	Figures	Words	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and hailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects. Including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	15.00	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	8.00 8007.00
2	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	27.00	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	164066.00
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	48.60	Cubic Metre.	2843.20	Rupees two thousand eight hundred forty three paise twenty only.	138180.00
Total in words :- Three lac ten thousand two hundred fifty five only.						310255.00

Percentage %


 Executive Engineer
 Bagar Division
 HPPWD Bagar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banjar Bye Pass (Bhumar Nallah to Gheligaad) road Km. 0/00 to 1/ Estimated Cost:- Rs.225901/- only.
(SH :- Providing and laying Kharanja Stone Soling at various reaches). (under PDNA).

1/946 Earnest Money :-Rs.4600/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Preparation of sub-grade by dressing to camber earth work for the conitting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specifications including carriage of material with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	1044.00	Square metre	1.90	Rupees one paise ninety only.	Per Square metre	1984.00
2	Consolidation of Sub-grade with road roller including making the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade completed as per HPPWD specification including carriage of material with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	1044.00	Square metre	2.30	Rupees two paise thirty only.	Per Square metre	2401.00
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification, 100 mm spread thickness (finished work including materials and labour) with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	152.25	Cubic Metre.	1454.95	Rupees one thousand four hundred tifty four paise ninety five only.	Per cubic metre.	221516.00
Total in words :- Two lac twenty five thousand nine hundred one only.							225901.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banjar Bye Pass (Bhumar Nallah to Gheliga) road Km. 0/00 to 1/945.
(SH :- Construction of PCC Toe wall alongwith Retaining wall at RD. 0/166 to 0/177). (Under PDNA).

Estimated Cost:- Rs.413562/- only.
Earnest Money :- Rs.8300/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects. Including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	29.86	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	15940.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.08	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	14619.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	59.40	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	360949.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (V:H) towards draining face complete as per drawing and technical specifications clause 614, 709, 1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	27.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	11288.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through, with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.59	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	10766.00
		Total in words :- Four lac thirteen thousand five hundred sixty two only.				Total:-	413562.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

21

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Sidhwan to Godigad road Km. 0/00 to 8/00.
(SH :-Construction of Breast wall at RD.3/975 to 3/997.50)(Under PDNA).

Estimated Cost:- Rs.423607/- only.
Earnest Money :-Rs.8500/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	78.97	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	26348.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	21.82	Cubic Metre.	533.01	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	11648.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704, 1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	44.00	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	220979.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/carryage of all labour equipment and materials to various location through all modes of transportation with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	39.11	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	164632.00
						Total:-	423607.00

Total in words :-Four lac twenty three thousand six hundred seven only.

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Banjar Bye Pass (Bhumar Nallah to Gheligid) road Km. 0/00 to 1/945.
(SH :- Providing and laying Kharanja Stone Soling at various reaches).(under PDNA).

Estimated Cost:- Rs.159681/- only.
Earnest Money :-Rs.3200/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount	
		3	4	Figures	Words			
1	2	738.00	Square metre	1.90	Rupees one paise ninety only.	7	8.00	
2	Consolidation of Sub-grade by dressing to camber earth work for the contitting involved for sub-grade to be paid for separately depending upon the classification of soil completed as per HPPWD specifications including carriage of material. with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	738.00	Square metre	2.30	Rupees two paise thirty only.	Per Square metre	1402.00	
3	Consolidation of Sub-grade with road roller including making the undulation etc. with earth or quarry soil etc. and re-rolling the sub-grade completed as per HPPWD specification including carriage of material. with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	107.62	Cubic Metre.	1454.95	Rupees one thousand four hundred tifty four paise ninety five only.	Per cubic metre.	1697.00	
	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.						156582.00	
Total in words :-One Lac fifty nine thousand six hundred eighty one only.							Total:-	159681.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

23

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Banjar Bye Pass (Bhumar Nallah to Gheligaad) road Km. 0/00 to 1/945.
(SH :-Construction of Hume pipe culvert 900 mm dia at RD. 1/731) (under PDNA).

Estimated Cost:- Rs.366912/- only.
Earnest Money :-Rs.7400/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST Figures	Unit		Amount
		3	4		Words	7	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	70.31	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	37532.00
2	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clause 702,704,1202 and 1204 in cement mortar 1:5 (one cement: five sand) including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	8.99	Cubic Metre.	6268.81	Rupees six thousand two hundred sixty eight paise eighty only.	Per cubic metre.	56357.00
3	Providing and laying reinforced cement concrete pipe NP3 (900mm dia for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work and back filling and concrete work in head wall and parapets clause 1106. including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.50	Running metre.	4423.95	Rupees four thousand four hundred twenty three paise ninety five only.	Per Running metre.	33180.00
4	Providing and laying of dry rubble flooring complete as per drawings and technical specification clause 1303.3 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	1.47	Cubic Metre.	2325.85	Rupees two thousand three hundred twenty five paise eighty five only.	Per cubic metre.	3419.00
5	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.94	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	32941.00
6	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	31.74	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	192871.00
7	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1 (v):20 (H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	15.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	6271.00

8	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.38 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.06	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	4341.00
Total in words :- Three lac sixty six thousand nine hundred twelve only.							Total:- 366912.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain to Shangher road Km. 0/00 to 8/00.
(SH :- Removal of slips / Land Slide at various reaches).-(Under PDNA).

Estimated Cost:- Rs.412455/- only.
Earnest Money :-Rs.8300/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along the road side as per direction of Engineer-in-Charge.	3108.18	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	412455.00
Total in words :-Four lac twelve thousand four hundred fifty five only.							Total:- 412455.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain to Shangher road Km. 0/00 to 8/00.
(SH :- Removal of slips / Land Slide at various reaches).(Under PDNA).(Job No.1).

Estimated Cost:- Rs.479237/- only.
Earnest Money :-Rs.9600/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along,the road side as per direction of Engineer-in-Charge.	3611.43	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	8.00 479237.00
Total in words :-Four lac seventy nine thousand two hundred thirty seven only.							Total:- 479237.00

Percentage %


 Executive Engineer
 Banjar Division
 HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Suchain to Shangher road Km. 0/00 to 8/00.
(SH :- Removal of slips / Land Slide at various reaches),(Under PDNA),(Job No.II).

Estimated Cost:- Rs.480691/- only.
Earnest Money :-Rs.9700/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along,the road side as per direction of Engineer-in-Charge.	3622.39	Cubic Metre.	5 132.70	6 Rupees one hundred thirty two paise seventy only.	7 Per cubic metre.	8.00 480691.00
Total in words :-Four lac eighty thousand six hundred ninety one only.							Total:- 480691.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Rural Ghrat to Naro road Km. 0/00 to 4/300.
(SH :-Construction of PCC Breast wall at RD.0/00 to 0/014),(Under PDNA).

Estimated Cost:- Rs.392310/- only.
Earnest Money :-Rs.8000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	17.70	Cubic Metre.	333.65	Rupees three hundred thirty three paise six five only.	Per cubic metre.	5906.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	50.40	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	26904.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	14.59	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	88657.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	49.50	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	248601.00
5	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20(H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	53.20	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	22242.00
Total in words :-Three lac ninety nine two thousand three hundred ten only.							392310.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Bagmati

28

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Rural Ghat to Narol road Km. 0/00 to 4/300.
(SH :- Construction of PCC Breast wall at RD.0/015 to 0/030). (Under PDNA).

Estimated Cost:- Rs.395842/- only.
Earnest Money :- Rs.8000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	17.70	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	5906.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	50.40	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	26904.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	14.59	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	88657.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	50.12	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	251715.00
5	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	54.20	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	22660.00
Total in words :- Three lac ninety five thousand eight hundred forty two only.							395842.00

Percentage %


Engineer
Nagar Division
HPPWD Bargar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Mangalore to Panihar road Km. 0/00 to 8/00.
(SH:-Construction of PCC toe wall alongwith Retaining wall at RD.6/135 to 6/148.50)(under PDNA).

Estimated Cost:- Rs.429105/- only.
Earnest Money :-Rs.8600/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes Excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	33.61	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	8.00 17941.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	5.88	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	27910.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	22.68	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	137817.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	21.46	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	107777.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	29.70	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	125021.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.38 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge.	8.91	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	12639.00
Total in words :-Four lac twenty nine thousand one hundred five only.							429105.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Chilladhar Bihar road Km. 0/00 to 4/00.
(SH :-Construction of Breast wall at RD.2/690 to 2/700).(Under PDNA).

Estimated Cost:- Rs.379582/- only.
Earnest Money :-Rs.7600/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/ carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	65.20	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	21754.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermedate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/ carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	22.00	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	11744.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	39.65	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	199132.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	34.91	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	146952.00
						Total:-	379582.00

Total in words :- Three lac seventy nine thousand five hundred eighty two only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Manglore to Panihar road Km. 0/00 to 8/00.
(SH :- Construction of Breast wall at RD.6/080 to 6/097).(Under PDNA).

Estimated Cost:- Rs.416385/- only.
Earnest Money :- Rs.8400/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge.	56.69	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	8.00 18915.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	18.53	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	9891.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	40.00	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	200890.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge.	44.35	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	186689.00
		Total in words :- Four lac sixteen thousand three hundred eighty five only.		Total:-			416385.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

32

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Thatiber Sheuli Jouri road Km. 0/00 to 9/500.
(SH :- Construction of PCC Toe wall along with wire crated Retaining wall at RD.2/005 to 2/020). (under PDNA).

Estimated Cost:- Rs.452113/- only.
Earnest Money :-Rs.9100/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes Excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	42.75	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	22820.00
2	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:3:6 (one cement: three sand: six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	33.75	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	205085.00
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-1 wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	71.00	Cubic Metre.	2843.20	Rupees two thousand eight hundred forty three paise twenty only.	Per cubic metre.	201867.00
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge.	15.75	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	22341.00
Total in words :- Four lac fifty two thousand one hundred thirteen only.							452113.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Hiring of Bolero Camper neo for Sub Division Banjar HP.PWD. Banjar

(2059 s(m))

Estimated cost :312000.00
Earnest Money :-6500.00
Time :- 6 Months

Sr.No.	Description of items	Quantity/Period	Rate with all taxes excluding GST		Unit	Amount
			Figures 4	Words 5		
1	(i) Hiring of Bolero Camper neo Sub Division Banjar (for 1500km or per month including night charges. The rates are inclusive of petrol/diesel, dirver, taxes or toll tax levies maintenance etc. The vehicle will fully remain under the control of officer in charge.	3 6.00 Months	52000.00	Rupees fifty two thousand only	6 Per 1500.00 km or per one month	7 312000.00
Total in words :-Three lac twelve thousand only.					Total	312000.00

Percentage %

Note:-If the vehicle has covered more than 1500Km in one month, in that case,additional payment Rs. 23.00 per kilometer shall be made for extra Kilometerage.


Executive Engineer
Banjar Division
HPPWD Banjar