

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2026-
To

7641-43

Dated:- 26-8-2026

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:-

Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing above 1 upto 5.00 Lakh as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025 and PWD-B-A 0(3)/8/2025-300858 dated 09-10-2025, even file No. 300858 dated 13-11-2025, 08-12-2025 and even file No. 241828 dated 02-02-2026. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.


Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa.

HP.P.W.D. TENDER NOTICE (offline)

Sealed item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP,PWD; Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD. Kalpa on or before **05-09-2026 up to 11.00 A.M.** and shall be opened on the same day at **11:30 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HPPWD Kalpa) against cash payment (Non-refundable) on **03-09-2026 upto 4:00 P.M.** No application for issue of tender forms will be received on **03-09-2026 after 4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/ opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R,s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD. Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 120 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	Restoration of Rain damages (PDNA) on Peo Karchham Shilti road Km 0/000 to 11/635. (SH:- Providing PCC retaining wall and edging at various RDs between Km. 2/570 to 2/600, 5/790 to 5/806)	4,98,625/-	10,000/-	One Month	350/-	"C" & "D" Class
2	Restoration of Rain damages (PDNA) on Peo Karchham Shilti road Km 0/000 to 11/635.(SH:- Providing PCC retaining wall at RD. 10/645 to 10/670)	4,99,059/-	10,000/-	One Month	350/-	"C" & "D" Class
3	Restoration of Rain damages (PDNA)on Peo Karchham Shilti road Km 0/000 to 11/635.(SH:- Providing PCC retaining wall at RD 8/600 to 8/645)	4,99,598/-	10,000/-	One Month	350/-	"C" & "D" Class
4	Special repair to Dispensary Building at Ropa Tehsil Pooch in Distt. Kinnaur (HP) (SH:- C/O R/wall in RR Masonry and P.C.C R/wall for Protection work).	4,41,881/-	9,000/-	One Month	350/-	"C" & "D" Class

5	Special repair to Dispensary Building at Ropa Tehsil Pooh in Distt. Kinnaur (HP) (SH:- P/F Roof Covering and Flooring)	1,89,592/-	4,000/-	One Month	350/-	"C" & "D" Class
---	--	------------	---------	-----------	-------	-----------------



Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:- 26-8-2026

No.: PW/KNR-E-Tender/NIT/2026- 7627-40

Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.



Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this office Letter No. PW/KNR/E-Tender/2026- 7627-40 dated 26-8-2026 and Five numbers of works are of urgent nature and essential for public safety or restoration of infrastructure and public interest.



**Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.**



(1)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Dams (PDNA) on Peo Karchham Shilti road Km 0/000 to 11/635.
 (SH:- Providing PCC retaining wall and edging at various RDs between Km 2/570 to 2/600, 5/790 to 5/806)

Estimated Cost :- 4,98,625/-
 Earnest Money :- 10,000/-
 Time One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation for Structures Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government	7.46	₹ 261.05	Rupees Three Hundred Four and paise ninety two only	Per Cubic meter	₹ 1,948.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C (Mechanical mix and vibrated graded crushed stone aggregate) 1:4:8 (40 mm (Forty millimeter) aggregates) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government	39.662	₹ 5,100.00	Rupees thousand four hundred ninety One and paise Fifty Three only	Per Cubic meter	₹ 202,277.00
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government	92.00	₹ 3,200.00	Rupees thousand seven hundred and four paise Twenty Four only	Per running Meter	₹ 294,400.00
Total:-						₹ 498,625.00
Total in figures:-		Rupees Four Lakh Ninety Eight Thousand Six Hundred Twenty Five Only				
Total in Words:-		Rupees Four Lakh Ninety Eight Thousand Six Hundred Twenty Five Only				
Quoted percentage rate upto three Digits:-		(+)/(-)				

Executive Engineer,
 Kalpa Division (B&R),
 HP. PWD, Kalpa.

2.

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,059/-
 Earnest Money :- 10,000/-
 Time One Month

Name of work:- Restoration of Rain Damges (PDNA) on Peo Karchham Shilti road Km 0/000 to 11/635.
 (SH:- Providing PCC retaining wall at RD 10.645 to 10.670)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Excavation for Structures Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	4.04	₹ 261.05	Rupees Three hundred and paise ninety two only	Per Cubic meter	₹ 1,055.00
2	Providing and laying parapet with PCC M-15 as per drawing & technical specifications clauses 800 and 1208.4 Nominal mix (1:3:6) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	4.04	₹ 6,152.50	Rupees Five thousand hundred thirteen and paise Fifty Ninety Eight only	Per Cubic meter	₹ 24,856.00
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C (Mechanical mix and vibrated graded crushed stone aggregate) 1:4:8 (40 mm (Forty millimeter) aggregates) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	30.500	₹ 5,100.00	Rupees Four thousand hundred ninety One and paise Fifty Three only	Per Cubic meter	₹ 155,550.00

4	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	89.00	₹ 3,200.00	Rupees thousand and four paise Twenty only	Two Seven and Fifty Four	Per running Meter	₹ 284,800.00
5	Steel work welded in built up sections (TATA/SAIL/Apollo/JSW Make) framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete upto floor all level including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	310.00	₹ 105.80	Rupees Eighty Nine and paise Sixty Six only	Nine Six	Per Kilograms	₹ 32,798.00
Total in figures:-						Total:-	₹ 499,059.00
Total in Words:-							
Quoted percentage rate upto three Digits:-							
			Rupees Four Lakh Ninety Nine Thousand Fifty Nine Only				
			(+/-)				

Executive Engineer,
Kalpa Division (B&R),
HP.PWD
K. Kalpa

3

SCHEDULE OF QUANTITY

Estimated Cost :- 4,99,598/-
 Earnest Money :- 10,000/-
 Time One Month

Name of work:- Restoration of Rain Danges (PDNA) on Peo Karchham Shilti road Km 0/000 to 11/635.
 (SH:- Providing PCC retaining wall at RD 8.600 to 8.645)

Sr. No.	Description of items	Qty.	Rate	In Words	Unit	Amount
			In Fig.			
1	Excavation for Structures Earth work in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	18.45	₹ 261.05	Rupees Three Hundred and paise ninety two only	Per Cubic meter	₹ 4,816.00
2	Providing and laying parapet with PCC M-15 as per drawing & technical specifications clauses 800 and 1208.4 Nominal mix (1:3:6) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	0.809	₹ 6,152.50	Rupees Five thousand two hundred thirteen and paise Fifty Ninty Eight only	Per Cubic meter	₹ 4,974.00
3	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C (Mechanical mix and vibrated graded crushed stone aggregate) 1:4:8 (40 mm (Forty millimeter) aggregates) including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	44.100	₹ 5,100.00	Rupees Four thousand four hundred ninty One and paise Fifty Three only	Per Cubic meter	₹ 224,910.00
4	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm thick corrugated sheet metal beam rail, 70 cm above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm spaced 2 m centre to centre, 1.8 m high, 1.1 m below ground/road level, all steel parts and fittings to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm, 330 mm long complete as per clause 810 including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	56.00	₹ 3,200.00	Rupees Two thousand Seven hundred and Fifty four paise Twenty Four only	Per running Meter	₹ 179,200.00

5	Steel work welded in built up sections (TATA/SAIL/Apollo/JSW Make) framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete upto floor all level .including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of GST, octroi, royalty, malkana, toll tax, sale tax, or other taxes imposed by the Government	810.00	₹ 105.80	Rupees Eighty Nine and paise Sixty Six only	Per Kilograms	₹ 85,698.00
Total in figures:-		Total:-				
Total in Words:-		Rupees Four Lakh Ninety Nine Thousand Five Hundred Ninety Eight Only				
Quoted percentage rate upto three Digits:-		(+)/(-)				

Executive Engineer,
Kalpa Division (B&R),
HP. PWT

SCHEDULE OF QUANTITY

Estimated Cost :- 4,41,881/-

Earnest Money :- 9000/-

Name of work:-Special repair to Dispensary Building at Ropa Teh. Pooh in Distt. Kinnaur (HP) (SH:- C/O R/wall in RR Masonry and P.C.C R/wall for Portion work).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (within all lead and lift including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes (but excluding GST) imposed by the Government	36.14	₹ 270.05	Two Hundred Seventy Rupees and Five Paise Only	Per Cubic meter	₹ 9,760.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. P.C.C nominal mix 1:6:12 (40 mm aggregates).including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes (but excluding GST) imposed by the Government	2.34	₹ 4,962.30	Four Thousand Nine Hundred Sixty Two Rupees and Thirty Paise Only	Per Cubic meter	₹ 11,612.00
3	Random rubble masonry with hard stone in foundation band plinth including levelling up with cement concrete 1:6:12 (1 cement: 6 coarse sand: 12 graded stone aggregate 20 mm nominal size) upto plinth level with: Cement mortar 1:6 (1 cement: 6 coarse sand), including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes (but excluding GST) imposed by the Government	30.42	₹ 5,233.65	Five Thousand Two Hundred Thirty Three Rupees and Sixty Five Paise Only	Per Cubic meter	₹ 1,59,208.00
4	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203.P.C.C grade M 10 Nominal mix 1:3:6, including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes (but excluding GST) imposed by the Government	38.29	₹ 6,378.20	Six Thousand Three Hundred Seventy Eight Rupees and Twenty Paise Only	Per Cubic meter	₹ 2,44,221.00

5	Providing weepholes in brick masonry / stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including entire carriage of materials in all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, or other taxes (but excluding GST) imposed by the Government	61.00	₹ 280.00	Two Hundred Eighty Rupees Only	each	₹ 17,080.00
	Total in figures:-				Total =	441881.00
	Total in Words:-	Four Lakh Forty One Thousand Eight Hundred Eighty One Rupees Only				
	Quoted percentage rate upto three Digits:-	(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD/Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Special repair to Dispensary Building at Ropa TehPooh in Distt. Kinnaur (H. P.) (SH:- P/F Roof Covering and flooring)

Estimated Cost :- 1,89,592/-

Earnest Money :- 4000/-

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In beams joists hannels, angles, tee, flats with connecting plates or angle cleats as in main and cross beams, hip and jack rafters, purlins connected to common rafters and the like.	4.02	₹ 9,850.60	Nine Thousand Eight Hundred Fifty Rupees and Sixty Paise Only	Per Qtl.	₹ 39,599.00
2	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron Jor L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge.	59.28	₹ 842.00	Eight Hundred Forty Two Rupees Only	Per sqm	₹ 49,914.00
3	Providing and fixing M.S. BP Sheet 1.66mm to 2mm thick in eaves board/facia/offits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately)	23.10	₹ 1,780.25	One Thousand Seven Hundred Eighty Rupees and Twenty Five Paise Only	Per sqm	₹ 41,124.00
4	Repairs to plaster in patches of 2.50 Sq.M. and under and 10 to 15mm thick including cutting the patch in proper shape and replastering the surface of the wall including disposal of rubbish to the dumping ground within a Lead of 20 metres with: Cement Mortar 1:3 (1 Cement: 3 Sand)	16.50	₹ 348.50	Three Hundred Forty Eight Rupees and Fifty Paise Only	Per sqm	₹ 5,750.00
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work up to plinth level 1:2:4 (1 cement: 2 coarse sand): 4 graded stone aggregate 20 mm nominal size).	3.20	₹ 8,350.60	Eight Thousand Three Hundred Fifty Rupees and Sixty Paise Only	Per cum	₹ 26,722.00
6	Providing and laying Ceramic glazed floor tiles of size 300x300 mm (thickness to be specified by the manufacturer), of 1st quality conforming to IS: 15622; of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick bed of cement mortar 1:4 (1 Cement: 4 Coarse sand), jointing with grey cement slurry @3.3 kg/sq.m including pointing the joints with white cement and matching pigments etc., complete.	16.00	₹ 1,580.85	One Thousand Five Hundred Eighty Rupees and Eighty Five Paise Only	Per Sqm	₹ 25,294.00

Supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary:-Plain Glass: 4mm thick

supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary:-Plain Glass: 4mm thick.				
Total in figures:-				
Total in Words:-				
Quoted percentage rate upto three Digits:-				



Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.