

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-AD-EA-I-Tender-2026-27 6996-7004

Dated:- 05/09/2026

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.P.W.D. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **15.09.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **14.09.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **14.09.2026 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1.	Restoration of rain damages on Reota Kulawan road km. 0/0 to 4/0(SH:-C/o PCC R/wall between km. 0/030 to 0/480, 3/695 to 3/715 and 900mm dia hume pipe culvert)PDNA 2025	4,99,423/-	10,000/-	1 Month	350/-
2.	Restoration of rain damages on various roads under Kunihar Sub-Division,HP,PWD, Kunihar under Jainagar sections(SH:-Hiring of JCB for removal of slips in various roads)Job No.8	99,000/-	2,000/-	1 Month	350/-
3.	R/R damages on Jablu Sera Samana Thera road km. 0/0 to 6/675(SH:-C/o R/wall at RDs 5/455 to 5/470)DMFT	1,54,866/-	3100/-	1 Month	350/-
4	R/R damages on Jablu Sera Samana Thera road km. 0/0 to 6/675(SH:-C/o R/wall at RDs 5/334 to 5/352)DMFT	4,82,706/-	10,000/-	1 Month	350/-
5	Restoration of rain damages on Shimla Kunihar Ramshear Nalagarh road portion km. 38/600 to 80/500(SH:-Providing and laying 1:3:6 for U shape drain 1:4:8 under Paver Block bed and 1:2:4 for locking of tiles both sides in between k. 49/915	3,03,675/-	7,000/-	1 Month	350/-

	to 50/015)Job No.1				
6	Restoration of rain damages on Shimla Kunihar Ramshear Nalagarh road portion km. 38/600 to 80/500(SH:-Providing and fixing interlocking paver block tiles in between km. 49/915 to 50/015Job No.2)	4,40,000/-	9,000	1 Month	350/-
7	C/o link road Chamla Baggi Jawi Taun to Syar road km. 0/0 to 3/500(SH:-Stone soling, C.C. 1:4:8 C.C.1:2:4 Steel Reinforcement, C.C. 1:3:6 for Cause way & Hard Rock Blasting)DMFT	4,99,794/-	10,000/-	2 Month	350/-
8	Balance work of C/o Abulance road from Rudal to Harizen Basti Kathalu km, 0/0 to 0/250(SH:-C/o R/wall at RDs 0/078.50 to 0/98.50)DMFT	1,70,452/-	3,500/-	1 Month	350/-
9	R/R damages on Chandi Rudal Harsang Dhar road km. 0/0 to 8/300(SH:-C/o R/wall at RDs 1/050 to 1/062, 3/135 to 3/143 & 0/215 to 0/222)PDNA 2025	3,90,822/-	8,000/-	1 Month	350/-
10	Restoration of rain damages on KBSB road portion from km. 0/0 to 8/0(SH:-Construction of Retaining wall at RD 2/200 to 2/212)PDNA 2025	3,00,689	7,000/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. Arki

No: PW-AD-EA-I-Tender-2026-27-

6996-7004

Dated:- 05/09/2026


Copy forwarded for the following for information and necessary action to:-

- 1.The Superintending Engineer 3rd Circle HPPWD Solan.
- 2.The all Assistant Engineer working under this division for information and necessary action.
- 3.All the heads of the branches in this office.
- 4.Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

Certificate

Certified that the tenders called vide this notice inviting tender for 10(Ten) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs4,99,423/- only
Name of Work:-Restoration of Rain Damages on Reota Kulawan Road km 0/000-4/000 (SH:- C/O PCC R/Wall between km 0/030 to 0/480, 3/695 to 3/715 and 900 mm dia Hume Pipe Culvert) PDNA 2025						Earnest Money :-Rs 10,000/-Only
						Time :-One Month
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specifications clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification as per direction of Engineer in Charge.	54.90	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	9410
2	Providing and laying plain/reinforced concrete in open foundations complete as per drawing and technical specification clause 802,803,1202 & 1203 including carriage of materials upto all leads and lifts (1) 1:5:10 (40 mm nominal size stone aggregates) as per direction of Engineer in Charge.	86.710	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	380709
3	Providing and laying weep holes in stone/brick masonry/plain reinforced concrete abutment, wing wall, return walls with 100 mm (one hundred millimetre) dia PVC pipe extending through full width of structures with slope of 1(vertical):20(Horizontal) towards drawing face complete as per drawings and technical	40.70	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	11162
4	Backfilling with Granular material behind abutment, wing wall and return wall complete as per drawing and technical specifications Clause 1204.3.8 including carriage of materials within all leads, lifts and as per direction of Engineer in Charge.	15.03	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	18086
5	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm diapipe. including carriage of materials in all leads and lifts. and as per the direction of Engineer-In-Charge.	7.50	3882.55	Rupees three thousand eight hundred eighty two and paise fifty five only	P.Rmt	29119
6	P/L concrete mechanically mixed and vibrated PCC M-10 1:3:6 20 mm nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification rural road August 2004 and clauses 802,803,1202 & 1203. Cement concere 1:3:6 (20 mm) nominal size within all leads, lifts and as per	9.62	5294.95	Rupees five thousand two hundred ninety four and paise ninety five only	P.Cum.	50937
					Total	499423

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar Sub Division
HP,PWD Kunihar under Jainagar Sections.(Sh :Hiring of JCB for removal of slips in various roads) Job No.8

Estimated Cost :- Rs 99,000.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.N o.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paisenil Only	Per Hours	99000.00
						Total	99000.00

Percentage Rates Quated in figure

Percentage Rates Quated in words

Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY						
Name of Work:-R/R Damages on Jablu Sera Samana Thera Road Km 0/00 to 6/675. (SH:- C/o R/wall at RD 5/455 to 5/470) DMFT			Estimated Cost: -Rs1,54,866/- only			
			Earnest Money :-R3,100/-Only			
			Time :-One Month			
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	12.90	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	2211
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	30.75	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	135011
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts. and as per the direction of Engineer-In- Charge	11.70	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	14079
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	13.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	3565
					Total	154866

Quoted Rate Percentage in Fig. —

Quoted Rate Percentage in Words —


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Jablu Sera Samana Thera Road Km 0/00 to 6/675. (SH:- C/o R/wall at RD 5/334 to 5/352) DMFT

Estimated Cost: -Rs4,82,706/- only

Earnest Money :-R10,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	41.76	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	7158
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	98.10	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	430718
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	27.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	32489
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	45.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	12341
					Total	482706

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY							
Name of work :-Restoration of Rain damages on Shimla Kunihar Ramsehar Nalagarh Road Portion km 38/600 to 80/500.(Sh:-Providing and Laying 1:3:6 for U-shape drain, 1:4:8 under Paver block bed and 1:2:4 for locking of Tiles both sides in between km 49/915 to 50/015) Job no.1					Estimated Cost :- Rs 3,03,675.00		
					Earnest money :- Rs 7,000.00		
					Time: One month		
Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	36.00	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	6170.00
2.00	Providing concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specifications Clauses 802,803,1202 and 1203. (II) P.C.C. Grade M-10 (i) Nominal mix 1:3:6 (20 mm Nominal Size) including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	16.00	Cum	5294.95	Rupees Five Thousand Two Hundred Ninety four and Ninety Five paise Only	Per cubic metre	84719.00
3.00	Providing and laying Plain Cement Concrete Mechanically mixed and vibrated Plain cement concrete in open foundation complete P.C.C. 1:4:8 40 mm (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five milimetre) nominal size for plain /reinforced concreetas per drawing and technical specification clauses 802,803,1202 and 1203. nominal size including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	40.00	Cum	4855.20	Rupees Four thousand eight Hundred fifty five and paise twenty Only	Per cubic metre	194208.00
4.00	Providing and laying Plain Cement Concrete Mechanically mixed and vibrated Plain cement concrete 1:2:4 (one cement isto two sand isto four graded crushed stone aggregate 20mm (twenty milimetre) nominal size for plain /reinforced concreet in open foundations and plinths or similar works and curing complete as per drawings and technical specifications for RURAL ROAD AUGUEST 2004 AND CLAUSES 802,803,1202 & 1203 and curing complete including the cost of form work including carriage of materials in all leads & lifts and as per entire stisfaction of Engineer-in -Charge.	3.12	cum	5954.35	Rupees Five thousand Nine Hundred fifty four and paise thirty five Only	Per cubic metre	18578.00
						Total	303675.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot. Percentage Rates Quated in figure

Percentage Rates Quated in words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of work :- Restoration of Rain damages on Shimla Kunihar Ramsehar Nalagarh Road Portion km 38/600 to 80/500. (Sh:- Providing and fixing interlocking paver block tiles in between km 49/915 to 50/015) Job no.2

Estimated Cost :- Rs 4,40,000.00

Earnest money :- Rs 9,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Providing and laying 80 mm thick factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of Engineer-inCharge . 80 mm thick C.C. paver block of M-35 grade with approved color design and pattern including carriage of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge	400.00	sqm	1100.00	Rupees One Thousand one Hundred and zero paise Only	Per square metre	440000.00
						Total	440000.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

Percentage Rates Quoted in figure

Percentage Rates Quoted in words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

Job No 7

SCHEDULE OF QUANTITY				Estimated Cost: -Rs4,99,794/- only		
Name of Work:-C/o Link Raod Chamla Baggi Jawi Taun to Syar Road Km 0/00 to 3/500.(SH:-Stone Soling, C.C.1:4:8, C.C.1:2:4, Steel Reinforcement, C.C. 1:3:6 for Cause way & Hard Rock Blasting.) DMFT				Earnest Money :-Rs10,000/-Only		
				Time :-Two Months		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3		4	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	94.38	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	16177
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) and as directed by Engineer-In- Charge	21.00	1425.25	Rupees one thousand four hundred twenty five and paise twenty five only	P.Cum.	29930
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 20mm (Twenty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts . The rate including sale tax or other taxes imposed by the Government.	10.50	4955.20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	52030
4	Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compacting with vibrator and curing complete excluding cost of form work and reinforced concrete work including carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge	10.50	5954.35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	62521
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials within all leads lifts and other incidentals as per the direction of Engineer-in-charge.	525.00	92.30	Rupees ninety two and paise thirty only	P.Kg	48458
6	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 d1203 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6 (20mm) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	43.68	5291.95	Rupees five thousand two hundred ninety one and paise ninety five only	P.Cum.	231152
7	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges and safe disposal of unsuitable cut materiel inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 9.12 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	91.18	652.85	Rupees six hundred fifty two and paiseeighty five only	P.Cum.	59527
					Total	499794

Quoted Rate Percentage in figure:
Quoted Rate Percentage in word:

Executive Engineer
Arki Division,
HPPWD, Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs1,70,452/- only	
Name of Work:- Balance work of C/o Ambulance Road from Rudal to Harizon Basti Katha <u>2.4</u> Km 0/00 0/250 (SH:- C/o R/wall at RD,s 0/078.50 to 0/98.50.)DMFT						Earnest Money :-Rs3,500/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
1	2	3	Figure	Words	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	15.60	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	2674	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	33.80	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	148402	
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	12.00	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	14440	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	18.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4937	
					Total	170452	

Quoted Rate Percentage In Fig.-

Quoted Rate Percentage in Words-


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs3,90,822/- only	
Name of Work:-R/R Damages on -Chandi Rudal Harsang Dhar Road Km 0/00 to 8/300. (SH:- C/o R/wall at RD,s 1/050 to 1/062, 3/135 to 3/143 & 0/215 to 0/222) PDNA 2025						Earnest Money :-R8,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
1	2	3	Figure	Words	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	34.93	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	5987	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	77.21	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	338998	
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	27.54	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	33139	
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	46.30	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	12698	
					Total	390822	

Quoted Rate Percentage in Figure —

Quoted Rate Percentage in Words —


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on KBSB road Portion from km 0/00 to 8/00. (SH:-Construction of Retaining wall at RD 2/200 to 2/212) PDNA 2025

Estimated Cost :- Rs 3,00,689.00

Earnest money :- Rs 7,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal of surplus excavated earth upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials and disposing of unserviceable material, disposed earth to be levelled and neatly dressed as per MORD Specification and as per the direction of Engineer-In- Charge	36.48	Cum	171.40	Rupees One Hundred Seventy One and Forty paise Only	Per cubic metre	6253.00
2.00	Providing and laying Plain cement concrete 1:5:10 (one cement isto Five sand isto ten graded crushed stone aggregate 40 milimetre(forty milimetre) nominal size for plain /reinforced concrete in open foundation complete as per drawings and technical specifications clause 802,803,1202 &1203 and curing complete including the cost of form work and carriage of materials in all leads lifts as per the direction of Engineer-In-Charge.	64.08	Cum	4390.60	Rupees Four Thousand Three Hundred Ninety and Sixty paise Only	Per cubic metre	281350.00
3.00	Providing and laying weapholes in brick masonry /stone masonry /plain reinforced concrete abutment, wing wall return wall with 100mm (one hundred)milimetre dia PVC pipe extending through the full width of the structures with slop of 1(v);20 (H) towards drawing face complete as per drawings and technical specifications MORD clause 614,709,1204.3.7 including carriage of materials within all leads and lifts as per the direction of Engineer-In-Charge.	25.60	Rmt	274.25	Rupees Two Hundred Seventy Four and Twenty Five paise Only	Per running metre	7021.00
4.00	Back filling behind abutment ,wing wall and retaining wall of granular material complete as per drawings and technical specifications MORD clause 1204.3.8 including carriage of materials within all leads lifts and as per the direction of Engineer-In-Charge.	5.04	Cum	1203.30	Rupees One Thousand Two Hundred Three and Thirty paise Only	Per cubic metre	6065.00
						Total	300689.00

Conditions:- (i) All the material will be procured by the contractor himself and bills will be submitted.

(ii) The cement will be procured by the contractor from the nearest HP Civil Supply Depot.

Percentage Rates Quated in figure

Percentage Rates Quated in words


Executive Engineer
Arki Division (B&R)
HP. PWD. Arki.