

Uttarakhand Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2026/ 19,049-19,074 Dated/ 29/9/

To

The Chief Engineer (KZ),
HP.PWD Dharamshala.

Subject:-

Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per directions received through e-mail dated 22.05.2026 of worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur


Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office
NIT No. PWP/ Agr. Asstt/ NIT/ 2026/- 10049-10074
Dated 29/9/2026 are urgent in nature and in public interest.


Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **07.10.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 06.10.2026 up to 4.00 P.M and the application for issue of tender form shall be received 05.10.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	R/D link road Balla Badsar Jugehar Kharti road Km 0/00 to 7/600 (SW:- C/o R/Wall at RD 0/760 to 0/770 (PDNA 2025-26)	Rs. 1,23,940.00	Rs. 2,500.00	Three Months
2	R/R damages on Harizan Basti Chamarkhar Jaisi Ram House to Tank KM 0/00 to 0/500 (SH:- P/L CC Pavement at RD 0/200 to 0/372 (PDNA-2025)	Rs. 4,22,771.00	Rs. 8,400.00	Three Months
3	Restoration of Rain damages on Rathan Ropa Ghar Kapoor Basti via Jagrena Km 0/00 to 7/150 (SW:- C/o Edge Wall at RD 2/200 to 2/216 (PDNA-2025)	Rs. 1,70,232.00	Rs.3,400.00	Three Months
4	R/R Damages on Jia to Fotta road M 0/00 to 1/500 (SW:- P/L G-II, CC Pavement at RD 0/500 to 0/670 (PDNA-2025-26)	Rs. 4,23,686.00	Rs.8,500.00	Three Months
5	C/o Samshan Ghat at Rathan Ropa (SW:- C/o R/Wall at RD 0/00 to 0/07 & B/Wall at RD 0/00 to 0/010 (VKVNY)	Rs. 1,69,242.00	Rs.3,400.00	Three Months
6	R/R damages on Kandi to Thalla Malenta road Km 0/00 to 4/500 (SW:- C/o Wire Crate at RD 0/750 to 0/760)	Rs. 2,34,957.00	Rs 4,700.00	Three Months
7	Restoration of Rain damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- P/L WBM G-III, Tarring Work & CC Pavement at various RDs between Km 34/500 to 36/300 (PDNA-2025)	Rs. 4,23,549.00	Rs 8,500.00	Three Months
8	Restoration of Rain damages on Tanda Pantehar Band Vihar Molichak Road Km 0/00 to 10/00 (Sw:- P/L Interlocking Paver Block at RD 3/325 to 3/350 & 3/275 to 3/300 (PDNA-2025)	Rs. 1,67,757.00	Rs 3,400.00	Three Months
9	Restoration of Rain damages on Palampur Neugal Park road (SW:- Improvement of road at RD 0/250 to 0/370 & 0/400 to 0/475 (PDNA-2025)	Rs. 1,68,129.00	Rs. 3,400.00	Three Months

10	Restoration of Rain damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 15/00 to 31/00 (SH:- C/o R/Wall at RD 16/400 to 16/420 (PDNA-2025)	Rs. 1,96,266.00	Rs. 3,900.00	Three Months	
11	Restoration of Rain damages on Topo Basti road 0/000 to 0/400 (SW:- P/L WBM G-II, G-III & CC Pavement 0/250 to 0/301.50 (PDNA-2025)	Rs. 1,67,932.00	Rs. 3,400.00	Three Months	
12	Restoration of rain damages on Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/00 to 10/00 (SW:- C/o R/Wall at RD 5/200 to 5/206 & 5/125 to 5/131 (PDNA-2025)	Rs. 1,68,756.00	Rs. 3,400.00	Three Months	
13	Restoration of Rain damages on Tanda Pantehar Band Molichak Dharaman Kandwari road Km 0/00 to 10/00 (SW:- C/o R/Wall at RD 0/600 to 0/606, 2/510 to 2/516 (PDNA-2025)	Rs. 2,51,577.00	Rs. 5,000.00	Three Months	
14	Restoration of Rain damages on Rathan Ropa Ghar Kapoor Basti via Jagraina KM 0/00 to 7/150 (SW:- P/L Interlocking Paver Block at RD 3/510 to 3/535 & 3/590 to 3/615 (PDNA-2025)	Rs. 1,68,072.00	Rs. 3,400.00	Three Months	
15	Restoration of rain damages on Palampur Neugal Park road (SW:- Providing and laying Interlocking Paver Block 2/120 to 2/144, 2/250 to 2/270 & C/o U-shape drain at RD 1/920 to 1/925 & V-shape drain alongwith grating at RD 2/150 to 2/160.20 (PDNA-2025)	Rs. 1,68,831.00	Rs. 3,400.00	Three Months	
16	Restoration of Rain damages on Holta to Tanda Holta road Km 0/00 to 5/500 (SH:- P/L Interlocking Paver Block at RD 2/650 to 2/675 & 3/600 to 3/625 (PDNA-2025)	Rs. 1,67,757.00	Rs. 3,400.00	Three Months	
17	Restoration of Rain damages on Palampur Neugal Park road (SW:- P/L Interlocking Paver Block 1/720 to 1/740, 1/930 to 1/960 & C/o U-shape drain alongwith grating at RD 1/830 to 1/840 & 1/850 to 1/860 (PDNA-2025)	Rs. 1,67,968.00	Rs. 3,400.00	Three Months	
18	Restoration of Rain damages on Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road Km 0/00 to 10/00 (SW:- C/o 900 MM dia Hume Pipe Culvert at RD 4/425, U-Shape drain at RD 4/375 to 4/425 (PDNA-2025)	Rs. 1,84,604.00	Rs. 3,700.00	Three Months	
19	Bandla Ghuggar Thakurdwara road 0/00 to 6/00, Dharamshala Yol Dadh Palampur road 27/100 to 33/00, Cienema Hall Bye Pass road 0/00 to 1/500 (SW:- Writing letters with Black Japan paint)	Rs. 83,972.00	Rs. 1,700.00	Three Months	

20	Restoration of Rain damages on Parour Lahla Chachian MDR-55 from Km 0/00 to 33/00 (SW:- Writing painting on bridges, roads from Km 0/00 to 10/00)	Rs. 83,426.00	Rs. 1,700.00	Three Months
21	Restoration of Rain damages on Spedu to Goarth road (SH:- C/o U-shape drain at RD 0/200 to 0/280 & P/L CC Pavement at RD 0/200 to 0/229.50 (PDNA-2025)	Rs. 1,59,955.00	Rs. 3,200.00	Three Months
22	Restoration of rain damages on Kand to Tikkar via Kalohi Mata (SW:- C/o Both side approaches of 2.00 mtrs Span RCC Slab Culvert at RD 0/990 (RD 0/969 to 0/977.50 & 0/992.50 to 1/001.50 (PDNA-2025)	Rs. 4,04,801.00	Rs. 8,100.00	Three Months
23	Restoration of Rain damages on Link road to village Drognu road Km 0/00 to 1/600 (SW:- C/o R/Wall at RD 1/300 to 1/315 (PDNA-2025-26)	Rs. 1,89,412.00	Rs. 3,800.00	Three Months
24	Restoration of Rain damages on Patti Bodhal Pahra road KM 0/00 to 5/00 (SW:- Maintenance of Earthen Shoulders and unlined surface drain at RD 1/200 to 1/700 , 1/750 to 5/00 (PDNA-2025)	Rs. 1,66,260.00	Rs. 3,300.00	Three Months
25	Restoration of rain damages on Dharamshala Yol Dadh Chadiyar Sandhole road (SH:- Maintenance Maintenance of Earthen Shoulders and unlined surface drain at RD 33/200 to 33/700 & 34/250 to 34/600 (PDNA-2025)	Rs. 1,66,490.00	Rs. 3,300.00	Three Months
26	Restoration of rain damages on Palampur to Lohna Langha road (SW:- C/o U-shape drain at RD 3/385 to 3/451 & B/Wall at RD 5/185 to 5/204 (PDNA-2025)	Rs. 2,52,709.00	Rs. 5,100.00	Three Months

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

Schedule of Quantity

Name of Work:- R/D Link road Balla Badsar Jughar Khrafi road Km 0/00 to 7/600(SH:-C/O RWall at Rd 0/760 to 0/770)(PDNA 2025-26)

Estimated Cost :- Rs. 1,23,940/-
Earnest Money :- Rs. 2500/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST. Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST. Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	12.00	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per cubic metre.	Rs. 2847.00
2		31.50	3644.06	Rupees Three Thousand Six Hundred Forty Four And Paise Six Only	Per cubic metre.	114788.00
3		6.00	576.27	Rupees Five Hundred Seventy Six And Paise Twenty Seven Only	Per cubic metre.	3458.00

4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	12.00	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	No	2847.00
	Quoted rates percentage in figures				Total:-	123940.00
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work:- R/R Damages on Harijan basti Charamkar Jasi Ram house to tank Km 0/00 to 0/500 (SH:- P/L CC Pavement at Rd 0/200 to 0/372)(PDNA) 25

Estimated Cost :- Rs. 4,22,771/-
Earnest Money :- Rs. 8400/-

S. No	Description of Item	Quantity	Rate			Time Limit :- Three Months	
			In figure	In Words	Unit	Amount	Rs.
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	5.00	1906.77	Rupees One Thousand Nine Hundred Six And Six Paise Seventy Seven Only	Per cubic metre.		9534.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	77.40	5338.98	Rupees Five Thousand Three Hundred Thirty Eight And Paise Ninety Eight Only	Per cubic metre.		413237.00
Quoted rates percentage in figures						Total:-	422771.00
Quoted rates percentage in words							

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Rathana Ropa Ghar Kapoor Basti via Jagrena Km 0/00 to 7/150 (SH:- C/o Edge wall at RD 2/200 to (PDNA-2025)

Estimated Cost :- Rs. 1,70,232/-
Earnest Money :- Rs. 3400/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	In figure	Rate In Words	Unit	Amount Rs.
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	34.19	228.80	Rupees Two Hundred Twenty Eight And Paise Eighty Only	Per Cubic metre	7823.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	40.97	3813.55	Rupees Three Thousand Eight Hundred Thirteen And Paise Fifty Five Only	Per Cubic metre	156241.00
3	Steel work welded in built up sections including cutting,hoisting, fixing, in position and applying a priming coat of red lead paint in grating, Framed guards, bars, ladders railings,brackets & similar works complete as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	28.00	220.30	Rupees Two Hundred Twenty And Paise Thirty Only	per Kilogram	6168.00
Total:-						170232.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work:- R/R Damages on Jia to fotta road Km 0/00 to 1/500(SH:-P/L GII,CC Pavement at Rd 0/500 to 0/670)(PDNA 2025-26)

Estimated Cost :- Rs. 4,23,686/-
Earnest Money :- Rs. 8500/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five milimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	8.00	1906.77	Rupees One Thousand Hundred Six And Paise Seventy Seven Only	Per cubic metre.	15254.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in sub structure nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty milimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	76.50	5338.98	Rupees Five Thousand Three Hundred Thirty Eight And Paise Ninety Eight Only	Per cubic metre.	408432.00
Quoted rates percentage in figures					Total:-	423686.00
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- C/O Samshan Ghat at Rathan Ropa.(SW:- C/O R/wall at Rd 0/00 to 0/07 & B/wall at Rd 0/00 to 0/010) (DC Deposit VKVNY)

Estimated Cost :- Rs. 1,69,242/-
Earnest Money :- Rs. 3400/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	12.26	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per cubic metre.	2909.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	34.52	3728.80	Rupees Three Thousand Seven Hundred Twenty Eight And Paise Eighty Only	Per cubic metre.	128718.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	9.00	228.80	Rupees Two Hundred Twenty Eight And Paise Eighty Only	Each	2059.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	2.38	576.30	Rupees Five Hundred Seventy Six And Paise Thirty Only	Per cubic metre.	1372.00
5	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	6.86	1127.10	Rupees One Thousand One Hundred Twenty Seven And Paise Ten Only	Per cubic metre.	7732.00

5

and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	6.86	3655.93	Rupees Three Thousand Eight Hundred Fifty Five And Paise Ninety Three Only	Per cubic metre	20492.00
				Total:-	169242.00

Executive Engineer
Palampur Division
HP PWD Palampur

Draft Schedule of Quantity

Name of Work:- R/R Damages on Kandi to Thalla Malenta Road Km 0/00 to 4/500 (SH:- C/o Wire Crate at RD 0/750 to 0/760) (PDNA 20/5-2026)

Estimated Cost :- Rs. 2,34,957/-
Earnest Money :- Rs. 4700/-
Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	12.50	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre	2966.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetre) dia GI wire conforming to IS:280 and IS:4826 in 100mm x100mm (Hundred millimetre into hundred millimetre) mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone bounders weighing not less than 25 Kg (Twenty five kilogram) each as per drawing and technical specification clause 1301 as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	93.75	2474.57	Rupees Two Thousand Four Hundred Seventy Four And Paise Fifty Seven Only	Per Cubic metre	231991.00
			Total:-			234957.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Draft Schedule of Quantity approved
234957.00 only

Executive Engineer
Palampur Division
HP PWD Palampur

5

Schedule of Quantity

Name of work:- Restoration of rain damages on Dharamshala Yol Dadh Holta Chadiar Sandhole road Km 33/00 to 40/500 (SH:- P/L WBM G-III, Tarring work & CC Pavement at various Rd's in between Km 34/500 to 36/300) (PDNA-2025)							Estimated Cost :- Rs. 4,23,549/- Earnest Money :- Rs. 8500/- Time Limit :- Three Months		
S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.			
			In figure	In Words					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	111.38	228.80	Rupees Two Hundred Twenty Eight And Paise Eighty Only	Per cubic metre.	25484.00			
2	Construction of Granular Sub Base 150mm thick (One hundred fifty millimetre thick) by providing well graded material, spreading in uniform layers with tractor grader on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compacting with three wheel roller 80-100 (Eighty to hundred) KN static roller to achieve the desired density, complete as per MORD Technical Specificationsection 400 for grading-I material and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	51.75	1525.40	Rupees One Thousand Five Hundred Twenty Five And Paise Forty Only	Per Cubic metre	78939.00			
3	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge.The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	51.75	1949.15	Rupees One Thousand Nine Forty Nine And Paise Fifteen Only	Per Cubic metre	100869.00			
4	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.85 Kg. (Zero decimal eight five Kilogram) per Square metres using mechanical means as per technical specification clause 502, and as per the directions of Engineer-in-charge including carriage of materials within all leads and lifts and other incidents. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	345.00	80.50	Rupees Eighty And Paise Fifty Only	Per Cubic metre	27773.00			

7

	Providing and applying tack coat with Bitumen emulsion (RS-1) using emulsion pressure distributor at the rate of 0.275 Kg. (Zero decimal two seven five Kilogramme) per Square metres on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per technical specification clause 503, as per directions of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	345.00	38.00	Rupees Thirty Eight Only	Per Cubic metre	13110.00
6	Providing and laying 25mm (Twenty five millimetre) compacted thick Bituminous Concrete with crushed stone aggregate of grading -II (Two), 13.2 (Thirteen point two) millimetre nominal size, using bitumen VG-10 (VG-Ten) minimum 5.5% (Five point five percent) of weight of mix and filler on thoroughly cleaned surface by mechanical broom and dust removed by compressed air, mixed in computerised batch mix/HMP of 80-100 (Eighty to hundred) TPH capacity calibrated from time to time, mixing the bituminous concrete, transporting the mix material in clean insulated vehicles covered while in transit or awaiting, tipping and laying with hydrostatic paver finisher with sensor control to the required level alignment and grade, rolling with smooth wheeled, vibratory and tandem power road roller to achieve the desired compaction as per MORT&H specification clause 507(5th revision) complete , within all leads and lifts including carriage of materials, plants and equipments by mechanical transport, as per the direction of Engineer-in- Charge. The rate is including octroi, royalty, Malkana. toll tax, sale tax, GST or other taxes imposed by the Government.	8.63	15500.00	Rupees Fifteen Thousand Five Hundred Only	Per Cubic metre	133765.00
7	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	4.05	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	21623.00
8	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental .The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	5.52	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per Cubic metre	21986.00
Total :-						423549.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Tanda Panthar Band Vihar Mollichak Road Km 0/00 to 10/00 (SH:- P/L Interlocking Paver Block at 3/350 & 3/275 to 3/300) (PDNA-2025)

Estimated Cost :- Rs. 1,67,757/-
Earnest Money :- Rs. 3400/-

Time Limit :- Three Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre) to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	6.00	1804.00	Rupees One Thousand Eight Hundred Four Only	Per cubic metre	10824.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	138.00	1049.60	Rupees One Thousand Forty Nine And Paise Sixty Only	Per square metre.	144845.00
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	2.34	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per cubic metre.	12088.00
Total :-						167757.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Palampur Neugal Park road (SH:- Improvement of road at RD 0/250 to 0/370 & 0/400 to 0/475)

Estimated Cost :- Rs. 1,68,129/-
 Earnest Money :- Rs. 3400/-
 Time Limit :- Three Months

Description of Item	Quantity	Rate		Unit	Amount Rs.
		In figure	In Words		
Excavation in hilly area in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of un-useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material to the approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling fine dressing and carriage of machineries, materials, tools, equipment and safety measured and other incidentals necessary to complete the work by mechanical means and labour if required. Recovery of stones to the tune of 75.20 cubic metre quantity at the rate of Rs. 300/- per cum shall be effected from the contractor's running bill on Pro-rata basis as per actual quantity executed. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	566.74	296.66	Rupees Two Hundred Ninety Six And Paise Sixty Six Only	Per Cubic metre	168129.00
Total :-					168129.00

Quoted rates percentage in figures

Quoted rates percentage in words

Executive Engineer
 Palampur Division
 HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Dharamshala Yol Dadh Holta Chadiar Sandhole road Km 15/00 to 31/00 (SH:- C/o R/wall at RD to 16/420) (PDNA-2025)

Estimated Cost :- Rs. 1,96,266/-
Earnest Money :- Rs. 3900/-
Time Limit :- Three Months

S. No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	22.40	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	Rs. 5316.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	50.00	3644.05	Rupees Three Thousand Six Hundred Forty Four And Paise Five Only	Per Cubic metre	182203.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	15.0	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Each	3560.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	9.00	576.30	Rupees Five Hundred Seventy Six And Paise Thirty Only	Per cubic metre.	5187.00
Total:-						196266.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division,
HP PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of rain damages on Topo Basti road 0/000 to 0/400 (S.H :-P/L WBM G-II, G-III & C.C Pavement 0/250 to 0/301.50) (PDNA 2025)

Estimated Cost :- Rs. 1,67,932/-
Earnest Money :- Rs. 3400/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	11.98	1804.00	Rupees One Thousand Eight Hundred Four Only	Per Cubic metre.	21612.00
2	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	11.98	1886.00	Rupees One Thousand Eight Hundred Eighty Six Only	Per Cubic metre.	22504.00
3	Providing and laying cement concrete 1:2:4(One cement: Two sand:four graded crushed stone aggregate 20 mm (Twenty millimetre) nominal size mechanically mixed and vibrated as per approved specification, excluding cost of form work and reinforcement for reinforced concrete work in suspended floor roofs, landing and shelves and their supports balconies, beams, girder, bressumers and cantiliver in all depth/ height upto any floor level. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	23.95	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per Cubic metre	123726.00
Quoted rates percentage in figures						Total :- 167932.00
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Tanda Pantehar Band Vihar Molichak Dharamman Kandwari road Km 0/00 to 10/00 (SH:- C/o
RD 5/200 to 5/206 & 5/125 to 5/131) (PDNA-2025)

Estimated Cost :- Rs. 1,68,756/-
Earnest Money :- Rs. 3400/-
Time Limit :- Three Months

	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	21.60	230.00	Rupees Two Hundred Thirty Only	Per Cubic metre	4968.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect of per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	40.06	3700.00	Rupees Three Thousand Seven Hundred Only	Per Cubic metre	148222.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	24.0	215.00	Rupees Two Hundred Fifteen Only	Each	5160.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	16.92	615.00	Rupees Six Hundred Fifteen Only	Per cubic metre.	10406.00
Total:-						168756.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Tanda Panthar Band Vihar Molichak Dharamman Kandwari road Km 0/00 to 10/00 (SH:- C/o
RD 0/600 to 0/606, 2/500 to 2/506 & 2/510 to 2/516) (PDNA-2025)

Estimated Cost :- Rs. 2,51,577/-
Earnest Money :- Rs. 5000/-
Time Limit :- Three Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	32.40	230.00	Rupees Two Hundred Thirty Only	Per Cubic metre	7452.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	59.40	3700.00	Rupees Three Thousand Seven Hundred Only	Per Cubic metre	219780.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	36.0	215.00	Rupees Two Hundred Fifteen Only	Each	7740.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	27.00	615.00	Rupees Six Hundred Fifteen Only	Per cubic metre.	16605.00
Total:-						251577.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of rain damages on Rathan Ropa Ghar Kapoor Basti via Jagdena Km 0/00 to 7/150 (SH:- P/L Interlocking Paver block at RD 3/510 to 3/535 & 3/590 to 3/615) (PDNA-2025)

Estimated Cost :- Rs. 1,68,072/-
Earnest Money :- Rs. 3400/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	6.00	1804.00	Rupees One Thousand Eight Hundred Four Only	Per Cubic metre.	10824.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	138.30	1049.60	Rupees One Thousand Forty Nine And Paise Sixty Only	Per square metre.	145160.00
3	Providing and laying cement concrete 1:2:4(One cement: Two sand:four graded crushed stone aggregate 20 mm (Twenty millimetre) nominal size mechanically mixed and vibrated as per approved specification, excluding cost of form work and reinforcement for reinforced concrete work in suspended floor roofs, landing and shelves and their supports balconies, beams, girder, bressumers and cantiliver in all depth/ height upto any floor level. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	2.34	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per Cubic metre	12088.00
Total :-						168072.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of work:- Restoration of rain damages on Palampur Neugal Park road (SH:- P/L Interlocking paver block 2/120 to 2/144, 2/250 to 2/270 & C/o U-shape drain at RD 2/150 to 2/160.20) (PDNA-2025)

Estimated Cost :- Rs. 1,68,831/-
Earnest Money :- Rs. 3400/-

Time Limit :- Three Months

Sl. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	26.43	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	6272.00
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and combar including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	1.98	1127.15	Rupees One Thousand One Hundred Twenty Seven And Paise Fifteen Only	Per Square metre	2232.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	6.60	3813.60	Rupees Three Thousand Eight Hundred Thirteen And Paise Sixty Only	Per Cubic metre	25170.00
4	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make NTC or equivalent having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	66.00	1169.50	Rupees One Thousand One Hundred Sixty Nine And Paise Fifty Only	Per Square metre	77187.00
5	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	0.66	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per cubic metre.	3524.00

15

Hoisting and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure Concrete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	3.93	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per Cubic metre	15653.00
Framed guards, bars, ladders railings, brackets & similar works complete as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	481.60	80.55	Rupees Eighty And Paise Fifty Five Only	per Kilogram	38793.00
Total :-					168831.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

of work:- Restoration of rain damages on Holta to Tanda Holta road Km 0/00 to 5/500 (SH):- P/L Interlocking Paver Block at RD 2/650 to 2/675
00 to 3/625) (PDNA-2025)

Estimated Cost :- Rs. 1,67,757/-
Earnest Money :- Rs. 3400/-
Time Limit :- Three Months

No	Description of item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre) to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	6.00	1804.00	Rupees One Thousand Eight Hundred Four Only	Per cubic metre	10824.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	138.00	1049.60	Rupees One Thousand Forty Nine And Paise Sixty Only	Per square metre.	144845.00
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	2.34	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per cubic metre.	12088.00
Total :-						167757.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

17

Schedule of Quantity

Estimated Cost :- Rs. 1,67,968/-
Earnest Money :- Rs. 3400/-
Time Limit :- Three Months

of work:- Restoration of rain damages on Palampur Neugal Park road (SH:- P/L Interlocking paver block 1/720 to 1/740, , 1/930 to 1/960 & shape drain alongwith grating at RD 1/830 to 1/840 & 1/850 to 1/860) (PDNA-2025)

Description of Item	Quantity	Rate		Unit	Amount Rs.
		In figure	In Words		
Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	25.74	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	6108.00
Imposed by the Government but excluding GST. Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	1.80	1127.15	Rupees One Thousand One Hundred Twenty Seven And Paise Fifteen Only	Per Square metre	2029.00
Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	6.00	3813.60	Rupees Three Thousand Eight Hundred Thirteen And Paise Sixty Only	Per Cubic metre	22882.00
Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make NTC or equivalent having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	60.00	1169.50	Rupees One Thousand One Hundred Sixty Nine And Paise Fifty Only	Per Square metre	70170.00
Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	0.60	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per cubic metre.	3203.00

Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	4.58	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per Cubic metre	18242.00
Steel work welded in built up sections including cutting, hoisting, fixing, in position and applying a priming coat of red lead paint in grating, Framed guards, bars, ladders railings, brackets & similar works complete as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	562.80	80.55	Rupees Eighty And Paise Fifty Five Only	per Kilogram	45334.00
Total :-					167968.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Line of Work:- Restoration of rain damages on Tanda Panthar Band Vihar Molichak Dharamman Kandwari road Km 0/00 to 10/00 (SH:- C/o 900mm dia Hume pipe culvert at RD 4/425, U-shape drain at RD 4/375 to 4/425) (PDNA-2025)

Estimated Cost :- Rs. 1,84,604 /-
Earnest Money :- Rs. 3700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	58.56	221.40	Rupees Two Hundred Twenty One And Paise Forty Only	Per Cubic metre	12965.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	27.76	3854.00	Rupees Three Thousand Eight Hundred Fifty Four Only	Per Cubic metre	106987.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1 : 2 ½ : 5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetra and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	9.97	4264.00	Rupees Four Thousand Two Hundred Sixty Four Only	Per Cubic metre	42512.00
4	Providing and laying (to level or slope) 900mm dia (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the entire satisfaction and direction of Engineer in-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	7.50	2952.00	Rupees Two Thousand Nine Hundred Fifty Two Only	Per Running metre	22140.00
					Total:-	184604.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work:- Bandla Chuggar Thakurdwara road 0/00 to 6/000, Dharamshala Yol Dadh Palampur road 27/00 to 33/000, Cinema Hall byepass road 0/00 to 1/500.(SW:-Writing letters with black Japan paint)

Estimated Cost :- Rs. 83,972/-

Earnest Money :- Rs. 1700

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	94.50	76.20	Rupees Seventy Six And Paise Twenty Only	Per square metre.	7201.00
2	Painting two coats (excluding priming coats) on new concrete masonry/ asbestos cement/plaster surfaces with ready mixed synthetic enamel paint of approved brand other than white paint brushing to give an any shade including cleaning the surface of all dirt, dust and other foreign matters and sand papering and stopping within all leads lifts and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	81.00	72.90	Rupees Seventy Two And Paise Ninety Only	Per square metre.	5905.00
3	Writing letters or figures on any surface with black japan paint (stops,comas,hyphens and the like not to be measured and paid separately) as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	38100.00	1.86	Rupees One And Paise Eighty Six Only	Per letter Per cubic metre.	70866.00
Quoted rates percentage in figures					Total:-	83972.00
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work:- Restoration of rain damages on Parour Lahia Chachian MDR-55 from Km 0/00 to 33/00 (S.H :- Writing Painting on bridges, roads from Km 0/00 to 100/00)

Estimated Cost :- Rs. 83,426/-
Earnest Money :- Rs. 1700/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Removing white wash or colour wash by steel wire brushing and/or scrapping sand papering and preparing the wall surface smooth including necessary repairs to scratches complete. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	330.00	12.70	Rupees Twelve And Paise Seventy Only	Per square metre.	4191.00
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	16.20	76.30	Rupees Seventy Six And Paise Thirty Only	Per square metre.	1236.00
3	Painting two coats (excluding priming coats) on new concrete masonry/ asbestos cement/plaster surfaces with ready mixed synthetic enamel paint of approved brand other than white paint brushing to give an any shade including cleaning the surface of all dirt, dust and other foreign matters and sand papering and stopping within all leads lifts and other incidentals as per the direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	330.00	76.30	Rupees Seventy Six And Paise Thirty Only	Per square metre.	25179.00
4	Re-lettering with black Japan paint of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	27800.00	1.90	Rupees One And Paise Ninety Only	Per letter per cubic meter	52820.00
Total:-						83426.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of work:- Restoration of rain damages on Spedu to Gorath road (SH:-C/o U-shape drain at RD 0/200 to 0/280 & P/L CC Pavement at RD 0/200 to 0/229.50) (PDNA-2025)

Estimated Cost :- Rs. 1,59,955/-
Earnest Money :- Rs. 3200/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	30.80	230.00	Rupees Two Hundred Thirty Only	Per Cubic metre	7084.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement : Three sand : Six graded crushed / broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications. Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	18.20	3873.55	Rupees Three Thousand Eight Hundred Thirteen And Paise Fifty Five Only	Per Cubic metre	69407.00
3	Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	6.85	1845.00	Rupees One Thousand Eight Hundred Forty Five Only	Per Cubic metre	12638.00
4	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 KN in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.71	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per Cubic metre	70826.00
Total :-						159955.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work: Restoration of rain damages on Kand to Tikker via Kalohi Mata (SH:- C/o Both side approaches of 2.00 mtr span RCC slab culvert
10 (RD 0/969 to 0/977.50 & 0/992.50 to 1/001.50) (PDNA-2025)

Estimated Cost :- Rs.4,04,801/-
Earnest Money :- Rs.8100/-
Time Limit :- Three Months

No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST..	37.11	230.00	Rupees Two Hundred Thirty Only	Per Cubic metre	8535.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	97.83	3567.00	Rupees Three Thousand Five Hundred Sixty Seven Only	Per Cubic metre	348960.00
3	Government but excluding GST. Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	45	221.00	Rupees Two Hundred Twenty One Only	Each	9945.00
4	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	37.81	557.60	Rupees Five Hundred Fifty Seven And Paise Sixty Only	Per cubic metre.	21083.00

Embankment for road way with approved materials from borrowpits , or other sources in layers of suitable thickness not less than 200mm (Two hundred millimeter) thick each layers and compacted with 80-100 (Eighty - Hundred) K.N static/ vibratory road roller to meet the requirement of table 300.1 and 300.2 of technical specifications to lines, grades, levels and cross sections as per drawings or direction of the Engineer-in-Charge to Technical specification clause 301 and other relevant clauses including preparation of foundation for embankment in all kinds and classification of soils including saturated soil and dewatering/ bailing out of water where ever required including handling of material for construction of embankments within all leads and lifts. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.

Quoted rates percentage in figures

Quoted rates percentage in words

120.58	135.00	Rupees One Hundred Thirty Five Only	Per Cubic metre	16278.00
Total:-				404801.00

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Link road to village drognu road Km 0/00 to 1/600.(S.H:- C/O R/Wall at Rd 1/300 to 1/315) (PDNA 2025-26)

Estimated Cost :- Rs. 1,89,412/-
 Earnest Money :- Rs. 3800/-
 Time Limit :- Three Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	20.25	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre.	4805.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	48.04	3644.06	Rupees Three Thousand Six Hundred Forty Four And Paise Six Only	Per Cubic metre.	175061.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	8.33	576.27	Rupees Five Hundred Seventy Six And Paise Twenty Seven Only	Per Cubic metre.	4800.00

ing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete	20.00	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	No	4746.00
putment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal)					
towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of					
Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, sale					
tax, or other taxes imposed by the Government but excluding GST.				Total:-	189412.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Patti Bhodal Pahra road Km 0/00 to 5/00 (SH:- Maintenance of earthen shoulders & un-lined
face drain at RD 1/200 to 1/700) (PDNA-2025) 11750 to 5100 (CPWD-2025)

Estimated Cost :- Rs. 1,66,260/-
Earnest Money :- Rs. 3300/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1275.00	50.00	Rupees Fifty Only	Per Square metre	63750.00
2	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	2010.00	51.00	Rupees Fifty One Only	Per Running metre	102510.00
Total :-						166260.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

of work:- Restoration of rain damages on Dharamshala Yol Dadh Chadiyar Sandhole road (SH:- Maintenance of earthen shoulders & un-
d surface drain at RD 33/200 to 33/700 & 34/650 to 34/600) (PDNA-2025)

Estimated Cost :- Rs. 1,66,490/-
Earnest Money :- Rs. 3300/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Maintenance of Earthen shoulder (Filling with fresh selected soil) Making up loss of material/ irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per Technical specification clause 1903. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1300.00	50.00	Rupees Fifty Only	Per Square metre	65000.00
2	Construction of un lined surface drain of average cross sectional area 0.40 Sqm. In soil to specified lines, grades, level and dimension excavated materials to be used in embankment with a lift upto 3 m and lead of 50m (Average lead 25m) as per technical specification clause 307. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1990.00	51.00	Rupees Fifty One Only	Per Running metre	101490.00
Total :-						166490.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					


 Executive Engineer
 Palampur Division
 HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Palampur to Lohna Langha road (SH:- C/o U-shape drain at RD 3/385 to 3/451 & B/wall at RD 5/185 (PDNA-2025)

Estimated Cost :- Rs. 2,52,709/-
Earnest Money :- Rs. 5100/-
Time Limit :- Three Months

	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
	Demolishing R.C.C. work manually/ by mechanical means including cutting reinforcement bars and stacking of steel bars and disposal of unserviceable material within 50 metres as per direction of Engineer - in- charge. as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	10.000	932.20	Rupees Nine Hundred Thirty Two And Paise Twenty Only	Per cubic metre.	9322.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	72.91	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	17302.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	55.90	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per Cubic metre	222652.00
4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	15	228.85	Rupees Two Hundred Twenty Eight And Paise Eighty Five Only	Each	3433.00
Total :-						252709.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur