



Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

No.PWD/JSPR/CB/Tenders/2026-27-7701-09
To,

Dated:- 26-9-26

The Chief Engineer (KZ),
Himachal Pradesh, PWD,
Dharamshala (HP).

Subject:- Publication of Tender Notice on departmental website.

Sir,

Enclosed please find herewith tender notice for publication of the same on departmental website as per Notification issued by the worthy Principal Secretary (PW) to the Govt. of HP letter No. PBW-(B) A-(3) 1/2024 dated Shimla-2 dated 03.01.2025 and instructions issued by the worthy E-in-C, HPPWD Shimla letter No. PWD/ ICT Wing/ Website dated 22.05.2026.

It is certified that the works for which tenders invited are of urgent nature and in public interest.

DA/ As above.

Executive Engineer,
Jaisinghpur Division,
HPPWD Jaisinghpur

Copy forwarded to the following for information and necessary please:-

1. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
- 2-4. All the Assistant Engineers working under this Division.
- 5-6. The Drawings Branch and Accounts Branch in this office.
7. Notice Board.
8. N.I.T. Register

Executive Engineer
Jaisinghpur Division,
HP.PWD., Jaisinghpur.


OFFICE OF
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur
Himachal Pradesh Works Department Jaisinghpur 176095 Phone No. 01894-228030,
Email ee-jalpud-hp@gov.in

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **03.10.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **01.10.2026** up to **4:00 PM** and the application for issue of tender form shall be received on or before **01.10.2026** up to **1:00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the Earnest Money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-

Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar Sandhole road Km 0/00 to 87/00 (SH:-C/O R/wall at Km 75/432 to 74/445) PDNA 2025	199017.00	4000.00	Two Month	350/-
2	Restoration of rain Damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O B/wall from RD 14/540 to 14/557) PDNA 2025	176622.00	3600.00	Two Month	350/-
3	Restoration of rain Damages on Bhuana to Ashapuri road Km 0/00 to 12/135 (SH:-P/L soling and CC pavement work at RD 10/560 to 10/678) PDNA 2025	351699.00	7100.00	Two Month	350/-
4	Restoration of rain Damages on Trehla Badhala Dali road Km 0/00 to 4/500 (SH:-P/L CC pavement from RD 2/00 to 2/070) PDNA 2025	334692.00	6700.00	Two Month	350/-
5	Restoration of rain Damages on Gallu Bhoda Shivnagar road Km 0/00 to 13/600 (SH:-C/O B/wall to protect the existing Bridge in Km 3/942.50 to 3/995.50) Shivnagar side) PDNA	499987.00	10000.00	Two Month	350/-
6	C/O Lambagaon to Lower Lambagaon via Kunjeshwar Mahadev road (SH:- C/O CC pavement from RD 2/250 to 2/308) DC Deposit	169476.00	3400.00	Two Month	350/-
7	Restoration of rain Damages on Upper Lambagaon to Vishwakarma Mandir road Km 0/00 to 0/750 (SH:-C/O side drain from RD 0/600 to 0/610) PDNA 2025	89984.00	2000.00	Two Month	350/-
8	Restoration of rain Damages on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:-C/O R/wall from RD 22/040 to 22/048) PDNA 2025	192484.00	3900.00	Two Month	350/-
9	Restoration of rain Damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O B/wall from RD 14/557 to 14/580) PDNA 2025	226825.00	4600.00	Two Month	350/-
10	Restoration of rain Damages on Gallu Bhoda Shivnagar road Km 0/00 to 13/600 (SH:-C/O B/wall to protect the existing Bridge in Km 3/995.50 to 4/048) Shivnagar side) PDNA	499818.00	10000.00	Two Month	350/-


Executive Engineer
Jaisinghpur Division
HPPWD Jaisinghpur

— Contd. P-2 —



Terms & Conditions:-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.




Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.
(On behalf of Governor of Himachal Pradesh)

(4)

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar Sandhole road Km 0/00 to 87/00 (SH:-C/O R/wall at Km 75/432 to 74/445) PDNA 2025				Estimated cost Rs.		199017.00
				Earnest Money Rs.		4000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	90.00	130.00	Rupees One Hundred Thirty Only	Per cubic Metre	11700.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	23.40	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	4914.00

3	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	51.48	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	175032.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	11.70	210.00	Rupees Two Hundred Ten Only	Per Running Metre	2457.00
5	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	7.02	700.00	Rupees Seven Hundred Only	Per cubic Metre	4914.00
	Total					199017.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 H.P.W.D Jaisinghpur


(2)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O B/wall from RD 14/540 to 14/557) PDNA 2025

S. N.	Description of Item	Quantity	Estimated cost Rs.		Earnest Money Rs.		Time Limits	
			176662.00		3600.00		Two month	
			Rate		Unit		Amount	
			In Figures	In Word				
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	23.46	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre		4927.00	
2	Providing and laying in position cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and vibrated curing complete excluding the cost of centering and shuttering in foundation and plinth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications and as directed by the Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	45.90	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Per Cubic Metre		167535.00	


3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the	20.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	4200.00
	Total					176662.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

(3)

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Bhuana to Ashapuri road Km 0/00 to 12/135 (SH:-P/L soling and CC pavement work at RD 10/560 to 10/678) PDNA 2025			Estimated cost Rs.		351699.00	
			Earnest Money Rs.		7100.00	
			Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Providing laying spreading and compacting by manual means of stone aggregate of size 90mm to 45mm (ninety millimetre to forty five millimetre) Grading-I to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to hundred) K.N. static roller in stages to proper grade and camber, applying and brooming, stone screening type-B of size 11.2mm (eleven decimal point two millimetre) nominal size at the rate of 0.30 cum (zero point three zero cubic metre) per ten square metre and binding material at the rate of 0.08 (zero decimal zero eight) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per M.O.R.D. technical specifications clause 405 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	35.40	1460.00	Rupees One Thousand Four Hundred Sixty Only	Per Cubic Metre	51684.00
2	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishig and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	53.10	5650.00	Rupees Five Thousand Six Hundred Fifty Only	Per Cubic Metre	300015.00
Total						351699.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 H.P.WD Jaisinghpur

(4)


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Trehla Badhala Dali road Km 0/00 to 4/500 (SH:-P/L CC pavement from RD 2/00 to 2/070) PDNA 2025

Estimated cost Rs.	334692.00
Earnest Money Rs.	6700.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	36.23	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	7608.00
2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	18.38	1800.00	Rupees One Thousand Eight Hundred Only	Per Cubic Metre	33084.00

3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finish and reinforcement- All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty milimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	49.00	6000.00	Rupees Six Thousand Only	Per Cubic Metre	294000.00
	Total					334692.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 U.P.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Gallu Bhoda Shivnagar road Km 0/00 to 13/600 (SH:-C/O B/wall to protect the existing Bridge in Km 3/942.50 to 3/995.50) Shivnagar side) PDNA

Estimated cost Rs.	499987.00
Earnest Money Rs.	10000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	31.80	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	6678.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	121.90	3400.00	Rupees Three Thousand Four Hundred Only	Per cubic Metre	414460.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	80.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	16800.00
4	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	238.65	260.00	Rupees Two Hundred Sixty Only	Per cubic Metre	62049.00
Total						499987.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 H.P.W.D Jaisinghpur


(6)

SCHEDULE OF QUANTITY

Name of work :-C/O Lambagaon to Lower Lambagaon via Kunjeshwar Mahadev road (SH:- C/O CC pavement from RD 2/250 to 2/308) Deposit SDF/2026/1094

from RD 2/250 to 2/308) Deposit SDF/2026/1094			Estimated cost Rs.		169476.00	
			Earnest Money Rs.		3400.00	
			Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	2.00	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	420.00
2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	1.92	1800.00	Rupees One Thousand Eight Hundred Only	Per Cubic Metre	3456.00

3	Providing and laying in position cement concrete of specified grade of reinforcement concrete excluding the cost of centering and shuttering finishing and reinforcement. All work up to plinth level : 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	27.60	6000.00	Rupees Six Thousand Only	Per Cubic Metre	165600.00
	Total					169476.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					



 Executive Engineer,
 Jaisinghpur Division,
 MP PWD Jaisinghpur

(7)

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Upper Lambagaon to Vishwakarma Mandir road Km 0/00 to 0/750 (SH:-C/O side drain from RD 0/600 to 0/610) PDNA 2025				Estimated cost Rs.		89984.00
				Earnest Money Rs.		2000.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	33.00	140.00	Rupees One Hundred Forty Only	Per cubic Metre	4620.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	5.28	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	1109.00


3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 20mm(twenty millimetre) nominal size) on ground or under water including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work and curing complete in drain as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	19.38	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	82365.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	9.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	1890.00
Total						89984.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 H.P.WD Jaisinghpur

SCHEDULE OF QUANTITY


Name of work :-Restoration of rain Damages on Bhawarna to Jhunga Devi road Km 15/500 to 26/250 (SH:-C/O R/wall from RD 22/040 to 22/048) PDNA 2025				Estimated cost Rs.		192484.00
				Earnest Money Rs.		3900.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	45.76	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	9610.00
2	Providing and laying in position cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and vibrated curing complete excluding the cost of centering and shuttering in foundation and plinth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications and as directed by the Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	40.76	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Per Cubic Metre	148774.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	10.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	2100.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	40.00	800.00	Rupees Eight Hundred Only	Per cubic Metre	32000.00
	Total					192484.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 MP.PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on Tinbar to Jaisinghpur road Km 0/00 to 18/300 (SH:-C/O B/wall from RD 14/557 to 14/580) PDNA 2025			Estimated cost Rs.		226825.00	
			Earnest Money Rs.		4600.00	
			Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	31.74	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	6665.00
2	Providing and laying in position cement concrete 1:4:8 (One cement isto four sand isto eight graded broken/crushed stone aggregate 40mm (Forty millimetres) nominal size mechanically mixed and vibrated curing complete excluding the cost of centering and shuttering in foundation and plinth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design, specifications and as directed by the Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	60.03	3650.00	Rupees Three Thousand Six Hundred Fifty Only	Per Cubic Metre	219110.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the	5.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	1050.00
	Total					226825.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					


 Executive Engineer,
 Jaisinghpur Division,
 HP.PWD Jaisinghpur


SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Gallu Bhoda Shivanagar road Km 0/00 to 13/600 (SH:-C/O B/wall to protect the existing Bridge in Km 3/995.50 to 4/048) Shivanagar side) PDNA

Estimated cost Rs.	499818.00
Earnest Money Rs.	10000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	31.80	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	6678.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	121.90	3400.00	Rupees Three Thousand Four Hundred Only	Per cubic Metre	414460.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	80.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	16800.00
4	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock, soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.	238.00	260.00	Rupees Two Hundred Sixty Only	Per cubic Metre	61880.00
Total						499818.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						


 Executive Engineer,
 Jaisinghpur Division,
 P.W.D Jaisinghpur