

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-I-Tender-2026-27

7546-54

Dated:- 15/09/2026

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. 
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. 

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **24.09.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **23.09.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **23.09.2026 up to 5:00 PM**.


The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1.	Construction of Ambulance road from NH-205 to Daseran (Harijan Basti) Ward No. 4 Km 0/00 to 0/380 (SH:- C/o R/wall at RD 0/077 to 0/101 & C/o RCC Hue Pipe Culvert at RD 0/075) DMFT Deposit.	4,79,461/-	9,600/-	2 Months	350/-
2.	Restoration of Rain damages of Darla Sub Division (SH:- Hiring of JCB for removal of slips in Navgaoun Section Various roads) Job No.4	99,000/-	2,000/-	15 days	350/-
3.	R/R damages on Arki Jalana road km. 0/0 to 5/500 (SH:-C/o R/wall in k. 0/950 to 0/954 and B/wall at Rd 1/045 to 1/055)	99,990/-	2,000/-	1 Month	350/-
4	C/o Path House of Durga Ram to Parkash and others village Banali (G.P Sewra Chandi) (SH:-C/o Edge wall at Various Rds) DFMT	4,12,017/-	10,000/-	1 Month	350/-
5	R/R damages on Kharsi Kandhar road km. 0/0 to 14/0 (SH:-C/o R/wall at Rd 4/825 to 4/835.50) PDNA 2025	1,97,045/-	4,000/-	1 Month	350/-

6	R/R daages on Nauri Mainthi road km. 0/0 to 2/300(SH:-C/o R/wall at Rd 0/015 to 0/023.20)PDNA 2025	99,383/-	2,000/-	1 Month	350/-
	R/R damages on Bathalang Jawara Palog road k. 0/0 to 9/0(SH:-C/o B/wall at R 7/030 to 7/086)PDNA 2025	4,98,602/-	10,000/-	1 Month	350/-
8	Restoration of rain damages of Arki Sub-Division HPPWD Arki under Arki-II section(SH:-Removal of slips/Dressing of road by hiring of JCB)Job No.11	99,000/-	2,000/-	1 Month	350/-
9	Restoration of rain damages of Kunihar Sub-Division HPPWD Kunihar under Diggall section section(SH:-Hiring of JCB for removal of slips in various roads locations etc)Job No.3	99,000/-	2,000/-	1 Month	350/-
10	Restoration of rain damages of Kunihar Sub-Division HPPWD Kunihar under Diggall section section(SH:-Hiring of JCB for removal of slips in various roads locations etc)Job No.4	99,000/-	2,000/-	1 Month	350/-
11	Restoration of rain damages of Darla Sub-Division HPPWD Darla (SH:-Hiring of JCB for removal of slips in Mangal section various roads)Job No.7	99,000/-	2,000/-	1 Month	350/-
12	Restoration of rain damages of Darla Sub-Division HPPWD Darla (SH:-Hiring of Tipper for removal of slips in Mangal section various roads)Job No.2	97,500/-	2,000/-	1 Month	350/-
13	C/o Culvert /Causeway in link road from Bhalag to Sehnali km. 0/0 to 4/555(SH:-P/L C.C. Pavement 1:4:8 & 1:2:4 & Cause way at Rds 3/0, 3/045, 3/105 and 3/210)DMFT	4,99,988/-	10,000/-	1 Month	350/-
14	C/o Boundary wall in Govt. High School Bagga, GP. Bagga, Tehsil Arki, Distt. Solan HP. (SH:-Providing and Fixing Fencing Gate, Plaster work and Painting.) DMFT Deposit.	2,29,672/-	5,000/-	1 Month	350/-
15	C/o boundary wall in Govt. High school Bagga GP Bagga(SH:-C/o boundary wall in school campus	4,04,828/-	8100/-	1 Month	350/-

Followings documents should be attached with the application for tenders:-

- The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division,
H.P.P.W.D. 

No: PW-AD-EA-I-Tender-2026-27- 7546-54

Dated:- 15/09/2026

Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3rd Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D. 

Certificate

Certified that the tenders called vide this notice inviting tender for 15 (Fifteen) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. 

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,79,461/- only	
Name of Work:- C/o Ambulance Road from NH-205 to Daseran (Harijan Basti) Ward No 4 Km 0/00 to 0/380.(SH:- C/o R/wall at Rd 0/077 to 0/101 & C/o RCC Hume Pipe Culvert at Rd 0/075) DMFT Deposit					Earnest Money :-Rs9,600/-Only	
					Time :- Two Months	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	67.86	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	11631
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	9.83	5291.95	Rupees. five thousand two hundred ninety one and paise ninety five only	P.Cum.	52020
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm dia pipe including carriage of materials in all leads and lifts. and as per the	7.50	3851.55	Rupees three thousand eight hundred fifty one and paise twenty only	P.Rmt	28887
4	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	79.20	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	347736
5	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	23.04	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	27724
6	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	41.80	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	11464
					Total	479461

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99000/- only ▶	
Name of Work:-Restoration of Rain Damages of Darla Sub Division . (SH:-Hiring of JCB for removal of Slips in Navgaoun Section Various Roads) Job No-4						Earnest Money :-Rs2000/-Only	
						Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4		5	6
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
						Total	99000

Quoted Rate Percent In Figure —

Quote Rate Percent In Words —


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Arki Jalana Road Km 0/00 to 5/500.(SH:- C/O R/wall in Km 0/950 to 0/954and B/wall at Rd 1/045 to 1/055)

Estimated Cost: -Rs99.990/- only

Earnest Money :-Rs2,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
			3	4		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	6.50	171.40	Rupees One hundred seventy one and paise fourty only	P.Cum.	1114
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	22.37	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	98218
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	2.40	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	658
					Total	99990

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:- C/o Path House of Durga Ram to Parkash and others Village Banali (G.P.Sewra Chandi). (SH:- C/o Edge wall at Various RD,s) DMFT

Estimated Cost:-Rs4,12,017/- only

Earnest Money :-Rs10,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	62.40	171.40	Rupees One hundred seventy one and paise forty only	P Cum.	10695
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	87.23	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	382992
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	12.60	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	15162
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	11.55	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	3168
					Total	412017

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY				Estimated Cost: -Rs1,97,045/- only		
Name of Work:- R/R Damages on Kharsi Kandhar Road Km 0/00 to14/00.(SH:- C/o R/wall at Rd 4/825 to 4/835.50)PDNA 2025				Earnest Money :-Rs4,000/-Only		
				Time :-One Month		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	16.17	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	2772
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	39.67	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	174175
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	12.60	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	15162
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	18.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	4937
					Total	197045

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Estimated Cost: -Rs99,383/- only

Earnest Money :-Rs2,000/-Only

Time :-One Month

Name of Work:- R/R Damages on Nanu Mainthi Road Km 0/00 to 2/300) (SH:- C/o R/wall at Rd 0/015 to 0/023.20) PDNA 2025

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	11.73	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	2011
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	19.93	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	87505
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	6.40	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	7701
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	7.90	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	2167
					Total	99383

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs4,98,602/- only	
Name of Work:- R/R Damages on Bathalang Jawara Palog Road Km 0/00 to 9/00 (SH:- C/o B/wall at Rd 7/030 to 7/086) PDNA 2025						Earnest Money :-Rs10,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
			Figure	Words			
1	2	3	4	5	6		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	82.35	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	14115	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	106.35	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	466940	
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	63.98	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	17547	
					Total	498602	

Quoted Rate Percentage in Figure
Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: 99000.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Arki-II Section						Earnest Money: 2000.00	
(SH:- Removal of slips/ Dressing of road by hiring of JCB) Job No-II						Time Period: 15 Days	
S. No	Sub head and items of work	Qty		Rate		Unit	Amount
1	2	3		In figures	In words	6	7
1	Hiring of JCB for removal of landslide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials within all leads, lifts and as per technical specification clause 302.3.5 and 1611 including carriage of materials upto all leads, lifts and as per direction of Engineer in Charge.	99.00	Hour	1000.00	Rupees one thousand and paise nil only	Per Hour	99000.00
	Total=						99000.00
	Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.						

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


Executive Engineer
Arki Division (B&R)
HPPWD Arki

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar sub division under Diggal Section HP,PWD Diggal.(Sh :Hiring of JCB for removal of slips in various roads-locations etc.) Job No.3

Estimated Cost :- Rs 99,000.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paise zero Only	Per Hours	99000.00
						Total	99000.00

Percentage Rates Quated in figure

Percentage Rates Quated in words


 Executive Engineer
 Arki Division (B&R)
 HP. PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain Damages on various roads under Kunihar sub division under Diggall Section HP,PWD Diggall.(Sh :Hiring of JCB for removal of slips in various roads-locations etc.) Job No.4

Estimated Cost :- Rs 99,000.00

Earnest money :- Rs 2,000.00

Time: One month

Sr.No.	Sub Head and Items of Work	Qty.		Rate		Unit	Amount
1	2	3		In figure	In words	6	7
1.00	Hiring of JCB for removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 meters and lead upto 1000 meters as per technical specification 302.3.5 and 1611 including carriage of materials upto all leads and lifts and as per the direction of Engineer in charge.	99.00	Hours	1000.00	Rupees One thousand and paise zero Only	Per Hours	99000.00
						Total	99000.00

Percentage Rates Quated in figure

Percentage Rates Quated in words

Executive Engineer
Arki Division (B&R)
HP, PWD. Arki.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of Rain Damages in Darla Sub Division . (SH:-Hiring of JCB for removal of slips in Mangal Section Various Roads.) (Job No-7)

Estimated Cost:-Rs99000/- only

Earnest Money :-Rs2000/-Only

Time :-Fifteen Days

S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
		3			4	5	6
1		99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge						
						Total	99000


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs97,500/- only	
Name of Work:-Restoration of Rain Damages of Darla Sub Division . (SH:-Hiring of Tipper for removal of slips in Mangal Section Various Roads.) (Job No- 2)						Earnest Money :-Rs2000/-Only	
						Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4		5	6
1	Hiring of Tipper for removal of slips and debris with minimum capacity of 5.5 cum per trip and minimum working 6(six)hours per day. The contractor /owner of the tipper shall bear the expension of P.O.L. charges , repair of machineries . Any accident and other damages to be the private and govt. property occur durring the working hours is the responsibility of contractor and debris disposed with in all leads and lifts as per the direction of Engineer-In- Charge.	150.00	Hour	650.00	Rupees six hundred fifty and paise nil only	P.Hour.	97500
						Total	97500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:- C/o Culvert /Cause way in Link Raod from Bhalag to Sehnali KM 0/00 to 4/555.(SH:-P/L
C.C. Pavement 1:4:8. & 1:2:4 & Cause way at Rds 3/00,3/045,3/105,3/210.) DMFT


Estimated Cost:-Rs4,99,988/- only

Earnest Money:-Rs10,000/-Only

Time :-One Month

Sub head and items of work

S. No.	2	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and	126.00	171 40	Rupees One hundred seventy one and paise fourty only	P.Cum.	21596
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	63.00	1425.25	Rupees one thousand four hundred twenty five and paise twenty five only	P.Cum.	89791
3	Providing and Laying concrete for plain/reinforced concrete 1:4:8 (one cement : four sand: eight graded stone aggregate 20mm (Twenty millimeter) nominal size in open foundations and curing complete including cost of form work plain/ reinforced concrete as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials within all leads and lifts and as directed by Engineer-In- Charge	31.50	4955 20	Rupees four thousand nine hundred fifty five and paise twenty only	P.Cum.	156089
4	Providing and laying cement concrete work 1:2:4 (one cement : two sand : four graded stone aggregate 20mm nominal size) mechanically mixed and compecting with vibrator and curing complete including the cost of centering and shuttering - All work up to plinth level carriage of materials within all leads and lifts and as per the direction of Engineer-In- Charge .	31.50	5954 35	Rupees five thousand nine hundred fifty four and paise thirty five only	P.Cum.	187562
5	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Mild steel and Medium Tensile steel bars including carriage of materials within all leads lifts and other incidentals as per the direction of Engineer-in-charge.	487.00	92 30	Rupees ninety two and paise thirty only	P.Kg	44950
					Total	499988


Executive Engineer
 Arki Division,
 HPPWD, Arki

SCHEDULE OF QUANTITY						Estimated Cost :-Rs2,29,672/- only	
Name of Work:-C/o Boundary wall in Govt. High School Bagga, G.P. Bagga, Tehsil Arki Distt. Solan H.P. (SH:- Providing and Fixing Fencing ,Gate, Plaster work and Painting.)DMFT Deposit						Earnest Money :-Rs5,000/-Only	
S. No. Sub head and items of work						Time :-One Month	
1	2	Qty.	Figure	Rate In Words	Unit	Amount	
1	2	3	4	5	6		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	1.11	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	190	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802, 803 , 1202 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(1 Cement :3 sand : 6 Agg. 20mm nominal Size) i/c carriage of material within all leads & lifts As per the direcion of Engineer In-Charge.	1.11	5424.85	Rupees five thousand four hundred twenty four and paise eighty five only	P.Cum.	6022	
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials in all leads,lifts and as per the direction of Engineer-In- Charge	497.55	107.45	Rupees one hundred seven and paise forty five only	P.Kg	53462	
4	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge upto all leads and lifts. Made of G.I. wire of dia 4 mm.	58.80	658.60	Rupees six hundred fifty eight and paise sixty only	P.Sqm	38726	
5	Providing and fixing M.S. B.P. sheet 1.66 to 2 mm thick in eaves board / facia / soffits / ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete (Base members of steel paid separately) as per HP. PWD. Specifications of 1990 vplume-I including carriage of materials, labour, tool and plant through all modes of transportation within all leads and lifts and as per direction of Engineer-in- Charge	0.90	1851.20	Rupees One thousand eight hundred fifty one and paisa twenty only	P.Sqm	1666	
6	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture including carriage of materials in all leads and lifts and as per the direction of Engineer-in-Charge	58.80	89.90	Rupees eighty nine and paise ninty only	P.Sqm	5286	
7	20mm cement plaster in single coat on fair rough side of brick/concrete/stone walls for interior plastering upto floor two level including arrises,internal rounded angles, chamfers and/or rounded angles not exceeding 80mm in girth and finished even and smooth. Cement Mortar 1.4 (1 cement 4 sand)in all leads and lifts. and as per the direction of Engineer-In- Charge	480.28	241.40	Rupees two hundred forty one and paise forty only	P.Sqm	115940	

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2		3	4	5	6
8	White washing with lime to give an even shade in New work (three or more coats) complete and as per direction of Engineer-in- Charge.	480.28	17.45	Rupees seventeen and paise forty five only	P.Sqm	8381
					Total	229672


 Executive Engineer
 Arki Division,
 HPPWD, Arki

SCHEDULE OF QUANTITY


Name of Work:-C/o Boundary wall in Govt. High School Bagga, G.P. Bagga, Tehsil Arki Distt. Solan
H.P. (SH:- C/o Boundry wall in School Campus.)DMFT Deposit

Estimated Cost -Rs 4,04,828/- only

Earnest Money -Rs8100/-Only

Time -One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	21.46	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	3678
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	21.46	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	94222
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation ,plinth & in super structure above plinth level in cement mortar 1:4(1cement : 4coarse sand) within all leads and lifts. and as per the direction of Engineer-In- Charge	55.52	5528.25	Rupees five thousand five hundred twenty eight and paise twenty five only	P.Cum.	306928
		(2/3)			Total	404828


Executive Engineer
Arki Division,
HPPWD, Arki