



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

No. PWD/BWD/TA/NIT/ 2026-27-

5627-36

Dated:- 11-09-2026

To

The Chief Engineer (KZ),  
HPPWD Dharamshala.

**Subject:-**

**Publication of Tender Notice.**

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders along with schedule of quantities for uploading on departmental website as per directions received through e-mail dated 25.06.2026 from Worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla.

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ As Above

  
Executive Engineer  
Bhawarna Division  
HP.PWD Bhawarna

Copy along with copy of tender Notice is forwarded to the following for information.

1. The Superintending Engineer, 5<sup>th</sup> Circle, HPPWD Palampur.
2. All Assistant Engineers working under this division.
3. The Drawing/ Accounts Branch in this office.
4. Notice Board.

  
Executive Engineer  
Bhawarna Division  
HP.PWD Bhawarna



**Himachal Pradesh**  
**Public Works Department**  
**HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083**  
**Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in**

**"NOTICE INVITING TENDERS"**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Bhawarna Division HP.PWD. Bhawarna on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **19-09-2026** up to 11.00 AM. and the same shall be opened on the same day at **11.30 A.M.** in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Non-refundable) on 18-09-2026 up to **4.00 P.M** and the application for issue of tender form shall be received on 18-09-2026 up to **1.00 PM**.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

| Sr. No. | Name of Work                                                                                                                                        | Estimated Cost | Earnest Money | Time Limit  | Cost of Tender form |
|---------|-----------------------------------------------------------------------------------------------------------------------------------------------------|----------------|---------------|-------------|---------------------|
| 1       | Restoration of rain damages on Rud Panyali Lahar Chalaina Chowki Parmar Nagar road (SH:- Construction of Retaining wall at RD. 10/280 to 10/287.60) | 99,123/-       | 2000/-        | Three Month | 350/-               |

**Terms & Conditions:-**

1. The contractor/firm should be registered as or dealer GST No.
2. The intending contractor/firm has to produce the copy of latest enlistment and renewal enlisted in HP.PWD.
3. If any of the date mentioned above happened to be Gazetted Holiday the same shall be processed on next working day.
4. The Executive Engineer reserves the right to accept/reject any tender/application or all tender without assigning any reason.


  
Executive Engineer  
Bhawarna Division  
HPPWD Bhawarna.  
On behalf of Governor of Himachal Pradesh



Himachal Pradesh  
Public Works Department  
HP.PWD Division Bhawarna, Distt. Kangra (H.P)-176083  
Tel:01894-247777, e-mail id: eepwd-bhaw-hp@gov.in

CERTIFICATE

Certified that tender of works being called are of emergent nature and for larger public interest so there is exigencies/ emergency in calling these tenders without press vide this office letter No. PWD/BWD/TA/NIT/2026-27/- 5627-36 dated. 11/08/2026

  
Executive Engineer,  
Bhawarna Division,  
HPPWD. Bhawarna.

## Schedule of Quantity

Work :- Restoration of rain damages on Rud Panyali Lahar Chhalina Chowki Parmar Nagar road, (SH). Construction of Retaining wall at  
to 10/287.60).

Estimated Cost :- Rs. 99,123/-  
Earnest Money :- Rs. 2,000/-  
Time Limit :- Three Months

| No                                 | Description of Item                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Quantity | Rate      |                                         | Unit              | Amount<br>Rs. |
|------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|-----------|-----------------------------------------|-------------------|---------------|
|                                    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          | In figure | In Words                                |                   |               |
| 1                                  | Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiselling wedging out rocks ( Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm ( one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water ) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-In-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 9.04     | 250.00    | Rupees Two Hundred Fifty Only           | Per Cubic metre   | 2260.00       |
| 2                                  | Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 ( One cement : four sand : eight graded crushed/ broken stone aggregate 40mm ( forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -In-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                | 19.91    | 4300.00   | Rupees Four Thousand Three Hundred Only | Per Cubic metre   | 85613.00      |
| 3                                  | Providing and laying 100mm dia ( One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- In-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 6.00     | 250.00    | Rupees Two Hundred Fifty Only           | Each              | 1500.00       |
| 4                                  | Providing and laying ( to level or slope) 900mm dia (Nine hundred millimetre) diameter reinforced cement concrete non pressure pipes IS Class NP-2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1 : 2 ( One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per the entire satisfaction and direction of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 2.50     | 3900.00   | Rupees Three Thousand Nine Hundred Only | Per Running metre | 9750.00       |
| Total :-                           |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                         |                   | 99123.00      |
| Quoted rates percentage in figures |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                         |                   |               |
| Quoted rates percentage in words   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |          |           |                                         |                   |               |

Executive Engineer  
Bhawanid Division  
HP PWD Bhawanid