

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No.PW-AD-EA-I-Tender-2026-27 7811-19

Dated:- 19/09/2026

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT


Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.


Executive Engineer,
Arki Division
H.P.P.W.D. Arki

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before **29.09.2026 up to 11:30 AM** and the same shall be opened on the same day at **12:00 A.N.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **28.09.2026 up to 4:30 PM** and the application for issue of tender form shall be received on **28.09.2026 up to 5:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1.	Construction of Ambulance road fro NH-205 to Daseran (Harijan Basti) Ward No. 4 Km 0/00 to 0/380 (SH:- C/o R/wall at RD 0/00 to 0/018) DMFT Deposit.	4,82,215/-	10,000/-	1 Month	350/-
2	Restoration of Rain damages in various roads under Darla Sub Division (SH:- Supplying and staking of VI Pot Seal Bag)	4,99,500/-	10,000/-	1 Month	350/-
3	Restoration of rain damages of Darla Sub-Division(SH:-Hiring of JCB for removal of slips in Navgaon section various roads)Job No.3	99,000/-	2,000/-	Fifteen days	350/-
4	R/R damages on link road Banlighatti to Bairghat Pajeena road km. 0/0 to 3/500(SH:-C/o R/wall at Rds 0/495 to 0/503 & 2/210 to 2/218)PDNA	2,20,905/-	5,000/-	1 Month	350/-
5	C/o link road Delag to Shivghatti Gram Panchyat Sanan km.0/0 to 1/500(SH:-C/o 900mm dia hume pipe culvert with wing wall between Rds 0/0 to 0/600)DMFT	4,84,510/-	10,000/-	2 Month	350/-
6	C/o link road from Main road Barsanu to village Pujiyara Km 0/0 to 0/250(SH:-C/o R/wall at RDs 0/125 to 0/140, 0/180 to 0/197.50)DMFT	4,97,739/-	10,000/-	1 Month	350/-

Following documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

No: PW-AD-EA-I-Tender-2026-27-

7811-19

Dated:- 19/09/2026

Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3rd Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

Certificate

Certified that the tenders called vide this notice inviting tender for 6 (Six) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,82,215/- only	
Name of Work:- C/o Ambulance Road from NH-205 to Daseran(Harijan Basti) Ward No 4 Km 0/00 to 0/380.(SH:- C/o R/wall at Rd 0/00 to 0/018) DMFT Deposit					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	56.34	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	9657
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	434669
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	18.36	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	22093
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	57.60	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	15797
					Total	482215

Quoted Rate Percentage in Word:-

Quoted Rate Percentage in figure:-


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs4,99,500/- only	
Name of Work: Restoration of Rain Damages in various road under Darla Sub Division (SH:- Supplying and staking of VI Pot Seal Bag) PDMA						Earnest Money :-Rs10,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4	5	6	
1	Supplying Staking VI Pot Seal bag of 25 Kg Cold mix including carriages of material up to all leads and lifts as per direction of Engineer-	666.00	Nos	750.00	Rupees Seven Hundred fifty and paise nil only	Each	499500
						Total	499500

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99000/- only	
Name of Work:-Restoration of Rain Damages of Darla Sub Division . (SH:-Hiring of JCB for removal of Slips in Navgaoun Section Various Roads) Job No-3						Earnest Money :-Rs2000/-Only	
						Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4		5	6
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY

Name of Work:-R/R Damages on Link Road Banalighati to Bairghat Pajeena Road Km 0/00 to 3/500.(SH:C/o R/wall at Rd,s 0/495 to 0/503, & 2/210 to 2/218.)PDNA

Estimated Cost: -Rs2,20,905/- only

Earnest Money :-Rs5,000/-Only

Time :-One Month

S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	19.12	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	3277
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	43.52	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	191079
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	16.32	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	19638
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	25.20	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	6911
					Total	220905

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

DRAFT SCHEDULE OF QUANTITY						
Name of Work:-C/o Link Road Delag to Shivghati Gram Panchyat Sanan Km 0/00 to 1/500. (SH:- C/o 900 mm dia Hume Pipe Culvert with wing wall Between Rd,s 0/00 to 0/600)DMFT				Estimated Cost: -Rs4,84,510/- only		
				Earnest Money :-Rs10,000/-Only		
				Time :-Two Months		
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2	3	Figure	Words	5	6
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In- Charge	108.03	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	18516
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803,1202 d1203 &1203 including carriage of materials in all leads and lifts. a)P.C.C 1:3:6.(20mm) i/c carriage of material within all leads & lifts As per the direcion of Engineer In- Charge.	35.22	5424.85	Rupees five thousand four hundred twenty four and paise eighty five only	P.Cum.	191063
3	Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work, back filling concrete and masonry work in head walls and parapets clause 1108. 900 mm dia pipe.including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	22.50	3882.55	Rupees three thousand eight hundred eighty two and paise fifty five only	P.Rmt	87357
4	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	39.90	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	175185
5	Backfilling behind abutment wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	7.56	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	9097
6	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	12.00	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	3291
					Total	484510

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY					Estimated Cost: -Rs4,97,739/- only	
Name of Work:- C/o Link Road from Main Road Barsanu to Village Pujiyara Km 0/00 to 0/250. (SH:-C/o R/wall at Rds 0/125 to 0/140, 0/180 to 0/197.50.) DMFT					Earnest Money :-Rs10,000/-Only	
					Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
1	2		Figure	Words		
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	43.73	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	7495
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	98.23	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	431289
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts.and as per the direction of Engineer-In- Charge	36.30	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	43680
4	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	55.70	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	15276
					Total	497739

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki