

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PW-AD-EA-1-Tender-2026-27

8179-87

Dated:-26/09/2026

To

The Executive Engineer (IT Cell)
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- Notice Inviting Tender for uploading the same on departmental website.

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office as per notification Secy.(PW) to the Govt. of Himachal Pradesh letter no. PBW(B)A0(3)8/2025-300858 dated shimla-2 the 09.10.2025 and letter No. PWD-B0(3)1/2024-241828 dated Shimla 2.02.2026 as the works mentioned in the tender notice are uploading the same on departmental website at the earliest please.

Encl:-Copy of NIT

Executive Engineer,
Arki Division
H.P.P.W.D. Arki
Ph. 01796-220714

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla.
3. The Superintending Engineer, 3rd Circle, HPPWD., Solan.
4. The Deputy Commissioner Solan, Distt. Solan.
5. The Sub Divisional Magistrate Arki.
6. All the Executive Engineers in HPPWD, (SZ).
7. All the Assistant Engineer, working under this division.
8. All the heads of the branches in this office.
9. Notice Board.

Executive Engineer,
Arki Division
H.P.P.W.D. Arki

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Arki Division H.P.P.W.D. Arki on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Service Tax Act, 2017 so as to reach in this office on before 04.10.2026 up to 11:30 AM and the same shall be opened on the same day at 12:00 A.N. in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on 03.10.2026 up to 4:30 PM and the application for issue of tender form shall be received on 03.10.2026 up to 5:00 PM.

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Arki Division HPPWD Arki must be accompanied with the application for tender documents. Please not no exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No	Name of Work	Estimated Cost	Earnest Money	Time	Cost of Form
1.	Restoration of rain damages of Darla Sub-Division(SH:-Hiring of JCB for removal of slips in Shalaghat Section various roads)Job No.6	99,000/-	2,000/-	1 Month	350/-
2	R/R damages on Shalaghat Soria road km.0/0 to 9/0(SH:-C/o B/wall at Rds 2/180 to 2/223.	99,052/-	2,000/-	1 Month	350/-
3	R/R damages on Khajla Ghatti to Katal Karyalu road km 0/0 to 3/500(SH:-C/o R/wall at Rds 1/518 to 1/525	97,734/-	2,000/-	1 Month	350/-
1	Restoration of rain damages on Arki Sub-Division HP,PWD Arki under Bhumti section(SH:-Hiring of Tipper for carriage of slips/debris etc)Job No.II	99,450/-	2,000/-	Fifteen days	350/-
5	Restoration of rain damages on Arki Sub-Division HP,PWD Arki under Bhumti section(SH:-Hiring of Tipper for carriage of slips/debris etc)Job No.I	99,450/-	2,000/-	Fifteen days	350/-
6	R/R damages on ADB road km.0/0 to 18/0(SH:- Removal of Formation Deficiency between km 6/675 to 6/700)Under PDNA	4,61,480/-	10,000/-	2 Months	350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

No: PW-AD-EA-I-Tender-2026-27-


8179-87

Dated:-

26/09/2026


Copy forwarded for the following for information and necessary action to:-

1. The Superintending Engineer 3rd Circle HPPWD Solan.
2. The all Assistant Engineer working under this division for information and necessary action.
3. All the heads of the branches in this office.
4. Notice Board.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

Certificate

Certified that the tenders called vide this notice inviting tender for 6 (Six) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Arki Division
H.P.P.W.D. Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99000/- only	
Name of Work:-Restoration of Rain Damages of Darla Sub Division . (SH:-Hiring of JCB for removal of Slips in Shalaghat Section Verious Roads) Job No-6						Earnest Money :-Rs2000/-Only	
						Time :-Fifteen Days	
S. No.	Sub head and items of work	Qty.		Rate In		Unit	Amount
				Figure	Words		
1	2	3		4		5	6
1	Hiring of JCB Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in all leads and lifts as per technical specification 302.3.5 and 1611.)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	99.00	Hour	1000.00	Rupees One Thousand and paise nil only	P.Hour.	99000
						Total	99000

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: -Rs99,052/- only	
Name of Work:-R/R Damages on Shalaghat Soria Road Km 0/00 to 9/00.(SH:C/o B/wall at Rd,s 2/180 to 2/223.)						Earnest Money :-Rs2,000/-Only	
						Time :-One Month	
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount	
1	2		Figure	Words			
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing ,removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	10.75	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	1843	
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 &1203 . P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts. and as per the direction of Engineer-In- Charge	21.50	4390.60	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	94398	
3	Providing and laying 100mm dia metre PVC pipe for wheep holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	10.25	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt	2811	
					Total	99052	

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 Arki Division HPPWD
 Arki

SCHEDULE OF QUANTITY						Estimated Cost: Rs 97,734/- only
Name of Work: -R/R Damages on Khajla Ghatti to Katal Karyalu Road Km 0/00 to 3/500.(SH.C/o R/wall at Rd.s 1/518 to 1/525.)						Earnest Money: -Rs 2,000/- only
						Time: -One Month
S. No.	Sub head and items of work	Qty.	Rate In		Unit	Amount
			Figure	Words		
1	2	3	4	5	6	7
1	Earthwork in excavation for structures as per drawing and technical specification clause 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-In-Charge	12.84	171.40	Rupees One hundred seventy one and paise forty only	P.Cum.	2201
2	Providing and laying concrete for plain /reinforced concret in open foundation complete as per drawings and technical specifications MORD clause 802,803, 1202 & 1203. P.C.C. nominal mix 1:5:10 (1 cement: 5 sand :10 aggregates-40mm)including carriage of materials in all leads and lifts, and as per the direction of Engineer-In- Charge	20.10	4390.80	Rupees four thousand three hundred ninety and paise sixty only	P.Cum.	88251
3	Backfilling Granular materials behind abutment, wing wall and retaining wall complete as per drawings & technical specification Clause 1204.3.8 including carriage of materials in all leads, lifts and as per the direction of Engineer-In- Charge	4.32	1203.30	Rupees one thousand two hundred three and paise thirty only	P.Cum.	5198
4	Providing and laying 100mm dia metre PVC pipe for wheel holes complete of approved quality Including carriage of material within all leads, lifts and as per the direction of Engineer-In- Charge	7.60	274.25	Rupees two hundred seventy four and paise twenty five only	P.Rmt.	2084
					Total	97734

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


Executive Engineer
Arki Division HPPWD
Arki

SCHEDULE OF QUANTITY						Estimated Cost: 99450.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Bhumati Section						Earnest Money: 2000.00	
(SH:- Hiring of Tipper for carriage of slips/ debris etc) Job No. II						Time Period: 15 Days	
S. No	Description of Item	Qty		Rate		Unit	Amount
1	2	3		In figures	In words	6	7
1	Hiring of Tipper for removal of land slide and debris with minimum capacity of 5.50 cum per trip and minimum working 6.00 (Six) hours per day. The contractor/ owner of the tipper shall bear the expenses of P.O.L charges, repair of machineries any type of accident and other damages to the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed with in all leads, lifts and as per direction of Engineer in charge.	153.00	Hour	650.00	Rupees Six hundred fifty and paise nil	Per Hour	99450.00
	Total=						99450.00
	Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.						

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki

SCHEDULE OF QUANTITY						Estimated Cost: 99450.00	
Name of Work:- Restoration of Rain damages of Arki Sub Division HPPWD Arki under Bhumati Section						Earnest Money: 2000.00	
(SH:- Hiring of Tipper for carriage of slips/ debris etc) Job No. I						Time Period: 15 Days	
S. No	Description of Item	Qty		Rate		Unit	Amount
1	2	3		In figures	In words	6	7
1	Hiring of Tipper for removal of land slide and debris with minimum capacity of 5.50 cum per trip and minimum working 6.00 (Six) hours per day. The contractor/ owner of the tipper shall bear the expenses of P.O.L charges, repair of machineries any type of accident and other damages to the private and govt property occur during the working hours is the responsibility of the contractor and debris disposed with in all leads, lifts and as per direction of Engineer in charge.	153.00	Hour	650.00	Rupees Six hundred fifty and paise nil	Per Hour	99450.00
	Total=						99450.00
	Condition:- (i) All the machinery/ material will be provided by the contractor himself and bills will be submitted.						

Rate Quoted by contractor in figures

Rate Quoted by contractor in words


 Executive Engineer
 Arki Division (B&R)
 HPPWD Arki

SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on ADB Road Km 0/00 to 18/00.(SH:-Removal of Formation Deficiency between Km 6/675 to 6/700.)Under PDNA				Estimated Cost: -Rs 4,61,480/- only		
				Earnest Money :-Rs10,000/-Only		
				Time :- Two Months		
S.No	Sub head and items of work	Qty.	Unit	Rate		Amount
				Figure	Words	
1	Excavation in earthwork in hilly area by mechanical means all hights and depth, in all kind of soil including saturated soil comprising of mixed soil , ordinaryrock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damage to hill side,water pollution , etc. and to protect stabality of hill side . Rock shall be excavated with chiseling and wedging out rock (where blasting is prohibited). All earth work in cutting / excavation , including rock excavation shall be carried out true to lines grades , side slopes, width, chamber, super elevation and level as shown on the drawings or as directed by the Engineer-in - Charges, in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General Conditions for Contract to achieve designed formation wodth including hauling and stacking of material useful for construction at suitable sites and safe disposal of unsuitable cut matereial inspecified manner,tremming, filling of unevenness, blindage and finishing of the road to specified dimensions or as directed by the Engineer-in -Charge for smooth riding. The recovery of useful stone that is 117.81 cubic meter in all cases falling which recovery @ Rupees 300/- only (Rupees three hundereed only) per cubic metre shall be effected on prorata basis. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	706.87	Per. Cum.	652.85	Rupees six hundred fifty two and paise eighty five only .	461480
					Total	461480

Quoted Rate Percentage in Figure

Quoted Rate Percentage in Words


 Executive Engineer
 B&R Division HPPWD
 Arki