

**Himachal Pradesh
Public Works Department**

No. PWP/Agr. Asstt./Tender/2026/ 9555-75

Dated/ 24-9-2025

To

The Chief Engineer (KZ),
HP.PWD Dharamshala.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per directions received through e-mail dated 22.05.2026 of worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

Executive Engineer
Palampur Division
HPPWD Palampur

Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office
NIT No. PWP/ Agr. Asstt/ NIT/ 2026/- 9555- 75
Dated 24/9/26 are urgent in nature and in public interest.

~~Executive Engineer~~
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **01.10.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 30.09.2026 up to 4.00 P.M and the application for issue of tender form shall be received 29.09.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S. No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	Maintenance of HP.PWD Rest House Dadh (SW:- P/F of Prepainted sheet for extension of Chazza of Dadh Rest House)	Rs. 84,694..00	Rs. 1,700.00	Three Months
2	Maintenance of HP.PWD Rest House Dadh (SW:- P/L of Tile in Room No 2 & Gallery Area)	Rs. 76,307.00	Rs. 1,500.00	Three Months
3	Construction of link road from GPS Holsu to Dharda Mm 0/00 to 1/500 under PMGSY-IV Tehsil Palampur Distt. Kangra (HP) (SH:- Preparation of DPR and CBR Test)	Rs. 90,000.00	Rs. 1,800.00	Three Months
4	C/o link road NH-154 to SCVB Degree College to connect SC Basti Tanda Km 0/00 to 5/00 (SW:- C/o U-shape drain alongwith grating in Km 4/763 to 4/860)	Rs. 83,752.00	Rs. 1,700.00	Three Months
5	C/o link road NH-154 to SCVB Degree College to connect SC Basti Tanda Km 0/00 to 5/00 (SW:- C/o U-shape drain in Km 4/870 to 4/950)	Rs. 62,739.00	Rs. 1,200.00	Three Months
6	C/o link road from Machlu Ram House towards Vinod Kumar House (SW:- C/o Edge wall at RD 0/070 to 0/100, 0/100 to 0/110 & 0/110 to 0/145, P/L Stone Soling & CC Pavement at RD 0/071 to 0/078 (MMGSY)	Rs 82,268.00	Rs. 1,600.00	Three Months
7	Repair of road from Arth to Ree Gidda Km 0/00 to 3/900 (SH:- Hiring of JCB (DC Deposit)	Rs. 83,813.00	Rs. 1,700.00	Three Months
8	C/o drain at Ganesh Vihar Colony Khilroo MC Palampur (SW:- C/o V-Shape drain 0/060 to 0/078 & U-shape drain 0/092 to 0/110.70 (MC Deposit)	Rs. 83,246.00	Rs. 1,700.00	Three Months

9	C/o R/Wall and drainage and Paver Tile work near the house of Sh. Parkash Chand Ward No. 1 Village Snah Mohal (SW:- C/o U-shape drain & P/L 80 MM thick Interlocking Paver Block)	Rs. 84,291.00	Rs. 1,700.00	Three Months
10	C/o R/Wall and drainage on road near the house of Sh. Kunj Ram and others Ward No. 1 Village Surdi Mohal (SW:- C/o U-shape drain & P/L 80 MM thick Interlocking Paver Block (DC Deposit)	Rs. 84,441.00	Rs.1,700.00	Two Months
11	C/o road from Main road Darati towards Gharati Basti (SW:- C/o CC Pavement at RD 0/085 to 0/117 (MMGSY)	Rs. 83,883.00	Rs. 1,700.00	Three Months
12	Restoration of Rain damages on Shitla Mata Tikka Nihang road Km 0/00 to 1/600 (SW:- P/L Interlocking Paver at RD 1/550 to 1/572 (PDNA-2025)	Rs. 84,627.00	Rs. 1,700.00	Three Months
13	Restoration of Rain damages on Shitla Mata Tikka Nihang road Km 0/00 to 1/600 (SW:- P/L Interlocking Paver at RD 1/500 to 1/522 (PDNA-2025)	Rs. 82,782.00	Rs.1,700.00	Three Months
14	Restoration of Rain damages on Lohna Jersey Farm road (SW:- C/o U-shape drain alongwith grating at RD 0/350 to 0/410 (PDNA-2025)	Rs. 83,974.00	Rs.1,700.00	Three Months
15	C/o Path from Late Chuni Lal to main road Rathan GP Ghar (SW:- P/L G-II, G-III & CC work at RD 0/00b to 0/015 (DC Deposit)	Rs. 84,545.00	Rs.1,700.00	Three Months
16	C/o Pucca Path from House of Mamta Devi D/o Sh. Bhuru Ram to Rajmal land Ward No. 2 Chandropa (SW:- C/o path at RD 0/050 to 0/097 (DC Deposit)	Rs. 42,335.00	Rs.800.00	Three Months
17	R/D on link road from Kudan to Dehal Km 0/00 to 1/900 (SW:- C/O Wire crate at RD 1/600 to 1/605 (PDNA-2025)	Rs. 78,516.00	Rs.1,600.00	Three Months
18	Restoration of Rain Damages Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road 0/00 to 10/00 (SW:- C/o U-Shapde drain alongwith grating work at RD 1/240 to 1/360 (PDNA-2025)	Rs 83,723.00	Rs.1,700.00	Three Months
19	C/o link road Rajpur to Choudhary Basti Km 0/00 to 0/500 (SW:- C/o R/Wall at RD 0/013.20 to 0/018.90 (MC Deposit)	Rs 72,671.00	Rs 1,500.00	Three Months
20	C/o Sidh Baba Mandir to LoharLadi (SW:- P/L Soling & CC Pavement at RD 0/00 to 0/034.75 (MMGSY Deposit)	Rs 83,998.00	Rs 1,700.00	Two Months
21	C/o Sidh Baba Mandir to LoharLadi (SW:- P/L Soling & CC Pavement at RD 0/036 to 0/070.75 (MMGSY Deposit)	Rs 83,998.00	Rs 1,700.00	Two Months

22	Repair of Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 0/00 to 33/00 (SW:- Hiring of Excavator cum Loader for removal of slips & clearance of drain in between KM 23/00 to 27/00)	Rs 83,813.00	Rs 1,700.00	Three Months	
23	C/o Link road Banuri to Deogran Km 0/00 to 2/500 (SW:- P/L Interlocking Paver Block at RD 1/225 to 1/247)	Rs 83,347.00	Rs 1,700.00	Three Months	
24	Balance work of Dharamshala Yol Dadh Palampur road 27/00 to 33/00 near Santoshi Mata Chowk Ghuggar (SW:- P/F Grating over Kuhal (M.C. Deposit)	Rs. 83,429.00	Rs 1,700.00	Three Months	
25	C/o Somkunj Circuit House at Palampur Distt. Kangra (HP) (SW:- P/F Shirley 2 seated Sofa & ROMA 2 seated Sofa for VIP Set) (GF)	Rs. 70,216.00	Rs. 1,400.00	Three Months	
26	Link road from Brantheru Assanpatt Gharthoon via Darati Bridge over Krini Khad Km 0/00 to 4/00 (SW:- C/o Edge Wall at RD 0/090 to 0/117)	Rs. 81,904.00	Rs 1,700.00	Three Months	
27	Restoration of Rain Damages on Arth to Ree Gidda road Km 0/00 to 4/00 (Sw:- C/o Edge Wall & Drain at RD 0/700 to 0/728 (PDNA-2025)	Rs. 83,323.00	Rs. 1,700.00	Three Months	
28	A/R & M/O N.R Building at EE HP.PWD Office at Palampur (SW:- P/F 1 No. Smart Webcam & Smart Speakerphone for VC at EE HP.PWD Office at Palampur)	Rs. 44,468.00	Rs. 1,000.00	Three Months	
29	A/R & M/O N.R Building at EE HP.PWD Office at Palampur (SW:- P/F 1 No. Desktop PC at EE HP.PWD Office at Palampur for WAMIS use)	Rs. 84,178.00	Rs. 1,700.00	Three Months	

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

Schedule of Quantity

Maintenance of HPPWD Rest House Dadh(SH:- P/F of Prepainted sheet for extension of Chazza of Dadh

Estimated Cost :- Rs. 84,694/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
	Dismantling roofing including ridges, hips, valleys and gutters etc., and stacking the material within 50 metres lead of:GI Sheet roofing including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	7.80	59.15	Rupees Fifty Nine And Paise Fifteen Only	Per square metre.	461.00
2	Providing and Fixing 0.60 mm (zero decimal six zero milimetre) thick prepainted steel sheet Tata/ Reliance/ Jindal Sheets in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RMP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating including fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limp-et and rubber washers complete with all accessories with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	19.04	1144.06	Rupees One Thousand One Hundred Forty Four And Paise Six Only	Per square metre.	21783.00
3	Providing and fixing M.S. BP sheet 1.66 to 2 mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying acoat of red lead primer complete as per instruction of Engineer-in-charge (Base members of steel work shall be measured & paid seperately). The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	19.04	1525.42	Rupees One Thousand Five Hundred Twenty Five And Paise Forty Two	Per square metre.	29044.00
4	Steel work welded in built up sections/ framed work/tubler section/angle section, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.In gratings, frames ,guard bar, ladder, railing, brackets, gates and similar works as per the entire satisfaction and direction of Engineer-in- Charge.The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	371.28	83.05	Rupees Eighty Three And Paise Five Only	Per Kilogram	30835.00
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	19.04	76.27	Rupees Seventy Six And Paise Twenty Seven Only	Per square metre.	1452.00

①

fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes 110 mm diameter with in all leads, lifts and other incidental as per specification of Engineer-in- Charge. The rate is including octroi, royalty, Malkana, toll tax, or other charges imposed by the Government time to time but excluding GST.	6.00	186.44	Rupees One Hundred Eighty Six And Paise Forty Four Only	Per Running meter	1119.00
Quoted rates percentage in figures				Total:-	84694.00
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Maintenance of HPPWD Rest House Dadh(SH:- P/L of Tile in Room no 2&Gallery Area)

Estimated Cost :- Rs. 76,307/-

Earnest Money :- Rs. 1500/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Dismantling tile work for thickness of tiles 10 mm to 25 mm in floors and roofs laid in cement mortar including stacking material within 50 metres lead. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	59.67	50.00	Rupees Fifty Only	Per square metre.	2984.00
2	Providing and laying 600x600 mm (Six hundred into six hundred millimetre) double charge / Ultra Charge vetrified tiles of Resitile/ Nitco/ Kajaria/Rak/Johnson/Bell water proof stain and impact resistant heavy duty vitrified tiles of approved shade and colour in flooring laid over 12mm (Twelve millimetre) thick cement mortar 1:3 (one cement isto three sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete as per specifications, approved drawing and design including cost and carriage of material with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	59.67	1228.81	Rupees One Thousand Two Hundred Twenty Eight And Paise Eighty One Only	Per square metre.	73323.00
					Total:-	76307.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of work:- Construction of Link Road from GPS Holsu to Dharda km 0/00 to 1/500 under PMGSY-IV Tehsil Palampur Distt. Kangra (H.P). (SH:- Preparation of DPR and CBR Test)

Estimated Cost :- Rs. 90,000/-
Earnest Money :- Rs. 1800/-
Time Limit :- Three Months

S. No	Description of item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Preparation of detailed project report which include the following provision as given Topography Survey by Digital Total Station with two second accuracy, showing all features on survey plan like trees, culverts, bridge, electric pole, telephone poles, hand pump, schools, Haditratns Villages etc. Draw cross-sections at 15 m (fifteen metre) intervals, L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provisions and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Reports of 3 days traffic count survey along with soft copy as per requirement of MoRD/NRIDA. Test reports must include at least following field test per km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii)Optimum Moisture Content (iv)Maximum Dry Density (v) Grain size Analysis. Detailed Project Report and working drawings (Draft and final). Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR copy (soft & Hard copy) and as per the direction and entire satisfaction of Engineer-in-charge complete. The rate is including octroi, royalty, toll tax, or any other taxes imposed by the government excluding GST.	1,500	60000.00	Rupees Sixty Thousand Only	Per Kilometre	90000.00
Total :-						90000.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- C/o link road NH-154 to SCVB Degree College to connect SC Basti Tanda Km 0/00 to 5/00 (SH:- C/o U-shape alongwith grating in Km 4/763 to 4/860)

Estimated Cost :- Rs. 83,752/-
Earnest Money :- Rs. 1700/-

Time Limit :- Three Months

No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	21.83	228.81	Rupees Two Hundred Twenty Eight And Paise Eighty One Only	Per Cubic metre	4995.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.39	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per Cubic metre	53332.00
3	Steel work welded in built up sections including cutting,hoisting, fixing, in position and applying a priming coat of red lead paint in grating, Framed guards, bars, ladders railings,brackets & similar works complete as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	300.00	84.75	Rupees Eighty Four And Paise Seventy Five Only	per Kilogram	25425.00
	Quoted rates percentage in figures				Total:-	83752.00
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- C/o link road NH-154 to SCVB Degree College to connect SC Basti Tanda Km 0/00 to 5/00 (SH:- C/o U-shape in Km 4/870 to 4/950)

Estimated Cost :- Rs. 62,739/-
Earnest Money :- Rs. 1200/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	19.80	228.81	Rupees Two Hundred Twenty Eight And Paise Eighty One Only	Per Cubic metre	4530.00
2	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete in sub-structure for all type of structure complete nominal mix 1: 2 ½ :5 (One cement : two point five sand : five graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths in abutments, parapet etcetra and the like including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	3.00	4745.77	Rupees Four Thousand Seven Hundred Forty Five And Paise Seventy Seven Only	Per Cubic metre	14237.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	11.04	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per Cubic metre	43972.00
Quoted rates percentage in figures						
Quoted rates percentage in words						
Total:-						62739.00

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- C/o Link road from Machlu Ram house towards Vinod Kumar House (SH:- C/o Edge wall at RD 0/070 to 0/100, 0/100 to 0/110 & 0/110 to 0/145, P/L stone soling & CC Pavement at RD 0/071 to 0/078) (MMGSY Deposit)

Estimated Cost :- Rs. 82,268/-

Earnest Money :- Rs. 1600/-

S. No	Description of Item	Quantity	Rate			Time Limit :- Three Months	
			In figure	In Words	Unit	Amount	Rs.
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	8.85	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per cubic metre.		2100.00
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1.96	1101.69	Rupees One Thousand One Hundred One And Paise Sixty Nine Only	Per cubic metre.		2159.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	2.94	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre		15697.00

Supplying mechanically mixed and vibrated plain cement concrete in open foundation for all type of complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	17.10	3644.00	Rupees Three Thousand Six Hundred Forty Four Only	Per Cubic metre	62312.00
Total:-					82268.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Repair of road from Arth to Ree Gidda Km 0/00 to 3/500.(SH:-Hiring of JCB)(DC Deposit)

Estimated Cost :- Rs. 83,813/-

Earnest Money :- Rs. 1700

Time Limit :- Three Months

Sl. No.	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Hiring of excavator cum loader for maintenance of berms, clearance of side drain, removal of slip etc. including cost of fuel oil lubricants and wages of operating staff, any repair/ breakage during operation will be carried out by the contractor on risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hours will be accounted for the payment. Earth cutting in all kinds of soils, including loading into tipper/ truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	86.00	974.57	Rupees Nine Hundred Seventy Four And Paise Fifty Seven Only	Per Hour	83813.00
	Quoted rates percentage in figures				Total:-	83813.00
	Quoted rates percentage in words					


 Executive Engineer
 Palampur Division
 HP PWD Palampur

Schedule of Quantity

Name of Work:- C/O Drain at Ganesh Vihar Colony Khilroo MC Palampur.(SW:- C/O V-Shape drain 0/060 to 0/078 & U-Shape drain 0/092 to 0/110.70((MC Deposit)

Estimated Cost :- Rs. 83,246/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Demolishing R.C.C. work manually/ by mechanical means including cutting reinforcement bars and stacking of steel bars and disposal of unserviceable material within 50 metres as per direction of Engineer - in- charge. as per the direction and entire satisfaction of Engineer-In-Charge.The rate including of octroi,royalty,Malkana,Toll tax, or any other taxes imposed by the Government but excluding GST.	3.93	851.00	Rupees Eight Hundred Fifty One Only	Per cubic metre.	3344.00
2	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate including of octroi,royalty,Malkana,Toll tax, or any other taxes imposed by the Government but excluding GST.	5.81	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per cubic metre.	1379.00
3	Providing Cement concrete 1:3:6 (One Cement : Three Sand : Six crushed stone aggregate) Nominal Mix P.C.C. grade M-10 (M-Ten) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clasue 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate including of octroi,royalty,Malkana,Toll tax, or any other taxes imposed by the Government but excluding GST.	8.29	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per cubic metre.	33019.00
4	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads lifts and other incidentals. The rate including of octroi,royalty,Malkana,Toll tax, or any other taxes imposed by the Government but excluding GST.	565.20	80.51	Rupees Eighty And Paise Fifty One Only	Per Kg	45504.00
Total:-						83246.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- C/o R/wall and drainage and paver tile work near the house of Sh. Parkash Chand Ward No. 1 Village Snah Mohal (SH:- C/o U-shape drain & P/L 80mm thick Interlocking paver block) (DC Deposit)

Estimated Cost :- Rs.84,291/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	4.95	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	1175.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	2.93	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per Cubic metre	11670.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make NTC or equivalent having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	56.80	1169.49	Rupees One Thousand One Hundred Sixty Nine And Paise Forty Nine Only	Per Square metre	66427.00

9

	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	0.94	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	5019.00
	Quoted rates percentage in figures			Total :-		84291.00
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Title of Work :- C/o R/wall and drainage on road near the house of Sh. Kunj Ram and others Ward No. 1 Village Surdi
 Estimated Cost :- Rs. 84,441/-
 Earnest Money :- Rs. 1700/-
 Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	5.39	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	1279.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	3.19	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per Cubic metre	12706.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) of approved make NTC or equivalent having compressive strength of M-50 as per drawings and MORD Technical Specification section 1500 including sand bedding, carriage of material within all leads and lifts, other incidentals. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	56.00	1169.49	Rupees One Thousand One Hundred Sixty Nine And Paise Forty Nine Only	Per Square metre	65491.00

providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	0.93	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	4965.00
Total :-					84441.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- C/O road from main road Darati towards Gharati Basti.(SH:-C/O CC Pavement at Rd 0/085 to 0/117)(MMGSY)

Estimated Cost :- Rs. 83,883/-

Earnest Money :- Rs. 1700

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	3.00	1906.77	Thousand Nine Hundred Six And Paise Seventy Seven Only	Per cubic metre.	5720.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	14.64	5338.98	Rupees Five Thousand Three Hundred Thirty Eight And Paise Ninety Eight Only	Per cubic metre.	78163.00
Total:-						83883.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Shitla Mata Tikka Nihang road Km 0/00 to 1/600 (SH:- P/L Interlocking Paver Block at RD 1/550 to DNA-2025)

Estimated Cost :- Rs. 84,627/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

	Quantity	Description of item	Rate		Unit	Amount Rs.
			In figure	In Words		
1	5.00	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre) to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	1845.00	Rupees One Thousand Eight Hundred Forty Five Only	Per cubic metre	9225.00
2	66.00	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	1054.00	Rupees One Thousand Fifty Four Only	Per square metre.	69564.00
3	1.13	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per cubic metre.	5838.00
Total :-						84627.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work of work:- Restoration of rain damages on Shitla Mata Tikka Nihang road Km 0/00 to 1/600 (SH:- P/L Interlocking Paver Block at RD 1/500 to 2/2) (PDNA-2025)

Estimated Cost :- Rs. 82,782/-

Earnest Money :- Rs. 1700/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre) to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	4.00	1845.00	Rupees One Thousand Eight Hundred Forty Five Only	Per cubic metre	7380.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	66.00	1054.00	Rupees One Thousand Fifty Four Only	Per square metre.	69564.00
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	1.13	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per cubic metre.	5838.00
Total :-						82782.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

of Work:- Restoration of rain damages on Lohna jersey farm road (SH:- C/o U-shape drain alongwith grating at RD 0/350 to 0/410) (PDNA-
 Estimated Cost :- Rs. 83,974/-
 Earnest Money :- Rs. 1700/-
 Time Limit :- Three Months

No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	23.10	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	5482.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.68	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per Cubic metre	54488.00
3	Steel work welded in built up sections including cutting,hoisting, fixing, in position and applying a priming coat of red lead paint in grating, Framed guards, bars, ladders railings,brackets & similar works complete as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	298.00	80.55	Rupees Eighty And Paise Fifty Five Only	per Kilogram	24004.00
					Total:-	83974.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
 Palampur Division
 HP PWD Palampur

Schedule of Quantity

Work:- C/O Path from of Late Chuni Lal to main road Rathana GP Ghar.(SW:- P/L WBM GILGILL & CC work at Rd 0/00 to 0/015) (DC Deposit)

Estimated Cost :- Rs. 84,545/-

Earned Money :- Rs. 1700/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	4.50	228.80	Rupees Two Hundred Twenty Eight And Paise Eighty Only	Per cubic metre.	1030.00
2	Construction of embankment with approved materials deposited at site from road way cutting and excavation from drains and foundations of other structures or other sources graded and compacted in 200mm (two hundred millimeters) thickness in every layers and compacted with three Wheel Road Roller 80-100 (eighty-hundred) KN static weight roller to meet the requirement of tables 300.1 and 300.2 as per M.O.R.D. technical specification Clause 301 and 1603.5 and as per the entire satisfaction and direction of the Engineer-In -Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	42.00	228.80	Rupees Two Hundred Twenty Eight And Paise Eighty Only	Per cubic metre.	9610.00
3	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	2.63	1864.00	Rupees One Thousand Eight Hundred Sixty Four Only	Per cubic metre.	4902.00
4	Providing, laying, spreading and compacting stone aggregates of size 53mm to 22.4mm (Fifty three millimetre to Twenty two point four millimetre) Grading -III, 75mm (Seventy five millimetre consolidated thick) to water bound macadam specification including spreading in uniform thickness, using template hand packing, rolling with Three wheel 80-100 KN static roller to stages to proper grade and camber, applying and brooming, stone screening Type B of size 11.2mm (Eleven point two millimetre) nominal size at the rate of 0.18 Cum. (Zero point one Eight Cubicmetre) per ten square metre and to fill up the interstices of coarse aggregate watering and compacting to the required density as per technical Specification Clause 405 as per entire satisfaction and direction of the Engineer -in-Charge.The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	2.63	1949.00	Rupees One Thousand Nine Hundred Forty Nine Only	Per cubic metre.	5126.00
5	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (Twenty millimeter) nominal size in open foundation in flooring of catchpit as per drawing and M.O.R.D. technical specifications clause 802, 803, 1202 and 1203, including the cost of form work, curing complete and hauling of materials in all kinds of leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge.The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	5.25	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per cubic metre.	28030.00

and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work in drain as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	9.00	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per cubic metre.	35847.00
				Total:-	84545.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Plot:- C/O Pucca Path from house of Mamta Devi D/O Sh.Bhuru Ram to Rajmal land W.No 2 Chandropa.(SW:-C/O Path at Rd 0/050 to 0/097)

Estimated Cost :- Rs. 42,335/-
Earnest Money :- Rs. 800/-

Time Limit :- Three Months

	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	8.41	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per cubic metre.	1996.00
2	Providing, laying, Soling 90 to 45mm (Ninety to forty five millimetre) nominal size Grading-1, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with three wheel 80-100 Kn. Static roller in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 1 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	5.60	1864.45	Rupees One Thousand Eight Hundred Sixty Four And Paise Forty Five Only	Per cubic metre.	10441.00

and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental .The rate is including octroi, royalty, Malkana, toll tax, or other taxes	5.60	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per cubic metre.	29898.00
imposed by the Government time to time but excluding GST.				Total:-	42335.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work:- R/D on Link road from Kudan to Dehal Km 0/00 to 1/900 Name of work(S.H):- C/O Wire Crate at RD 1/600 to 1/605)(PDNA 2025-26)

Estimated Cost :- Rs. 78,516/-
Earnest Money :- Rs. 1600/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out constructin of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and any quantam of water including cleaning of slush which may arise out during dewatering as per the direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	5.00	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre	1186.00
2	Providing and Laying of Boulder Apron Laid in Wire Crates with 4 mm. dia G.I.wire confirming to IS:280 and IS:4826 in 100mmx100mm mesh (woven diagonally) including 10% extra for laps and joints laid with stone boulders weighing not less than 25 kg.each as per Drawing and Technical Specification 1301 including carriage of materials with in ali leads, lifts and other incidental as per the direction of Engineer-in- Charge.The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	31.25	2474.57	Rupees Two Thousand Four Hundred Seventy Four And Paise Fifty Seven Only	Per Cubic metre	77330.00
Total:-						78516.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

18

Schedule of Quantity

Name of Work:- Restoration of rain Damages Tanda Pantehar Band Vihar Molichak Dharaman Kandwari road 0/00 to 10/00(Sw:- C/O U-shape Drain along with grating work at Rd 1/240 to 1/360)(PDNA 2025)

Estimated Cost :- Rs. 83,723/-
Earnest Money :- Rs. 1700

Time Limit :- Three Months

S. No	Description of Item	Quantity	In figure	Rate In Words	Unit	Amount Rs.
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	26.10	228.81	Rupees Two Hundred Twenty Eight And Paise Eighty One Only	Per cubic metre.	5972.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (twenty Millimeters) nominal and below size in or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arisen at the time of laying under water complete for all heights/depths including the cost of form work, as per drawings and technical specifications Clause 802, 803, 1202 & 1203 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals .The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	16.01	3983.00	Rupees Three Thousand Nine Hundred Eighty Three Only	Per cubic metre.	63768.00
3	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	150.00	93.22	Rupees Ninety Three And Paise Twenty Two Only	Per cubic metre.	13983.00
Total:-						83723.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Reference No 1-18

Schedule of Quantity

Name of Work:- C/o link road Rajpur to Choudhary Basti Km 0/00 to 0/500 (SH:- C/o R/wall at RD 0/013.20 to 0/018.90) (MC Deposit)

Estimated Cost :- Rs. 72,671/-
 Earnest Money :- Rs. 1500/-
 Time Limit :- Three Months

Estimated Cost :- Rs. 72,671/- Earnest Money :- Rs. 1500/- Time Limit :- Three Months						
S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.22	229.00	Rupees Two Hundred Twenty Nine Only	Per Cubic metre	3027.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	18.81	3644.00	Rupees Three Thousand Six Hundred Forty Four Only	Per Cubic metre	68544.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	5	220.00	Rupees Two Hundred Twenty Only	Each	1100.00
Quoted rates percentage in figures						Total:- 72671.00
Quoted rates percentage in words						

Executive Engineer
 Palampur Division
 HP PWD Palampur

Schedule of Quantity

Name of Work: C/O Biddh Baba Mandir to Lohar Ladi (SH:- C/O Soling & CC Pavement at RD 0/00 to 0/034.75) (MMGSY)

Estimated Cost :- Rs. 83,998/-
Earnest Money :- Rs. 1700/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	11.73	1822.00	Rupees One Thousand Eight Hundred Twenty Two Only	Per Cubic metre	21372.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (Twenty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	11.73	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	62626.00
Quoted rates percentage in figures					Total:-	83998.00
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work:- C/O Sidh Baba Mandir to Lohar Ladi (SH:- C/O Soling & CC Pavement at RD 0/036 to 0/070.75) MMGSY

Estimated Cost :- Rs. 83,998/-

Earnest Money :- Rs. 1700/-

Time Limit :- Two Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	11.73	1822.00	Rupees One Thousand Eight Hundred Twenty Two Only	Per Cubic metre	21372.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (Twenty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	11.73	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	62626.00
					Total:-	83998.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

of Work:-Repair on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 0/00 to 33/00 (SH:- Hiring of excavator loader for Removal of slips & clearance of drain in between Km 23/00 to 27/00).

Estimated Cost :- Rs. 83,813/-

Earnest Money :- Rs. 1700/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Hiring of excavator cum loader for maintenance of berms, clearance of side drain, removal of slip etc. including cost of fuel oil lubricants and wages of operating staff, any repair/ breakage during operation will be carried out by the contractor on risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hours will be accounted for the payment. Earth cutting in all kinds of soils, including loading into tipper/ truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in- Charge. Rate is inclusive of toll tax, and any other taxes imposed by the government but excluding GST.	86.00	974.57	Rupees Nine Hundred Seventy Four And Paise Fifty Seven Only	Per Hour	83813.00
	Quoted rates percentage in figures				Total:-	83813.00
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

of Work:- C/o Link road Banuri to Deogran Km 0/00 to 2/500 (SH:- P/L Interlocking Paver Block at RD 1/225 to 1/247)

Estimated Cost :- Rs. 83,347/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	3.00	1906.80	Rupees One Thousand Nine Hundred Six And Paise Eighty Only	Per cubic metre.	5720.00
2	Providing and Laying of Interlocking Concrete Block Pavements having thickness 60 mm as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	66.00	1084.75	Rupees One Thousand Eighty Four And Paise Seventy Five Only	Per square metre.	71594.00
3	Providing concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix,P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803,1202 & 1203. including the cost of form work and curing complete, carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1.13	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per cubic metre.	6033.00
Total:-						83347.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work:- Balance work of Dharamshala Yol Dadh Palampur road 27/00 to 33/00 near Santoshi Mata Chowk Ghuggar.(SW:- P/F Grating over Kuhl)(MC Deposit)

Estimated Cost :- Rs. 83,429/-

Earnest Money :- Rs. 1700/-

S. No	Description of Item	Quantity	Time Limit :- Three Months			Amount Rs.
			Rate	In figure	Unit	
1	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including carriage of materials within all leads lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	1035.74	80.55 Rupees Eighty And Paise Fifty Five Only	Per kilogram		83429.00
	Quoted rates percentage in figures				Total:-	83429.00
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- C/o Somkunj Circuit House at Palampur Distt. Kangra (HP) (SH):- P/F Shirley 2 seated sofa & ROMA 2 seated sofa for VIP set (GF)

Estimated Cost :- Rs. 70,216/-
Earnest Money :- Rs. 1400/-
Time Limit :- Three Months

	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
	Providing and Fixing Shirley 2 seated sofa (2000 x 860 x 850 mm) superior quality rate as per seat with all leads, lift and other incidentals as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	3.00	16731.35	Rupees Sixteen Thousand Seven Hundred Thirty One And Paise Thirty Five Only	Each	50194.00
2	Providing and Fixing ROMA 2 seated sofa (1550mmx860mmx860mm) superior quality rate as per seat with all leads, lift and other incidentals including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	1.00	20022.05	Rupees Twenty Thousand Twenty Two And Paise Five Only	Each	20022.00
Quoted rates percentage in figures			Total :-			70216.00
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

To Name of work:- Link road from Bramtheru Assanpatt Gharthoon via Drati Bridge over Krini Khad Km 0/00 to 4/00 (SH:- C/o Edge wall at RD 0/090 to 0/117)

Estimated Cost :- Rs. 81,904/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	9.75	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre	2313.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	21.06	3644.06	Rupees Three Thousand Six Hundred Forty Four And Paise Six Only	Per Cubic metre	76744.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.00	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Each	2847.00
Total :-						81904.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of work:- Restoration of rain damages on Arth to Ree Gidda road Km 0/00 to 4/00 (SH:- C/o edge wall & Drain at RD 0/700 to 0/728)
(PDNA-2025)

Estimated Cost :- Rs. 83,323/-

Earnest Money :- Rs. 1700/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	11.34	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre	2691.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	17.64	3644.06	Rupees Three Thousand Six Hundred Forty Four And Paise Six Only	Per Cubic metre	64281.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	4.20	3893.05	Rupees Three Thousand Eight Hundred Ninety Three And Paise Five Only	Per Cubic metre	16351.00
		Total :-				
Quoted rates percentage in figures						83323.00
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Scope of work:- A/R & M/O N/R Building at EE HPPWD Office at Palampur Distt. Kangra (HP) (SH:- P/F 1 No. Smart webcam & smart speakerphone for VC at EE HPPWD Office at Palampur).

Estimated Cost :- Rs. 44,468/-

Earnest Money :- Rs. 1000/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing & fixing Philips PSE0520 smart webcam- Premium video conferencing solution, 2K Ultra HD Clarity @ 30 FPS- sharp & smooth visuals auto focus + Light intelligence-perfect portraits every time all complete including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	1.00	17325.00	Rupees Seventeen Thousand Three Hundred Twenty Five Only	Each	17325.00
2	Providing & fixing Philips PSE-0401 smart speakerphone -compact & portable design 4mic Array, 360 degree pickup- captures voices from all directions clear audio up to 6m range all complete including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	1.00	27142.50	Rupees Twenty Seven Thousand One Hundred Forty Two And Paise Fifty Only	Each	27143.00
Total :-						44468.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

of work:- A/R & M/O N/R Building at EE HPPWD Office at Palampur Distt. Kangra (HP) (SH:- P/F 1 No. Desktop PC at EE HPPWD Office at Palampur for WAMIS use).

Estimated Cost :- Rs. 84,178/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing & fixing Lenovo Idea Centre AIO (All in One) desktop PC with 23.8 Inch FHD (Full High Definition) AMD Ryzen 5 7535HS, Cores 6, Thread 12, CPU Frequency 4.4 GHz, RAM 8GB DDR5-4800 MHz, a 512 GB M.2 2280 PCIe 4.0x4 NVMe SSD, and Integrated AMD Radeon 660M Graphics with Windows 11 Pro (64 bit). The Package includes a 23.8" FHD IPS monitor, Wireless EOS keyboard and mouse and an internal speaker with a one year comprehensive onsite warranty all complete and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST.	1.00	84177.97	Rupees Eighty Four Thousand One Hundred Seventy Seven And Paise Ninety Seven Only	Each	84178.00
Total :-						84178.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur