

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No. PWD/DPD/CB/EA-I/Tender/2026- 3397-98
To

Dated: - 14-09-2026

The Chief Engineer (HZ)
HPPWD Hamirpur (HP)

Subject: - Publication of tender Notice.
Sir,

Enclosed please find herewith tender notice for the works as given in the Notice inviting Tender along with Schedule of Quantities for uploading on departmental website as per Notification No. PBW (B)A(3)1/2024 dated 03.01.2025 of Secretary (PW) to the Govt. of HP and further in compliance of Engineer-in-Chief, HPPWD Nigam Vihar, Shimla-2 office letter No. PWD/ICT Wing/Website- dated 22.05.2026, as the work mentioned in the tender notice are urgent in nature and in public interest.

DA/ As above.



Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur Chowk.
On behalf of Governor of Himachal Pradesh

Copy along with tender notice is forwarded to the Superintending Engineer, 15th Circle, HPPWD Una for information please.
DA/ As above.


Executive Engineer,
Daulatpur Chowk Division,
HPPWD Daulatpur Chowk.

CERTIFICATE

Certified that tenders called vide this office letter No. PWD/DPD/CB-Tender/2026- 3390-96 dated 14-09-2026 is required to be carried out immediately being emergent nature of work in the public interest.


Executive Engineer,
Daulatpur chowk Division,
HPPWD Daulatpur Chowk.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed **Percentage rates** tenders on form 6 & 8 are hereby invited by the Executive Engineer Daulatpur Chowk Division, HPPWD, Daulatpur Chowk on behalf of Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office and opened as per time schedule given below. The offer of the tender will be kept open for 75 days from the date of opening of the tenders.

Last Date and time of receipt of applications for the tender form	: 22.09.2026 up to 05.00 PM
Date and time of issue/Sale of tender forms against cash Payment	: 23.09.2026 (03.00 PM to 5.00 PM)
Date and time of receipt of tenders	: 24.09.2026 up to 11.00 AM
Date and time of opening of tenders	: 24.09.2026 at 11.30 AM


The tender forms will be issued against cash payment (non-refundable). The earnest money in the shape of NSC/Time Deposit/FDR of nationalized bank duly pledged in the name of undersigned must be accompanied with each tender. The conditional tender and tender not accompanying the earnest money in the proper mode of deposit will summarily be rejected.

Sr. No.	Name of Work	Estimated Cost	Earnest money	Time Limit	Cost of Form	Eligible Class of Contractor
1	Restoration of Rain Damages on NMT road from Mubarikpur to Marwari (Punjab Boundary) KM 54/675 to Km 72/555, (SH:- Repair of road with Interlocking Concrete Paver Block due to road crust damaged between KM 66/868 to 66/900) Under PDNA-2023	405437.00	8100.00	Three Month	350-	Class- C&D
2	Repair & Restoration of Rain Damages on link road Gagret Oel Ispur road Km. 0/0 to 13/690. (SH:- Repair of road Pot Hole due to road crust damaged at various RD,s) Under PDNA 2023	407016.00	8200.00	Three Month	350-	Class- C&D
3	VKV/2024/179, C/O (Construction of) link road Saghnai Kala Panga to Harijan Basti Kala Panga in Gram Panchayat Saghnai Tehsil Ghanari Distt. Una, (SH:- Balance work C/O Retaining wall in Culvert approaches at RD 0/250) Under VKVNY	276350.00	5500.00	Three Month	350-	Class- C&D
4	Construction of link road Mistry Mohalla Ward No. 5 Nangal Jariyalan in Gram Panchayat Nangal Jariyalan Km 0/00 to 0/500, (SH:- Balance work Interlocking Concrete Paver Block) Under MMSY 2025-26	84600.00	1700.00	Three Month	350-	Class- C&D
5	Restoration of Rain Damages on NMT road from Mubarikpur to Marwari (Punjab Boundry) KM 54/675 to Km 72/555, (SH:- Repair of road with Interlocking Concrete Paver Block due to road crust damaged between KM 66/900 to 66/932) Under PDNA-2023	405437.00	8100.00	Three Month	350-	Class- C&D
6	Repair & Maintenance of PM Shri GMSSS Mubarikpur Tehsil Ghanari Distt. Una (H.P). (SH:- Balance work Repair and Maintenance of School Building)	84680.00	1700.00	Three Month	350-	Class- C&D

Cont. Page-2

TERMS AND CONDITIONS: -

1. The contractor should produce a latest copy of enlistment/renewal letter at the time of application.
2. The contractor/firm shall have his registration and GST No. and copy of the same be attached with the application.
3. The earnest money for the above works should be submitted duly pledged in favour of Executive Engineer, Daulatpur Chowk Division, and HPPWD Daulatpur chowk with the application for the purchase of tender forms. The application received without earnest money shall be summarily rejected.
4. The contractor/firms are required to insert the rate in words as well as in figures failing which Executive Engineer reserves the right to accept/rejects any or all tenders.
5. If any of the date mentioned above happens to be Local/Gazetted Holidays the same shall be process on next date.
6. The tender form will be issued to those contractors who have relevant machinery and equipment, list of which may be attached with their application along with proof of ownership of machinery/legal tie up.
7. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reasons.


Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

No. PWD/DPD/CB-Tender/2026-

3390-96

Dated: - 14-09-2026

Copy forwarded to the following for information and necessary action: -

1. The Engineer-in-Chief, HPPWD Nirman Bhawan Shimla.
2. The Chief Engineer (HZ) HPPWD Hamirpur.
3. The Superintending Engineer, 15th Circle, HPPWD Una.
4. All the Assistant Engineers working under this division.
5. Drawing Branch in this office.
6. Notice Board.


Executive Engineer,
Daulatpur Chowk Division
HP.PWD Daulatpur Chowk.

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 405437/-
 Earnest Money: Rs. 8100/-
 Time Limit : Three Months

Name of Work:- Restoration of Rain Damages on NMT road from Mubarikpur to Marwari (Punjab Boudry) KM 54/675 to Km 72/555, (SH:- Repair of road with Interlocking Concrete Paver Block due to road crust damaged between KM 66/900 to 66/932) Under PDNA-2023

Sr. No.	Description of Item	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Scarifying the existing bituminous road surface to a required depth, disposal of scarified material with in all leads and lifts as per Technical Specification Clause 301.4. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-Charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	220.50 Squire metre.	8.00	Rupees Eight Only	Per squire metre	1764.00
2	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	82.68 Cubic metre.	200.00	Rupees Two Hundred Only	Per cubic metre	16536.00
	Construction of Granular Sub-Base by providing well graded material of nominal maximum size grading 80 mm (eight millimetre) as per table 2.3 (two point three) of IRC SP-72-2008 (IRC-SP-seventy two-two thousand eight), spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN (eighty to one hundred kilonewton) static Roller capacity to achieve the desired density complete as per specifications contained in para 2.2 (two point two), 3.6 (three point six), & 3.7 (three point seven) of IRC SP-77-2008 (IRC-SP-seventy seven-two thousand eight) (By Using fresh material) and as per MORTH specifications and as per the direction of Engineer-in-Charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	23.62 Cubic metre	930.00		Per cubic metre	21967.00

Cont p-2

Sr. No.	Description of Item	Quantity	Rates in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C (Plain cement concrete) grade M-10 (M - ten) Nominal mix 1:3:6 (one cement:three sand:six aggregate) [40 mm fourty millimetre) Nominal Size]. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects. The rate including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	47.25 Cubic metre.	3800.00	Rupees Three Thousand Eight Hundred Only	Per cubic metre	179550.00
4	Providing & Laying of Interlocking concrete Block Pavements having thickness 80 mm (eighty millimetre) M-40 Grade (M-fourty grade) ISI Marked as per drawing and HP PWD technical specifications in all respect including carriage of materials within all leads and lifts and other incidentals. The rate including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	226.80 Square metre.	800.00	Rupees Eight Hundred Only	Per square metre	181440.00
5	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in Substructures complete as per drawing and Technical Specification Clause 802, 804,805,806,807, 1202 & 1203. P.C.C grade M-20 (M-twenty) design mix with minimum cement content @ 350 kg per cum (at the rate three hundred fifty kilogram per cubic metre). The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects. The rate including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	0.95 Cubic metre.	4400.00	Rupees Four Thousand Four Hundred Only	Per cubic metre	4180.00
Total Amount						405437.00
Quoted Rate in Figure						% above/below
Quoted Rate in Words						

1295
Executive Engineer,
HPPWD Division,
Daultpur Chowk.

501

RD,s) Under PDNA 2023

Ref:

Executive Engineer,
HPPWD Division,
Daulatpur Chowk

DRAFT BILL OF QUANTITY

Name of Work:- VKV/2024/179, C/O (Construction of) link road Saghnai Kala Panga to Harijan Basti Kala Panga in Gram Panchayat Saghnai Tehsil Ghanari Distt. Una, (SH:- Balance work C/O Retaining wall in Culvert approaches at RD 0/250) Under VKVNY

Estimated Cost: Rs. 276350/-
Earnest Money: Rs. 5500/-
Time Limit : Three Months

Job-3

Sr. No.	Description of Item	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiselling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess. Toll taxes of local bodies or other taxes imposed by the Government.	21.000	180.00	Rupees One Hundred Eighty Only	Per cubic metre	3780.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORTH technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess. Toll taxes of local bodies or other taxes imposed by the Government.	77.400	3450.00	Rupees Three Thousand Four Hundred Fifty Only	Per cubic metre	267030.00
3	Providing weep holes in brick masonry/plain reinforced concrete abutments, wing wall return wall, retaining walls and breast walls etcetra with 100mm (One Hundred millimeter) diametre PVC pipe make of D-Plast/Repipe, working pressure not less than 4.50 Kg/Sq. cm. (four point five zero kilogram per square centimetre), extending through the full width of the structure with slope of 1V:20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORTH technical specification section 700 and 1200 and as per the directions and entire satisfactions of Engineer-in-Charge, including carriage of materials with in all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess. Toll taxes of local bodies or other taxes imposed by the Government.	16.000	200.00	Rupees Two Hundred Only	Each	3200.00
4	Back filling behind abutment Retaining wall/Breast wall, Wing walls and the like with approved granular materials complete as per drawings and MORTH technical specification section 1200 and 1600 as directed by the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess. Toll taxes of local bodies or other taxes imposed by the Government.	3.600	850.00	Rupees Six Hundred Fifty Only	Per cubic metre	2340.00
Total Amount						276350.00
Quoted Rate in Figure						
Quoted Rate in Words						

Executive Engineer,
HPWD Division,
Daulatpur Chowk

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 84600/-
Earnest Money: Rs. 1700/-
Time Limit : Three Months

Name of Work:- Construction of link road Mistry Mohalla Ward No. 5 Nangal Jariyalan in Gram Panchayat Nangal Jariyalan Km 0/00 to 0/500, (SH:- Balance work Interlocking Concrete Paver Block) Under MMSY 2025-26

Sr. No.	Description of item	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	7.500 Cubic metre.	180.00	Rupees One Hundred Eighty Only	Per cubic metre	1350.00
2	Construction of Granular Sub-Base by providing well graded material of nominal maximum size grading 80 mm (eight millimetre) as per table 2.3 (two point three) of IRC SP-72-2008 (IRC-SP-seventy two-two thousand eight), spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN (eighty to one hundred kilonewton) static Roller capacity to achieve the desired density complete as per specifications contained in para 2.2 (two point two), 3.6 (three point six), & 3.7 (three point seven) of IRC SP-77-2008 (IRC-SP-seventy seven-two thousand	7.500 Cubic metre.	880.00	Rupees Eight Hundred Eighty Only	Per cubic metre	6600.00
3	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:4:8 (one cement isto four sand isto eight graded crushed stone aggregate 25mm (twenty five millimeter) nominal size) for plain cement concrete in all heights/depths on ground or under water, including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying concrete, for all heights/depths and any quantum of water, including cost of form work and curing complete in all type of structures like Retaining Walls & Breast Walls etcetera complete as per drawing and MORTH technical specification section 800, 900, 1200 and 1600 and as per the direction and the entire satisfaction of Engineer-in-Charge, including carriage of materials within all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	7.000 Cubic metre.	3400.00	Rupees Three Thousand Four Hundred Only	Per cubic metre	23800.00

Cost- 8-2

P-2

Sr. No.	Description of Item	Quantity	Rates in		Unit	Amount
			Figures	Words		
4	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete Grade M20 (M-Twenty) nominal mix 1:2:4 (One cement is to two sand is to four graded stone aggregate 20mm (twenty millimetre) nominal size in or under water in open foundation for all types of structure and the like, including cost of form work and curing complete as per drawing and CPWD specification 2019 including pumping or bailing out water/dewatering (surface and sub-soil water) and removal of the slush which may arise at the time of laying under water for all heights/depts and any quantum of water complete including carriage of materials up to all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	0.500 Cubic metre.	4300.00	Rupees Four Thousand Three Hundred Only	Per cubic metre	2150.00
5	Providing and laying factory made chamfered edge Cement Concrete paver blocks 80mm (Eighty millimetre) thick of M-30 (thirty) grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm(fifty millimetre) thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per CPWD specification 2019 including carriage of materials up to all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	65.000 Square metre.	780.00	Rupees Seven Hundred Eighty Only	Per square metre	50700.00
Total Amount						84600.00
Quoted Rate in Figure						
Quoted Rate in Words						
% above/below						

1298
Executive Engineer,
HPPWD Division,
Daulatpur Chowk

50-5

DRAFT BILL OF QUANTITY

Estimated Cost: Rs. 405437/-
Earnest Money: Rs. 8100/-
Time Limit : Three Months

Name of Work:- Restoration of Rain Damages on NMT road from Mubarikpur to Marwari (Punjab Boundary) KM 54/675 to Km 72/555, (SH:- Repair of road with interlocking Concrete Paver Block due to road crust damaged between KM 66/868 to 66/900) Under PDNA-2023

Sr. No.	Description of Item	Quantity	Rates in		Unit	Amount
			Figures	Words		
1	Scarifying the existing bituminous road surface to a required depth disposal of scarified material with in all leads and lifts as per Technical Specification Clause 301.4. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects as per direction of Engineer-in-Charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	220.50 Squire metre.	8.00	Rupees Eight Only	Per squire metre	1764.00
2	Earth work in excavation in foundation for all types of structures such as retaining walls, breast walls, culverts, drains, parapets and other similar structures in all kinds and classification of soil, including saturated soil comprising of ordinary mix soil, ordinary rock, hard rock, chiseling/ wedging out rocks (where blasting is prohibited) complete in accordance with the lines and dimensions shown on the drawings, including setting out, construction of shoring, bracing, removal of stumps and other deleterious materials and disposal of excavated material upto any leads and lifts including dressing of sides and bottom and obstructions necessary for placing the foundations, trimming, leveling and ramming and watering bottom of excavation and backfilling in trenches with excavated suitable approved materials to the original surface in layers not exceeding 15cm (fifteen centimeter) compacted thickness including shoring and strutting and pumping or bailing out water (surface and sub-soil water) up to any depth and any quantum of water and cleaning of slush which may arise out during dewatering complete as per drawing and MORTH Technical Specification section 304 and as per the direction and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	82.68 Cubic metre.	200.00	Rupees Two Hundred Only	Per cubic metre	16536.00
	Construction of Granular Sub-Base by providing well graded material of nominal maximum size grading 80 mm (eight millimetre) as per table 2.3 (two point three) of IRC SP-72-2008 (IRC-SP-seventy two-two thousand eight), spreading in uniform layers with tractor mount appropriate grading arrangements on prepared surface, mixing by mix in place method at OMC with tractor mount appropriate rotavator attachment and compaction with three wheel 80-100 KN (eighty to one hundred kilonewton) static Roller capacity to achieve the desired density complete as per specifications contained in para 2.2 (two point two), 3.6 (three point six), & 3.7 (three point seven) of IRC SP-77-2008 (IRC-SP-seventy seven-two thousand eight) (By Using fresh material) and as per MORD specifications and as per the direction of Engineer-in-Charge including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	23.62 Cubic metre.	930.00		Per cubic metre	21967.00

Conf 1-2

P-2

Sr. No.	Description of Item	Quantity	Rates in		Unit	Amount
			Figures	Words		
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations, complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203. P.C.C (Plain cement concrete) grade M-10 (M - ten) Nominal mix 1:3:6 (one cement:three sand:six aggregate) [40 mm fourty millimetre) Nomial Size]. The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects. The rate including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	47.25 Cubic metre	3800.00	Rupees Three Thousand Eight Hundred Only	Per cubic metre	179550.00
4	Government Providing & Laying of Interlocking concrete Block Pavements having thickness 80 mm (eighty millimetre) M-40 Grade (M-fourty grade) ISI Marked as per drawing and HP.PWD technical specifications in all respect including carriage of materials within all leads and lifts and other incidentals. The rate including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	226.80 Square metre.	800.00	Rupees Eight Hundred Only	Per square metre	181440.00
5	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in Substructures complete as per drawing and Technical Specification Clause 802, 804, 805, 806, 807, 1202 & 1203. P.C.C grade M-20 (M-twenty) design mix with minimum cement content @ 350 kg per cum (at the rate three hundred fifty kilogram per cubic metre). The rate shall include carriage of machineries, equipment, tools, materials and safety measures, payment of all taxes and other incidentals necessary to complete the work in all respects. The rate including entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	0.95 Cubic metre.	4400.00	Rupees Four Thousand Four Hundred Only	Per cubic metre	4180.00
Total Amount						405437.00
Quoted Rate in Figure						
Quoted Rate in Words						


 Executive Engineer,
 HPPWD Division,
 Daulatpur Chowk

Draft Bill of Quantity

Job-6

Estimated Cost: Rs. 84680/-
Earnest Money: Rs. 1700/-
Time Limit: Three month

Name of work :- Repair & Maintenance of PM Shri GMSSS Mubarikpur Tehsil Ghanari Distt. Una (H.P.). (SH:- Balance work Repair and Maintenance of School Building)

Sr. No.	Sub-Head and Items of work	Quantity		Rates in		Unit	Amount
		Figures	Words	Figures	Words		
1	Providing and laying in position specified grade of reinforced cement concrete work M-25 (M-twenty five) with minimum cement contents not less than 400 kgs.(four hundred kilogram) per cubic metre including curing complete excluding cost of form work and reinforcement for reinforced concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, stair cases and spiral stair cases above plinth level upto all floor level as per the direction by the Engineer in charge including entire carriage of materials with in all leads and lifts and other incidentals . The rates excluding of Goods Services Tax but including Labour cess, other levies/taxes, duties /royalties, cess, Toll taxes of local bodies or other taxes imposed by the Government.	14.600	Cubic meter .	5800.00	Rupees Five Thousand Eight Hundred Only	Per Cubic meter .	84680.00
Total Amount in Figures							84680.00
Quoted Rate in Figure							
Quoted Rate in Words		% above/below					

Ref
Executive Engineer,
HPPWD Division,
Daultapur Chowk