

Himachal Pradesh
Public Works Department
NO.PW- JDT-CB-EA-I- /Tender Notice/2026-27- 4004-08
To

Dated:- 26/09/2026

✓
The Chief Engineer (HZ),
HPPWD Hamirpur (HP).

SUBJECT: -


Publication of Tender Notice.

Sir,

Jai Hind!

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification of Secretary (PW) to the Govt. of HP vide Notification No. PBW (B)A(3)1/2024 Dated 03/01/2025 and further in compliance of the Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICT Wing/website dated 22/5/2026 as the matter is of urgent nature and in public interest, you are requested to kindly get it published on departmental website before 29/09/2026.

DA:-As above.


Executive Engineer,
Jhandutta, Division.
HPPWD, Jhandutta.

On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- As above.


Executive Engineer,
Jhandutta, Division.
HPPWD., Jhandutta.

On behalf of Governor of Himachal Pradesh

"NOTICE INVITING TENDERS"

Sealed item / percentage rate tender(s) on PWD form No 6 & 7/8 are hereby invited by the Executive Engineer Jhandutta HPPWD Jhandutta on behalf of the Governor of HP for the following works from the approved and eligible contractors/firms of appropriate class enlisted in HPPWD as per latest instructions so as to reach in this office as per time schedule given below. The offer of the tender will be kept open for 90 days from the date of opening of the tenders. The undersigned reserves the right to accept / reject any application / tender or all the tenders without assigning any reasons.

Date of receipt of application for tender form
Date of issue/sale of Tender forms
Date of opening of tender

03/10/2026 upto 12:00 PM
03/10/2026 from 02:00 PM to 04:00 PM
05/10/2026 at 11:00AM

The tender shall be received up to **10:30AM on 05/10/2026** and will be opened on the same day at **11:00AM** in the presence of intending contractors or their authorized representative who may like to be present. The tender form can be had from this office against cash payment (Non-refundable) on **03/10/2026** from 02:00 PM to 04:00 PM.

The Earnest money in the shape of National Saving Certificate/Deposit at call/ Time Deposit /Account/ in any of the Post-Office /Nationalized Bank in H.P. duly pledged in favour of Executive Engineer, Jhandutta Division, HP-PWD, Jhandutta must accompany with each application. Conditional tender and the tenders received without earnest money will simultaneously be rejected. The offer of the tender shall be kept open for 90 days. The Executive Engineer reserves the right to accept or reject the tender without assigning any reasons.

Sr. No	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1	RRD on Dokru to Neri via Rohal road Km. 0/0 to 2/600 (SH: P/L C.C. Pavement at RD 0/600 to 0/628)	84031.00	1681.00	350.00	One Month
2	RRD on Dokru to Neri via Rohal road Km. 0/0 to 2/600 (SH: P/L C.C. Pavement at RD 0/629 to 0/657)	84031.00	1681.00	350.00	One Month
3	C/o link road Malraon to Boatghat Km. 0/0 to 2/500 (SH: C/o RCC Slab Culvert at RD 0/640 a/w wing wall both side) BSP/2023/47 Deposit Work	254101.00	5082.00	350.00	Two Month
4	R/R Damages on link road from SDM office to Jhandutta via Block (SH: P/L soling & C.C. at RD 0/850 to 0/881.50)	84587.00	1692.00	350.00	One Month
5	R/R Damages on link road from SDM office to Jhandutta via Block (SH: P/L soling & C.C. at RD 0/890 to 0/921.50)	84587.00	1692.00	350.00	One Month
6	R/R Damages on link road from SDM office to Jhandutta via Block (SH: P/L soling & C.C. at RD 0/990 to 0/021.50)	84587.00	1692.00	350.00	One Month
7	Restoration of rain damages on various road under Berthin Section (SH: Removal of slips of Ghumarwin Berthin Talai road from RD 4/0 to 14/0 & Badgaon to Ree Radoh road from RD 0/0 to 4/0 under PDNA 2023)	423000.00	8460.00	350.00	One Month

8	Restoration of rain damages on Jhandutta to Narlaghat road Km. 0/0 to 4/0 (SH: C/o R/wall at RD 1/210 to 1/217.75)	84104.00	1682.00	350.00	One Month
9	Restoration of rain damages on Jhandutta to Narlaghat road Km. 0/0 to 4/0 (SH: C/o R/wall at RD 1/220 to 1/227.75)	84228.00	1685.00	350.00	One Month

Certificate:- Certified that tenders are being called for due to exigencies of works (landslide and road sinking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Jhandutta Division, HP.PWD, Jhandutta and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The contractor/ Firms are requested to insert the rate in percentage only both in words and in figures failing which XEN reserves the rights to accept/reject any tender without assigning any reason at any stage.

... HIM SUCHNA AVAM JAN SAMPARK...

Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.

DRAFT SCHEDULE OF QUANTITY

Name of Work :- RRD on Dokru to Neri via Rohal road km 0/00 to 2/600 (SH:- P/L C.C. Pavement at Rd 0/600 to 0/628)		Estimated cost:- ₹ 84031.00				
		Earnest Money:- ₹ 1681.00				
		Time allowed:- One Month				
Sr. No.	Description of iteams	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1	Providing and laying stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD pecification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax,(excluding Goods and service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not enterain any claim whatsoever in this respect of the same.	13.02	1149.00	Rupees One thousand one hundred fourty nine and paise zero zero only	Per Cubic Meter	14960.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement isto two coarse sand) isto four graded crushed stone aggregate 40 mm (Fourty millimeter) nominal size) including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax,(excluding Goods and service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not enterain any claim whatsoever in this respect of the same.	13.02	5305.00	Rupees Five thousand three hundred five and Paise zero zero only	Per Cubic Meter	69071.00
	Total:-					84031.00

Estimate No. :- 99
DNIT No. :- 99
Head of account :-

Draft schedule of quantity approved for Rs. 84031/only for the year 2026-27

[Signature]
Executive Engineer,
Jhandutta Division,
HPPWD Jhandutta.



DRAFT SCHEDULE OF QUANTITY						
Name of Work :- RRD on Dokru to Neri via Rohal road km 0/00 to 2/600 (SH:- P/L C.C. Pavement at Rd 0/629 to 0/657)			Estimated cost:- ₹		84031.00	
			Earnest Money:- ₹		1681.00	
			Time allowed:-		One Month	
Sr. No.	Description of iteams	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1	Providing and laying stone soling properly hand packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD pecification. 100 mm (one hundred millimeter) spread thickness (finished work including materials and labour) including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax,(excluding Goods and service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not enterain any claim whatsoever in this respect of the same.	13.02	1149.00	Rupees One thousand one hundred forty nine and paise zero zero only	Per Cubic Meter	14960.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement isto two coarse sand) isto four graded crushed stone aggregate 40 mm (Fourty millimeter) nominal size) including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax,(excluding Goods and service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contractor and Government shall not enterain any claim whatsoever in this respect of the same.	13.02	5305.00	Rupees Five thousand three hundred five and Paise zero zero only	Per Cubic Meter	69071.00
Total:-						84031.00

Estimate No. :- 100
 DNIT No. :- 100
 Head of account :-

Draft Schedule of Quantity approved for Rs 84031/only for 2026-27

[Signature]
 Executive Engineer,
 Jhandutta Division,
 HPPWD Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Name of Work :- C/o Link road Malroun to Boatghat km 0/00 to 2/500 (SH:- C/o RCC slab culvert at Rd 0/640 a/w wing wall both side) 0SP/2023/47 Deposit work.			Estimated cost:- ₹ 254101.00			
			Earnest Money:- ₹ 5082.00			
			Time allowed:- Two Months			
Sr. No.	Description of iteams	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and carriage of materials and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax,(excluding Good Service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	24.86	208.00	INR Two hundred eight and Paise zero zero Only	Per Cubic Meter	5171.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one cement isto five coarse sand) isto ten graded crushed stone aggregate 40 mm (fourty milimeter nominal size) including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, (excluding Good Service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	58.31	4121.00	INR Four thousand one hundred twenty one and Paise zero zero Only	Per Cubic Meter	240296.00
3	Banking excavated earth in layers not exceeding 20 cm in depth, breaking clods, watering, rolling each layer with ½ tonne roller, or wooden or steel rammers, and rolling every 3rd and top-most layer with power roller of minimum 8 tonnes and dressing up, in embankments for roads, flood banks, marginal banks, and guide banks etc., lead upto 50 m and lift upto 1.5 mtr within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax, (excluding Good Service Tax), building and other constnuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.40	284.00	INR Two hundred eighty four and paise zero zero only	Per cubic metre	2386.00
4	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm (one hundered milimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material within all leads and lifts and other incidental. The rate includes octroi, royalty Malkana toll tax, (excluding Good Service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the Contracwtor and Government shall not enterain any claim whatsoever in this respect of the same.	22.00	284.00	INR Two hundred eighty four and paise zero zero only	Each	6248.00
Total:-						254101.00

Draft Schedule of quantity approved
for Rs- 254101/- only for year 2026-27

Estimate No. :- 77
DNIT No. :- 77
Head of account :-

Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta.



DRAFT SCHEDULE OF QUANTITY						
Name of Work :- R/R Damages on link road from SDM office to Jhandutta via block (SH:- P/L soling, C.C. at various Rds) 0/850 to 0/881.50)			Estimated cost:- ₹ 84587.00			
			Earnest Money:- ₹ 1692.00			
			Time allowed:- One Month			
Sr. No.	Description of iteams	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.64	208.00	INR Two hundred eight and Paise zero zero Only	Per Cubic Meter	3045.00
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.64	1149.00	INR One thousand one hundred forty nine and Paise zero zero only	Per Cubic Meter	16821.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement isto two coarse sand) isto four graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.20	5305.00	INR Five thousand three hundred five and Paise zero zero only	Per Cubic Meter	64721.00
	Total					84587.00

Estimate No. :- 98
DNIT No. :- 98
Head of account :-

*Draft Schedule of Quantity
approved for Rs- 84587/- only
for year 2026-27*

[Signature]
Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta.



DRAFT SCHEDULE OF QUANTITY						
Name of Work :- R/R Damages on link road from SDM office to Jhandutta via block (SH:- P/L soling, C.C. at various Rds) 4/890 to 0/921.50		Estimated cost:- ₹ 84587.00				
		Earnest Money:- ₹ 1692.00				
		Time allowed:- One Month				
Sr. No.	Description of iteams	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1.	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.64	208.00	INR Two hundred eight and Paise zero zero Only	Per Cubic Meter	3045.00
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.64	1149.00	INR One thousand one hundred fourty nine and Paise zero zero only	Per Cubic Meter	16821.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement isto two coarse sand) isto four graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other constrcution worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.20	5305.00	INR Five thousand three hundred five and Paise zero zero only	Per Cubic Meter	64721.00
Total						84587.00

Estimate No. :- 10/
 DNIT No. :- 10/
 Head of account :-

*Draft schedule of quantity
 approved for Rs 84587/- only
 for year 2026-27*

[Signature]
 Executive Engineer,
 Jhandutta Division,
 HP.PWD Jhandutta.

DRAFT SCHEDULE OF QUANTITY						
Name of Work :- R/R Damages on link road from SDM office to Jhandutta via block (SH:- P/L soling, C.C. at various Rds) 0/990 to 0/021.50)			Estimated cost:- ₹ 84587.00			
			Earnest Money:- ₹ 1692.00			
			Time allowed:- One Month			
Sr. No.	Description of iteams	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.64	208.00	INR Two hundred eight and Paise zero zero Only	Per Cubic Meter	3045.00
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	14.64	1149.00	INR One thousand one hundred fourty nine and Paise zero zero only	Per Cubic Meter	16821.00
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:2:4 (one cement isto two coarse sand) isto four graded stone aggregate 20 mm (twenty millimeter) nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	12.20	5305.00	INR Five thousand three hundred five and Paise zero zero only	Per Cubic Meter	64721.00
Total						84587.00

Estimate No. :- 102
DNIT No. :- 102
Head of account :-

*Draft Schedule of Quantity
approved for Rs. 84,587/- only
for year 2026-27*

[Signature]
Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of Rain damages on various road under Berthin Section (SH:- Removal of slips of Ghumarwin Berthin Talai road from Rd 4/00 to 14/00 & Badgaoun to Ree Radoh Road from Rd 0/00 to 4/00 under PDNA-2023				Estimated cost:- ₹ 423000.00		Only
				Earnest Money:- ₹ 8460.00		Only
				Time allowed:- One Month		
Sr. No.	Description of items	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figures	Words		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material as per technical specification 302.3.5 and 1611 including carriage of materials within all leads and lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods and Service Tax), building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	3859.49	109.60	Rupees One hundred nine and paise six zero only	Per Cubic Meter	423000.00
Total:-						423000.00

Draft Schedule of quantity approved
for Rs 4,23,000/- only for year 2026-27.

Estimate No. :- 78
DNIT No. :- 78
Head of Account:-

[Signature]
Executive Engineer,
Jhandutta Division,
HPPWD, Jhandutta.



DRAFT SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damages on Jhandutta to Narlaghat road km 0/00 to 4/00 (SH:-C/o R/wall at RD 1/210 to 1/217.75)

Estimated cost:- ₹ 84104.00
Earnest Money:- ₹ 1682.00

Time allowed:- One Month

Sr. No.	Description of items	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods and Service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.67	208.00	INR Two hundred eight and Paise zero zero Only	Per Cubic Meter	1387.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:3:10 (one cement isto five coarse sand) isto ten graded crushed stone aggregate 40 mm (fourty millimeter nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods and Service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.29	4011.00	INR Four thousand eleven and Paise zero zero Only	Per Cubic Meter	73361.00
3	Providing weep hole in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100mm (one hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods and Service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	284.00	INR Two hundred eighty four and Paise zero zero Only	Each	2272.00
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana, Toll tax, (excluding Goods and Service Tax) building and other construction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.43	1101.70	INR One Thousand one hundred one and Paise seven zero zero only	Per Cubic Meter	7084.00
Total:-						84104.00

*Draft schedule of quantity approved
dtds. 8/10/21 only after 2008-2017*

Estimate No. :- 105
DNIT No. :- 105
Head of account :-

Executive Engineer,
Jhandutta Division,
HP, PWD Jhandutta



DRAFT SCHEDULE OF QUANTITY

Name of Work :- Restoration of rain damages on Jhandutta to Narlaghat road km 0/00 to 4/00 (SH:-C/o R/wall at RD 1/220 to 1/227.75)			Estimated cost:- ₹ 84228.00			
			Earnest Money:- ₹ 1685.00			
			Time allowed:- One Month			
Sr. No.	Description of iteams	Quantity	Rate excluding GST (in Rs.)		Unit	Amount
			Figure	Words		
1	Earth work in excavation for foundation of structures in all type of soil by Manual /mechanical means as per drawing and technical specification including setting out construction of shoring and bracing, removal of stumps and other deleterious material, and disposal of material upto any lead and lift, dressing of sides and bottom and back filling with approved material and pumping and bailing out water (surface and sub-soil water) upto all depth and any quantum of water including cleaning of slush which may arise out during dewatering and including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , (excluding Goods and Service Tax) building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.06	208.00	INR Two hundred eight and Paise zero zero Only	Per Cubic Meter	1676.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:5:10 (one cement isto five coarse sand) isto ten graded crushed stone aggregate 40 mm (fourty milimeter nominal size) including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , (excluding Goods and Service Tax) building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	18.29	4011.00	INR Four thousand eleven and Paise zero zero Only	Per Cubic Meter	73361.00
3	Providing weep hole in brick masonry/ stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100mm (one hundred milimeter) dia. PVC pipe extending through the full width of the structures with slope of 1V:20H towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , (excluding Goods and Service Tax) building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	8.00	284.00	INR Two hundred eighty four and Paise zero zero Only	Each	2272.00
4	Back filling behind abutment wing wall and return wall complete as per Drawing and technical specifications clause 1204.3.8 including carriage of materials within all leads lifts and other incidentals as per direction of Engineer-in-Charge. The rate includes, octroi, Malkhana , Toll tax , (excluding Goods and Service Tax) building and other constreuction worker, welfare cess royalty or any other tax, levy or cess in respect of input for or output by this contract shall be payable by the contractor and Government shall not entertain any claim whatsoever in this respect of the same.	6.28	1101.70	INR One Thousand one hundred one and Paise seven zero only	Per Cubic Meter	6919.00
Total:-						84228.00

Draft schedule of quantity approved for Rs. 842287 only year 2026-27

Estimate No. :- 104
DNIT No. :- 104
Head of account :-

[Signature]
Executive Engineer,
Jhandutta Division,
HP.PWD Jhandutta.

