



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Office of the Executive Engineer Nadaun Division HPPWD Nadaun

Web:- www.hppwd.gov.in. Email:- ee-pwdndn-hp@hp.gov.in Phone No:- 01972-298570

No:- PW-NDN/Tender/GA/2026-27 9841-47 Dated:- 28/09/2026

To

**The Chief Engineer (HZ).
HPPWD Hamirpur (H.P.).**

Subject:- Publication of Tender Notice.

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary (PW) to the Govt. of HP vide No. PBW(B)A(23)1/2024 Dated 03-01-2025 and further in compliance of Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICTWing/website dt 22/05/2026 as the matter is of urgent nature and in public interest, you are requested to kindly get it published on departmental website.

DA/- As above

**Executive Engineer
Nadaun Division
HPPWD Nadaun**

Copy forwarded with its enclosures for information to:-

1. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
2. The Assistant Engineer, Sub Division, HPPWD Nadaun and Dhaneta.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Supdt of C Branch in this office.
6. Notice Board.

**Executive Engineer
Nadaun Division
HPPWD Nadaun.**

NOTICE INVITING TENDER.

Sealed percentage rate tender on form 6 & 8 are hereby invited by the Executive Engineer Nadaun Division HPPWD Nadaun on behalf of Governor of HP. from the approved eligible contractors enlisted in HPPWD, for the following works; so as to reach this office on **09-10-2026 up to 10.30 A.M.** and same will be opened on the same day at **11.00 A.M.** in presence of the interested contractors or their authorized representative. The application will be received in this office on dated **06-10-2026 upto 1:30 P.M.**. The tender form can be had from the office of Executive Engineer Nadaun Division HPPWD Nadaun on cash payment (Non-refundable) on **05-10-2026** during office hours **10:00 A.M. to 12:00 P.M.** The application must be accompanied with earnest money in shape of NSD/FDR/Time deposit etc. of any post office of HP. or Nationalized Bank duly pledged in the name of Executive Engineer Nadaun Division HPPWD Nadaun cash order will not be entertained, it may be ensure that the earnest money shall have to be prepared work wise otherwise forms will not be issued. The offer of tender shall be kept upon for 60 days. The conditional tender or tender received by post will also be rejected. The undersigned reserves the right to reject any or all tenders without assigning any reason. All the approved eligible contractors should bring copy of their valid enlistment/renewal/exemption from, earnest money with them. The tender documents will be issued only to those who fulfill the eligibility conditions.. The contractor should be registered as dealer under GST Act, Valid copy of Registration as required along with latest returns, Copy of PAN Card, EPF along with latest returns failing which no tender form will be issued to him. All the required documents must be attached with the application.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Cost of Tender form	Time limit	Eligible Class
1	C/O Retaining wall with path from road to the house of Sh. Parshotam Chand village Jani Jagian, P.O. Booni, GP Booni Tehsil Nadaun Distt. Hamirpur (HP) (SH:- P/L CC Pavement & V-shape Drain at RD 0/00 to 0/020). Time Limit: One Month	66576.00	1400/-	350.00	One Month	C&D
2	C/O Path from house of Sh. Jai Karan to Sh. Gurdas house in village Kuthare G.P. Gauna (SH: P/L CC Pavement at RD 0/00 to 0/040). Time Limit:- One Month	55650.00	1200/-	350.00	One Month	C&D
3	Repair and Restoration on link road Bara Sandhora Pitaji Pattan road km 0/00 to 7/00. (SH:- C/O V-shape drain/U-shape drain, Hard shouldering & Edge wall in between RD 0/00 TO 7/00). Under PDNA 2025))	4,25,692/-	8,600/-	350.00	One Month	C&D
4	Repair and Restoration on link road Maloti to Dhanpur (KVK) road km 0/00 to 1/00. (SH:- C/O V-shape drain/U-shape drain, Hard shouldering & Edge wall in between RD 0/00 to 0/320). Under PDNA 2025))	4,53,176/-	9,100/-	350.00	One Month	C&D
5	A/R & M/O HPPWD Rest House at Sera Tehsil Nadaun Distt. Hamirpur (H.P.) (SH:- Providing and fixing curtains excluding Rods)	92,425/-	1,900/-	350.00	One Month	C&D
6	C/O Path to the house of Smt sunita Devi in Vill. Kutharli GP Gauna Tehsil Nadaun km 0/0 to 0/040 (SH: P/L CC Path from RD 0/0 to 0/055)	75,923/-	1,600/-	350.00	One Month	C&D

Certified that the tenders for Job No. 1 and 2 are of urgent nature and in public interest.

HIM SUCHANA AVAM JAN SAMPARK.

13/10/26
Executive Engineer
Nadaun Division
HPPWD Nadaun
On behalf of Governor of Himachal Pradesh

DNIT

DNT						
Name of Work:- C/O Retaining wall with path from road to the house of Sh. Parshotam Chand village Jani Jagian, P.O. Booni, GP Booni Tehsil Nadaun Distt. Hamirpur (HP) (SH:- P/L CC Pavement & V-shape Drain at RD 0/00 to 0/020).					Estimated Cost:-Rs. 66576.00	
					Earnest Money:- Rs. 1400.00	
					Time Limit:- One Month	
Sr. No.	Description of Items	Qty.	Rate inclusive all taxes excluding words	Unit	Amount	
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	2.00	400.00	Rupees Four Hundred and Paise Zero Only	800.00	
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802.803, 1202 & 1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	7.74	4400.00	Rupees Four Thousand Four Hundred and Paise Zero Only	34056.00	

3	Providing and laying in position ready mixed plain cement concrete, M-20 (M-Twenty) with cement content as per approved design mix and manufactured in fully automatic batching plant and transported to site of work in transit mixer for all leads, having continuous agitated mixer, manufactured as per mix design of specified grade for plain cement concrete work, including pumping of R.M.C. from transit mixer to site of laying and curing, excluding the cost of centering, shuttering and finishing, including cost of curing, admixtures in recommended proportions as per IS : 9103 to accelerate/retard setting of concrete, improve workability without impairing strength and durability. All works upto plinth level as per direction of the Engineer-in-charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	6.10	5200.00	Rupees Five Thousand Two Hundred and Paise Zero Only	Per cubic metre	31720.00
				Total:-		66576.00

DNIT approved for Rs. 66,576/- only

Executive Engineer,
Nadaun Division,
HPPWD, Nadda

Job No 2

182

DNT

Name of Work:- C/O Path from house of Sh. Jai Karan to Sh. Gurdas house in village Kuthare G.P. Gauna (SH: P/L CC Pavement at RD 0/00 to 0/040).

Estimated Cost:- Rs. 55650.00
Earnest Money:- Rs. 1200.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate inclusive all taxes excluding		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	18.00	400.00	Rupees Four Hundred and Paise Zero Only	Per cubic metre	7200.00
2	Stone soling properly hand packed filling interstices with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	6.00	1250.00	Rupees One Thousand Two Hundred Fifty and Paise Zero Only	Per cubic metre	7500.00
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:4:8 (one cement : four coarse sand : eight graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate for all works upto plinth level including the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals .The rates are inclusive of octroi, royalty, malkana, Toll tax, GST or other taxes imposed by the Government.	4.50	3900.00	Rupees Three Thousand Nine Hundred and Paise Zero Only	Per cubic metre	17550.00

4	Providing and laying mechanically mixed and vibrated /plain /reinforced cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate in super structure/ abutment using minimum cement contents of 344kg (three hundred forty four kilogram) per cubic metre with 20mm (twenty millimetre) nominal size crushed stone aggregate upto any heights including cost of form work and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths as per drawing and MORTH technical specification 802,804,805,806,807,1202 & 1204 including entire carriage of material in all leads and lifts. The rates are inclusive of octroi, royalty, malkana, Toll tax, GST or other taxes imposed by the Government.	4.50	5200.00	Rupess Five Thousand Two Hundred and Paise Zero Only	per cubic metre	23400.00
			Total:-			55650.00

DNT approved for Rs. 55,650/- only

Executive Engineer,
Nadann Division,
HPPWD, Nadann

Job No 3

95

Name Of Work:- Repair and Restoration on link road Bara Sandhora Pitaji Pattan road km 0/00 to 7/00. (SH:- C/O V-shape drain/U-shape drain, Hard shouldering & Edge wall in between RD 0/00 TO 7/00) Under PDNA 2025))

DNIT

Estimated Cost:-Rs. 425692.00

Earnest Money:- Rs.8600.00

Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate inclusive all taxes excluding G.S.T	Unit	Amount
			Figure		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	71.89	400.00	Rupees Four Hundred and Paise Zero Only	28756.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	81.63	4400.00	Rupees Four Thousand Four Hundred and Paise Zero Only	359172.00
3	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths. In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	10.49	3600.00	Rupees Three Thousand Six Hundred and Paise Zero Only	37764.00
Total					425692.00

DNIT approved for Rs. 4,25,692.00 only

Executive Engineer,
Nadaun Division,
HPPWD, Nadaun

To 5204
(96)

DNIT

Name Of Work:- Repair and Restoration on link road Maloti to Dhanpur (KVK) road km 0/00 to 10/00. (SH - C/O V-shape drain/U-shape drain, Hard shouldering & Edge wall in between RD 0/00 to 0/320). Under PDNA 2025))

Estimated Cost:-Rs. 453176.00
Earnest Money:- Rs.9100.00
Time Limit:- One Month

Sr. No.	Description of Items	Qty.	Rate inclusive all taxes excluding G.S.T		Unit	Amount
			Figure	words		
1	Earth work in excavation for all type of road structure such as retaining walls ,breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	66.85	400.00	Rupees Four Hundred and Paise Zero Only	Per cubic metre	26740.00
2	Providing and laying mechanically mixed and vibrated cement concrete nominal mix 1:3:6 (one cement :three Sand :six graded crushed stone aggregate 20mm (twenty millimetre nominal size) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work for plain concrete in drain and channel etc. open foundations complete as per drawing and technical specification clause 802,803, 1202 &1203 including carriage of material within all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	88.67	4400.00	Rupees Four Thousand Four Hundred and Paise Zero Only	Per cubic metre	390148.00
3	Providing and laying cement concrete 1:5:10 mechanically mixed (one cement : Five sand : ten graded crushed / broken stone aggregate 40mm (forty millimetre nominal size) and curing complete including the cost of form work with M.S plates for plain concrete on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths . In retaining walls / breast walls as per drawing and technical specifications clause 802,803,1202and 1203 and as per direction of Engineer-in- Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	10.08	3600.00	Rupees Three Thousand Six Hundred and Paise Zero Only	Per cubic metre	36288.00
Total						453176.00

DNIT approved for Rs. 4,53,176/- only

Executive Engineer,
Nadaun Division,
HPPWD, Nadaun

Job No 5

K.C.

DNIT

Name of Work:- A/R & M/O HPPWD ~~HPPWD~~ Rest House at Sera Tehsil Nadaan Distt. Hamirpur (H.P.) (SH:- Providing and fixing curtains excluding Rods)

Estimated Cost:-Rs. 92425

Earnest Money:- Rs.1900.00

Time Limit:- One month

Sr. No.	Description of Items	Qty.	Rate inclusive all taxes excluding G.S.T		Unit	Amount
			Fig.	Words		
1	Providing and fixing curtains make by S.N. Home Decor and Bombay mills with heavy quality cloth and blackout fabric lining and stitching and fixing excluding curtain rods and side clamp with ornamental hooks size of curtain having (8.6 x 4ft)(eight point six into four feet) with satisfaction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	34.80	1919.35	Rupees One Thousand Nine Hundred Nineteen and Paise Thirty Five Only	Per Running Metre	66793.00
2	Providing and fixing of curtain dicor making S.N. Home decor with lining blackout fabric stitching and fixing excluding curtain roads, clamp and ornamental side hooks size of curtain having (7x4ft)(seven into four feet) complete with satisfaction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	16.80	1525.70	Rupees One Thousand Five Hundred Twenty Five and Paise Seventy Only	Per Running Metre	25632.00
Total						92425.00

DNIT approved for Rs. 92,425/- only

1-1

Executive Engineer
Nadaan Division
HPPWD Nadaan

Job No 5

K.C.

DNIT

Name of Work:- A/R & M/O HPPWD ~~HPWD~~ Rest House at Sera Tehsil Nadaun Dist. Hamirpur (H.P.) (SH:- Providing and fixing curtains excluding Rods)						Estimated Cost:-Rs. 92425
						Earnest Money:- Rs. 1900.00
						Time Limit:- One month
Sr. No.	Description of Items	Qty.	Rate inclusive all taxes excluding G.S.T		Unit	Amount
			Fig.	Words		
1	Providing and fixing curtains make by S.N. Home Decor and Bombay mills with heavy quality cloth and blackout fabric lining and stitching and fixing excluding curtain rods and side clamp with ornamental hooks size of curtain having (8.6 x 4ft)(eight point six into four feet) with satisfaction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	34.80	1919.35	Rupees One Thousand Nine Hundred Nineteen and Paise Thirty Five Only	Per Running Metre	66793.00
2	Providing and fixing of curtain dicor making S.N. Home decor with lining blackout fabric stitching and fixing excluding curtain roads, clamp and ornamental side hooks size of curtain having (7x4ft)(seven into four feet) complete with satisfaction of Engineer-in-Charge including entire carriage of material with in all leads and lifts and other incidentals . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	16.80	1525.70	Rupees One Thousand Five Hundred Twenty Five and Paise Seventy Only	Per Running Metre	25632.00
Total						92425.00

DNIT approved for Rs. 92,425/- only

Executive Engineer
Nadaun Division
HPPWD Nadaun

Job No. 6
744

DNT

Name of Work:- C/O to the house of Smt. Sunita Devi in village Kuthari G.P. Gauna, Tehsil Nadaun ~~Rs. 5000.00~~
 (SH:- P/L CC Path from RD 0/00 to 0/055)
 Estimated Cost:-Rs. 75923.00
 Earnest Money:- Rs. 1600.00
 Time Limit:- One Months

Sr. No.	Description of Items	Qty.	Rate inclusive all taxes excluding	Unit	Amount
			Figure		
1	Earth work in excavation for all type of road structure such as retaining walls , breast walls, culverts, drains and parapets etcetera in all type of classification of soil comprising of ordinary soil . ordinary rock, hard rock, chiseling/ wedging out of rock (where blasting is prohibited) as per drawings and M.O.R.D technical specification clause 305-1 and as per direction of the Engineer-in- Charge including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal of materials upto any leads and lifts including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm(one hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in- Charge including carriage of materials within all leads and lifts and other incidentals . The	24.75	400.00	Rupees Four Hundred and Paise Zero Only	Per cubic metre 9900.00
2	Stone soling properly hand packed filling intersities with spells and consolidating with power road roller to the required gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per drawing and technical specification 100mm(one hundred millimeter) spread thickness including material and labour including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	8.25	1250.00	Rupees One Thousand Two Hundred Fifty and Paise Zero Only	Per cubic metre 10313.00
3	Providing and laying cement concrete 1:4:8 (one cement : four sand : eight graded crushed/broken stone aggregate 40 mm (forty millimetre nominal size) mechanically mixed and vibrated on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights and depths including cost of form work in open foundation complete as per drawing and technical specification clause 802.803,1202&1203 as per direction of Engineer-in- Charge . including carriage of material within all leads and lifts and other incidentals The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	6.19	3800.00	Rupees Three Thousand Eight Hundred and Paise Zero Only	Per cubic metre 23522.00

4	Providing and laying in position cement concrete 1:2:4 (one cement : two coarse sand : four graded stone aggregate) 20 mm (twenty millimetre) nominal size) of specified grade excluding the cost of centering and shuttering - All work up to plinth level including entire carriage of material in all leads and lifts . The rates are inclusive octroi, royalty, Malkana, toll tax, or other taxes, but excluding GST imposed by Government.	6.19	5200.00	Rupees Five Thousand Two Hundred and Paise Zero Only	Per cubic metre	32188.00
	Total:-					75923.00

DNIT Approved For The 75,923/- only

15-1
Executive Engineer,
Nadaun Division,
HPP WD, Nadaun
2