

HIMACHAL PRADESH
PUBLIC WORK DEPARTMENT

No. PW/DT/TA/ NIT /2026-27-

4686

Dated:- 07-09-2026

To,

The Chief Engineer (KZ)
HP PWD Dharmshala HP
e-mail:-hp-kan@nic.in

Subject:_

Publication of Tender Notice .

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per directions received through e-mail dated 22.05.2026 of worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

Encls:- 14 Nos copy of Schedule of quantity.

Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

CERTIFICATE

Certified that the tenders of works, called vide
this office letter No. PW-DT-NIT-2026-27- 4687-4701 Dated:-07-09-2026
are urgent nature.


Executive Engineer
Tanda Division HP PWD
at Nagrota Bagwan

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Sealed Percentage rate tender on form No. 6 & 8 are hereby invited by the **Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan** on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HP PWD (B & R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **16.09.2026** up to **11:00 A.M.** And the same shall be opened on the same day at **04:00 P.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **15.09.2026** up to **4:00 P.M.** and the application for issue of tender form shall be received on **14.09.2026** up to **12:00 noon.** The applications for issue of tender forms accompanied with enlistment letter or renewal letter and the earnest money in the shape of National Saving Certificates/Saving Account of the Post Office /Time Deposit account/FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP PWD Division Tanda at Nagrota Bagwan.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for 120 days.

Sr. No.	Name of work	Estimated Cost	Earnest Money	Time limit
1	Restoration of rain damages on link road Rajiana Jhang Surani via Churan road in District Kangra HP (SH: Providing laying soling grading- III and cement concrete pavement at RD 3/600 to 3/632).	84203.00	1700.00	Two Months
2	Construction of Shed Near Administrative block at Dr. RPGMC Tanda Distt. Kangra HP (SH: Providing and fixing pre-painted sheet roofing etc).	84067.00	1700.00	Two Months
3	Restoration of damages due to laying of pipeline on link road Thana Busal in Distt. Kangra HP Deposit Work (SH: Construction of Retaining wall in km 2/900 to 2/910). D.C. Deposit.	124548.00	2500.00	Two Months
4	Repair of Girls Hostel at Dr. R.P. Govt. Medical college Tanda in Tehsil Nagrota Bagwan distt. Kangra HP (SH: Providing and fixing granite on study table in various rooms).	76557.00	1550.00	Two Months
5	Construction of Shed Near Administrative Block at Dr. RPGMC Tanda Distt. Kangra HP (SH: Providing and fixing pre-painted sheet roofing etc).	84067.00	1700.00	Two Months
6	Balance work of 1 st Year MBBS Girls Hostel at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan Distt. Kangra HP Deposit Work (SH: Providing and applying putty and painting etc. In various Rooms (28 Nos).	84422.00	1700.00	One Mnths
7	Repair of Paraclinic Block Department of Pharmacology at Dr. RPGMC Tanda Distt. Kangra HP Deposit work (SH: Providing and fixing plain multipurpose cement board in roofing and painting & Distemping.)	50203.00	1050.00	Two Months
8	Repair of Type-III Senior Resident Colony at Dr. R.P. Govt. medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra HP Deposit work (SH: Cleaning of bushes, weeds plants and gutter in Block- A to H & 1 to 6 (14 Nos).	87343.00	1750.00	One Months
9	Restoration of rain damages on link road for NH-303 to Kabir Basti km 0/00 to 1/500 in Distt. Kangra HP SDF/2025/1898(SH: Construction of Retaining wall in km 0/240 to 0/250)	250650.00	5050.00	Two Months
10	Construction of link road Near BDO Office Baroh to Danoa khas km 0/00 to 2/200 in Tehsil baroh Distt. Kangra HP (SH: Preparation of Detailed Project Report and CBR Test).	132000.00	2650.00	One Months
11	Restoration of rain damages on link road from Baoi to Subidha Complex road km 0/00 to 1/500 in Distt. Kangra HP (SH: Removal of slips, Dressing of Berms at various Rds).	94406.00	1900.00	Two Month
12	Construction of Saria at G.P. Sunehar in Tehsil Nagrota Bagwan in District Kangra HP Deposit Work VKV (SH: Construction of Shed).VKV/2025/927.	418581.00	8400.00	Three months
13	Balance work of 1 st Year MBBS Boys Hostel at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan Distt. Kangra HP Deposit Work (SH: Providing and applying putty and painting etc. In various Rooms (25 Nos).	83060.00	1700.00	One Mnths
14	Restoration of rain damages on link road Rajiana Jhang Surani via Churan road in District Kangra HP (SH: Construction of link road Rajiana Jhang Surani via Churan road in distt. Kangra (SH: Construction of Retaining wall in Km 3/645 to 3/654 (Left side).	84545.00	1700.00	Two Months

Terms & Conditions:-)

- The contractor/firm should be registered as or dealer GST No.
- The intending contractor / firm have to produce the copy of latest enlistment and renewal enlisted in HPPWD.
- If any of the date mentioned above happened to be Gazetted Holidays the same shall be processed on next working day.
- The Executive Engineer reserves the right to accept/reject any tender/application or all tenders without assigning any reason.
- The Contractor will have to submit affidavit along with application for issue of tender form.
- Next tender will be issued only after completion of previous works in hand.

HIMSUCHANA AVAM & JAN SAMPARK

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

(On behalf of Governor of Himachal Pradesh)

No.PW/NBD/TA/Tender/NIT/2026-27- **4687-4701**

Dated/

07-09-2026

Copy to the following for information and necessary action:-

- The Chief Engineer (KZ), HPPWD, Dharamshala.
- The Executive Engineer IT Cell Shimla HP PWD Shimla.
- The Superintending Engineer, 5th Circle, HPPWD, Palampur.
- The Deputy Commissioner, Kangra at Dharamshala.
- All the S.E.s/E.E.s under North Zone.
- The Sub-Divisional Officer(C) Nagrota Bagwan.
- All the Assistant Engineer under this Division.
- The Drawing /Accounts Branch in this office.
- Notice Board.

Executive Engineer
H.P.P.W.D. Tanda Division
at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 84203.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road Rajjana Jhang Surani via Churan road in Distt. Kangra (H.P.)
 SUB HEAD: - Providing laying *soling grading-III* and cement concrete pavement at RD 3/600 to 3/632

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregate of size 53mm to 22.4mm (Fifty three millimeter to Twenty two point four millimeter) Grading-III size [75mm (seventy five millimeters) compacted thickness] to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty-Hundred) K.N. static roller in stages to proper grade and camber applying and brooming, stone screening type-A of size 13.2mm (thirteen point two millimetres) nominal size at the rate of 0.22 cum (zero point Twenty two) cubic metres per 10 sqm (per ten square metres) and binding material at the rate 0.06 cum (zero point zero six cubic metre) to fill up the interstices of coarse aggregate, watering and compacting to the required density as per technical specifications clause No. 405 as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	7.20 Cubic metres	1737.29	Rupees Two thousand fifty and paise Nil only.	Per cubic metre	12508.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	14.10 Cubic metres	5084.75	Rupees Five thousand eight hundred fifty and paise Nil only.	Per cubic metre	71695.00
TOTAL:-						84203.00
<i>Quoted rates percentage in figure</i>						
<i>Quoted rates percentage in words</i>						


 Executive Engineer,
 H.P.P. W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :- Construction of Shed near Administrative Block at Dr.R.P.G.M.C. Tanda Distt Kangra H.P.					ESTIMATED COST :- ₹ 84067.00	
Sub Head : Providing and fixing prepainted sheet roofing etc;					₹ 1700.00	
					TIME LIMIT :- TWO MONTHS	
Sr. No	Description Of Item	Qty.	Rate (Rs.)		Unit	Amount (Rs.)
			In Fig.	In words		
1	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per drawing and HP.PWD technical specifications and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	65.50	1059.32	Rupees One thousand fifty nine and paise thirty two only.	Per square metre	69385.00
2	Providing and fixing M.S. BP Sheet 1.66mm to 20mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) as per drawing and HP.PWD technical specifications and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	5.66	1288.81	Rupees One thousand two hundred eighty eight and paise eighty one only	Per square metre	7295.00
3	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ² . as per drawing and HP.PWD technical specifications and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	5.10	466.86	Rupees Four hundred sixty six and paise eighty six only.	Per running metre	2381.00
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work as per drawing and HP.PWD technical specifications and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	59.35	69.83	Rupees Sixty nine and paise eighty three only.	Per square metre	4144.00
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per drawing and HP.PWD technical specifications and as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	11.32	76.19	Rupees Seventy six and paise nineteen only.	Per square metre	862.00
					Total:-Rs.	84067.00
<i>Quoted rates percentage in figure</i>						
<i>Quoted rates percentage in words</i>						


 Executive Engineer,
 H.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 124548.00
 EARNEST MONEY: - ₹ 2500.00
 TIME LIMIT: - TWO MONTHS

NAME OF WORK:- Restoration of damages due to laying of pipeline on link road Thana Busal in Distt. Kangra (H.P.) Deposit work
 SUB HEAD:- Construction of Retaining wall in Km 2/900 to 2/910

Sr. No.	Description	Quantity	In fig.	Rate		Unit	Amount
				in words			
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within any lead complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	3 10.70 Cubic metres	4 262.71	5 Rupees Two hundred sixty two and paise seventy one only.		6 Per cubic metre	7 2811.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	34.72 Cubic metres	3372.88	Rupees Three thousand three hundred seventy two and paise eighty eight only.		Per cubic metre	117106.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	10.00 Running metres	271.19	Rupees Two hundred seventy one and paise nineteen only.		Per running metre	2712.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	3.02 Cubic metres	635.59	Rupees Six hundred thirty five and paise fifty nine only.		Per cubic metre	1919.00
TOTAL:-							124548.00
Quoted rates percentage in figure							
Quoted rates percentage in words							


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagfota Bagwan.

Schedule of Quantity

ESTIMATED COST :-	₹	76557.00
EARNEST MONEY :-	₹	1550.00
TIME LIMIT	:	TWO MONTHS

Name of Work:- Repair of Girls Hostel at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.)

Sub Head:- Providing and fixing granite on study table in various rooms.

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre-moulded and pre-polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels. Granite of any colour and shade Area of slab over 0.50 sqm complete as per drawing and HP.PWD technical specifications, as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	24.75	3093.22	Rupees Three thousand ninety three and paise twenty two only.	Per Square metre	76557.00
Total:-						76557.00
<i>Quoted rates percentage in figure</i>						
<i>Quoted rates percentage in words</i>						


 Executive Engineer,
 HP PWD Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

NAME OF WORK :- Construction of Shed near Administrative Block at Dr.R.P.G.M.C. Tanda Distt Kangra H.P.		ESTIMATED COST :-	₹ 84067.00
Sub Head :- Providing and fixing prepainted sheet roofing etc;		EARNEST MONEY :-	₹ 1700.00
		TIME LIMIT :-	TWO MONTHS

Sr. No	Description Of Item	Qty.	Rate (Rs.)		Unit	Amount (Rs.)
			In Fig.	In words		
1	Providing and fixing 0.60mm thick prepainted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per drawing and HP.PWD technical specifications and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	65.50	1059.32	Rupees One thousand fifty nine and paise thirty two only.	Per square metre	69385.00
2	Providing and fixing M.S. BP Sheet 1.66mm to 20mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) as per drawing and HP.PWD technical specifications and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	5.66	1288.81	Rupees One thousand two hundred eighty eight and paise eighty one only	Per square metre	7295.00
3	Providing ridges or hips of width 60 cm overall width plain G.S. sheet fixed with polymer coated J or L hooks, bolts and nuts 8 mm dia G.I. limpet and bitumen washers complete. 0.63 mm thick with zinc coating not less than 275 gm/m ² . as per drawing and HP.PWD technical specifications and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	5.10	466.86	Rupees Four hundred sixty six and paise eighty six only.	Per running metre	2381.00
4	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work as per drawing and HP.PWD technical specifications and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	59.35	69.83	Rupees Sixty nine and paise eighty three only.	Per square metre	4144.00
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture as per drawing and HP.PWD technical specifications and as directed by the Engineer-In-charge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	11.32	76.19	Rupees Seventy six and paise nineteen only.	Per square metre	862.00
Total:-Rs.						84067.00

Quoted rates percentage in figure

Quoted rates percentage in words


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 50203.00
 EARNEST MONEY :- ₹ 1050.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK :- Repair of Paraclic Block Department of Pharmacology at Dr.R.P.G.M.C. Tanda Distt Kangra H.P. DEPOSIT WORK

SUB HEAD :- Providing and fixing plain multipurpose cement board in roofing and Painting & Distempering.

Sr. No	Description Of Item	Qty.	Rate (Rs.)		Unit	Amount (Rs.)
			In Fig.	In words		
1	Providing and fixing plain multipurpose cement board(Hight pressure steam cured) with suitable screws for cement particle board in ceiling etc. complete (frame work to be paid seperately)6 mm thick Cement fiber board as per IS: 14862 as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	48.73	493.18	Rupees Four hundred ninety three and paise eighteen only	Per square metre	24033.00
2	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	48.73	69.83	Rupees Sixty nine and paise eighty three only.	Per square metre	3403.00
3	Wall painting with acrylic emulsion paint of approved brand and manufacture to give an even shade :Two or more coats as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	91.73	69.49	Rupees Sixty nine and paise forty nine only.	Per square metre	6374.00
4	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	27.52	49.15	Rupees Forty nine and paise fifteen only.	Per square metre	1353.00
5	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	164.46	87.29	Rupees Eighty seven and paise twenty nine only	Per kilogram	14356.00
6	Renewing Glasss panes with putty and nails wherever necessary including racking out the old putty:Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm) as per drawing and HP.PWD technical specifications, as directed by the Engineer-Incharge including carriage of materials within all leads, lifts and other incidentals. The rate inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	0.95	720.34	Rupees Seven hundred twenty and paise thirty four only.	Per square metre	684.00
Total:-Rs.						50203.00
Quoted rates percentage in figure						
Quoted rates percentage in words						


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST:- Rs. 87343.00
EARNEST MONEY :- Rs. 1750.00
TIME LIMIT :- ONE MONTH

NAME OF WORK :- Repair of Type-III Senior Resident Colony at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.) (Deposit Work)

SUB-HEAD :- Cleaning of bushes, weeds plants and gutter in Block-A to H & I to 6 (14 Nos.)

S. No.	Description of items	Quantity	Rate		Unit	Amount
			In fig	In words		
1	2 Clearance/Removal of bushes, weeds, plants and Root drainage System (Gutter etc.) in all depth and height upto 4 storey Building Blocks complete as per direction of Engineer-In-charge including carriage of material within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	3 14 Numbers	4 6238.75	5 Rupees Six thousand two hundred thirty eight and paise seventy five only	6 Each	7 87343.00
TOTAL :-						87343.00

Quoted rates percentage in figures

Quoted rates percentage in word

Executive Engineer,
H.P.P.W.D., Division,
Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 250650.00
 EARNEST MONEY: - ₹ 5050.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road fro NH-303 to Kabir Basti Km 0/000 to 1/500 in Distt. Kangra (H.P.) SDF/2025/1898.
 SUB HEAD: - Construction of Retaining wall in Km 0/240 to 0/250

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	31.50 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	8275.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	64.60 Cubic metres	3372.88	Rupees Three thousand three hundred seventy two and paise eighty eight only.	Per cubic metre	217888.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	28.00 Running metres	271.19	Rupees Two hundred seventy one and paise nineteen only.	Per running metre	7593.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	9.30 Cubic metres	635.59	Rupees Six hundred thirty five and paise fifty nine only.	Per cubic metre	5911.00
5	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:2:4 (One Cement : Two coarse sand : Four graded stone aggregate 20mm (Twenty millimetres) nominal size complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	2.16 Cubic metres	5084.75	Rupees Five thousand eight four and paise seventy five only.	Per cubic metre	10983.00
TOTAL: -						250650.00

Quoted rates percentage in figure
 Quoted rates percentage in words


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 132000.00
 EARNEST MONEY :- ₹ 2650.00
 TIME LIMIT : ONE MONTH

NAME OF WORK :- Construction of Link Road Near BDO Office Baroh to Danoa Khas kms 0/00 to 2/200 in Tehsil Baroh, Distt. Kangra (H.P).
SUB-HEAD :- Preparation of Detailed Project Report and CBR Test.

S. No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Preparation of detailed project report which include the following provision as given Topography Survey by Digital Total Station with two second accuracy, showing all features on survey plan like trees, culverts, bridge, electric pole, telephone poles, hand pump, schools, Haditmatns Villages etc. Draw cross-sections at 15 m (fifteen metre) intervals, L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provisions and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Reports of 3 days traffic count survey along with soft copy as per requirement of MoRD/NRIDA. Test reports must include at least following field test per km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii) Optimum Moisture Content (iv) Maximum Dry Density (v) Grain size Analysis. Detailed Project Report and working drawings (Draft and final). Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR copy (soft & Hard copy) and as per the direction and entire satisfaction of Engineer-in-charge complete. The Rate are including of Royalty, Malkana, Octroi, toll tax excluding GST or any other taxes imposed by the Government. (GST shall be paid separately).	2.200 Kilometres	60000.00	Rupees Sixty thousand and paise NIL only	Per Kilometre	132000.00
TOTAL :-						132000.00

Quoted rates percentage in figure

Quoted rates percentage in words


 Executive Engineer,
 H.P.P.W.D., Division,
 Tanda at Nagrota Bagwan

SCHEDULE OF QUANTITY

ESTIMATED COST: - ₹ 94406.00
 EARNEST MONEY : - ₹ 1900.00
 TIME LIMIT : - TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road from Baroi to Subidha Complex road Km 0/000 to 1/500 in Distt. Kangra (H.P.)
 SUB HEAD:- Removal of slips, Dressing of Berms at various RDs.

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2	3	4	5	6	7
1	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials within lift upto 1.50mtrs(One decimal fifty meters) and lead upto 1000 mtrs (One thousand metres) as per technical specifications 302.3.5 and 1611 complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	457.86 Cubic meters	84.75	Rupees Eighty four and paise seventy five only.	Per cubic metre	38804.00
2	Earth Filling in road side berms completed as per drawing and technical specification Clause 305.3.9 complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	330.00 Cubic metres	168.49	Rupees One sixty eight and paise forty nine only.	Per cubic metre	55602.00
TOTAL: -						94406.00
Quoted rates percentage in figure						
Quoted rates percentage in words						


 Executive Engineer,
 H.P.P.W.D. Division,
 Tanda at Nagrota Bagwan.

SCHEDULE OF QUANTITY

ESTIMATED COST: - Rs. 418581.00
 EARNEST MONEY :- Rs. 8400.00
 TIME LIMIT : THREE MONTHS

NAME OF WORK:- Construction of Sarai at G.P. Sunehar in Tehsil Nagrota Bagwan in District Kangra, (H.P.). Deposit work.

SUB-HEAD:- Construction of Shed. *VKV/2.025/927*

Sr No.	Description of items	Quantity	RATES		Unit	Amount
			In fig	In words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils as directed, within a any lead as directed by the Engineer-in-charge, within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	1.37 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy one only.	Per cubic metre	360.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level cement concrete 1:2:4 (One cement; two sand; four graded broken/crushed stone aggregate 20mm (Twenty millimetres) nominal size mechanically mixed and curing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design, specifications and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	1.37 Cubic metres	5042.36	Rupees Five thousand forty two and paise thirty six only.	Per cubic metre	6908.00
3	Providing and fixing 0.60 mm (Zero point sixty millimetres) thick preprinted steel sheet of Tata Durashine / Sail / Reliance / Jindals steels in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 (Twenty) microns over 5 (five) microns primer coating to back coat of polyester of 5 (five) microns over 5 (five) microns primer coating including fixing with preprinted iron J or L hooks, bolts and nuts 6mm (Six millimetres) diameter with preprinted limpet and rubber washers complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	132.61 Square metres	974.57	Rupees Nine hundred seventy four and paise fifty seven only.	Per Square metre	129238.00
4	Structural steel work of Tata / Sail / Reliance / Jindal riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	1001.63 Kilograms	97.45	Rupees Ninety seven and paise forty five only.	Per kilo-gram	97609.00

5

5	Structural steel work of Tata / Sail / Reliance / Jindal riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer in grating, frames, guard bar, ladder, railing, brackets, gates and similar works complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	1591.59 Kilograms	88.97	Rupees Eighty eight and paise ninety seven only.	Per kilo-gram	141604.00
6	Providing and fixing factory made ridges or hips having proper gola shape 60 cm (Sixty centimetres) overall with 0.60 mm (Zero point sixty millimetres) thick prepainted steel sheets of Tata / Sail / Reliance / Jindal steels in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 (Twenty millimetres) microns over 5 (five) microns primer coating + back coat of polyester of 5 (five) microns over 5 (five) microns primer coating fixing with prepainted iron J or L hooks, bolts & nuts 6 mm (Six millimetres) dia & prepainted G.I. limpet and bitumen washers complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	10.30 Running metre	466.10	Rupees Four hundred sixty six and paise ten only.	Per Running metre	4801.00
7	Providing and fixing M.S. B.P. sheet 2.0mm (Two point zero millimetres) thick eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-In-charge (Base members of steel work shall be measured and paid separately) including fixing complete including carriage of material within all leads, lifts and other incidentals as per specifications, approved drawing, design and as directed by the Engineer-in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	28.98 Square metres	1186.44	Rupees One thousand one hundred eighty six and paise forty four only.	Per Square metre	34383.00
8	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm (Zero point ninety litre per ten square metre) over an under coat of primer applied @ 0.80 ltr/ 10 sqm (Zero point eighty litre per ten square metre) of approved brand and manufacture complete upto all floor level complete including carriage of material with in all leads, lifts and other incidentals as per drawing, design and specifications, as per the direction and entire satisfaction of Engineer-in-Charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax, excluding GST and any other taxes imposed by the Government.	57.88 Square metres	63.55	Rupees Sixty three and paise fifty five only.	Per Square metre	3678.00
TOTAL :-						418581.00

Quoted Rates Percentage in figure

Quoted Rates Percentage in word

Dr. Chakrabarti approved

Executive Engineer,
H.P.P.W.D. Division,
Tanda at Nagrota Bagwan.

418581/-

SCHEDULE OF QUANTITY

ESTIMATED COST :- ₹ 84545.00
 EARNEST MONEY :- ₹ 1700.00
 TIME LIMIT :- TWO MONTHS

NAME OF WORK:- Restoration of rain damages on link road Rajiana Jhang Surani via Churan road in Distt. Kangra (H.P.)
 SUB HEAD:- Construction of Retaining wall in Km 3/645 to 3/654 (Left side).

Sr. No.	Description	Quantity	Rate		Unit	Amount
			In fig.	in words		
1	2	3	4	5	6	7
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m (One point five metre) in width or 10 sqm (Ten square metre) on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m (One point five metre), including getting out the excavated soil and disposal of surplus excavated soils complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	9.22 Cubic metres	262.71	Rupees Two hundred sixty two and paise seventy only.	Per cubic metre	2422.00
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:5:10 (One cement : Five coarse sand : Ten graded stone aggregate 40 mm (Forty millimetres nominal size) complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	23.21 Cubic metres	3347.46	Rupees Three thousand three hundred forty seven and paise forty six only.	Per cubic metre	77695.00
3	Providing weepholes in brick masonry/stone masonry, plain/reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	10.00 Running metres	271.19	Rupees Two hundred seventy one and paise nineteen only.	Per running metre	2712.00
4	Backfilling with granular material behind abutment, wing wall and return wall complete as per drawings and technical specification Clause 1204.3.8, granular material complete as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government	2.70 Cubic metres	635.59	Rupees Six hundred thirty five and paise fifty nine only.	Per cubic metre	1716.00
TOTAL:-						84545.00
<u>Quoted rates percentage in figure</u>						
<u>Quoted rates percentage in words</u>						


 Executive Engineer,
 H.P.P.W.D Division,
 Tanda at Nagrota Bagwan.

(122)

Schedule of Quantity

ESTIMATED COST :- ₹ 83060.00
EARNEST MONEY :- ₹ 1700.00
TIME LIMIT : ONE MONTH

Name of Work:- Balance work of 1st Year MBBS Boys Hostel at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.) Deposit work

Sub Head:- Providing and applying putty and painting etc. in various Rooms (25 Nos.)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and applying white cement based putty of average thickness 1 mm (One millimetres), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete and as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	253.92 Square metres	49.15	Rupees Forty nine and paise fifteen only.	Per Square metre	12480.00
2	Wall painting (Two coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly bushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for marking the surface complete and as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1015.68 Square metres	69.49	Rupees Sixty nine and paise forty nine only.	Per Square metre	70580.00
Total:-						83060.00

Executive Engineer,
HP-PWD Division,
Tanda at Nagrota Bagwan.

Draft Schedule of Quantity

ESTIMATED COST :- ₹ 84422.00
EARNEST MONEY :- ₹ 1700.00
TIME LIMIT : ONE MONTH

Name of Work:- Balance work of 1st Year MBBS Girls Hostel at Dr. R.P. Govt. Medical College Tanda in Tehsil Nagrota Bagwan, Distt. Kangra (H.P.) Deposit work

Sub Head:- Providing and applying putty and painting etc. in various Rooms (28 Nos.)

Sr. No	Description Of Item	Quantity	Rate		Unit	Amount
			In fig	In words		
1	Providing and applying white cement based putty of average thickness 1 mm (One millimetres), of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete and as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	113.34 Square metres	49.15	Rupees Forty nine and paise fifteen only.	Per Square metre	5571.00
2	Wall painting (Two coat) with plastic emulsion paint of approved brand and manufacture on undecorated wall surfaces to give an even shade including thoroughly bushing the surface free from mortar droppings and other foreign matter and sand papered smooth including applying of putty as required for marking the surface complete and as per approved drawing, design and as directed by the Engineer-in-charge and as per HPPWD technical specification including carriage of materials within all leads, lifts and other incidentals. The rate is inclusive of octroi, royalty, Malkana, toll tax, sale tax or other taxes excluding GST imposed by the Government.	1134.71 Square metres	69.49	Rupees Sixty nine and paise forty nine only.	Per Square metre	78851.00
Total:-						84422.00

Executive Engineer,
HP-PWD Division,
Tanda at Nagrota Bagwan.