

Himachal Pradesh
Public Works Department

No. PW-KD- CTR- Tender-NIT/2026-2027- 16598-99 Dated:- 3/9/26

To


The Executive Engineer (IT Cell)
Nigam Vihar Shimla.

Subject :- Publication of Tender Notice.

Jai Hind


Enclosed please find herewith the tender Notice of work as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 the 03-01-2024 and PWD-B-A0(3)/8/2025- 300858 dated 09-10-2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender & Schedule of Quantity and Certificate.


Executive Engineer,
HPPWD, Division Kasumpti
Shimla.

Copy forwarded to for further necessary action please.

1. The Superintending Engineer 4th Circle HPPWD Shimla .


Executive Engineer,
HPPWD., Division Kasumpti
Shimla.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDERS**

Executive Engineer B&R Division Kasumpti HPPWD Shimla for the following works on behalf of the Government of Himachal Pradesh from the eligible contractors enlisted in HPPWD, so as to reach in the office as per time schedule given below:-

- | | |
|--|-----------------------------------|
| 1. Date of receipt of application for tender forms:- | 14-09-2026 10:00 AM upto 12:00 PM |
| 2. Dated of Issue /sale of tender forms:- | 14-09-2026 12:00 PM upto 4:00 PM |
| 3. Date of receipt of tender:- | 15-09-2026 up to 10:30 AM |
| 4. Date of opening of tender:- | 15-09-2026 up to 11:00 AM |

Sr. No.	Name of Work	Estimated cost	EMD(Rs .)	Cost of Tender (Rs.)	Time Limit	Eligible class of Contractor
1	A/R & M/O on various roads AIMSS section under Sub-Division No.1 (SH:- Supplying and stacking pot seal bags cold mix in various RDs).	83644/-	1700/-	350/-	30 days	Class-D
2	A/R & M/O on various roads Bharari Section under Sub-Division No.1 (SH:-Supplying and stacking pot seal bags cold mix in various RDs) (Without GST).	83644/-	1700/-	350/-	30 days	Class-D
3	A/R & M/O on various roads Lakkar Bazar section under sub-Division No.1 (SH:- Supplying and stacking pot seal bags cold mix in various RDs).	80085/-	1600/-	350/-	30 days	Class-D
4	A/R & M/O on various roads Mehli Section under Sub-Division No.1 (SH:- Supplying and stacking pot seal bags cold mix in various RDs).	82754/-	1700/-	350/-	30 days	Class-D
5	A/R & M/O on various roads Dhalli section under Sub-Division No.1 (SH:- Supplying and stacking pot seal bags cold mix in various RDs).	82754/-	1700/-	350/-	30 days	Class-D
6	A/R & M/O on various roads Fagu Section under Mashobra Sub-Division (SH:- Supplying and stacking pot seal bags cold mix in various RDs).	81864/-	1700/-	350/-	30 days	Class-D
7	Restoration of rain damages on Shilabag to Kwanti road in Km. 1/000 to 1/000 (SH:- C/O B/Wall between RD 0/780 to 0/807) (Under PDNA) (Excluding GST).	410550/-	8200/-	350/-	30 days	Class-D
8	Restoration of rain damages on Shilabag to Kwanti road in Km. 1/000 to 1/000 (SH:- C/O B/Wall between RD 0/615 to 0/642) (Under PDNA) (Excluding GST).	409110/-	8200/-	350/-	30 days	Class-D
9	Repair & Maintenance of Rest House Building at Fagu Shimla (SH:- Providing and Fixing ACP Sheets for penelling of wall in First Floor Room No.1 outer portion)(Excluding GST).	80678/-	1700/-	350/-	30 days	Class-D
10	R/R damages on Shimla to Mandi road km. 6/00 to 22/00 (SH:- C/O B/wall at RD. 15/095 to 15/120)(under PDNA)(Excluding GST).	373130/-	7500/-	350/-	30 days	Class-D
11	Restoation of rain Damages on Shoghi mehli junga sadhupul road km. 12/375 to 48/925 (SH:- C/O R/wall between RD. 24/500 to 24/515)(Under PDNA)	343210/-	6900/-	350/-	30 days	Class-D
12	Repair & Maintenance of Rest House Building at Fagu Shimla (SH:- Providing and fixing ACP sheets for peneling of wall in first Floor Dining Hall with Galary prtition)(Excluding GST).	72033/-	1500/-	350/-	30 days	Class-D
13	Repair & Maintenance of Rest House Building at Fagu Shimla (SH:- Providing and fixing ACP Sheets for peneling of wall in Ground floor Two Rooms sets)(Excluding GST).	69153/-	1400/-	350/-	30 days	Class-D
14	Repair & Maintenance of Rest Houe Building at Fagu Shimla (SH:- Providing and fixing ACP sheets for peneling of wall in Ground floor Lobby portion)(Excluding GST).	80101/-	1600/-	350/-	30 days	Class-D

It is certified that the above works are required to be carried out immediately being emergent nature of work in public interest. The tender documents shall be issued only to those contractor/Firm who fulfill the following documents with the application.

- The valid enlistment/Registration of contractor in Appropriate Class.
- Permanent account No. (PAN NO).
- G.S.T No.
- Earnest Money in the shape of National saving certificate/time deposit account in the any of the post office in HP. F.D.R from any Nationalized Bank duly pleaded in favour of the Executive Engineer Division Kasumpti HPPWD Shimla.
- The earnest & cost of tender form for the above works should be submitted with the application for the purchase of the tender form. The application received without earnest money & cost of tender form shall summarily be rejected.
- The officer of the tender shall remain valid up to 75 days after the opening of tender.
- Ambiguous/telephonic /conditional tenders or tender by fax/E mail shall not be considered and will be summarily be rejected.
- Executive Engineer reserve the right to reject or cancel any or all tenders without assigning any reasons.
- If the date given above happens to be holiday the same shall be processed on next working day.
- The Contractor/firms must quote their rates in words as well as in figures failing which EXN reserve the right to accept/reject any or all tenders.
- The tender forms shall not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed the previous awarded works within the stipulated period of completion.
- One contractor shall not have more than two major works in hand at a time.
- Work should be completed by the contractor within stipulated period.

Executive Engineer,
Division Kasumpti.,
HPPWD Shimla-3.


No.PW-SD-I/CB-Tender/2026-2027-

16600-17

Dated :- 3/9/26

Copy forwarded to:-

1. Copy to the Deputy Commissioner Shimla Distt. Shimla.
2. Copy to the Executive Engineer Shimla Division No-III HPPWD Shimla.
3. Copy to the Sub Divisional Magistrate (U) Shimla.
4. Copy to the Sub Divisional Magistrate (R) Shimla.
5. Copy to Municipal committee Shimla Distt. Shimla.
6. Copy to Block Development officer Mashobra Distt. Shimla.
7. All the Assistant Engineers under this Division, HPPWD Shimla-3.
8. Superintendent / HDM / DAO.
9. Notice Board.


Executive Engineer,
Division Kasumpti,
HPPWD Shimla.

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 83,644.00		
NAME OF WORK:- A/R & M/O on Various roads AIMSS section under Sub Division No.1 (SH:-					Earnest Money :-1,700.00		
Supplying and Stacking Pot seal bags cold mix in Various Rds).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	94.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	83644.02
						Total	83644.02
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-505 T/S No-16209-10 Rs. 101661/- Dt 29/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti, Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 83,644.00		
NAME OF WORK:- A/R & M/O on Various roads Bharari section under Sub Division No.1					Earnest Money :-1,700.00		
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds). (Without GST)					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	94.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	83644.00
						Total	83644.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-504 T/S No-16202-203 Rs.10/66/- Dt 29/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 80,085.00		
NAME OF WORK:- A/R & M/O on Various roads Lakkar Bazar section under Sub Division No.1 (SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds).					Earnest Money :-1,600.00		
					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	90.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	80085.00
						Total	80085.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-503 1/3 No-16207-08 Rs. 97335/- Dt 29/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 82,754.00		
NAME OF WORK:- A/R & M/O on Various roads Mehli section under Sub Division No.1 (SH:-					Earnest Money :-1,700.00		
Supplying and Stacking Pot seal bags cold mix in Various Rds).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	93.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	82754.19
						Total	82754.19
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-501 T/S No-16204-05 RA-100579/- Dt 29/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 82,754.00		
NAME OF WORK:- A/R & M/O on Various roads Dhalli section under Sub Division No.1 (SH:-					Earnest Money :-1,700.00		
Supplying and Stacking Pot seal bags cold mix in Various Rds).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	93.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only.	Per Each	82754.00
						Total	82754.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

SRNo-499 T/SNo-16211-12 Rs.82,754/- Dt 29/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-					Estimated Cost:- 81,864.00		
NAME OF WORK:- A/R & M/O on Various roads Fagu section under Mashobra Sub Division					Earnest Money :-1,700.00		
(SH:- Supplying and Stacking Pot seal bags cold mix in Various Rds).					Time:- One Month		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Supplying and laying pot seal beg of 25 kgs cold mix The rate including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge	92.00	Nos	889.83	Rupees Eight Hundred Eighty Nine and Paise Eighty Three Only	Per Each	81864.00
						Total	81864.00
	Quated rates Percentage in figures						
	Quoted rates Percentage in words						

SR No-495T/S No-16221-22 Rs. 81,864/- dt 29/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
HPPWD Division
Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.	Estimated Cost:- 410550.00
Name of Work :-Restoration of Rain Damages on Shilabag to Kwanti road in Km. 1/000 to 1/000. (SH:-	Earnest Money :- 8200.00
Construction of B/Wall between Rd 0/780 to 0/807) (Under PDNA).(Excluding GST).	Time:- Two Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils. including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site.. according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.as per direction of Engineer-In-Charge .	62.00	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	17076.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification. including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge .	13.00	Cum	338.98	Rupees Three Hundred Thirty Eight and Paise Ninety Eight Only	Per Cubic Metre	4407.00

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge . (a) Cement Mortar 1:6:12 (One cement: six sand: Twelve graded stone agg.40mm nominal size).	13.50	Cum	2881.36	Rupees Two Thousand Eight Hundred Eighty One and Paise Thirty Six Only	Per Cubic Metre	38898.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203.But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge (a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate40 mm(forty milimetre) nominal size).	93.00	Cum	3728.81	Rupees Three Thousand Seven Hundred Twenty Eight and Paise Eighty One Only	Per Cubic Metre	346779.00
5	Providing weep holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge .	20.00	Rmt	169.49	Rupees One Hundred Sixty Nine and Paise Forty Nine Only	Per Runing metre	3390.00
					Total		410550.00

SR No- 477 T/S NO 15555-56 Rs. 4,98,982/- Dt 21/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY

Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.	Estimated Cost:- 409110.00
Name of Work :-Restoration of Rain Damages on Shilabag to Kwanti road in Km. 1/000 to 1/000. (SH:-	Earnest Money :- 8200.00
Construction of B/Wall between Rd 0/615 to 0/642) (Under PDNA).(Excluding GST).	Time:- Two Month.

Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the H.P.P.W.D. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.as per direction of Engineer-In-Charge .	62.00	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	17076.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-in-Charge .	13.00	Cum	338.98	Rupees Three Hundred Thirty Eight and Paise Ninety Eight Only	Per Cubic Metre	4407.00

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge . (a) Cement Mortar 1:6:12 (One cement: six sand: Twelve graded stone agg.40mm nominal size).	13.00	Cum	2881.36	Rupees Two Thousand Eight Hundred Eighty One and Paise Thirty Six Only	Per Cubic Metre	37458.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203.But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge (a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate40 mm(forty milimetre) nominal size).	93.00	Cum	3728.81	Rupees Three Thousand Seven Hundred Twenty Eight and Paise Eighty One Only	Per Cubic Metre	346779.00
5	Providing weep holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 .But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge .	20.00	Rmt	169.49	Rupees One Hundred Sixty Nine and Paise Forty Nine Only	Per Runing metre	3390.00
					Total		409110.00

SR NO-478 T/S NO-15557-58 MS-497232/- Dt 21/8/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer,
HPPWD Division,
Kasumpti Shimla


SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 80678.00		
Name of Work :-Repair & Maintenance of Rest House Building at Fagu Shimla (SH:- Providing & Fixing ACP Sheets for Penelling of wall in First Floor Room No.1 Outer portion).(Excluding GST).					Earnest Money :- 1700.00		
					Time:- Two Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 9mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.as per direction of Engineer-In-Charge .	28.00	Sqm	847.46	Rupees Eight Hundred Forty Seven and Paise Forty Five Only	Per Square Meter	23729.00
2	Providing and fixing ACP sheet (4mm thick) in aluminium door,wiondow, ventilator shutters and partition with PVC/Neoprehs gasket etc complete But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge .	28.00	Sqm	2033.90	Rupees Two Thousand Thirty Three and Paise Eighty Nine Only	Per Square Meter	56949.00
				Total			80678.00

SR NO 518 T/S NO -16428-29 Rs. 98056 /- Dt 3/9/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

Executive Engineer
HPPWD Division,
Kasumpti Shimla



SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER SHIMLA DIVISION No-I, H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 3,73,130.00		
Name of Work :- R/R damages on Shimla to Mandi Road Km. 6/00 to 22/00. (SH:- C/O B/Wall at RD 15/095 to 15/120.) (Under PDNA) (Excluding GST)					Earnest Money :- 7,500.00		
					Time:- One Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount (Excluding GST)
				In figures	In words		
1	Cutting in Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (ten Square Metre) on plan) including getting out and disposal of excavated earth all lead and lift as directed by Engineer-in-charge and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required) Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects including all incidental charges. (i)All kinds of soil. (Excluding GST)	62.75	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	17283.00
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 including carriage of materials in all leads and lifts as per directions of the Engineer-in-Charge. (a) Cement Mortar 1:4:8 (one cement : four sand: Eight graded stone aggregate 40mm(Forty milimetre) nominal size). (Excluding GST)	94.75	Cum	3728.81	Rupees Three Thousand Seven Hundred Twenty Eight and Paise Eighty One Only	Per Cubic Metre	353305.00

3	Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and MORD technical specification clauses 614, 709, 1204.3.7 including carriage of materials in all leads and lifts as per the directions of the Engineer-in-Charge.(Excluding GST)	15.00	Rmt	169.49	Rupees One Hundred Sixty Nine and Paise Forty Nine Only	Per Running Metre	2542.00
						Total	373130.00
	Quoted rates Percentage in figures						
	Quoted rates Percentage in words						
						G.Total	

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

DNIT approved for Rs. 3,73,130 /- Only vide DNIT Register Sr.No. 1191 the financial year 2026-27. T/S NO.....DATE.....AMT 4,53,502 /- only
15782-83 25/8/26

Executive Engineer,
B& R Division Kasumpti
HPPWD Winter Field Shimla -3

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 343210.00		
Name of Work :- Restoration of rain Damages on Shoghi Mehli Junga Sadhupul road Km 12/375 to 48/925					Earnest Money :- 6900.00		
(SH:- Construction of R/Wall between Rd 24/500 to 24/515) Under PDNA.					Time:- Two Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Cutting and disposal of earth work in by mechanical in all heights and depths in all kinds of soils, including saturated soils comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock (where blasting is prohibited) and their intermediate classification of soils including, dewatering wherever required. setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site., according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site as per satisfaction of Engineer- in -charge through all modes of transportation including head load ,animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical means and labour (if required). All the surplus excavated earth to be dumped at dumping site(dumping sites will be arranged by the contractor on his own cost). Any loss to the public and private propriety, human being, machinery during the course of execution and disposal of serviceable and unserviceable materials shall be the absolute responsibility of the contractor and shall have to be duly compensated by him in all respects But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.	25.65	Cum	275.42	Rupees Two Hundred Seventy Five and Paise Forty Two Only	Per Cubic Metre	7065.00
2	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material. Hard Roack blasting prohibited and their intermediate classification of soils including, dewatering wherever required, setting of to the required lines, levels as shown on the drawing and directed by the Engineer -in-charge at site, according to the HP.PWD. specification of 1990 (one thousand nine hundred ninety) volume-I (one) and sorting out useful and unuseful material and transportation of the unuseful material for disposing at dumping site (To be arranged by the contractor) including payment of prescribed charges of dumping to the owner of dumping site as per satisfaction of Engineer-in-Charge through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and with all kinds of labour, machineries, tools equipments and safety measures and incidentals necessary to complete the work by mechanical But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.	20.25	Cum	338.98	Rupees Three Hundred Thirty Eight and Paise Ninety Eight Only	Per Cubic Metre	6864.00

3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge. (a) Cement Mortar 1:5:10 (One cement: five sand: Ten graded stone agg.40mm nominal size).	5.70	Cum	3220.34	Rupees Three Thousand Two Hundred Twenty and Paise Thirty Three Only	Per Cubic Metre	18356.00
4	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802,803,1202 and 1203 But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge..(a) Cement Mortar 1:4:8(One cement:Four sand:Eight graded stone aggregate 40 mm(Forty millimetre) nominal size).	76.73	Cum	3728.81	Rupees Three Thousand Seven Hundred Twenty Eight and Paise Eighty One Only	Per Cubic Metre	286112.00
5	Providing weep holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm(One hundred milimetre) dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614. 709, 1204.3.7 But Excluding GST. including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.	60.00	Rmt	169.49	Rupees One Hundred Sixty Nine and Paise Forty Nine Only	Per Runing metre	10169.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8 But Excluding GST. including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.(a) Granular material.	14.40	Cum	1016.95	Rupees One Thousand Sixteen and Paise Ninety Four Only	Per Cubic Metre	14644.00
					Total		343210.00

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.

DNIT approved, for Rs 343210/- Only) vide DNIT Register Sr.No.508.
the financial year 2025-26.. T/S NO.....DATE.....AMT 417137 /-
Only). 16362-63 1-9-26

Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 72033.00		
Name of Work :-Repair & Maintenance of Rest House Building at Fagu Shimla (SH:- Providing & Fixing ACP Sheets for Peneling of wall in First Floor Dinning Hall with Galary portion).(Excluding GST).					Earnest Money :- 1500.00		
					Time:- Two Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 9mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.as per direction of Engineer-In-Charge .	25.00	Sqm	847.46	Rupees Eight Hundred Forty Seven and Paise Forty Five Only	Per Square Meter	21186.00
2	Providing and fixing ACP sheet (4mm thick) in aluminium door,wiondow, ventilator shutters and partition with PVC/Neoprehs gasket etc complete But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge .	25.00	Sqm	2033.90	Rupees Two Thousand Thirty Three and Paise Eighty Nine Only	Per Square Meter	50847.00
					Total		72033.00

SR No-517 T/S No- 16431-32 Rs. 87549/- Dt 31/9/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


Executive Engineer,
HPPWD Division,
Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 69153.00		
Name of Work :-Repair & Maintenance of Rest House Building at Fagu Shimla (SH:- Providing & Fixing ACP Sheets for Peneling of wall in Ground Floor Two Rooms Sets).(Excluding GST).					Earnest Money :- 1400.00		
					Time:- Two Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 9mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.as per direction of Engineer-In-Charge .	24.00	Sqm	847.46	Rupees Eight Hundred Forty Seven and Paise Forty Five Only	Per Square Meter	20339.00
2	Providing and fixing ACP sheet (4mm thick) in aluminium door,wiondow, ventilator shutters and partition with PVC/Neoprehs gasket etc complete But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge .	24.00	Sqm	2033.90	Rupees Two Thousand Thirty Three and Paise Eighty Nine Only	Per Square Meter	48814.00
				Total			69153.00

SR No- 516 T/S No- 16433-34 Rs 84049/- Dt 3/9/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.



 Executive Engineer,
 HPPWD Division,
 Kasumpti Shimla

SCHEDULE OF QUANTITY							
Tender Inviting Authority : EXECUTIVE ENGINEER KASUMPTI DIVISION , H.P.P.W.D., SHIMLA-3.					Estimated Cost:- 80101.00		
Name of Work :-Repair & Maintenance of Rest House Building at Fagu Shimla (SH:- Providing & Fixing ACP Sheets for Peneling of wall in Ground Floor Lobby portion).(Excluding GST).					Earnest Money :- 1600.00		
					Time:- Two Month.		
Sr. No	Description of Work / Item (S)	No.of Qty.		Estimated Rate		Unit	Amount
				In figures	In words		
1	Providing and fixing 9mm thick water proof commercial board in shelves/shutters box for cup board with butt joints & fixing with nails & screws etc complete) But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.as per direction of Engineer-In-Charge .	27.80	Sqm	847.46	Rupees Eight Hundred Forty Seven and Paise Forty Five Only	Per Square Meter	23559.00
2	Providing and fixing ACP sheet (4mm thick) in aluminium door,wiondow, ventilator shutters and partition with PVC/Neoprehs gasket etc complete But Excluding GST, including hauling of materials in all leads and lifts as per entire satisfaction and direction of Engineer-in- Charge.as per direction of Engineer-In-Charge .	27.80	Sqm	2033.90	Rupees Two Thousand Thirty Three and Paise Eighty Nine Only	Per Square Meter	56542.00
					Total		80101.00

SRNO- 515 T/SNG-16435-36 RS. 97355/- Dt 3/9/26

CONDITION:-

1. Rates should be quoted for all heights including all leads and lifts.
2. Sample of all the material to be used on work shall be got approved from the Engineer-in-Charge in advance before actual use on work and any or all of the material which are available as per Indian standard in the market should confirm to bureau of indian standars.


 Executive Engineer,
 HPPWD Division,
 Kasumpti Shimla