

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2026:- **5327-34**
To,

Dated:- **01-09-2026**



The Chief Engineer (KZ),
HPPWD Dharamshala (HP)
e-mail:- hp-kan1@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec.(PW) to the Govt. of HP letter No. PBW (B) A(3)1/2020 dated Shimla-2 the 16th July,2021 and further in compliance of the Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICT Wing/website dated 22/5/2026 as the work mentioned in the tender notice are urgent in nature and in public interest. You are requested to kindly get it published on departmental website.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur. 

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur. 

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 09.09.2026 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 10.09.2026 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 11.09.2026 upto 11.00AM |
| 4. Date and time of opening of tenders: | 11.09.2026 at 11.30 AM |


The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for **75 days** from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contract or
1.	Restoration of Rain Damage on MTN to Larhoon khas road km 0/0 to 2/700 (SH:- Providing and laying Grading-III and cement concrete pavement at R.D. 1/270 to 1/356) Under PDNA-2023	Rs.245004/-	Rs.4900/-	One month	350/-	Class D&C
2.	Restoration of Rain Damage on Baroh to Larth road km.0/0 to 2/0 (SH:- Construction of 1.00mtr. span RCC slab culvert at R.D.1/100) Under PDNA-2023	Rs.149332/-	Rs.3000/-	One month	350/-	Class D&C
3.	Restoration of Rain Damage on Talara to Kutlahr road km 0/0 to 2/750 (SH:- Providing and laying Grading-III and cement concrete pavement at R.D. 0/830 to 0/882.35) Under PDNA-2023	Rs.149188/-	Rs.3000/-	One month	350/-	Class D&C

CERTIFIED THAT TENDER OF ABOVE WORKS ARE BEING CALLED OF EMERGENT NATURE IN EXIGENCY OF PUBLIC INTEREST.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damage on Talara to Kutlahr road km 0/0 to 2/750 (SH:- Providing and laying Grading-III and cement concrete pavement at R.D. 0/830 to 0/882.35) Under PDNA-2023						Estimated cost:- Rs.149188/- only	
						Earnest Money : Rs.3000/- only	
						Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and brooming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	13.80	1290.10	Rupees One Thousand Two Hundred Ninety And Paise Ten Only	Per cubic meter	17803.00	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	28.50	4610.00	Rupees Four Thousand Six Hundred Ten Only	Per cubic meter	131385.00	
					Total:-	149188.00	
	Amount quoted by the contractor in % Above/Below						

Note:- 18% GST shall be paid separately

[Signature]
 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.D.)

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY										Estimated cost:- Rs.245004/- only	
Name of work:- Restoration of Rain Damage on MTN to Larhoon khas road km 0/0 to 2/700 (SH:- Providing and laying Grading-III and cement concrete pavement at R.D. 1/270 to 1/356) Under PDNA-2023										Earnest Money : Rs.4900/- only	
										Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount					
			In words	In figures							
1	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and broomming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading –III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	24.18	1290.00	Rupees One Thousand Two Hundred Ninety Only	Per cubic meter	31192.00					
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	46.38	4610.00	Rupees Four Thousand Six Hundred Ten Only	Per cubic meter	213812.00					
					Total:-	245004.00					
	Amount quoted by the contractor in % Above/Below										

Note:- 18% GST shall be paid separately


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damage on Baroh to Lath road km.0/0 to 2/0 (SH:- Construction of 1.00mtr. span RCC slab culvert at R.D.1/100) Under PDNA-2023						Estimated cost:- Rs.149332/- only	
						Earnest Money : Rs.3000/- only	
						Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	6.50	339.40	Rupees Three Hundred Thirty Nine And Paise Forty Only	Per cubic meter	2206.00	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in sub-structure for all type of structure complete of plain cement concrete grade M-15 (M fifteen) nominal mix 1:2.5:5 (One cement into two point five sand isto five graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in floor as per drawings and M.O.R.D. technical specification Clause 802,804, 805, 806, 807,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax. sale tax and any other taxes imposed by the Government but excluding GST.	18.20	4550.20	Rupees Four Thousand Five Hundred Fifty And Paise Twenty Only	Per cubic meter	82814.00	

3	Providing and laying mechanically mixed and vibrated reinforced cement concrete in super structure as per drawing and M.O.R.D. technical specification clause 800, 1205.4 & 1205.5 RCC Grade M-25 (M- twenty five) designed mix with minimum cement contents of 400 (Four hundred) Kilogramme per cubic meter with 20mm (Twenty millimeter) nominal size grade crushed stone aggregate and curing complete including cost of form work, but excluding the cost of reinforcement for reinforced cement concrete work in Deck slab as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	4.10	6580.00	Rupees Six Thousand Five Hundred Eighty Only	Per cubic meter	26978.00
4	Supplying, fitting and placing HYSD bar reinforcement in super structure complete as per drawing and technical specification clause 1002, 1010 & 1202 including cutting, bending, binding and placing in position complete in all respect including cost of binding wire upto any floor level as per the direction of the Engineer-in-charge including carriage of materials. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	0.51	68500.00	Rupees Sixty Eight Thousand Five Hundred Only	Per Metric tonne	34935.00
5	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	8.00	270.50	Rupees Two Hundred Seventy And Paise Fifty Only	Each	2164.00
6	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	0.35	670.00	Rupees Six Hundred Seventy Only	Per cubic meter	235.00
					Total:-	149332.00

Amount quoted by the contractor in % Above/Below

Note:- 18% GST shall be paid separately

[Signature]
 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)