

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2026:-
To,

5501-8

Dated:- 11/9/2026


✓ The Chief Engineer (KZ),
HPPWD Dharamshala (HP)
e-mail:- hp-kan1@nic.in

Subject: **Publication of Tender Notice.**

Dear Sir,


Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec.(PW) to the Govt. of HP letter No. PBW (B) A(3)1/2020 dated Shimla-2 the 16th July,2021 and further in compliance of the Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICT Wing/website dated 22/5/2026 as the work mentioned in the tender notice are urgent in nature and in public interest. You are requested to kindly get it published on departmental website on or before 14.09.2026.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NOTICE INVITING TENDER

Sealed item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 19.09.2026 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 21.09.2026 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 22.09.2026 upto 11.00AM |
| 4. Date and time of opening of tenders: | 22.09.2026 at 11.30 AM |


The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contract or
1.	Restoration of Rain Damages on Garan to Thathar road km. 0/0 to 1/225 (SH:- Providing and laying Cement Concrete pavement at various RD 0/540 to 0/770) Under PDNA-2023	Rs.407702/-	Rs.8200/-	One month	350/-	Class D&C
2.	Restoration of Rain Damages on Garan to Thathar road km. 0/0 to 1/225 (SH:- Providing and laying GSB and Grading-III at RD 0/540 to 0/770) Under PDNA-2023	Rs.161732/-	Rs.3300/-	One month	350/-	Class D&C
3.	Restoration of rain damages on Kandor Bhungtial road km.0/000 to 2/600 (SH:- Providing and laying cement concrete pavement at R.D. 1/600 to 1/714) Under PDNA-2023	Rs.259900/-	Rs.5200/-	Two months	350/-	Class D&C
4	Restoration of rain damages to Dehri Sakoh Padehar road km.0/000 to 2/500 (SH:- Providing and laying GSB on soulder portion at R.D. 0/020 to 0/470 Both side, 1/000 to 1/800 Both side and 2/000 to 2/500 Both side) Under PDNA-2023	Rs.395000/-	Rs.7900/-	Two months	350/-	Class D&C

Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender form shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

SCHEDULE OF QUANTITY						
Name of work:- Restoration of Rain Damages on Garan to Thathar road km. 0/0 to 1/225 (SH):- Providing and laying Cement Concrete pavement at various RD 0/540 to 0/770) Under PDNA-2023			Estimated cost:- Rs.407702/- only			
			Earnest Money : Rs.8200/- only			
			Time limit:- One month			
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	91.62	4449.92	Rupees Four Thousand Four Hundred Forty Nine And Paise Ninety Two Only	Per cubic meter	407702.00
					Total:-	407702.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						


 Executive Engineer
 Fatehpur Division, HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Garan to Thathar road km. 0/0 to 1/225 (SH:- Providing and laying GSB and Grading-III at RD 0/540 to 0/770) Under PDNA-2023					Estimated cost:- Rs.161732/- only		Earnest Money : Rs.3300/- only	
Sr. No	Description of items	Quantity	Rate		Unit	Amount	Time limit:- One month	
			In words	In figures				
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using naturally occurring gravel as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	120.75	739.30	Rupees Seven Hundred Thirty Nine And Paise Thirty Only	Per cubic meter	89270.00		
2	Providing, laying, spreading and compacting of stone aggregate of specific sizes to water bound Macadam specification including spreading in uniform thickness hand packing, rolling with three wheel 80-100(eighty-hundred) K.N. static Road roller in stages to proper grade and camber, applying and broomming, crushable screening at the rate of 0.22 cum (zero point two two cubic meters) per ten square meters, to fill up the interstices of coarse aggregate, watering and compacting to the required density grading -III, 53mm to 22.4mm (Fifty three millimeters to twenty two point four millimeters) size, 75mm (seventy five millimetre) compacted thickness as per M.O.R.D. technical specifications clause No. 405 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	60.38	1200.10	Rupees One Thousand Two Hundred And Paise Ten Only	Per cubic meter	72462.00		
					Total:-	161732.00		
	Note:- 18% GST shall be paid separately							
	Amount quoted by the contractor in % Above/Below							


 Executive Engineer
 Fatenpur Division HPPWD
 Fatenpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on Kandor Bhungtial road km.0/000 to 2/600 (SH:- Providing and laying cement concrete pavement at R.D. 1/600 to 1/714) Under PDNA-2023						Estimated cost:- Rs.259900/- only	
						Earnest Money : Rs.5200/- only	
						Time limit:- Two months	
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer –in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	27.40	3059.00	Rupees Three Thousand Fifty Nine Only	Per cubic meter	83817.00	
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	39.40	4469.10	Rupees Four Thousand Four Hundred Sixty Nine And Paise Ten Only	Per cubic meter	176083.00	
					Total:-	259900.00	
	Note:- 18% GST shall be paid separately						
	Amount quoted by the contractor in % Above/Below						


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages to Dehri Sakoh Padehar road km.0/000 to 2/500 (SH:- Providing and laying GSB on soulder portion at R.D. 0/020 to 0/470 Both side, 1/000 to 1/800 Both side and 2/000 to 2/500 Both side) Under PDNA-2023

Estimated cost Rs.395000/- only
Earnest Money Rs.7900/- only

Time limit :- Two months

Sl. No.	Description of work	Quantity	Unit	RATE In		Amount
				Figures	Words	
1	Construction of granular sub-base by providing well graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site with in all leads and lift spreading in uniform layers with motor grader on prepared surface and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401 for Grading-I material, as per the entire satisfaction and direction of Engineer-in-charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	534.26	Per cubic metre	739.34	Rupees Seven Hundred Thirty Nine And Paise Thirty Four Only	395000.00
					Total:-	395000.00
	Note:- 18% GST shall be paid separately					
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

Signature of Tenderer with seal