

H.P.P.W.D NOTICE INVITING TENDER

Sealed percentage rate tender on the form 6&8 are invited by the Executive Engineer, Sarkaghat Division, HPPWD Sarkaghat on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

TENDER SCHEDULE:

- | | | |
|---|---|--------------------------|
| 1 | Date and time of receipt of application for the tender form : | 12.10.2026 upto 4.00 PM |
| 2 | Date and time of issue of tender form : | 13.10.2026 upto 4.00 PM |
| 3 | Date and time of receipt of tenders: | 14.10.2026 upto 11.00 AM |
| 4 | Date and time of opening of tenders: | 14.10.2026 upto 12.30 AM |

The tender form will be issued against cash payment (non refundable), the earnest money in the shape of NSC/FDR/Deposit at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Sarkaghat Division, HPPWD Sarkaghat must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.

Sr.No	Name of work	Estimated cost (In Ra.)	Earnest Money (In Rs.)	Time
1	Restoration of rain damages on Dabrog Yoh Bakarta Gadhyani Kalahu road KM 0/00 to 1/00 (SH: C/o R/Wall in PCC 1:5:10 at RD 3/115 to 3/123 and 4/880 to 4/892)	422322/-	8450/-	One Month
2	Restoration of rain damages on Megal Hawani Bandropa Chahari road KM 0/00 to 5/00 (SH: C/o R/Wall in PCC 1:5:10 at RD 1/135 to 1/145) Under PDNA	388086/-	7800/-	One Month
3	Restoration of rain damages on Rissa Beri road KM 0/00 to 9/00 (SH: C/o R/Wall in PCC 1:5:10 at RD 0/825 to 0/840) Under PDNA	242693/-	4900/-	One Month
4	Restoration of rain damages on Tikkari Mandoli Khudla via Gehra Bhadrol road KM 0/00 to 2/500 (SH: C/o R/Wall in PCC 1:5:10 at RD 0/160 to 0/182) Under PDNA	404425/-	8100/-	One Month
5	Restoration of rain damages on Kalthari Tikkari Ropa Thathar road KM 0/00 to 7/300 (SH: C/o R/Wall in PCC 1:5:10 at RD 4/990 to 5/008) Under PDNA	410754/-	8220/-	One Month
6	Restoration of damages on Una Aaghar Bhota Mandi road KM 93/00 to 108/800 (SH: C/o R/Wall in PCC 1:5:10 at RD 99/300 to 99/308, 103/100 to 103/113 and 107/230 to 107/240) Under PDNA	419210/-	8400/-	One Month
7	Restoration of rain damages on various roads under Baldwara Sub Division HP PWD Baldwara (SH: Removal of slips on various RDs under Upper Bhambla and Khalyana Section) Under PDNA	403402/-	8100/-	One Month
8	Restoration of damages on Patrighat Jawali Gehra road KM 0/00 to 6/00 (SH: C/o 900 mm dia hume pipe culvert with wing wall at RD 4/015) Under PDNA	188148/-	3400/-	One Month
9	Restoration of rain damages on Trifalghat Badoun Bhatera Than Chowki road KM 0/00 to 10/00 (SH: Construction of wire crate R/Wall at KM 9/605 to 9/615) Under PDNA	374925/-	7500/-	One Month
10	Restoration of rain damages on Bakarta Gadhyani Rakhoh Dodar road KM 0/00 to 5/485 (SH: Providing and laying 80 mm thick interlocking paver block at KM 0/545 to 0/630) Under PDNA	499710/-	10000/-	One Month
11	Restoration of rain damages on Bakarta Gadhyani Rakhoh Dodar road KM 0/00 to 5/485 (SH: Providing and laying 80 mm thick interlocking paver block at KM 0/060 to 0/095) Under PDNA	212476/-	4250/-	One Month
12	Restoration of rain damages on Bakarta Gadhyani Rakhoh Dodar road KM 0/00 to 5/485 (SH: Providing and laying 80 mm thick interlocking paver block at KM 0/165 to 0/235) Under PDNA	413540/-	8300/-	One Month
13	Restoration of rain damages on Dabrog Yoh Bakarta Kalahu road KM 0/00 to 11/00 (SH: Providing and laying 80 mm thick interlocking paver block at KM 3/965 to 4/035) Under PDNA	413540/-	8300/-	One Month

Executive Engineer,
Sarkaghat Division,
HP.PWD, Sarkaghat

No.PW-SKT-CB-Tender/2026-27 :-

Copy forwarded to the following for information and necessary action:-

1. The Superintending Engineer, Dharampur Circle, HP PWD for information please.
2. Notice Board.

Executive Engineer,
Sarkaghat Division,
HP.PWD, Sarkaghat,

HIMACHAL PRADESH

PUBLIC WORKS DEPARTMENT

No. PW-SKT-CB-Tender/2026-27-

13920-22

Dated:- 28.9.2026

To

The Chief Engineer,
Hamirpur Zone,
HP PWD Hamirpur.

Subject:

Publication of Tender.

Sir,

Enclosed please find herewith the Tender Notice of works as given in the notice inviting tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of HP letter No. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B)A(3) 8/2025-300858 dated 13th Nov, 2025 as the works mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice inviting Tender.

Executive Engineer,
Sarkaghat Division,
HP.PWD. Sarkaghat.

Copy along with N.I.T. to the Superintending Engineer, Dharampur Circle, HPPWD Dharampur for information please.

Executive Engineer,
Sarkaghat Division,
HP.PWD. Sarkaghat.

Draft Schedule of Quantity

Name of work:- Restoration of rain damages on Dabrog Yoh Bakarta Gadhyani Kalahu road km 0/0 to 1/00
(SH:- C/O R/wall in PCQ: 5:10 at RD 3/115 to 3/123 and 4/880 to 4/892)

Name of work:- Restoration of rain damages on Dabrog Yoh Bakarta Gadhyani Kalahu road km 0/0 to 1/00						
(SH:- C/O R/wall in PCCQ.5:10 at RD 3/115 to 3/123 and 4/880 to 4/892)						
Sr. No.		Description of item		Quantity		Estimated Cost:-
						Rs.422322/-
						Earnest money:- Rs.8450/-
				Time allowed:- One month		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m fifty metre) and lift upto 1.5 m (One point five metre), including all leads and lifts and as per the direction of Engineer- in-Charge.	33.40	200.00	Rupees two hundred and paise nil only	Per cubic metre	6680
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	82.94	4800.00	Rupees four thousand eight hundred and paise nil only	Per cubic metre	398112
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	30.00	250.00	Rupees two hundred fifty and paise nil only	Each	7500
4	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	11.80	850.00	Rupees eight hundred fifty and paise nil only	Per cubic metre	10030
					Total:-	422322

DNR NOTHS for the year 2026-27
approved for Rs 422322/-

Executive Engineer
B&R Division H.P.W.D
Sarnam

Draft Schedule of Quantity

Name of work:-Restoration of rain damages on Megal Hawani Bandropa Chahari road km 0/00 to 5/00 (Sh:- C/O
RMall in PCC1:5:10 at RD 1/135 to 1/145) Under PDNA

Estimated Cost:- Rs.388086/-
Earnest money:- Rs. 7800/-

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m fifty metre) and lift upto 1.5 m(One point five metre), including all leads and lifts and as per the direction of Engineer-in-Charge.	32.00	170.00	Rupees one hundred seventy and paise nil only	Per cubic metre	5440
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1.5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer-in-Charge.	79.50	4068.00	Rupees four thousand sixty eight and paise nil only	Per cubic metre	323406
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer-in-Charge.	20.00	210.00	Rupees two hundred ten and paise nil only	Each	4200
4	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	7.00	720.00	Rupees seven hundred twenty and paise nil only	Per cubic metre	5040
					Total	338086

DNIT NO 466 for the year 2026.27
approved for Rs 338086/- only

Executive Engineer
RRR Division Haryana
S. K. Sharma

Draft Schedule of Quantity

Name of work:- Resoration of rain damages on Rissa Beri road km 0/0 to 9/0 (SH:- C/O R/wall in PCC):5:10 at RD 0/825 to 0/840) UNDER PDNA

Name of work:- Resoration of rain damages on Rissa Beri road km 0/0 to 9/0(SH:- C/O R/wall in PCC):5:10 at RD 0/825 to 0/840) UNDER PDNA							Estimated Cost:- Rs.242693/-	
							Earnest money:- Rs.4900/-	
							Time allowed:- One month	
Sr. No.	Description of item	Quantity	Rate		Unit	Amount		
			In figure	In words				
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m fifty metre) and lift upto 1.5 m(One point five metre), including all leads and lifts and as per the direction of Engineer- in-Charge.	20.40	200.00	Rupees two hundred and paise nil only	Per cubic metre	4080		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	47.10	4800.00	Rupees four thousand eight hundred and paise nil only	Per cubic metre	226080		
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	18.00	250.00	Rupees two hundred fifty and paise nil only	Each	4500		
4	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and Carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	9.45	850.00	Rupees eight hundred fifty and paise nil only	Per cubic metre	8033		
					Total:-	242693		

DNIT NO 457 for the year 2026-27
approved for RS 242693/-

Executive Engineer
B&R Division HP-PWD
Sarkisat

Draft Schedule of Quantity

Name of work:-Resoration of rain damages on Tikhari Mandoli Khudla via Gehra Bhadrol Road km 0/00 to 2/500
(Sh:- C/O RWall in PCC1:5:10 at RD 0/160 to 0/182) UNDER PDNA

Estimated Cost:- Rs.404425/-
Earnest money:- Rs.8100/-

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m fifty metre) and lift upto 1.5 m(One point five metre), including all leads and lifts and as per the direction of Engineer- in-Charge.	40.04	170.00	Rupees one hundred seventy and paise nil only	Per cubic metre	6807
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	91.25	4068.00	Rupees four thousand sixty eight and paise nil only	Per cubic metre	371205
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204,3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	33.00	210.00	Rupees two hundred ten and paise nil only	Each	6930
4	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	27.06	720.00	Rupees seven hundred twenty and paise nil only	Per cubic metre	19483
					Total:-	404425

DNIT NO 473 for the year 2026-27
Approved for RS 404425/- only

Executive Engineer
B&R Division Hyderabad
Sardar


Draft Schedule of Quantity

Name of work:- Resoration of rain damages on Kathhari Tikkari Ropa Thathar Batail Road km 0/00 to 7/300 (Sh:-
C/O R/Wall in PCC1:5:10 at RD 4/990 to 5/008) UNDER PDNA

Estimated Cost:- Rs.410754/-
Earnest money:- Rs.8220/-

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m fifty metre) and lift upto 1.5 m (One point five metre), including all leads and lifts and as per the direction of Engineer- in-Charge.	51.30	170.00	Rupees one hundred seventy and paise nil only	Per cubic metre	8721
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	95.30	4068.00	Rupees four thousand sixty eight and paise nil only	Per cubic metre	387680
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	27.00	210.00	Rupees two hundred ten and paise nil only	Each	5670
4	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	12.06	720.00	Rupees seven hundred twenty and paise nil only	Per cubic metre	8683
					Total:-	410754

DNIT NOUHQ for the year 2026-27
approved for RS 410754/- only

Executive Engineer
B&P Division HPPWD
Sarnar


Draft Schedule of Quantity

Name of work:- Restoration of damages on Una Aaghar Bhotia Mandi Road km 93/000 to 108/800 (Sh:- C/O R/Wall in PCC 1:5:10 at RD 99/300 to 99/308, 103/100 to 103/113, and 7/230 to 107/240) UNDER PDNA

Name of work:-Restoration of carriages on Una Aaghar Bnora Mahdi Road km 93/000 to 108/800 (Sh:- C/O RM/wall in PCC:1:5:10 at RD 99/300 to 99/308, 103/100 to 103/113, and 7/230 to 107/240) UNDER PDNA		Estimated Cost:-		Rs.419210/-		
		Earnest money:-		Rs.8400/-		
		Time allowed:-		One month		
Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five metre) in width as well as 10 sqm (Ten square metre) on plan) including getting out and disposal of excavated earth lead upto 50 m fifty metre) and lift upto 1.5 m(One point five metre), including all leads and lifts and as per the direction of Engineer- in-Charge.	70.47	170.00	Rupees one hundred seventy and paise nil only	Per cubic metre	11980
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in-Charge.	97.77	4068.00	Rupees four thousand sixty eight and paise nil only	Per cubic metre	397728
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-Charge.	45.00	210.00	Rupees two hundred tenand paise nil only	Each	9450
					Total	419158

DRAFT NOT FOR THE YEAR 2026-27
approved for Rs 419158/- only

~~Executive Engineer~~
~~Public Division HPPWD~~
Sarnam Singh

Draft Schedule of Quantity

Name of Work:- Restoration Rain Damages on various Roads under Baldwara sub Division HPPWD Baldwara
(SH: Removal of slips on various RD's under Upper Bhambla and Khalyana Section) **UNDER PDNA**

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Removal of land slides / slip clearance removal of land slide in hilly area in ordinary rock/Hard rock not requiring blasting by mechanical means including rock breaker, including cutting and trimming of slops and disposal of cut material within a left up to 1.5 metre and upto 1000 metre as per technical specification 302.3.5 and 1611 and entire satisfaction of the Engineer-in-charge.	2881.44	140.00	Rupees one hundred forty and paise nil only	Per cubic metre	403402.00
Total:-						403402

Estimated cost :- Rs. 403402/-
Earnest money:- Rs. 8100
Time allowed:- one month

*DRAFT NOT FOR THE YEAR 2026-27
approved for Rs 403402/- only*

*Executive Engineer
B&R Division HPPWD
Baldwara*

Draft Schdule of quantity

Name of Work :- Restoration of damages on Patrigat ,Jowali, Gehra road km 0/0 to 6/00 (Sh:-
Construction of 900 mm dia Hume pipe culvert with wing wall at RD 4/015) UNDER PDNA

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Time Limit	One month Amount
			In figure	In words			
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm (Thirty centimetre) in depth, 1.5 m (One point five five) metre in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge All kinds of soil including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	88.87	170.00	Rupees one hundred seventy and paise nil only	Per cubic metre		15108
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 One Cement : four coarse sand) : eight graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	3.69	4407.00	Rupees four thousand four hundred seven and paise nil only	Per Cubic Metre		16262
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:3:6 One Cement : three coarse sand : six graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	10.49	4746.00	Rupees four thousand seven hundred forty six and paise nil only	Per Cubic Metre		49786
4	Providing and laying reinforced concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement: Two approved sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, 900 mm (Nine hundred millimetres) dia including carriage of materials within all leads, lifts & other incidental complete as per direction and entire satisfaction of the Engineer-in-Charge	7.00	3306.00	Rupees three thousand three hundred six and paise nil only	Per Running Metre		23142
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :1:5:10 One Cement : five coarse sand : 10 graded stone aggregate 40 mm(Forty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	14.15	4068.00	Rupees four thousand sixty eight and paise nil only	Per Cubic Metre		57562
6	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 100mm (One hundred) dia PVC pipe extending through the full width of the structure with slope of 1 vertical : 20 horizontal towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in- Charge.	12.00	200.00	Rupees two hundred and paise nil only	Each		2400
7	Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-charge.	5.40	720.00	Rupees seven hundred twenty and paise nil only	Per cubic metre		3888
					Total		168148

DNR NO 483 for the year 2026-27
approved for Rs 168148/- only

Executive Engineer
S&R Division HPT
Sattergahat

Draft Schedule of Quantity

10

Work:- Restoration of rain damages on Trifalghat Badoun Bhatera Thana Chowki road Km 0/0 to 10/0 (SH:Construction of
ate Riwall at Km 9/605 to 9/615) Under PDNA

Work:- Restoration of rain damages on Trifalghat Badoun Bhatera Thana Chowki road Km 0/0 to 10/0 (SH:Construction of R/wall at Km 9/605 to9/615) Under PDNA							Estimated Cost:- Rs 3,74,925/-	
							Earnest money:- Rs.7500/-	
							Time allowed:- One Month	
Description of item	Quantity	Rate		Unit	Amount			
		In figure	In words					
1 Earth work in excavation in all kind of classification of soil in foundation of structures upto all depth/ height as per drawing and technical specification Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom and back filling with approved material and disposal of all surplus excavated earth in specified site and direction of Engineer-in-charge complete.	30.00	200.00	Rupees two hundred and paise zero only	Per cubic metre	6000			
2 Providing and laying of boulder apron laid in wire crates made with 4 mm(four millimetre) dia GI wire conforming to IS:280 (IS : Two hundred eighty) and IS : 4826 (IS : four thousand eight hundred twenty six) in 100mm x100mm (one hundred millimetre into one hundred millimetre) mesh (waved diagonally) including 10% (ten per cent) extra for laps and joints laid with stone boulders weighting not less than 25 kg (Twenty five kilogramme) including carriage of materials with in all leads and lifts complete in all respects as per the direction Engineer -in- charge.	93.75	3500.00	Rupees three thousand five hundred and paise zero only	Per cubic metre	328125			
3 Back filling behind retaining walls, breast walls, abutments, wing walls and return walls complete as per drawing and technical specifications clause 1204.3.8 in all leads and lifts and carriage of materials by all modes of transportation and as per direction of Engineer-in-Charge.	48.00	850.00	Rupees eight hundred fifty and paise zero only	Per cubic metre	40800			
						374925		

Duit No. 447 for the year 2026-27
approved for amounting to Rs.374925
only

~~Executive Engineer~~
B & R Division H.P.P.W.D
Sarkagolli

DRAFT SCHEDULE OF QUANTITY

Name of work:- Resoration of rain damages on Bakarta Gadhyani Rakhoth Dodar road km 0/00 to 5/485(SH):-
Providing and Laying 80 mm thick interlocking paver block at km 0/545 to 0/630) UNDER PDNA

Estimated cost :- Rs. 499710/-
Earnest Money:- Rs. 10000.00
Time Limit one Month

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 One Cement : four coarse sand) : eight graded stone aggregate 20 mm(twenty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	28.05	4407.00	Rupees four thousand four hundred seven and paise nil only	Per cubic metre	123616.00
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm (Eighty millimetre) thick C.C. paver block of M-30 grade of NTC make with approved color design and pattern, including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	259.25	1350.00	Rupees one thousand three hundred fifty and paise nil only	Per Square metre	349988
3	Providing and laying cement concrete plain/ reinforced concrete 1:2:4 (One Cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimetre) nominal size :including all leads and lifts and as per the direction of Engineer- in- Charge.	4.53	5763.00	Rupees five thousand seven hundred sixty three and paise nil only	Per cubic metre	26106
					Total	499710

DUT NO 479 for the year 2026-27
approved for Rs 499710/-

Executive Engineer
RRR Division HPPWD
Sardar Singh

DRAFT SCHEDULE OF QUANTITY

Name of work:- Resoration of rain damages on Bakarta Gadhyani Rakhoon Dodar road km 0/00 to 5/485(SH):-

Estimated cost :- Rs. 212476/-

Providing and Laying 80 mm thick interlocking paver block at km 0/060 to 0/095) UNDER PDNA

Earnest Money:-

Rs. 4250/-

Time Limit

one Month

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 One Cement : four coarse sand) : eight graded stone aggregate 20 mm(twenty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	11.55	4407.00	Rupees four thousand four hundred seven and paise nil only	Per cubic metre	50901.00
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm (Eighty millimetre) thick C.C. paver block of M-30 grade of NTC make with approved color design and pattern, including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	106.75	1350.00	Rupees one thousand three hundred fifty and paise nil only	Per Square metre	144113
3	Providing and laying cement concrete plain/ reinforced concrete 1:2:4 (One Cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimetre) nominal size :including all leads and lifts and as per the direction of Engineer- in- Charge.	3.03	5763.00	Rupees five thousand seven hundred sixty three and paise nil only	Per cubic metre	17462
					Total	212476

DRAFT NOV 180 for the year 2026-27
approved for Rs 2124761=only

Executive Engineer
GAD Division HPT
Sardar

DRAFT SCHEDULE OF QUANTITY

Name of work:- Resoration of rain damages on Bakarta Gadhyani Rakhoh Dodar road km 0/00 to 5/485(SH:- Providing and Laying 80 mm thick interlocking paver block at km 0/165 to 0/235) UNDER PDNA

Estimated cost :- Rs. 413540/-
Earnest Money:- Rs. 8300/-

Time Limit one Month

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 One Cement : four coarse sand) : eight graded stone aggregate 20 mm(twenty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	23.10	4407.00	Rupees four thousand four hundred seven and paise nil only	Per Square metre	101802
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm (Eighty millimetre) thick C.C. paver block of M-30 grade of NTC make with approved color design and pattern,including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	213.50	1350.00	Rupees one thousand three hundred fifty and paise nil only	Per Square metre	288225
3	Providing and laying cement concrete plain/ reinforced concrete 1:2:4 (One Cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimetre) nominal size :including all leads and lifts and as per the direction of Engineer- in- Charge.	4.08	5763.00	Rupees five thousand seven hundred sixty three and paise nil only	Per cubic metre	23513
Total						413540

DNIT NO 481 For the year 2026.27
approved for Rs 413540/-only

Executive Engineer
Bakarta Division HPPWD
Santosh

DRAFT SCHEDULE OF QUANTITY

Name of work:- Resoration of rain damages on Dabrog YohBakarta Kalahu road km 0/00 to 11/00(SH:- Providing and Laying 80 mm thick interlocking paver block at km 3/965 to 4/035) UNDER PDNA

Estimated cost :- Rs. 413540/-
Earnest Money:- Rs.8300/-

Time Limit one Month

Sr. No.	Description of item	Quantity	Rate (excluding GST)		Unit	Amount
			In figure	In words		
1	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 One Cement : four coarse sand) : eight graded stone aggregate 20 mm(twenty millimetre) nominal size including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	23.10	4407.00	Rupees four thousand four hundred seven and paise nil only	Per Square metre	101802
2	Providing and laying factory made chamfered edge Cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding/laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. 80 mm (Eighty millimetre) thick C.C. paver block of M-30 grade of NTC make with approved color design and pattern,including carriage of materials with in all leads and lifts and direction of Engineer- in- Charge.	213.50	1350.00	Rupees one thousand three hundred fifty and paise nil only	Per Square metre	288225
3	Providing and laying cement concrete plain/ reinforced concrete 1:2:4 (One Cement : two coarse sand) : four graded stone aggregate 20 mm (twenty millimetre) nominal size :including all leads and lifts and as per the direction of Engineer- in- Charge.	4.08	5763.00	Rupees five thousand seven hundred sixty three and paise nil only	Per cubic metre	23513
					Total	413540

DNR NO 482 for the year 2026-27
approved for Rs 413540/- only

Executive Engineer
B&R Division HPTMD
Sarkashof