



Office of
Executive Engineer Jaisinghpur Division HPPWD Jaisinghpur Himachal Pradesh
Works Department Jaisinghpur 176095 Phone No. 01894-228030
Email ee-jaipwd-hp@gov.in

No.PWD/JSPR/CB/Tenders/2026-27-7516-23

Dated:- 25-9-26

To,

✓ The Chief Engineer (KZ),
Himachal Pradesh, PWD,
Dharamshala (HP).

Subject:-

Publication of Tender Notice on departmental website.

Sir,

Enclosed please find herewith tender notice for publication of the same on departmental website as per Notification issued by the worthy Principal Secretary (PW) to the Govt. of HP letter No. PBW-(B) A-(3) 1/2024 dated Shimla-2 dated 03.01.2025 and instructions issued by the worthy E-in-C, HPPWD Shimla letter No. PWD/ ICT Wing/ Website dated 22.05.2026. It is certified that the tenders are of urgent nature and in public interest.

DA/ As above.


Executive Engineer,
Jaisinghpur Division,
HPPWD Jaisinghpur.

Copy forwarded to the following for information and necessary please:-

1. The Superintending Engineer, 5th Circle. HPPWD, Palampur.
- 2-4. All the Assistant Engineers working under this Division.
- 5-6. The Drawings Branch and Accounts Branch in this office.
7. Notice Board.

DA/ As above.


Executive Engineer
Jaisinghpur Division,
HP.PWD., Jaisinghpur.

"NOTICE INVITING TENDERS"

Sealed percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, HP.PWD., Division Jaisinghpur on behalf of Governor of Himachal Pradesh for the following work from the approved and eligible contractors enlisted in HPPWD (B&R) whose registration stood renewed as per revised rules so as to reach in his office on or before on **29.09.2026 up to 11:00 A.M.** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representatives. The tender form can be obtained from his office on cash payment (non refundable) on **28.09.2026 up to 4:00 PM** and the application for issue of tender form shall be received on or before **28.09.2026 up to 1:00 PM**. The applications for issue of tender forms should accompanied with enlistment letter or renewal letter and the Earnest Money in the shape of National Saving Certificates / Saving Account of the Post Office / Time Deposit account / FDR in Himachal Pradesh duly pledged in favour of Executive Engineer, HP.PWD., Division Jaisinghpur.

The conditional tender and the tender received without earnest money will summarily be rejected. The offer of the tender shall be kept open for **75 days**:-


Sr. No.	Name of Work	Estimated Cost (Rs.)	EMD	Time limit	Cost of tender form
1	Restoration of rain damages on Jangal to Oach Kallan road Km 0/00 to 11/00 (SH:- Removal of Dangerous hanging rocks, Hill slope scaling and widening of road at RD 5/760 to 5/890 and 6/010 to 6/050) PDNA	499481.00	10000.00	Two Month	350/-
2	Restoration of rain Damages on Dharamshala Dadh Holta Chadhiar Sandhole road Km 75/00 to 87/00 (SH:-C/O B/wall at Km 775/405 to 75/440) PDNA	499799.00	10000.00	Two Month	350/-
3	Restoration of rain Damages on various roads under Sub Division jaisinghpur (SH:-Providing and fixing boards and painting of boards, writing letters Km stone) PDNA	414272.00	8300.00	Two Month	350/-
4	Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780 (SH:-C/O U-Sha pe drain with edge wall at RD 3/221 to 3/296) PDNA	398924.00	8000.00	Two Month	350/-
5	Restoration of rain Damages on Dharamshala Dadh Palampur Holta Chadhiar Sandhole Road Km 40/500 to 56/00 (SH:- Extension of CC pavement work at RD 50/00 to 50/200) PDNA	498450.00	10000.00	Two Month	350/-
6	Restoration of rain Damages on Alampur Harsipattan road Km 0/00 to 24/250 (SH:-C/O 900 mm dia RCC hume pipe culvert at RD 0/00 for chenalization of drain) PDNA	208978.00	4200.00	Two Month	350/-
7	Restoration of rain Damages on Ropri Harot road Km 0/00 to 6/500 (SH:-C/O R/wall from RD 6/050 to 6/070) PDNA	421880.00	8500.00	Two Month	350/-
8	A/R & M/O on various roads under Sub-Division panchrukhi Section Jalag(SH:Painting of boards and writing letter Kms stone etc.	84217.00	2000.00	Two Month	350/-
9	Restoration of rain Damages on Chadhiar Mungal Haler road Km 0/00 to 10/00 (SH:-C/O R/wall at Km 9/137 to 9/145) PDNA 2025	176895.00	3600.00	Two Month	350/-
10	Restoration of rain damages on Jalag Dali Nahalana road Km 0/00 to 3/00 (SH:- C/O R/wall at RD 1/190 to 1/200)	76671.00	2000.00	Two Month	350/-

—Contd. P-2—

Terms & Conditions:-

-2-

1. The contractors will have to produce a copy of enlistment / renewal of valid class at time of application / tender form.
2. The contractors will have to produce a copy of GST, EPF and PAN.
3. The contractors are directed to insert the rate / percentage both in figures and words.
4. The tenders forms will not be issued to those contractors who have not completed their previous works / commitments or whose performance is not found satisfactory.
5. The Executive Engineer reserves the right to reject / cancel any or all the tenders without assigning any reason.



Executive Engineer
Jaisinghpur Division
HP.PWD., Jaisinghpur.

(On behalf of Governor of Himachal Pradesh)

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain damages on Jangal to Oach Kallan road Km 0/00 to 11/00 (SH:- Removal of Dangerous hanging rocks, Hill slope scaling and widening of road at RD 5/760 to 5/890 and 6/010 to 6/050)			Estimated cost Rs.		499481.00	
			Earnest Money Rs.		10000.00	
			Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Excavation in hilly area in all heights and depths and in all kind of soil by all manual /mechanical means including saturated soil comprising of ordinary soil, ordinary rock,soft rocks, hard rocks, chiseling/ wedging out rock (where blasting is prohibited) and their intermediate classification of soil, complete including setting out true to the required line, grades, width cutting and trimming of side slopes and level as shown in the drawing and as directed by the Engineer-in- Charge at site according to the M.O.R.D. technical specification section 300 and 1600 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of un useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus / unuseful material to the approved dumping sites through all modes of transporation including head load or animals transport or mechanical means along with its leveling fine dressing and hauling /carriage of machineries, materials, tools equipments and safety measures. Recovery for useful stone of 243.34 (two hundred forty three cubic decimalthree four) cubic metre at the rate of Rs. 300/- (Rupees Three Hundred) per cubic metre shall be effected from the contractors running bill on pro-rata basis as per actual quantity executed. Any loss to the public / private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	1921.08	260.00	Rupees Two Hundred Sixty Only	Per cubic Metre	499481.00
Total						499481.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

3	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	125.30	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	426020.00
4	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	67.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	14070.00
	Total					499799.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

SCHEDULE OF QUANTITY						
Name of work :-Restoration of rain Damages on various roads under Sub Division jaisinghpur (SH:-Providing and fixing boards and painting of boards, writing letters Km stone etc.) PDNA				Estimated cost Rs.		414272.00
				Earnest Money Rs.		8300.00
				Time Limits		Two month
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping , sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	468.00	8.20	Rupees Eight And Paise Twenty Only	Per square metre	3838.00
2	Applying priming coat on new concrete masonry/plaster surfaces with readymixed paint brushing for use on floors to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	116.00	55.00	Rupees Fifty Five Only	Per Square metre	6380.00
3	Finishing wall with Apex weather proof exterior emulsion of asian paints/Nerolac Suraksha or Nerolac paint, Berger paints, Dulux paint to give an even shade Interior including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	338.00	78.00	Rupees Seventy Eight Only	Per Square Metre	26364.00
5	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint of Asian/ Nerolac brushing to give an even shade including cleaning the surfaces of all dirt, dust and other foreign matters with enamel paint of approval shade as per specifications, approved drawing , design, as per the entire satisfaction and direction of the Engineer-In-Charge including carriage of material within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	50.00	55.00	Rupees Fifty Five Only	Per square metre	2750.00
6	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in- Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	180000.00	1.65	Rupees One And Paise Sixty Five Only	Per letter per centimetre	297000.00

7	Providing and fixing standard PMGSY/NABARD citizen informatory sign board 600 (six hundred) millimeter equilateral triangle board as per IRC:67 made of 1.5 mm(One decimal Five millimeter) thick MS sheet duly stove enamelled white colour in front and gray colour on back with red reflective border of 65 mm (Sixty Five millimeter) width and required letters and figures with reflective tape engineering grade required shade and colour supported and welded on 47mm x 47mm x12(Forty seven into forty seven into twelve) SWG sheet tube firmly fixed to the ground by mean of properly designed foundations with M-15 grade cement concrete 450 x450 x 600 mm, (Four Hundred Fifty into Four Hundred fifty into Six Hundred millimeter), 600 mm (six Hundred millimeter) below ground level as per approved drawing and MORD technical specification section 1700 as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate includes octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government but excluding GST.	2.00	11950.00	Rupees Eleven Thousand Nine Hundred Fifty Only	Each	23900.00
8	Providing and fixing of typical NABARD informatory sign board with Logo as per MORD specifications and drawing. Three MS Plates of 1.6 mm (one point six millimetre) thick, top and middle plate duly welded with MS flat iron 25mm x 5m (twenty five into five millimetre) size on back on edges. The lower plate will be welded with MS angle iron frame of 25mm x 25mm x 5mm. (twenty five into twenty five into five millimetre). The angle iron frame of the lower most plate and flat iron frame of middle plate will be welded to 2 nos. 75mm x 75 mm (seventy five into seventy five millimetre) of 12 SWG sheet tubes posts duly embedded in cement concrete M-15 grade blocks of 450mm x 450mm x 600mm, (four hundred fifty into four hundred fifty into six hundred millimetre) 600mm (six hundred millimetr) below ground level. The top most diamond plate will be welded to middle plate by 47mm x 47mm (forty seven into forty seven millimetre) of 12 SWG steel plate tube. All M.S. will be stove enameled on both sides. Lettering and printing arrows, border etc. will be painted with ready mixed synthetic enamel paint of superior quality in required shade and colour. All sections of framed posts and steel tube will be painted with primer and two coats of epoxy paint as per drawing Clause and MORD technical specification section 1700 including carriage of material within all leads, lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government but excluding GST.	2.00	8570.00	Rupees Eight Thousand Five Hundred Seventy Only	Each	17140.00

9	Supplying and stacking 900 x600 mm (One nine hundred into six hundred) size direction and place identification retro-reflective sign board as per IRC made of 1.5mm (One decimal five millimetre) thick sheeting and supported on 40mm (Forty millimetre) dia pipe painted with red lead primer as per approved drawing and technical specification clause vide clause 1701.2.3 and entire satisfaction / directions of Engineer-in-charge including hauling of materials in all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	10.00	3690.00	Rupees Three Thousand Six Hundred Ninety Only	Each	36900.00
	Total					414272.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP PWD Jaisinghpur

(4)

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain Damages on Gander Siyara Kudana road Km 0/00 to 9/780 (SH:-C/O U-Shape drain with edge wall at RD 3/221 to 3/296) PDNA

Estimated cost Rs.	398924.00
Earnest Money Rs.	8000.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	118.13	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	24807.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 20mm(twenty millimetre) nominal size) on ground or under water including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work and curing complete in drain as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	86.13	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	366053.00



3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	38.40	210.00	Rupees Two Hundred Ten Only	Per Running Metre	8064.00
	Total					398924.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur



5

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Dharamshala Dadh Palampur Holta Chadhiar Sandhole Road Km 40/500 to 56/00 (SH:-Extension of CC pavement work at RD 50/00 to 50/200) PDNA						Estimated cost Rs.		498450.00	
						Earnest Money Rs.		10000.00	
						Time Limits		Two month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount			
			In Figures	In Word					
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	81.00	190.00	Rupees One Hundred Ninety Only	Per Cubic Metre	15390.00			
2	Providing laying spreading and compacting by mechanical means 75 mm (seventy five millimetre) compacted thickness broken /crushed stone aggregate of size 63mm to 45mm (sixty three millimetre to forty five millimetre) Grading-II to water bound Macadam specification including spreading in uniform thickness using template, hand packing, rolling with three wheel 80-100 (eighty to one hundred) K.N. static roller in stages to proper grade and camber including applying and brooming, stone screening type-B of size 11.2mm (eleven decimal two millimetre) nominal size at the rate of 0.20 cum (zero point two zero cubic metre) per ten square metre and binding material at the rate of 0.06 (zero decimal zero six) cubic metre per ten square metre to fill up the interstices of coarse aggregate, watering and compacting to the required density as per drawing and M.O.R.D. technical specifications section 400 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals.The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	27.00	1800.00	Rupees One Thousand Eight Hundred Only	Per Cubic Metre	48600.00			



3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete using plain cement concrete grade M-10 (M ten) nominal mix 1:3:6 (one cement is to three sand is to six crushed stone aggregate 20mm(twenty millimetre) nominal size) on ground or under water including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work and curing complete in drain as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per the directions of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals and to the entire satisfaction of the Engineer-in-Charge .The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	54.00	4250.00	Rupees Four Thousand Two Hundred Fifty Only	Per Cubic Metre	229500.00
4	Providing and laying design mix cement concrete of M-30(Thirty) grade, in roads using cement content as per design mix, using coarse sand and graded stone aggregate of 20 mm(twenty millimetre) nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm)(ten millimetre wide into fifty millimetre deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineerincharge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to bepaid separately).Cement content considered in M-30(Thirty) is at the rate 440 kg/cum (at the rate four hundred forty kilograme per cubic metre). Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete prepared with batch mixing machine .as per direction of Engineer-in- charge.and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	29.28	7000.00	Rupees Seven Thousand Only	Per Cubic Metre	204960.00
Total						498450.00
Quoted Rate (in Figures) Percentage		Excess (+)			%	
		Less (-)			%	
G.Total in Figures						
G.Total in Words						

Executive Engineer,
Jaisinghpur Division,
H.P.WD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Alampur Harsipattan road Km 0/00 to 24/250 (SH:-C/O 900 mm dia RCC hume pipe culvert at RD 0/00 for chanalization of drain) PDNA

Estimated cost Rs.	208978.00
Earnest Money Rs.	4200.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	13.65	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	2867.00
2	Demolishing cement concrete work manually/ by mechanical means including disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	9.10	1000.00	Rupees One Thousand Only	Per cubic metre	9100.00
3	Providing and laying mechanically mixed and vibrated concrete for plain cement concrete M 15 (M- fifteen) nominal mix 1:2½:5 (one cement is to two and half sand is to five graded crushed stone aggregate 40mm (forty millimetre) nominal size) on ground or under water and curing complete for 14 (fourteen) days , in cradle bedding for hume pipe including pumping or bailing out water (surface and sub soil water) dewatering for all depths and any quantum of water including removal of slush which may arise at the time of laying concrete complete for all heights / depths including the cost of form work complete as per drawings and M.O.R.D. technical specification section 800,900 and 1100 as directed by the Engineer-in-Charge including carriage of material within all leads ,lifts and other incidentals. The rate includes octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government but excluding GST.	4.73	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	21758.00

4	Providing and laying (to level or slope) 900mm dia (nine hundred millimetre) diameter reinforced cement concrete heavy duty non pressure pipes IS Class NP-4 for culverts on first class bedding of granular materials in single row including fixing collar with cement mortar 1 : 2 (One cement : two sand) but excluding the cost of excavation, protection works, back filling, concrete and masonry work in head walls and parapets as per drawing and M.O.R.D. technical specifications section 1100 and as per direction of Engineer - in- Charge including carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental. The rate includes octroi, royalty, Malkana, toll tax or any other taxes imposed by the Government but excluding GST.	17.50	7300.00	Rupees Seven Thousand Three Hundred Only	Per running metre.	127750.00
5	Providing and laying design mix cement concrete of M-30(Thirty) grade, in roads using cement content as per design mix, using coarse sand and graded stone aggregate of 20 mm(twenty millimetre) nominal size in appropriate proportions as per approved & specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction & longitudinal joints (10 mm wide x 50 mm)(ten millimetre wide into fifty millimetre deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineerincharge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to bepaid separately).Cement content considered in M-30(Thirty) is at the rate 440 kg/cum (at the rate four hundred forty kilograme per cubic metre). Excess/ less cement used as per design mix is payable/ recoverable separately. Cement concrete prepared with batch mixing machine .as per direction of Engineer-in- charge.and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	7.09	6700.00	Rupees Six Thousand Seven Hundred Only	Per Cubic Metre	47503.00
	Total					208978.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Ropri Harot road Km 0/00 to 6/500 (SH:-C/O R/wall from RD 6/050 to 6/070) PDNA

Estimated cost Rs.	421880.00
Earnest Money Rs.	
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	36.23	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	7608.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	111.38	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	378692.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	22.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	4620.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	38.70	800.00	Rupees Eight Hundred Only	Per cubic Metre	30960.00
	Total					421880.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
H.P.W.D Jaisinghpur

8

Name of work :-A/R & M/O on various roads under Sub-Division panchrukhi Section Jalag(SH:Painting of boards and writing letter Kms stone etc)

SCHEDULE OF QUANTITY

Division panchrukhi Section Jalag(SH:Painting of

		Estimated cost Rs.		84217.00		
		Earnest Money Rs.		2000.00		
		Time Limits		Two month		
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping , sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	62.10	8.20	Rupees Eight And Paise Twenty Only	Per square metre	509.00
2	Applying priming coat on new concrete masonry/plaster surfaces with readymixed paint brushing for use on floors to give an even shade including cleaning the surface of all dirt,dust and other foreign matter and sand papering as required. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	62.10	50.00	Rupees Fifty Only	Per Square metre	3105.00
3	Writing letters of figures on any surface with synthetic enamel paint (other than white) (stop, comas, border, hyphens and like not to be measured and paid separately) in Indian letter/figure complete and as per directions of Engineer - in-Charge including hauling /carriage of materials to various location through all modes of transportation with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	48850.00	1.65	Rupees One And Paise Sixty Five Only	Per letter per centimetre	80603.00

Executive Engineer,
Jaisinghpur Division,
H.P.PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain Damages on Chadhiar Mungal Haler road Km 0/00 to 10/00 (SH:-C/O R/wall at Km 9/137 to 9/145) PDNA 2025

Estimated cost Rs.	176895.00
Earnest Money Rs.	3600.00
Time Limits	Two month

S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	26.89	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	5647.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	46.53	3400.00	Rupees Three Thousand Four Hundred Only	Per Cubic Metre	158202.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	12.60	210.00	Rupees Two Hundred Ten Only	Per Running Metre	2646.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	13.00	800.00	Rupees Eight Hundred Only	Per cubic Metre	10400.00
	Total					176895.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP/PWD Jaisinghpur

SCHEDULE OF QUANTITY

Name of work :-Restoration of rain damages on Jalag Dali nahalana road Km 0/00 to 3/00 (SH:- C/O R/wall at RD 1/190 to 1/200)

			Earnest Money Rs.		2000.00	
			Time Limits		Two Month	
S. N.	Description of Item	Quantity	Rate		Unit	Amount
			In Figures	In Word		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	9.10	210.00	Rupees Two Hundred Ten Only	Per Cubic Metre	1911.00
2	Providing and laying cement concrete 1:5:10 (One cement: five sand: ten graded crushed/broken stone aggregate 40mm nominal size) and curing complete, excluding cost of form work in foundation and plinth including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	20.10	3400.00	Rupees Three Thousand Four Hundred Only	Per cubic Metre	68340.00

3	Providing 100mm (one Hundred millimeter) dia ISI marked P.V.C. pipe Weep Holes in brick masonry/stone masonry plain/ reinforcement concrete abutments, wing wall/ return wall, retaining walls and breast walls, extending through the full width of the structure with slope of 1 (V):20H (One vertical : twenty Horizontal) towards draining face complete as per drawing and MORD technical specification section 700, 1200 and as per the direction and entire satisfaction of Engineer-in-Charge complete, including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	10.00	210.00	Rupees Two Hundred Ten Only	Per Running Metre	2100.00
4	Back filling with granular materials behind abutment, Retaining wall/Breast wall, Wing walls and the like complete as per drawings and MORD technical specification section 1200, 1600 and as per direction and entire satisfaction of the Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government but excluding GST	5.40	800.00	Rupees Eight Hundred Only	Per cubic Metre	4320.00
	Total					76671.00
	Quoted Rate (in Figures) Percentage	Excess (+)			%	
		Less (-)			%	
	G.Total in Figures					
	G.Total in Words					

Executive Engineer,
Jaisinghpur Division,
HP.PWD Jaisinghpur