



Public Works Department
Government of Himachal Pradesh, India

No. PW-MDII(P)E-Tender-NIT/2026-27-
To

10613-18 Dated:- 9/9/2026

The Chief Engineer (MZ),
HPPWD, Mandi.

Subject: - Publishing of tender notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P. letter No. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW (B) A (3) 8/2025- 300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:- Notice Inviting Tender.


Executive Engineer,
Mandi Division No-II,
HP.PWD. Mandi

Copy alongwith copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 1st Circle, HPPWD, Mandi H.P.
2. All the Assistant Engineers, Working under this Division.
3. The Drawing Branch of this office.
4. Notice Board.


Executive Engineer,
Mandi Division No-II,
HP.PWD. Mandi

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
"NOTICE INVITING TENDER"**

Sealed **Percentage rates** tender in emergent condition on form 6 & 7 are invited on behalf of Governor of Himachal Pradesh for the following work covered under emergent/inescapable nature from the approved and eligible contractors enlisted in H.P.PWD so as to reach in this office on or **16.09.2026 Up to 11.30 A.M.** and will be opened on the same day at 3.30 P.M. in the presence of interesting contractors or their authorized representatives who may like to be present. If it happens to be holiday on the schedule date of opening of tender, the same will be opened on next working day. The application for obtaining the tender form will be received upto **01.00 PM** & without EMD tender form will not be accepted, moreover the tender form can be had from this office against cash payment (Nonrefundable) up to 5.00 P.M. on **15.09.2026**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account in any of the Post Office and Banks of Himachal Pradesh duly pledged in favour of the Xen Mandi Division No. II must accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The earnest money should be attached with application. The offer of the tender shall be kept open for 75 days. The Executive Engineer reserves the right to reject the tender without assigning any reason.

Sr. No	Name of Work	Estimated Cost (Rs.)	Earnest Money Deposit (EMD) (Rs.)	Cost of Tender (Rs.)	Eligible Class of Contractor	Time Limit
1.	Restoration of rain damages on Gokhara Nichla Khajraon road km. 0/00 to 6/00 (SH:- C/O PCC B/wall at Rd 2/915 to 2/925 and R/wall at RD 3/690 to 3/700) Under PDNA 2025	4,97,042	10,000	350	Class "D"	One Month
2.	RRD on Baggi to Sain road KM. 0/00 to 6/500. (SH: C/O PCC R/wall at RD 1/540 to 1/548 and C/O Crated R/wall at RD 0/525 to 0/540) under PDNA 2025	4,83,743	9,700	350	Class "D"	One Month
3.	Restoration of rain damages on Kakarjahal Sarwan Batour road km. 0/00 to 4/100 (SH:- C/O wire crate R/wall on PCC Toe wall at Rd 1/710 to 1/75 and B/wall at RD 3/920 to 3/930) Under PDNA 2025	4,78,098	9,600	350	Class "D"	One Month
4.	Restoration of rain damages on Gokhara Nichla Khajraon road km. 0/00 to 6/00. (SH:- C/O PCC B/wall at Rd 0/700 to 0/710, 1/810 to 1/820 and R/wall at Rd 2/490 to 2/500) Under PDNA 2025	4,58,099	9,200	350	Class "D"	One Month
5.	Restoration of rain damages on Rath Pul to Alathu Saini Mohari road KM. 0/00 to 6/500 (SH: Construction of R/wall at RD 5/510 to 5/530) under PDNA 2025	4,53,647	9,100	350	Class "D"	One Month
6.	RRD on Deodhar Kheelgaloo road km. 0/00 to 24/500 (SH:- C/O U-shape drain at various Rds between km. 0/00 to 24/500) Under PDNA 2023	4,25,669	8,600	350	Class "D"	One Month
7.	Restoration of rain damages on NH-70 Fagla Samarahan Junction link road Harizan Basti Hawani km. 0/00 to 0/750 (SH:- C/O PCC R/wall at Rd 0/645 to 660) Under PDNA 2025	4,08,966	8,200	350	Class "D"	One Month
8.	Restoration of rain damages on Gharwan to Taryasal Dawahan road km. 0/00 to 6/00 (SH:- C/O wire crate R/wall on PCC Toe wall at Rd 2/165 to 2/175 to make the road motorable) under PDNA 2025	4,02,001	8,100	350	Class "D"	One Month
9.	Restoration of rain damages on Lot Paprahal road km. 0/00 to 2/00 (SH:- C/O PCC B/wall to Rd 0/910 to 0/925 and R/wall at Rd 1/600 to 1/615) Under PDNA 2025	3,70,099	7,500	350	Class "D"	One Month
10.	Annual repair and maintenance of various roads in Town section under Mandi Division no.II (SH:- Repair to pot holes and patch work in various Rds) Under PDNA 2025	3,14,061	6,300	350	Class "D"	One Month
11.	Restoration of rain damages on Rada Nallah Karkch Arthe road KM. 0/00 to 12/300 (SH: Construction of R/wall in PCC at RD 3/005 to 3/015) under PDNA 2025	3,08,416	6,200	350	Class "D"	One Month
12.	Restoration of rain damages on Roda Nallah Karkoh road km. 0/00 to 12/300 (SH:- C/O PCC R/wall at RD 0/315 to 0/324 to make the road Motorable) Under PDNA 2025	2,62,306	5,300	350	Class "D"	One Month
13.	RRD on Gokhara Nichla Lot Khajraon road km. 0/00 to 6/00 (SH:- C/O 900 mm dia RCC hume pipe culvert with wing all at Rd 3/850) Under PDNA 2025	2,35,316	4,700	350	Class "D"	One Month
14.	A/R & M/O AE Office Building at Kotli. (SH: Balance work of construction of Record room)	2,31,131	4,700	350	Class "D"	One Month
15.	Restoration of rain damages on Baggi to Sain road km. 0/00 to 6/500 (SH:- C/O 900 mm dia hume pipe culvert along with both side wing walls at Rd 1/610) under PDNA 2025	2,29,751	4,600	350	Class "D"	One Month
16.	Restoration of rain damages on Ratti Pull to Alathu Saini Mohari road KM. 0/00 to 6/500 (SH: Construction of R/wall at RD 1/730 to 1/740) under PDNA 2025	1,91,823	3,900	350	Class "D"	One Month
17.	C/O Path near Dev Balakameshwar Temple Bari, Ward No.9 Mandi (H.P) (SH: C/O R/wall at RD 0/00 to 0/010) MC Deposit	1,82,262	3,700	350	Class "D"	One Month
18.	RRD on Sain Gujra Ra Ropru road KM. 0/00 to 14/00 (SH: C/O B/wall at RD 0/075 to 0/090) under PDNA 2025	1,75,825	3,600	350	Class "D"	One Month
19.	Restoration of rain damages on old suketi bridge and new suketi bridge at Disitrcit Mandi H.P.(SH:- Providing and fixing steel work,	1,09,522	2,200	350	Class "D"	One Month

	repair of plaster and laying of cement concrete work etcetera) Under PDNA 2023					
20.	Restoration of rain damages on OLD PCM road at District Mandi H.P. (SH:- Dismantling of encroached structure near Mahamritunjaya Temple as per Direction of Higher Authorities Under PDNA 2025	39,039	800	350	Class "D"	One Month
21.	C/o Jogni More to Gochra road km. 0/00 to 1/00 (SH- 5/7 mtr wide formation cutting road in Km. 0/206 to 0/251) VKVNY	2,44,968	4,900	350	"D"	One month
22.	RRD on Nerchowk Pandoh bypass road (Section of NH-21) Km. 198/145 to 203/500. (SH Construction of drain, footpath over drain with precast RCC covers in RD 199/934 to 200/0 and 200/350 to 200/415)	4,38,768	8,800/-	350/-	Class "D"	One Month
23.	RRD on MRBU road km. 0/00 to 3/835. (SH- Construction of V-shape drain at Rd. 0/340 to 0/410).	123945	2500	350	"D"	One Month

CERTIFICATE

It is certified that the above works are required to be carried out immediately, being of emergent nature and in the larger public interest.

Tender Notice - Terms & Conditions

The tender documents shall be issued only to those Contractors/Firms who submit the following documents along with their application:

1. Valid enlistment/registration of contractor in the appropriate class.
2. Permanent Account Number (PAN).
3. GST Registration Number.
4. Earnest money in the shape of National Saving Certificate/Time Deposit Account in any Post Office in Himachal Pradesh, or F.D.R. from any Nationalized Bank duly pledged in favour of the Executive Engineer, Mandi Division No. 2, HPPWD, Mandi H.P.
5. Earnest money and cost of tender form for the above works must be submitted along with the application for purchase of tender form. Applications received without earnest money and cost of tender form shall be summarily rejected.
6. The offer of the tender shall remain valid for 75 (seventy-five) days after the opening of the tender.
7. Ambiguous, telephonic, conditional tenders or tenders submitted by fax/e-mail shall not be considered and will be summarily rejected.
8. The Executive Engineer reserves the right to reject or cancel any or all tenders without assigning any reason.
9. If the date specified above happens to be a holiday, the tenders shall be processed on the next working day.
10. The Contractor/Firm must quote their rates both in words as well as in figures, failing which the Executive Engineer reserves the right to accept or reject any or all tenders.
11. Tender forms shall not be issued to those Contractors/Firms whose past performance is not found satisfactory or who have failed to complete previously awarded works within the stipulated period.
12. No contractor shall have more than two major works in hand at a time.
13. The work shall be completed by the Contractor within the stipulated period.

No.PW-MDII-CB NIT (off line) /2025-

Copy forwarded to the following for information and necessary action:-

1. The Engineer-in-chief, HPPWD: Shimla.
2. The Chief Engineer, (MZ)HPPWD: Mandi.
3. The Superintending Engineer, 1st Circle, HPPWD: Mandi.
4. All the Assistant Engineers' Working under this Division
5. The President of Contractor's Association.
6. Notice Board/Accounts Branch/Drawing Branch.

Dated: -

Executive Engineer
Mandi Division No. II
HP.PWD Mandi

Executive Engineer
Mandi Division No. II
HP.PWD Mandi

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 497042.00
Earnest Money Rs: 10000.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Gokhra Nichla Khajroan road KM. 0/00 to 6/00 (SH:- C/O PCC B/wall at Rd 2/915 to 2/925 and R/wall at Rd 3/690 to 3/700)
under PDNA 2025

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in In	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	46.30	Per cubic metre	517.65	23967.00	Rupees Twenty Three Thousand Hundred Seven Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	93.77	Per cubic metre	4600.00	431342.00	Rupees Four Lakh Thirty One Thousand Three Hundred Forty Two Only
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	19.50	Per cubic metre	1331.00	25955.00	Rupees Twenty Five Thousand Nine Hundred Fifty Five Only
4	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment, wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	49.00	Each	322.00	15778.00	Rupees Fifteen Thousand Seven Hundred Eight Only
Total in Figure					4,97,042.00	Rupees Four Lakh Ninety Seven Thousand Forty Two Only
Quoted Rate in Words		Rupees Four Lakh Ninety Seven Thousand Forty Two Only				

BoQ. Approved for Rs. 497042.00

Executive Engineer,
Mandi Division No.-II,
H.P.P.W.D. Mandi.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 483743.00
Earnest Money Rs:- 9700.00
Time :- One month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work:- RRD on Baggi to Sain road KM. 0/00 to 6/500. (SH:- C/O PCC R/wall at RD 1/540 to 1/548 and C/O Crated R/wall at RD 0/525 to 0/540) under PDNA 2025.

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	33.68	Per cubic metre	517.65	17434.00	Rupees Seventeen Thousand Four Hundred Thirty Four Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	62.45	Per cubic metre	4600.00	287270.00	Rupees Two Lakh Eighty Seven Thousand Two Hundred Seventy Only
3	Providing and laying of boulder apron laid in wire crate with 4mm (four millimetre) dia. GI wire conforming to IS:280 and IS:4826 in 100x100 mm (one hundred into one hundred millimetre) mesh (woven diagonally) including 10 (ten) percent extra for laps and joints laid with stone boulders weighing not less than 25 kg (twenty five kilogram) each as per drawing and technical specifications clause 1301 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	46.88	Per cubic metre	3095.00	145094.00	Rupees One Lakh Forty Five Thousand Ninety Four Only

135

178

4	Providing weepholes in brick masonry / stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	12.00 Each	322.00	3864.00	Rupees Thousand Hundred Only	Three Eight Sixty Four
5	Back filling behind abutment , wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads , lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	22.60 Per cubic metre	1331.00	30081.00	Rupees Thousand One Only	Thirty Eighty
Total in Figure				483743.00	Rupees Eighty Thousand Hundred Three Only	Four Lakh Three Seven Forty
Quoted Rate in Words				Rupees Four Lakh Eighty Three Thousand Seven Hundred Forty Three Only		

Boa checked and approved for Rs. 4,83,743 /only.



Executive Engineer,
Mandi Division No.-II,
H.P.W.D. Mandi.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 478098.00
Earnest Money Rs: 9600/-
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Kakarjahal Sarwan Batour road KM. 0/00 to 4/100 (SH:- C/O wire crate RWall on PCC Toe wall at RD 1/710 to 1/725 and BWall at Rd 3/920 to 3/930) under PDNA 2021

PRICE SCHEDULE						
Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in	TOTAL AMOUNT with all Taxes excluding GST in words.
		3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	41.20	Per cubic metre	517.65	21327.00	Rupees Twenty One Thousand Three Hundred Twenty Seven Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	61.96	Per cubic metre	4600.00	285016.00	Rupees Two Lakh Eighty Five Thousand Sixteen Only
3	Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100*100 mm mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	46.88	Per cubic metre	3094.90	145089.00	Rupees One Lakh Forty Five Thousand Eighty Nine Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	15.68	Per cubic metre	1331.00	20870.00	Rupees Twenty Thousand Eight Hundred Seventy Five Only
3	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment, wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	18.00	Each	322.00	5796.00	Rupees Five Thousand Seven Hundred Ninety Six Only
Total in Figure					478098.00	Rupees Four Lakh Seventy Eight Thousand Ninety Eight Only
Quoted Rate in Words						Rupees Four Lakh Seventy Eight Thousand Ninety Eight Only

130 & Approved for RS 478098.00 only

Executive Engineer,
Mandi Division No.-II,
H.P.P.W.D. Mandi.

(16) (3)

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 458099.00
Earnest Money Rs: 9200.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Gokhra Nichla Khajroan road KM. 0/00 to 6/00 (SH:- C/O PCC B/wall at Rd 0/700 to 0/710, 1/810 to 1/820 and R/wall at Rd 2/490 to 2/500) under PDNA 2025

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT with	TOTAL AMOUNT with all Taxes
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	62.55	Per cubic metre	517.65	32379.00	Rupees Three Thousand Hundred Nine Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	86.83	Per cubic metre	4600.00	399418.00	Rupees Three Lakh Nine Thousand Four Hundred Eighteen Only
3	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	9.60	Per cubic metre	1331.00	12778.00	Rupees Twelve Thousand Seven Hundred Seventy Eight Only
4	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	42.00	Each	322.00	13524.00	Rupees Thirteen Thousand Hundred Four Only
Total in Figure					4,58,099.00	Rupees Four Lakh Fifty Eight Thousand Nine Only
Quoted Rate in Words		Rupees Four Lakh Fifty Eight Thousand			Ninety Nine Only	

BoQ. Approved for R's. 9,45,80,99.00

Executive Engineer,
Mandi Division No.-II,
H.P.P.W.D. Mandi.

(128)

PERCENTAGE RATE BILL OF QUANTITY

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Ratti Pull to Alathu Saini Mohari road KM. 0/00 to 6/500 (SH:- Construction of R/wall at RD 5/510 to 5/530) under PDNA 2025.

Estimated Cost Rs:- 453647.00
Earnest Money Rs:- 9100.00
Time :- One Month

Contract No.:

Bidder Name:

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	37.00	Per cubic metre	517.65	19153.00	Rupees Nineteen Thousand One Hundred Fifty Three Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	84.00	Per cubic metre	4600.00	386400.00	Rupees Three Lakh Eighty Six Thousand Four Hundred Only
3	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	38.00	Each	328.00	12464.00	Rupees Twelve Thousand Four Hundred Sixty Four Only
4	Back filling behind abutment , wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads , lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	25.80	Per cubic metre	1381.00	35630.00	Rupees Thirty Five Thousand Six Hundred Thirty Only

159

Total in Figure		Rupees Four Lakh Fifty Thousand Three Hundred Seven Only	
		453647.00	Rupees Four Lakh Fifty Thousand Three Hundred Seven Only
Quoted Rate in Words		Rupees Four Lakh Fifty Three Thousand Six Hundred Forty Seven Only	

Boa checked and approved for Rs. 4,53,647/- only.

[Signature]
Executive Engineer,
Mandi Division No.-II,
H.P. P.W.D. Mandi.

Estimated Cost :- 4,25,669/-
Earnest Money:-8,600/-
Time:- One Month

Tender Inviting Authority : Executive Engineer, Mandi Division No.II HPPWD Mandi
Name of work :- RRD on Deodhar Khealgaloo Road Km 0/00 to 24/500 (SH :- C/O U-Shape drain at various Rds between Km 0/00 to 24/500) under PDNA 2023

Percentage of BoQ

Contract No. :

Name of the Bidder/ Bidding Firm/ Company :

PRICE SCHEDULE						
[This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only]						
Sl. No.	Item Description	Quantity	Unit	Estimate Rate with all taxes excluding GST in Rs. P	TOTAL AMOUNT With all Taxes excluding GST in Rs. P	TOTAL AMOUNT with all Taxes excluding GST In Words
NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
1	Earth work in excavation in all kinds of soil for structure as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto any lead and dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer in-charge.	87.90	Per Cubic Metre	516.85	45,431.00	Rupees Forty Five Thousand Four Hundred Thirty One Only
2	Providing and laying P.C.C. 1:3:6 (one cement : three sand : six graded crushed stone aggregate) nominal mix in foundation with crushed stone aggregate 40mm (forty millimetre) nominal size upto any height mechanically mixed and vibrated placed in foundation including curing complete including carriage of materials with in all leads, lifts and other incidental or as per the direction of Engineer-in-charge.	44.25	Per Cubic Metre	4915.00	2,17,489.00	Rupees Two Lakh Seventeen Thousand Four Hundred Eighty Nine Only
3	Steel work in single sections including cutting, hoisting, fixing in position and applying a priming coat of red lead paint. In R.S. joists, channels, angles, tees including carriage of materials with in all leads, lifts and other incidentals.	1745.30	Per Kilogramme	93.25	1,62,749.00	Rupees One Lakh Sixty Two Thousand Seven Hundred Forty Nine Only
Total					4,25,669.00	Rupees Four Lakh Twenty Five Thousand Six Hundred Sixty Nine Only

Quoted Rate in Figures :
Quoted Rate in words:

BoQ approved for Rs. 4,25,669/- only

Executive Engineer,
Mandi Division No.II,
HPPWD, Mandi.

123

607

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 408966.00
Earnest Money Rs: 8200/-
Time :- One Month

Under PDNA 2025)

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work:- Restoration of rain damages on NH-70 Fagla Samarahan Junction link road Harizan Basti Hawani KM. 0/00 to 0/750 (SH:- C/O PCC R/wall at Rd 0/645 to 660) Under PDNA 2025)

Contract No.:		PRICE SCHEDULE				TOTAL AMOUNT with all Taxes excluding GST in words.	
Bidder Name:		Item Description				TOTAL AMOUNT with all Taxes excluding GST in	
Sr. No.		Quantity	Units	Estimated Rate excluding GST in Rs. P.	6	7	
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	33.30	Per cubic metre	517.65	17238.00	Rupees Thousand Two Hundred Thirty Eight Only	
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	81.00	Per cubic metre	4600.00	372600.00	Rupees Three Lakh Seventy Thousand Six Hundred Only	
3	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204:3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	16.00	Each	322.00	5152.00	Rupees Thousand Hundred Fifty Two Only	
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	10.50	Per cubic metre	1331.00	13976.00	Rupees Thirteen Thousand Nine Hundred Seventy Six Only	
Total in Figure					4,08,966.00	Rupees Four Lakh Eight Thousand Nine Hundred Sixty Six Only	
Quoted Rate in Words		Rupees Four Lakh Eight Thousand Nine Hundred Sixty Six Only					

BoQ Approved. For Rs. 408966.00

*Executive Engineer,
Mandi Division No.-II,
H.P.P.W.D. Mandi.*

20/7

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 402001.00
Earnest Money Rs: 8100/-
Time :- One Month

2/165 to 2/175 to make the road Motorable)

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work:- Restoration of rain damages on Gharwan to Taryasal Dawahan road KM. 0/00 to 6/00 (SH.- C/O wire crate R/wall on PCC Toe wall at RD 2/165 to 2/175 to make the road Motorable) under PDNA 2025.

Contract No.:-		PRICE SCHEDULE				TOTAL AMOUNT	
Bidder Name:-		Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT with	TOTAL AMOUNT with all Taxes
Sr. No.						6	7
1		Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	16.70	Per cubic metre	517.65	8645.00	Rupees Eight Thousand Six Hundred Forty Five Only
2		Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	42.60	Per cubic metre	4600.00	195960.00	Rupees One Lakh Ninety Five Thousand Nine Hundred Sixty Only
3		Providing and laying of boulder apron laid in wire crate with 4mm dia GI wire conforming to IS:280 and IS:4826 in 100*100 mm mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications clause 1301 complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	56.90	Per cubic metre	3094.90	176100.00	Rupees One Lakh Seventy Thousand One Hundred Only
4		Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	16.00	Per cubic metre	1331.00	21296.00	Rupees Twenty One Thousand Ninety Six Only
Total in Figure						402001.00	Rupees Four Lakh Two Thousand One Only
Quoted Rate in Words		Rupees Four Lakh Two Thousand One Only					

Boo approved for M 402001/-

*Executive Engineer,
Mandi Division No.-II,
H.P.P.W.D. Mandi.*

(248)

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 370099.00
Earnest Money Rs:- 7500/-
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Lot Paprahal road KM. 0/00 to 2/00 (SH:- C/O PCC B/wall at Rd 0/910 to 0/925 and R/wall at Rd 1/600 to 1/615) under PDNA 2025

PRICE SCHEDULE						
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT with	TOTAL AMOUNT with all Taxes
		3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	52.13	Per cubic metre	517.65	26985.00	Rupees Twenty Nine Hundred Eighty Five Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	72.49	Per cubic metre	4600.00	333454.00	Rupees Three Lakh Thirty Thousand Four Hundred Fifty Four Only
3	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	30.00	Each	322.00	9660.00	Rupees Thousand Six Hundred Sixty Only
Total in Figure					3,70,099.00	Rupees Three Lakh Seventy Thousand Ninety Nine Only
Quoted Rate in Words		Rupees Three Lakh Seventy Thousand Ninety Nine Only				

B.O.P. approved. For Rs. 3,70,099.00

Executive Engineer,
Mandi Division No.-II,
H.P.P.W.D. Mandi.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 314061.00
Earnest Money Rs: 6300.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.II, HP.PWD. Mandi.

Name of work:- Annual repair and maintenance of various roads in Town Section under Mandi Division No II (Sub Head :- Repair to pot holes and patch work in various RDs)

Under PDNA 2025

SCHEDULE OF WORKS						
Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2 Providing and applying tack coat with bitumen emulsion (RS-1) using emulsion distributor @ (at the rate of) 0.25 to 0.30Kg per sqm. (zero point two five to zero point three zero kilogram per squaremetre) on the prepared dry and hungry bituminous surface cleaned with hydraulic broom as per the Technical pecification Clause 503 complete in all respect including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	3 284.55	4 Per square metre	5 30.10	7 8565.00	8 Rupees Thousand Hundred Sixty Five Only
2	Providing and laying bituminous macadam with hot mix plant using crushed aggregates of grading as per Table 500.4 premixed with bituminous binder (VG-30), transported to site upto any lead laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled to achieve the desired compaction as per Technical Specification Clause 504 complete in all respect including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	14.23	Per cubic metre	11525.00	164001.00	Rupees One Lakh Sixty Four Thousand One Only
3	Providing and laying bituminous concrete with 100-120TPH batch type hot mix plant producing an average output of 75 (seventy five) tonnes per hour using crushed aggregates of specified grading,premixed with bituminous binder VG-30 (thirty) @ 5.4 to 5.6 (at the rate of five point four to five point six) percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandom rollers to achieve the desired compaction as per MORTH specification clause No. 509 complete in all respect including carriage of material within all leads, lifts and other incidental charges and as per the entire satisfaction and direction of Engineer-in-Charge.	8.54	Per cubic metre	16568.45	141495.00	Rupees One Lakh Forty One Thousand Four Hundred Ninety Five Only

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 308416.00
Earnest Money Rs: 6200.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Roda Nallah Karkoh Arthi road KM. 0/00 to 12/300 (SH:- Construction of R/wall in PCC at RD 3/005 to 3/015) under PDNA 2025.

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	3	Per cubic metre	5	6	7
1		25.80		517.65	13355.00	Rupees Thirteen Thousand Three Hundred Fifty Five Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	59.10	Per cubic metre	4600.00	271860.00	Rupees Two Lakh Seventy One Thousand Eight Hundred Sixty Only
3	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment, wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.00	Each	328.00	7872.00	Rupees Seven Thousand Eight Hundred Seventy Two Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	11.10	Per cubic metre	1381.00	15329.00	Rupees Fifteen Thousand Three Hundred Twenty Nine Only

24/11

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 262306.00
Earnest Money Rs: 5300/-
Time :- One Month
Under PDNA 2025)

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Roda Nallah Karkoh Road Km 0/00 to 12/300 (SH)- C/O PCC R/wall at Rd 0/315 to 0/324 to make the road Motorable)

PRICE SCHEDULE						
Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	20.07	Per cubic metre	517.65	10389.00	Rupees Ten Thousand Three Hundred Eighty Nine Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	50.22	Per cubic metre	4600.00	231012.00	Rupees Two Lakh Thirty One Thousand Twelve Only
3	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204,3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	24.00	Each	322.00	7728.00	Rupees Seven Thousand Seven Hundred Eighty Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	9.90	Per cubic metre	1331.00	13177.00	Rupees Thirteen Thousand One Hundred Seventy Seven Only
Total in Figure					2,62,306.00	Rupees Two Lakh Sixty Two Thousand Three Hundred Six Only
Quoted Rate in Words						Rupees Two Lakh Sixty Two Thousand Three Hundred Six Only

Boq approved for Rs. 262306.00

Executive Engineer,
Mandi Division No.-II,
H.P.P.W.D. Mandi.

2613

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 235316.00
Earnest Money Rs:- 4700.00
Time :- One month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work:- RRD on Gokhra Nichla Lot Khajron road KM. 0/00 to 6/00. (SH:- C/O 900 mm dia RCC hume pipe culvert with wing wall at RD 3/850) under PDNA 2025.

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Excavation of soil in Hilly area by mechanical means including dressing of sides and ramming of bottoms, upto any lift, including getting out the excavated soil and disposal of surplus excavated earth with a lift upto 1.5m, including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.61	Per cubic metre	168.35	608.00	Rupees Six Hundred Eight Only
2	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	49.37	Per cubic metre	517.65	25556.00	Rupees Twenty Five Thousand Hundred Fifty Six Only
3	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3.36	Per cubic metre	4495.00	15103.00	Rupees Fifteen Thousand Hundred Three Only
4	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	10.06	Per cubic metre	5639.30	56731.00	Rupees Fifty Six Thousand Hundred Thirty One Only

(221)

5	Providing and laying 900mm dia (nine hundred millimetre) reinforced cement concrete pipe NP 2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	7.50	Per running metre	4001.90	30014.00	Rupees Thousand Only	Thirty Fourteen
6	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads , lifts and other incidentals as per direction of Engineer-in-charge.	20.49	Per cubic metre	4600.00	94254.00	Rupees Thousand Hundred Only	Forty Nine Two Fifty Four
7	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	18.00	Each	322.00	5796.00	Rupees Thousand Hundred Only	Five Seven Ninety Six
8	Back filling behind abutment , wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	5.45	Per cubic metre	1331.00	7254.00	Rupees Thousand Hundred Only	Seven Two Fifty Four
Total in Figure					235316.00	Rupees Two Lakh Thirty Five Thousand Hundred Only	Two Lakh Five Thousand Three Hundred Sixteen
Quoted Rate in Words		Rupees Two Lakh Thirty Five Thousand Three Hundred Sixteen Only					

Boa checked and approved for Rs. 2,35,316 Only:


Executive Engineer
Mandi Division No.-II
M.P.P.W.D. Mandi

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 231131.00
Earnest Money Rs:- 4700.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
Name of work:- A/R & M/O AE Office Building at Kotli. (SH:- Balance work of construction of Record room).

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Brick work using common burnt clay building bricks in foundation and plinth in cement mortar (one cement : four sand) including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer - in-charge.	6.61	Per cubic metre	8305.85	54902.00	Rupees Fifty Four Thousand Nine Hundred Two Only
2	15mm (fifteen millimetre) cement plaster in single coat on the fair side of brick /concrete /stone walls for interior plastering upto floor all level including arises, internal rounded angles, chamfers and /or rounded angles not exceeding 80mm (Eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement : six sand) including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer - in-charge.	86.85	Per square metre	224.55	19502.00	Rupees Nineteen Thousand Five Hundred Two Only
3	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade New work (two or more coats) over and including water thinnable priming coat with cement primer including carriage of materials with in all leads, lifts and other incidentals as per direction and entire satisfaction of Engineer - in-charge.	86.85	Per square metre	82.05	7126.00	Rupees Seven Thousand One Hundred Twenty Six Only
4	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundation or similar works and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	10.25	Per cubic metre	4915.25	50381.00	Rupees Fifty Three Thousand Eighty One Only

20015

5	Providing and laying Antiskid digital Ceramic glazed floor tiles of size 300x300 mm (three hundred into three hundred millimetre) of Johnson / Kajaria/ AGT Tiles / RAK/ Orient Bell or its equivalent (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White , Ivory, Grey, Fume Red Brown , laid on 20 mm (twenty millimetre) thick cement mortar 1:4 (one cement : four coarse sand) , Jointing with grey cement slurry @ 3.3 kg/sqm (at the rate of three point three kilogram per square metre) including pointing the joints with white cement and matching pigment etc ., complete including carriage of materials with in all leads , lifts and other incidentals as per direction of Engineer-in-charge .	10.25	Per cubic metre	944.40	9680.00	Rupees Thousand Only	Nine Six Eighty
6	Providing second class kiln seasoned deodar wood work of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia and length (hold fast lugs or dash fastener shall be paid for separately) complete within all leads, lifts carriage of material and other incidentals complete in all respect as per direction and satisfaction of Engineer-in-Charge.	0.12	Per cubic metre	98120.00	11774.00	Rupees Thousand Four Only	Eleven Seven Seventy
7	Providing and fixing panelled glazed or panelled and glazed shutters for doors, windows and clerestory windows including black enamelled iron but hinges with necessary screws including carriage of material within all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	2.00	Per square metre	4661.00	9322.00	Rupees Thousand Hundred Two Only	Nine Three Twenty
8	Providing and fixing 35mm (thirty five millimetre) thick second class teak wood wire gauge shutters using stainless steel grade 304 wire gauge of average width of aperture 1.4 mm (one point four millimetre) in both directions with wire of dia 0.50 mm (zero point five zero millimetre) , for doors , windows and clerestory windows with ISI marked MS pressed butt hinges bright finished of required size complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	2.00	Per square metre	2410.20	4820.00	Rupees Thousand Hundred Only	Four Eight Twenty
9	Providing and fixing aluminium work for doors , windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS : 733 and IS: 1285, fixing with dash fasteners of required dia and size , including necessary filling up the gaps at junctions , i.e. at top, bottom and sides with required EPDM rubber / neoprene gasket etc . Aluminium sections shall be smooth , rust free , straight, mitred and jointed mechanically wherever required including cleat angle , Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws , all complete as per architectural drawings and the directions of Engineer -in charge . For shutters of doors , windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (fittings, glazing, paneling and dash fasteners to be paid for separately) including carriage of materials within all leads and lifts and other incidentals.	31.49	Per kilo gram	635.60	20015.00	Rupees Thousand Only	Twenty Fifteen

Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections / appropriate Z sections and other sections of approved make conforming to IS : 733 and IS : 1285, fixing with dash fasteners of required dia and size , including necessary filling up the gaps at junctions , i.e. at top, bottom and sides with required EPDM rubber / neoprene gasket etc . Aluminium sections shall be smooth , rust free, straight, mitted and jointed mechanically wherever required including cleat angle , Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws , all complete as per architectural drawings and the directions of Engineer-in-charge. For shutters of doors , windows & ventilators including providing and fixing hinges / pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (fittings, glazing, paneling and dash fasteners to be paid for separately) including carriage of materials within all leads and lifts and other incidentals.	56.85	Per kilo gram	657.00	37350.00	Rupees Thirty Seven Thousand Three Hundred Fifty Only
11 Providing and fixing 4mm (four millimetre) glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket complete as per architectural drawings in all respect including carriage of material within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	2.79	Per kilo gram	410.20	1144.00	Rupees One Thousand One Hundred Forty Four Only
12 Providing and fixing wire gauge in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket complete as per architectural drawings and direction and satisfaction of Engineer-in-Charge. (Cost of aluminium snap beading shall be paid in basic item).	2.79	Per square metre	816.65	2278.00	Rupees Two Thousand Two Hundred Seventy Eight Only
13 Finishing painting wood work with Deluxe Multi Surface Paint of required shade . Two or more coat applied @ 0.90 ltr/10 sqm (at the rate of zero point nine zero litre per ten square metre) over an under coat of primer applied @0.75 ltr/10 sqm (at the rate of zero point seven five litre per ten square metre) of approved brand and manufacture including carriage of materials with in all leads , lifts and other incidentals.	4.08	Per square metre	107.00	437.00	Rupees Four Hundred Thirty Seven Only
14 Providing and fixing 300x16 mm (three hundred into sixteen millimetre) aluminium sliding door bolts , ISI marked anodised (anodic coating not less than grade AC 10 as per IS : 1868), transparent or dyed to required colour or shade , with nuts and screws etc . complete as per the directions and satisfactions of Engineer -in-Charge including carriage of materials with in all leads , lifts and other incidentals.	2.00	Each	205.75	412.00	Rupees Four Hundred Twelve Only
15 Providing and fixing aluminium handles , ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade , with necessary screws etc . complete including carriage of materials with in all leads , lifts and other incidentals as per direction of Engineer-in-charge. 125mm (one hundred twenty five millimetre).	12.00	Each	61.45	737.00	Rupees Seven Hundred Thirty Seven Only
16 Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade , with necessary screws etc . complete including carriage of materials with in all leads , lifts and other incidentals as per direction and entire satisfaction of Engineer-in-charge. 300x10mm (three hundred into ten millimetre)	12.00	Each	104.25	1251.00	Rupees One Thousand Two Hundred Fifty One Only

er Inviting Authority
of work

PERCENTAGE RATE BILL OF QUANTITY

[illegible]

	Rupees Two Lakh Thirty One Thousand One
	for Rs. 2,31,131 only.
	Boa checked and approved

Executive Engineer,
Mandi Division No.-II,
P. P. W. D. Mandi.

PERCENTAGE RATE BILL OF QUANTITY

Tender Inviting Authority:- Executive Engineer, Mandi Division No-II, H.P.P.W.D. Mandi.
Name of work:- Restoration of rain damages on Baggi to Sain road KM. 0/00 to 6/500 (SH)- C/O 900 mm dia hume pipe culvert alongwith both side wing walls at Rd 1/610) under PDNA 2025

Estimated Cost Rs.:- 229751.00
Earnest Money Rs.:- 4600/-
Time :- One Month

Contract No.:-
Bidder Name:-

PRICE SCHEDULE (This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)						
Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	Excavation of soil in Hilly area by mechanical means including dressing of sides and ramming of bottoms, upto any lift, including getting out the excavated soil and disposal of surplus excavated earth with a lift upto 1.5m, including carriage of material within all leads, lifts and other incidental charges complete in all respect as per direction and satisfaction of Engineer-in-Charge.	3.61	Per cubic metre	168.35	608.00	Rupees Six Hundred Eight Only
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	49.37	Per cubic metre	517.65	25556.00	Rupees Twenty Five Thousand Hundred Fifty Six Only
2	Providing and laying 1:4:8 (One cement : four sand : eight graded stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	3.36	Per cubic metre	4788.00	16088.00	Rupees Thousand Eight Only
3	Providing concrete for plain concrete 1:3:6 (One cement : Three sand : Six graded stone aggregate) Mechanically Mixed in open foundation and curing complete including form work as per drawings and technical specification Clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	10.06	Per cubic metre	4915.00	49445.00	Rupees Forty Nine Thousand Four Hundred Forty Five Only
4	Providing and laying 900mm dia (Nine hundred millimetre) reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 (one cement : two sand) but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets Clause 1108 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	7.50	Per running metre	4001.90	30014.00	Rupees Thirty Thousand Only
5	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	20.65	Per cubic metre	4600.00	94990.00	Rupees Ninety Four Thousand Hundred Ninety Only

6	Providing weepholes in brick masonry / stone masonry / plain / reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614.709.1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	18.00 Each	322.00	5796.00	Rupees Thousand Hundred Only	Five Seven Ninety Six
7	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204.3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	5.45 Per cubic metre	1331.00	7254.00	Rupees Thousand Hundred Only	Seven Two Fifty Four
Total in Figure				2,29,751.00	Rupees Two Lakh Twenty Thousand Seven Hundred Fifty One	
Quoted Rate in Words						

BoP approved for RS.229751-00 f

[Signature]
Executive Engineer,
Mandi Division No.-II,
H.P.W.D. Mandi.

[Signature]

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 191823.00
Earnest Money Rs:- 3900.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work:- Restoration of rain damages on Ratti Pull to Alathu Saini Mohari road KM. 0/00 to 6/500 (SH:- Construction of R/wall at RD 1/730 to 1/740) under PDNA 2025.

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	16.20	Per cubic metre	517.65	8386.00	Rupees Eight Thousand Three Hundred Eighty Six Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain /reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	34.50	Per cubic metre	4600.00	158700.00	Rupees One Lakh Fifty Eight Thousand Seven Hundred Only
3	Providing weepholes in brick masonry/ stone masonry / plain/ reinforced concrete abutment, wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204:3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	11.00	Each	328.00	3608.00	Rupees Three Thousand Six Hundred Eight Only
4	Back filling behind abutment, wing wall and return wall complete as per drawings and technical specifications clause 1204 3.8 Granular material complete within all leads, lifts carriage of material and other incidentals as per direction of Engineer-in-Charge.	15.30	Per cubic metre	1381.00	21129.00	Rupees Twenty One Thousand Hundred Twenty Nine Only

Total in Figure	191823.00	Rupees One Lakh Ninety Thousand Eight Hundred Three Only
Quoted Rate in Words	Rupees One Lakh Ninety One Thousand Eight Hundred Twenty Three Only	

Boa checked and approved for Rs. 1,91,823 only.


Executive Engineer,
Mandi Division No.-II,
H.P.W.D. Mandi.

158

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 182262.00
Earnest Money Rs:- 3700.00
Time :- One month

Tender Inviting Authority:- Executive Engineer, Mandi Division No-II, H.P.P.W.D. Mandi.

Name of work:- C/O Path near Dev Balakameshwar Temple Bari, Ward No.9 Mandi (H.P.) (SH:- C/O R/wall at RD 0/00 to 0/0/010) MC Deposit.

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	8.75	Per cubic metre	517.65	4529.00	Rupees Four Thousand Five Hundred Twenty Nine Only
2	Cutting in earth work in all kinds of soil such as pick work, jumper work, pick jumper work, pick jumper blasting work, jumper blasting work, blasting work (soft and hard rock) conglomerate rock including/ chiseling wedging out of rocks (where blasting is prohibited), saturated soil and their intermediate classification of soil including ramming and de-watering where required as per the geometrics, grades and levels shown on the drawings, including clearing of jungles uprooting of trees, vegetation, grass wood trees and sapling of all girth upto any heights/depths and removal of rubbish up to any distance outside the periphery of the area including stacking the useful material along the road side and disposal of all unserviceable materials through all modes of transportation with in all leads and lifts, as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	17.45	Per cubic metre	168.10	2933.00	Rupees Two Thousand Nine Hundred Thirty Three Only
3	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-charge.	36.60	Per cubic metre	4800.00	168360.00	Rupees One Lakh Sixty Eight Thousand Three Hundred Sixty Only

AMOUNT
all Taxes
ding GST in
words.

Eight
and Four
ad Twenty
, Only

es One Lakh
Two Thousand
Hundred Fifty

es Five
sand Two
dred Forty Eight
y

2418

4 Providing weepholes in brick masonry / stone masonry / plain/ reinforced concrete abutment , wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical isto twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614,709,1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.

Total in Figure

Quoted Rate in Words

20.00 Each	322.00	6440.00	Rupees Six Thousand Four Hundred Forty Only
		182262.00	Rupees One Lakh Eighty Two Thousand Two Hundred Sixty Two Only
Rupees One Lakh Eighty Two Thousand Two Hundred Sixty Two Only			

Boa checked and approved for Rs. 1,82,262/- only


Executive Engineer,
Mandi Division No.-II,
P.P.W.D.-Mandi.

AL AMOUNT
in all Taxes
including GST in
words.

7
es Eight
sand Four
ired Twenty
n Only

ees One Lakh
y Two Thousand
; Hundred Fifty
y

pees Five
ousand Two
ndred Forty Eight
nly

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 175825.00
Earnest Money Rs:- 3600.00
Time :- One month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.

Name of work:- RRD on Sain Gujra Ra Ropru road KM. 0/00 to 14/00. (SH:- C/O B/wall at RD 0/075 to 0/090) under PDNA 2025.

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto a lead of 50m (fifty metre), dressing of sides and bottoms and back filling in trenches with excavated suitable material in ordinary soil upto 3m (three metre) depth including entire carriage of material within all leads and lifts as per entire satisfaction and direction of Engineer-in-Charge.	16.28	Per cubic metre	517.65	8427.00	Rupees Eight Thousand Four Hundred Twenty Seven Only
2	Providing and laying 1:5:10 (One cement : five sand : ten graded crushed stone aggregate 40mm (Forty millimetre nominal size) concrete for plain/reinforced concrete in open foundations and curing complete including form work as per drawing and technical specification clauses 802, 803, 1202 and 1203 including carriage of materials with in all leads, lifts and other incidentals as per direction of Engineer-in-Charge.	35.25	Per cubic metre	4600.00	162150.00	Rupees One Lakh Sixty Two Thousand One Hundred Fifty Only
3	Providing weepholes in brick masonry / stone masonry / plain/ reinforced concrete abutment, wing wall, return wall with 100mm diameter (one hundred millimetre diameter) PVC pipe extending through the full width of the structures with slope of 1V:20H (one vertical into twenty horizontal) towards drawing face complete as per drawing and technical specifications clauses 614, 709, 1204.3.7 including carriage of material and other incidentals as per direction of Engineer-in-Charge.	16.00	Each	328.00	5248.00	Rupees Five Thousand Hundred Forty Eight Only

(19)

Total in Figure	175825.00	Rupees One Lakh Seventy Thousand Hundred Five Only
Quoted Rate in Words	Rupees One Lakh Seventy Five Thousand Eight Hundred Only	Twenty Five

BOQ checked and approved for Rs. 1,75,825 / only.



Executive Engineer,
Mandi Division No.-II,
H.P. P.W.D. Mandi.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 109522.00
Earnest Money Rs: 2200.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.II, HP.PWD, Mandi.

Name of work:- Restoration of rain damages on old suketi bridge and new Suketi bridge at Distt. Mandi (H.P.) (SubHead:- Providing and fixing steel work, repair of plaster and laying of cement concrete work etcetera) **Under PDNA 2025**

Contract No.:

Bidder Name:

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Steel work welded in built up sections/framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etcetra as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	259.20	Per kilo gram	125.60	32556.00	Rupees Thirty Two Thousand Hundred Fifty Six Only
2	Repairs to plaster of thickness 12 mm (twelve millimetre) to 20 mm (twenty millimetre) in patches of area 2.5 sqm. (two point five squaremeters) and under, including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls in cement mortar 1:4 (one cement : four sand), including disposal of rubbish to the dumping ground, complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	53.55	Per square metre	347.95	18633.00	Rupees Eighteen Thousand Hundred Three Only
3	Providing concrete for plain/reinforced concrete Grade-M-20 nominal mix 1:2:4 (one cement : two sand : four graded,crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 curing complete including the cost of form work within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	8.10	Per cubic metre	7053.15	57131.00	Rupees Fifty Seven Thousand Hundred Thirty One Only
4	White washing with lime to give an even shade on old work (two or more coats) including thoroughly brooming the surface to remove all dirt, dust mortar dirt and other foreign matter including carriage of material in all leads and lifts and other incidentals complete and as per the entire satisfaction and direction of Engineer-in-Charge.	67.50	Per square metre	17.80	1202.00	Rupees Thousand Hundred Two Only

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1.	2	3	4	5	6	7
Total in Figure					109522.00	Rupees One Lakh Nine Thousand Five Hundred Two Only
Quoted Rate in Words						

Bill of quantity checked and approved for Rs. 1,09,522/-
Rupees one lac nine thousand five hundred twenty two only

Executive Engineer,
Mandi Division No II,
P.W.D. Mandi

Draft Schedule of Quantity

Estimated Cost:- Rs. 39039.00
 Earnest Money:- Rs. 800.00
 Time:- One Month

Name of work:- Restoration of rain damages on Old PCM road at Distt. Mandi H.P.
 Sub Head:- Dismantling of encroached structure near Mahamritunjaya Temple as per Direction of Higher Authorities. Under PDNA 2025.

Sr. No.	Description of item	Qty.	Rate excluding GST		Unit	Amount
			In Figure	In Words		
	2	3	4	5	6	7
1	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	3.50	2092.00	Rupees Two Thousand Ninety Two Only	Per cubic metre	7322.00
2	Demolishing brick work in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	4.41	1212.95	Rupees One Thousand Two Hundred Twelve and Paise Ninety Five Only	Per cubic metre	5349.00
3	Dismantling doors, windows and clerestory windows (steel or wood) shutter of area 3 sq. metres (three squaremetre) and below including chowkhats, architrave, holdfasts etcetera complete and stacking including carriage of material in all leads and lifts and other incidentals complete and as per the entire direction and satisfaction of Engineer-in-Charge.	3.00	218.50	Rupees Two Hundred Eighteen and Paise Fifty Only	Each	656.00
4	Demolishing nominal cement concrete 1:4:8 (one cement : four sand : eight graded stone aggregate) or leaner mix (including equivalent design mix) manually/ by mechanical means including disposal of material complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	4.32	885.30	Rupees Eight Hundred Eighty Five and Paise Thirty Only	Per cubic metre	3824.00
5	Demolishing stone rubble masonry in cement mortar manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material complete within all leads, lifts carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge. Recovery of useful stone of 5.04 cum. (five point zero four cubic metre) @ (at the rate of) Rs. 800/- (eight hundred only) per cubic metre amounting to Rs. 4032/- only shall be done on prorata basis for the quantity of stone rubble masonry effected.	15.12	1447.60	Rupees One Thousand Four Hundred Forty Seven and Paise Sixty Only	Per cubic metre	21888.00
				Total:-		39039.00

*Draft schedule of quantity checked and approved for Rs. 39039/-
 (Rupees thirty nine thousand thirty nine) only.*

Executive Engineer,
 Mandi Division No. II,
 ABPWD Mandi

138

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 244968.00
 Earnest Money Rs:- 4900.00
 Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.-II, H.P.P.W.D. Mandi.
 Name of work :- C/O Jogni more to Gochra road KM. 0/00 to 1/00. (SH:- 5/7 mtr wide formation cutting road in KM. 0/206 to 0/251). VKVNY Deport

Contract No.:

Bidder Name:

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

Sr. No.	Item Description	Quantity	Units	Estimated Rate including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering wherever required setting out to the required line grades, side slopes trimming bottom and level as shown on the drawings as directed by Engineer-in-charge at site according to technical specification clause 1603.1 & 1603.2 sorting out useful/un useful materials and stacking the same in all leads and lift and transportation of the un-useful materials for filling in road ways, embankments for grades improvements and leveling to the required grade and then disposing of surplus excavated earth in acquired width of roads or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by all means (if any required). Recovery for useful stone of 39.29 cubic metre @ Rs. 300/- per cubic metre amounting to Rs.11,788.00/- only, shall be done on prorata basis for the quantity of cutting in earth work effected. Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all respect. Including all leads and lift of materials and as per direction of Engineer-in-charge.	982.35	Per cubic metre	249.37	244968.00	Rupees Two Lakh Forty Thousand Nine Hundred Eight Only

25

Total in Figure		244968.00	Rupees Two Lakh Forty Thousand Nine Hundred Eight Only
Quoted Rate in Words			Rupees Two Lakh Forty Four Thousand Nine Hundred Sixty Eight Only

BOQ checked and approved for Rs. 2,44,968/- only.


Executive Engineer,
Mandi Division No.-II,
H.P. P.W.D. Mandi.

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 438768.00
Earnest Money Rs: 8800.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.II, HP.PWD, Mandi.

Name of work:- Special repair of Nerchowk Pandoh bypass road (Section of NH-21) Km.198/145 to 203/500. (Sub Head :-Construction of drain, footpath over drain with precast RCC covers in RD 199/934 to 200/0 and 200/350 to 200/415.)

Contract No.:

Bidder Name:

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	24.38	Per cubic metre	550.00	13409.00	Rupees Thousand Hundred Thirteen Four Nine Only
2	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	11.22	Per cubic metre	2059.20	23104.00	Rupees Thousand Hundred Four Only
3	Removal of debris, muck etcetera from drain by mechanical means complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	13.37	Per cubic metre	150.15	2008.00	Rupees Thousand Eight Only
4	Providing and laying mechanically mixed and vibrated plain/reinforced cement concrete grade M-20 (twenty) in foundation and plinth and similar work curing complete including cost of form work as per drawing and Technical specification clause 802.803,1202 and 1203 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	34.19	Per cubic metre	6899.40	235890.00	Rupees Two Lakh Thirty Five Thousand Eight Hundred Ninety Only
5	Stone soling of selected hard dry stone hand packed tightly in footpath complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	11.81	Per cubic metre	1425.70	16838.00	Rupees Thousand Hundred Thirty Eight Only

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes excluding GST in words.
1	2	3	4	5	6
6	Providing and laying mechanically mixed and vibrated plain/reinforced concrete grade M-25 (twenty five) in sub-structure and similar work curing complete including cost of form work as per drawing and Technical specification clause 802.803, 1202 and 1203 complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction and satisfaction of Engineer-in-Charge.	8.12	Per cubic metre	7631.45	Rupees Sixty One Thousand Nine Hundred Seven Only
7	Steel reinforcement thermo-Mechanically Treated bars of grade Fe-500 (five hundred) D or more for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level including carriage of materials within all leads and lifts complete in all respect as per direction and satisfaction of Engineer-in-Charge.	793.04	Per Kilogram	90.45	Rupees Seventy One Thousand Seven Hundred Thirty Only
8	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etcetra as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge	107.52	Per Kilogram	128.55	Rupees Thirteen Thousand Eight Hundred Twenty Two Only
Total in Figure					Rupees Four Lakh Thirty Eight Thousand Seven Hundred Sixty Eight Only
Quoted Rate in Words					

Bill of quantity checked and approved for Rs. 438768/- (Rupees four lac thirty eight thousand seven hundred sixty eight) only.

Executive Engineer,
Mandi Division No. II,
M.P.W.D. Mandi

PERCENTAGE RATE BILL OF QUANTITY

Estimated Cost Rs:- 123945.00
Earnest Money Rs: 2500.00
Time :- One Month

Tender Inviting Authority:- Executive Engineer, Mandi Division No.II, HP.PWD, Mandi.

Name of work:- Annual repair and maintenance of M.R.B.U. road No. 70 to 3/835. (Sub Head :- Construction of V-shape drain at RD. 0/340 to 0/410).

Contract No.:

Bidder Name:

SCHEDULE OF WORKS

Sr. No.	Item Description	Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.
1	2	3	4	5	6	7
1	Earth work in excavation for structures for all kinds of soil as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal upto any lead, dressing of sides and bottoms and back filling in trenches with excavated suitable materials complete within all leads, lifts, carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	11.20	Per cubic metre	648.00	7258.00	Rupees Thousand Hundred Fifty Eight Only
2	Supplying, filling, spreading and leveling stone boulders of size range 5 cm(five centimetre) to 20 cm (twenty centimetre) , in recharge pit, in the required thickness, complete in all respect including carriage of materials within all leads and lifts as per direction and satisfaction of Engineer-in-Charge.	8.40	Per cubic metre	1601.85	13456.00	Rupees Thousand Hundred Fifty Six Only
3	Providing concrete for plain/reinforced concrete Grade-M-20 nominal mix 1:2:4 (one cement : two sand : four graded, crushed stone aggregate 20mm (twenty millimetre) nominal size) in open foundations complete as per drawings and technical specification clause 802, 803, 1202 & 1203 curing complete including the cost of form work within all leads, lifts carriage of material and other incidental complete in all respect as per direction of Engineer-in-Charge.	8.40	Per cubic metre	7333.60	61602.00	Rupees Thousand Hundred Sixty One Only
4	Construction of V-Shape Drain with mechanically mixed and vibrated plain cement concrete M-10 (ten) grade nominal mix 1:3:6 (one cement : three sand : six graded, crushed stone aggregate 20mm (twenty millimeter) nominal size) with thickness of concrete 10cm (ten centimeter) and size of drain 45 x 25cm (forty five centimetre into twenty five centimeter) and curing complete including cost of excavation and form work consisting as per standard drawing and HP.PWD. specifications including carriage of material within all leads, lifts and other incidentals as per the direction of Engineer-in-Charge complete in all respect.	70.00	Per running metre	594.70	41629.00	Rupees Thousand Hundred Nine Only

Item Description		Quantity	Units	Estimated Rate Rs. P.	TOTAL AMOUNT with all Taxes including GST in words.	TOTAL AMOUNT with all Taxes including GST in Rs. P.
1	2	3	4	5	6	7
Total in Figure					123945.00	Rupees One Lakh Twenty Thousand Three Hundred Forty Five Only
Quoted Rate in Words						Rupees One Lac twenty three thousand nine hundred forty five only

Bill of quantity checked and approved for Rs. 123945/-
(Rupees one lac twenty three thousand nine hundred forty five) only


Executive Engineer,
Mandi Division No. II,
P.W.D. Mandi.