



Office of Executive Engineer, Banjar Division ,
Himachal Pradesh Public Works Department Banjar 175123
Phone No.01903-221031 Fax: 01903-21031
No.PW/BD/CB/TA/Ten.Not/2026-9415-44

Dated:- 14-09-26


To

✓ The Chief Engineer (MZ)
HPPWD. Mandi -175001.

Subject :- Publishing of Notice Inviting Tenders / Advertisement.


Enclosed please find herewith Copy of Notice Inviting Tender for the up-loading on department website as per Notification No. PBW(B) A (3) 8/2025-3000858 Dated 13.11.2025 and as direction issued Vide Engineer-in-Chief, HPPWD., Shimla letter No. PWD/ICTWing/Website Dated-22.05.2026 as the works mentioned in the Notice are emergent nature and in the public interest.

Encl:- Notice


Executive Engineer,
Banjar Division ,
H.P.P.W.D. Banjar.

Copy forwarded to followings for information and necessary action.

The Engineer-in-Chief, HPPWD Shimla .
The Superintending Engineer 6th circle HPPWD Kullu.
All the Contractors enlisted in HPPWD.
The Superintendent, DAO ,HDM of this Office.
Notice Board


Executive Engineer,
Banjar Division,
H.P.P.W.D. Banjar

Himachal Pradesh
Public works Department

Notice Inviting Tender

Sealed Percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Banjar Division, HP, PWD, Banjar on behalf of Governor of H.P. from the eligible contractors enlisted in HP, PWD for the following works, so as to reach in this office on or before 23.09.2026 up to 11.00AM and the tender will be opened on the same day at 11.30 A.M in the presence of intending contractors or their authorized representatives. The tender forms can be had from this office against cash payment (non-refundable) up to 22.09.2026 at 4.00 PM. The application for issue of tender forms shall be received up to 4.00 PM on 21.09.2026.

The Earnest money in the shape of FDR/National Saving Certificate/Time deposit/Saving Account in any of the post office/Saving Bank Account of Nationalized Bank in HP duly pledged in favour of Executive Engineer, Banjar Division, HPPWD Banjar must be accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The offer of tender shall remain open for 75 days from the date of opening. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

All the contractors will have to bring with them attested copy of enlistment/ renewal/ exemption in earnest money. Contractor will be issued the tender forms only when they fulfill the terms and condition of form No. 6 & 8. Contractors should be registered under HP, Sales Tax Act. 1968/EPF/GST.

Sr.No.	Description of item	Estimated cost	EMD	Time	Cost of form
1	RRD on Sidhwan to Godigad road Km.0/0 to 8/0. (SH:- C/O Breast wall at RD- 2/680 to 2/697) (under PDNA)	411184	8300	Three Months	350/-
2	RRD on Sidhwan to Godigad road Km.0/0 to 8/00. (SH:- C/O Breast wall at RD- 2/640 to 2/662) (under PDNA)	410386	8300	Three Months	350/-
3	RRD on Sidhwan to Godigad road Km.0/0 to 8/00. (SH:- C/O PCC Toe wall a/w Retaining wall at RD-3/080 to 3/093) (under PDNA)	492407	10000	Three Months	350/-
4	RRD on Khundan to Shatyaugi road Km.0/0 to 6/500. (SH:-C/O PCC Retaining wall at RD- 1/360 to 1/377) (under PDNA)	394080	7900	Three Months	350/-
5	RRD on Jhiri to Airport Gate Bhunter road Km.253/790 to 258/440. (SH:- Repair of pot holes in Km, 255/200 to 255/250) (under PDNA)	458136	9200	Three Months	350/-
6	RRD on Jhiri to Airport Gate Bhunter road Km.253/790 to 258/440. (SH:- Repair of pot holes in Km, 255/300 to 255/350) (under PDNA)	318370	6400	Two Months	350/-
7	RRD on Approach road Govt. Degree College at Banjar Tehsil Banjar Distt. Kullu (HP). (SH:- C/O PCC Breast wall at RD-0/0 to 0/17.50 damaged during the disaster 2025) (Dep.)	485374	9800	Three Months	350/-
8	RRD on Approach road Govt. Degree College at Banjar Tehsil Banjar Distt. Kullu (HP). (SH:- C/O RCC U-shape drain college out side front back & both side at RD- 0/0 to 0/165 damaged during the disaster 2025) (Dep.)	495830	10000	Three Months	350/-
9	RRD on Neuli to Shansher road Km.0/0 to 14/00. (SH:- Removal of slips /Land slide at various reaches) (under PDNA)	497738	10000	Three Months	350/-
10	RRD on Gushaini to Pekhri road 0/0 to 9/060. (SH:- C/O PCC Toe wall alongwith Retaining wall at RD-1/750 to 1/762) (under PDNA)	423252	8500	Three Months	350/-
11	RRD on Naglari to Sarchi road 0/0 to 16/500. (SH:- C/O PCC Toe wall alongwith Retaining wall at RD- 1/550 to 1/557) (under PDNA)	321632	6500	Three Months	350/-
12	RRD on Sidhwan to Godigad road Km.0/0 to 8/00. (SH:- C/O PCC Toe wall a/w Retaining wall at RD-0/580 to 0/594) (under PDNA)	495452	10000	Three Months	350/-
13	RRD on Helipad work approach road to Dhameuli (Banjar) Distt. Kullu Km.0/0 to 2/115. (SH:- C/O 2.00 mtr. Span slab culvert at RD-0/270) (under PDNA)(Job No.1)	496029	10000	Three Months	350/-

14	RRD on Helipad work approach road to Dhameuli (Banjar) Distt. Kullu Km. 0/0 to 2/115. (SH:- C/O PCC Retaining wall at RD- 0/135 to 0/155) (under PDNA)	461331	9300	Three Months	350/-
15	RRD on Dhoru to Plach road Km. 0/0 to 5/0. (SH:- C/O PCC Retaining wall at RD- 4/566 to 4/580) (under PDNA)	423885	8500	Three Months	350/-
16	RRD on Jibhi Bahu Gadagushaini road Km. 0/0 to 20/0. (SH:- C/O PCC Retaining wall at RD- 15/150 to 15/160) (under PDNA)	442485	8900	Three Months	350/-

TERMS AND CONDITIONS :-

The contractors/Bidders must quote their PAN/Income Tax Number/Sale Tax number(TIN number)/EPF No./GST No. on the tender along with the copy of the same be attached with the application. The contractor/Firms should attach copy of registration/Renewal with the application, Contractor/Bidder are advised to visit and examine the site where the work are to be carrying out and its surrounding. The contractors/Bidders should quote his rates Both in figure and words. Where there is any discrepancy between the rates in figure and in words. The rates in words will be governed. Contractors/Bidders must inspect the site to ascertain/familiar the site condition accessibility etc. Before quoting the bid/tender. Conditional and telegraphic tenders shall not be accepted and rejected straightway. Tenders received after due date and time will be rejected. Executive Engineer reserves the right to reject or all tenders without assigning any reason. Certified that tender of above works are being called for emergent nature in exigency and in the public interest.


Executive Engineer
Banjar Division,
HP,PWD, Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sidhwan to Godgad road Km. 0/00 to 8/00.
(SH :-Construction of Breast wall at RD.2/680 to 2/697),(Under PDNA).

Estimated Cost:- Rs.411184/- only.
Earnest Money :-Rs.8300/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation soil in hilly area by manual means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	75.39	Cubic Metre.	333.65	Rupees three hundred thirty three paise sixty five only.	Per cubic metre.	25154.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.20	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	12384.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	40.00	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	200890.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	41.04	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	172756.00
						Total:-	411184.00

Total in words :-Four lac eleven thousand one hundred eighty four only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Sidhwan to Godigad road Km. 0/00 to 8/00.
(SH :-Construction of Breast wall at RD.2/640 to 2/662).(Under PDNA).

Estimated Cost:- Rs.410386/- only.
Earnest Money :-Rs.8300/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation soil in hilly area by manual means including cutting and trimming of side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with in all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	73.00	Cubic Metre.	333.65	Rupoes three hundred thirty three paise sixty five only.	Per cubic metre.	24356.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.20	Cubic Metre.	533.81	Rupoes five hundred thirty three paise eighty one only.	Per cubic metre.	12384.00
3	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.	40.00	Cubic Metre.	5022.25	Rupoes five thousand twenty two paise twenty five only.	Per cubic metre.	200890.00
4	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge.	41.04	Cubic Metre.	4209.45	Rupoes four thousand two hundred nine paise forty five only.	Per cubic metre.	172756.00
						Total:-	410386.00

Total in words :-Four lac ten thousand three hundred eighty six only.

Percentage %


Executive Engineer
Banjar Division
HPPAWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on sidhwan to Godigad road Km. 0/00 to 8/00.
(SH :- Construction of PCC Toe wall alongwith Retaining wall at RD.3/080 to 3/093).(Under PDNA).

Estimated Cost:- Rs.492407/- only.
Earnest Money :-Rs.10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carrriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	42.31	Cubic Metre.	533.01	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	22586.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.64	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	17277.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carrriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	70.20	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	426576.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1% (v)20(H) towards draining face complete as per drawing and technical specifications clause 614.709,1206.6 including hauling/ carrriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	33.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	13797.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carrriage of all labour equipment and materials to various location through, with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	8.58	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	12171.00
						Total:-	492407.00

Total in words :- Four lac ninety two thousand four hundred seven only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Estimated Cost:- Rs.394080/- only.
Earnest Money :-Rs.7900/- only.
Time :- Three Month.

Name of Work:- Restoration of rain damages on Khundan to Shatyangi road km. 0/00 to 6/500.
(SH :-Construction of PCC Retaining wall at RD.1/360 to 1/377) (PDNA).

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidents to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various locations through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	34.59	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	18464.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.76	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	22593.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	53.55	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	325401.00
4	Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment/wing wall/return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (1V:20H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	28.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	11707.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/carryage of all labour equipment and materials to various locations through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	11.22	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	15915.00
Total in words :- Four lac ninety four thousand eighty only.							394080.00

Percentage %


Engineer
Banjar Division
HPPAVD Banjar.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Jhiri to Airport Gate Bhunter Km. 253/790 to 258/440.
(SH :-Repair of pot holes in Km. 255/200 to 255/250).(under PDNA).

Estimated Cost:- Rs.458136/- only.
Earnest Money :-Rs.9200/- only.
Time :-Two Month.

Sr.N o.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
				Figures	Words		
1	Providing and applying tack coat with Bitumen emulsion (RS-1) of HPCL/BPCL using emulsion distributor at the rate of 0.275 kg (Zero Point two hundred seventy five killogram) per Square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.complete including hauling/ carriage of materials, labour and equipments to various location through all modes of transportation within all leads and lifts and other incidentals and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	518.37	Square Metre	35.15	Rupees thirty five paise fifteen only.	Per Square metre	18221.00
2	Providing and laying bituminous macadam with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	14.8	Cubic metre	13311.85	Rupees thirteen thousand three hundred eleven paise eighty five only.	Per Cubic metre	197015.00
3	Providing, laying and rolling Bitumen concrete 25 mm thick with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed swtone aggregates of specified grading, premixed with bituminous binder (VG-30)@ 5.4 to 5.6 percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause no. 509 complete in all respects including hauling carriage of all labour and equipments and material to various locations through all modes of transports by mechanical mean with in all leads and lifts of material complete as per entire satisfaction & direction of Engineer-in-Charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	13.88	Square Metre	17500.00	Rupees seventeen thousand five hundred only.	Per Square metre	242900.00
						Total:-	458136.00

Total in words :-Four lac fifty eight thousand one hundred thirty six only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Jhiri to Airpot Gate Bhunter Km. 253/790 to 258/440.
(SH :-Repair of pot holes in Km. 255/300 to 255/350).(under PDNA).

Estimated Cost:- Rs.318370/- only.
Earnest Money :-Rs.6400/- only.
Time :-Two Month.

Sr.N o.	Description of items	Quantity		Rate with all taxes excluding GST			Unit	Amount
				Figures	Words			
1	Providing and applying tack coat with Bitumen emulsion (RS-1) of HPCL/BPCL using emulsion distributor at the rate of 0.275 kg (Zero Point two hundred seventy five killogram) per Square metre on the prepared dry and hungry bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503.complete including hauling/ carriage of materials, labour and equipments to various location through all modes of transportation within all leads and lifts and other incidentals and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	365	Square Metre	35.15	Rupees thirty five paise fifteen only.		Per Square metre	12830.00
2	Providing and laying bituminous macadam with 100-120 TPH hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 501.7 to achieve the desired compaction.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.95	Cubic metre	13311.85	Rupees thirteen thousand three hundre eleven paise eighty five only.		Per Cubic metre	145765.00
3	Providing, laying and rolling Bitumen concrete 25 mm thick with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed swtone aggregates of specified grading, premixed with bituminous binder (VG-30)@ 5.4 to 5.6 percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause no. 509 complete in all respects including hauling carriage of all labour and equipments and material to various locations through all modes of transports by mechanical mean with in all leads and lifts of material complete as per entire satisfaction & direction of Engineer-in-Charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	9.13	Square Metre	17500.00	Rupees thousand seven hundred only.		Per Square metre	159775.00
							Total:-	318370.00

Total in words :-Three lac eighteen thousand three hundred seventeen only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

7

DRAFT SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Approach road Govt. Degree College at Banjar Tehsil
Banjar Distt. Kullu (HP).

(SH :- Construction of PCC Breast wall at RD. 0/00 to 0/17.50 damaged during the disaster 2025) (Deposit).

Estimated Cost:- Rs.485374/- only.
Earnest Money :-Rs.9800/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all Taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation soil in hilly area by manual means including cutting and trimming at side slopes and disposal of excavated earth with lift up to 1.5 m and a lead up to 20 m any as per drawing and technical specification clause 1603.1 all kind of soil with all leads and lifts to the entire satisfaction as per direction of Engineer-in-Charge including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	60.81	Cubic Metre.	333.65	Rupees three hundred thirty three paise six only.	Per cubic metre.	20289.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	19.25	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	10276.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1-3-6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	71.75	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	435995.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1% (1 in 100) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	45.00	Each	418.09	Rupees four hundred eighteen paise nine only.	Each	18814.00
						Total:-	485374.00

Total in words :- Four lac eighty five thousand three hundred seventy four only.

Percentage%


Executive Engineer
Banjar Division
HPPWD Banjar.

8

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Govt Degree College at Banjar Tehsil Banjar Distt Kullu (H.P.).
(SH :- Construction of RCC U-Shape drain collage out side fornt back & both side Km. 0/00 to 0/165) damaged during the disaster 2025. (Deposit).

Estimated Cost:- Rs.495830/- only.

Earnest Money :-Rs.10000/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2	2475	Cubic Metre.	1434.00	Rupees one thousand four hundred thirty four only.	Per cubic metre.	35492.00
2	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bulking out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road side to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6930	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	36993.00
3	Providing and laying cement concrete for plain concrete in open foundation 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and sub structure of retaining walls, Breast walls and parapets etc. complete as per drawings and HP PWD, specification/MORD technical specification section and clause 800.1202 and 1203 and curing complete including the cost of form work and hauling / carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	1155	Cubic Metre.	5258.89	Rupees five thousand six hundred eighty one paise ninety only.	Per cubic metre.	60740.00
4	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.10	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	140369.00
5	Supplying, fitting and placing HYSD bar reinforcement in foundation complete as per drawing and technical specification clause 1303.3. including hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	2149.28	Kg	103.40	Rupees one lakh three thousand four hundred three only.	Per kg	222236.00
						Total:-	495830.00
						Total in words :- Four lac ninety five thousand eight hundred thirty only.	

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Neuli to Shansher road Km. 0/00 to 14/00.
(SH :- Removal of slips / Land Slide at various reaches).(Under PDNA).

Estimated Cost:- Rs.497738/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful material shall be stacked along the road side as per direction of Engineer-in-Charge.	3750.85	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	497738.00
Total in words :-Four lac ninety seven thousand seven hundred thirty eight only.							Total:- 497738.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Gushani to Pekhari road Km. 0/00 to 9/060.
(SH :-Construction of PCC Toe wall alongwith Retaining wall at RD.1/750 to 1/762),(Under PDNA).

Estimated Cost:- Rs.423252/- only.
Earnest Money :-Rs.8500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures		Words			
		3	4	5	6		
1	2 Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard water (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carrriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	44.94	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	23989.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	5.88	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	27910.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carrriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	21.60	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	131254.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carrriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	22.94	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	115210.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carrriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the government but excluding GST.	27.00	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	113655.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carrriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.92	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	11234.00
Total in words :-Four lac twenty three thousand two hundred fifty two only.						Total:-	423252.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Naglari to Sarchi road Km. 0/00 to 16/500.
(SH :- Construction of PCC Toe wall alongwith Retaining wall at RD.1/550 to 1/557).(Under PDNA).

Estimated Cost:- Rs.321632/- only.
Earnest Money :-Rs.6500/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST	Unit	Amount
		Figures	Words			
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3	4	5	7	8
1		32.31	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	17247.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.01	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	14287.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	31.30	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	190197.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	12.73	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	63933.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.20	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	30308.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.99	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	5660.00
					Total:-	321632.00

Total in words :- Three lac twenty one thousand six hundred thirty two only.

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar.

12

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on sidewalk to Godigad road Km. 0/00 to 8/00.
(SH :-Construction of PCC Toe wall alongwith Retaining wall at RD.0/580 to 0/594).(Under PDNA).

Estimated Cost:- Rs.495452/- only.
Earnest Money :-Rs.10000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST	Unit		Amount
		3	4	5	6	7	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	44.25	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	23621.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.02	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	28574.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	31.50	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	191412.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	21.86	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	109786.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	31.20	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	131335.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.56	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	10724.00
						Total:-	495452.00

Total in words :-Four lac ninety five thousand four hundred fifty two only.

Percentage %


 Executive Engineer
 Banjar Division
 HPPWD Banjar.

13

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Helipad with approach road to Dhameuli (Banjar) Distt. Kullu Km 0/00 to 2/115.
(SH :- Construction of 2.00 mtr Span Slab Culvert at RD. 0/270)(under PDNA) (Job No.1).

Estimated Cost:- Rs.496029/- only.
Earnest Money :-Rs.10000/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST	Unit		Amount
		3	4	5	6	7	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in- charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	78.85	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	8.00 42091.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification &MORD technical specification and curing complete including the cost of form work and hauling/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.91	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	32799.00
3	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clause 702,704,1202 and 1204 in cement mortar 1:5 (one cement: five sand) within all leads and lift of materials and as per direction of Engineer-in- charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	67.18	Cubic Metre.	6268.81	Rupees seven thousand two hundred seventy paise fifty five only.	Per cubic metre.	421139.00
						Total:-	496029.00

Total in words :-Four lac ninety six thousand twenty nine only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Helipad with approach road to Dhameuli (Banjar) Distt. Kullu Km 0/00 to 2/115.
(SH :- Construction of PCC Retaining wall at RD.0/135 to 0/155) (under PDNA).

Estimated Cost:- Rs.461331/- only.
Earnest Money :-Rs.9300/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, levelling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg- and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and unserviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	38.70	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	20658.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	5.60	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	26581.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	63.00	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	382825.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1% (v):20(H) towards draining face complete as per drawing and technical specifications clause 614.709,1206.6 including hauling/carryage of all labour equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	30.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	12543.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carryage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	13.20	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	18724.00
						Total:-	461331.00

Total in words :-Four lac sixty one thousand three hundred thirty one only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Dhoru to Plach road Km. 0/00 to 5/00.
(SH :- Construction of PCC Retaining wall at RD.4/566 to 4/580),(Under PDNA).

Estimated Cost:- Rs.423885/- only.
Earnest Money :-Rs.8500/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and hauling out and the excavation shall be kept dry whenever so required by the contractor at his own cost. including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other Incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in- charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	40.67	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	21710.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.62	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	21929.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	58.10	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	353049.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20(H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	28.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	11707.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carryage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.92	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	15490.00
						Total:-	423885.00

Total in words :-Four lac twenty three thousand eight hundred eighty five only.

Percentage %

Executive Engineer
Banjar Division
HPPWD Banjar.

16

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jibhi Bahu Gadagushaini road Km. 0/00 to 20/00.
(SH :-Construction of PCC Retaining wall at RD.15/150 to 15/160),(Under PDNA).

Estimated Cost:- Rs.442485/- only.
Earnest Money :-Rs.8900/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST	Words		Unit	Amount
		3	4		5	6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades , side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles,agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects,including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	37.05	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	19778.00	
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification &MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.30	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	15664.00	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	64.00	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	388901.00	
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	21.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	8780.00	
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carryage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.60	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	9362.00	
Total in words :-Four lac forty two thousand four hundred eighty five only.							Total:-	442485.00

Percentage %


Executive Engineer
Banjar Division
IPPWD Banjar.