



Office of Executive Engineer, Banjar Division ,
Himachal Pradesh Public Works Department Banjar 175123

Phone No.01903-221031 Fax: 01903-21031

No.PW/BD/CB/TA/Ten.Not/2026-9540-69 Dated: 16-9-2026

To

✓ The Chief Engineer (MZ)
HPPWD. Mandi -175001.

Subject :-

Publishing of Notice Inviting Tenders /Advertisement.

Enclosed please find herewith Copy of Notice Inviting Tender for the up-loading on department website as per Notification No. PBW(B) A (3) 8/2025-3000858 Dated 13.11.2025 and as direction issued Vide Engineer-in-Chief, HPPWD., Shimla letter No. PWD/ICTWing/Website Dated-22.05.2026 as the works mentioned in the Notice are emergent nature and in the public interest.

Encl:- Notice

Executive Engineer,
Banjar Division ,
H.P.P.W.D. Banjar.

Copy forwarded to followings for information and necessary action.

The Engineer-in-Chief, HPPWD Shimla .

The Superintending Engineer 6th circle HPPWD Kullu.

All the Contractors enlisted in HPPWD.

The Superintendent, DAO ,HDM of this Office.

Notice Board

Executive Engineer,
Banjar Division,
H.P.P.W.D. Banjar

Himachal Pradesh
Public works Department

Notice Inviting Tender

Sealed Percentage rate tender on form No. 6 & 8 are hereby invited by the Executive Engineer, Banjar Division, HP, PWD, Banjar on behalf of Governor of H.P. from the eligible contractors enlisted in HP, PWD for the following works, so as to reach in this office on or before 25.09.2026 up to 11.00AM and the tender will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender forms can be had from this office against cash payment (non-refundable) up to 24.09.2026 at 4.00 PM. The application for issue of tender forms shall be received up-to 3.00 PM on 23.09.2026.

The Earnest money in the shape of FDR/National Saving Certificate/Time deposit/Saving Account in any of the post office/Saving Bank Account of Nationalized Bank in HP duly pledged in favour of Executive Engineer, Banjar Division, HPPWD Banjar must be accompany with each tender. Conditional tender and the tender received without earnest money will summarily be rejected. The offer of tender shall remain open for 75 days from the date of opening. The undersigned reserves the right to reject any or all the tenders without assigning any reasons.

All the contractors will have to bring with them attested copy of enlistment/ renewal/ exemption in earnest money. Contractor will be issued the tender forms only when they fulfill the terms and condition of form No. 6 & 8. Contractors should be registered under HP, Sales Tax Act. 1968/EPF/GST.

Sr.No.	Description of item	Estimated cost	EMD	Time	Cost of form
1	RRD on Jibhi Bahu Gadagushaini road Km.0/0 to 20/0. (SH:- C/O PCC Retaining wall at RD-15/161 to 15/171) (under PDNA)	441503	8900	Three Months	350/-
2	RRD on Jibhi Bahu Gadagushaini road Km.0/0 to 20/0. (SH:- C/O PCC Retaining wall at RD- 15/390 to 15/403) (under PDNA)	491986	9900	Three Months	350/-
3	RRD on Thatibir to Sheuli Jouri road Km.0/0 to 9/500. (SH:- C/O PCC Toe wall a/w Retaining wall at RD-0/210 to 0/226) (under PDNA)	431573	8700	Three Months	350/-
4	RRD on Manglore to Panihar road Km.0/0 to 8/0. (SH:-C/OPCC Toe wall alongwith Retaining wall at RD- 2/200 to 2/208.50) (under PDNA)	415196	8400	Three Months	350/-
5	RRD on Khundan to Shatyaugi road Km.0/0 to 6/500. (SH:- Construction of Hume Pipe culvert 900mm dia at RD- 1/565) (under PDNA)	245623	5000	Three Months	350/-
6	RRD on Khundan to Shatyaugi road Km.0/0 to 6/500. (SH:- Construction of Hume Pipe culvert 900mm dia at RD- 1/100) (under PDNA)	127250	2600	Three Months	350/-
7	RRD on Jhiri to Airport Gate Bhunter road Km.253/790 to 258/440. (SH:- Providing and laying WBM -III for repair of Pot Holes Km.255/200 to 255/300) (under PDNA)	321445	6500	Two Months	350/-
8	RRD on Approach road Govt. Degree College at Banjar Tehsil Banjar Distt. Kullu (HP). (SH:- C/O PCC Retaining wall at RD- 0/018 to 0/028 damaged during the disaster 2025) (Dep.)	470080	9500	Three Months	350/-
9	RRD on Naglari to Sarchi road Km.0/0 to 16/500. (SH:- C/O PCC Toe wall alongwith R/wall at RD 1/557.50 to 1/564) (under PDNA)	288034	5800	Three Months	350/-
10	RRD on Gushaini to Pekhri road 0/0 to 9/060. (SH:- C/O Hume Pipe Culvert 900mm dia at RD- 2/215) (under PDNA)	250725	5100	Three Months	350/-
11	RRD on Helipad with approach road to Dhameuli (Banjar) Distt. Kullu Km.0/0 to 2/115. (SH:- C/O PCC Retaining wall at RD 0/157 to 0/166.50) (under PDNA)	494632	9900	Three Months	350/-
12	RRD on Helipad with approach road to Dhameuli (Banjar) Distt. Kullu Km.0/0 to 2/115. (SH:- C/O U-shape drain at Km.0/020 to 0/100) (under PDNA)	281632	5700	Three Months	350/-

13	RRD on Garsa to Khora aage road Km.0/0 to 6/0. (SH:- C/O PCC wire crated alongwith R/wall at RD-5/666 to 5/680) (under PDNA)	398192	8000	Three Months	350/-
14	RRD on Garsa to Khora aage road Km.0/0 to 6/0. (SH:- C/O PCC wire crated alongwith R/wall at RD-5/650 to 5/665.50) (under PDNA)	440517	8900	Three Months	350/-
15	Restoration of demolition potion of Ayush SOWA Rigpa Hospital at Bajaura Distt. Kullu HP. (SH:- C/O PCC Toe wall for protection of footing damaged due to flood along the river Beas as RD-0/00 to 0/010 damaged during the disaster 2023)	400168	8100	Three Months	350/-
16	Restoration of demolition potion of Ayush SOWA Rigpa Hospital at Bajaura Distt. Kullu HP. (SH:- C/O PCC Toe wall for protection of footing damaged due to flood along the river Beas as RD-0/010 to 0/020 damaged during the disaster 2023)	409195	8200	Three Months	350/-
17	RRD on Spangni to Kandha Km.0/0 to 9/900 . (SH:- Removal of slips/Land slide at various reaches) (under PDNA)	499907	10000	Three Months	350/-
18	RRD on Sainj Ghat Parganoo road Km.0/0 to 9/00 . (SH:- Removal of slips/Land slide at various reaches) (under PDNA)	492129	10000	Three Months	350/-

TERMS AND CONDITIONS :-

The contractors/Bidders must quote their PAN/Income Tax Number/Sale Tax number(TIN number)/EPF No./GST No. on the tender along with the copy of the same be attached with the application. The contractor/Firms should attach copy of registration/Renewal with the application, Contractor/Bidder are advised to visit and examine the site where the work are to be carrying out and its surrounding. The contractors/Bidders should quote his rates Both in figure and words. Where there is any discrepancy between the rates in figure and in words. The rates in words will be governed. Contractors/Bidders must inspect the site to ascertain/familiar the site condition accessibility etc. Before quoting the bid/tender. Conditional and telegraphic tenders shall not be accepted and rejected straightway. Tenders received after due date and time will be rejected. Executive Engineer reserves the right to reject or all tenders without assigning any reason. Certified that tender of above works are being called for emergent nature in exigency and in the public interest.

Executive Engineer
Banjar Division,
HP,PWD, Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jibhi Bahu Gadagushaini road Km. 0/00 to 20/00.
(SH :- Construction of PCC Retaining wall at RD.15/161 to 15/171). (Under PDNA).

Estimated Cost:- Rs.441503/- only.
Earnest Money :-Rs.8900/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution or disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	38.40	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	20498.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D. specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.30	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	15664.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	64.00	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	388901.00
4	Providing weep holes in brick masonry / stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1% (v) 20 (H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	21.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	8780.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	5.40	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	7660.00
						Total:-	441503.00

Total in words :- Four lac forty one thousand five hundred three only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Jibhi Bahu Gadagushaini road Km. 0/00 to 20/00.
(SH :- Construction of PCC Toe wall alongwith Retaining wall at RD.15/390 to 15/403).(Under PDNA).

Estimated Cost:- Rs.491986/- only.
Earnest Money :-Rs.9900/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all Taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock, hard rock (Requiring blasting), hard rock (blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, aggs. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	47.06	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	25121.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.37	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	30235.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803, 1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	29.25	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	177740.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702, 704, 1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.76	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	119329.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	30.00	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	126284.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	9.36	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	13277.00
						Total:-	491986.00

Total in words :- Four lac ninety one thousand nine hundred eighty six only.

Percentage %


 Executive Engineer
 Banjar Division
 HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Thatiber to Sheuli Jouri road Km. 0/00 to 9/500.
 (SH :-Construction of PCC Toe wall alongwith Retaining wall at RD.0/210 to 0/226),(Under PDNA).

Estimated Cost:-Rs.431573/- only.
 Earnest Money :-Rs.8700/- only.
 Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles,agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carrriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	46.68	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	24918.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D-specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.88	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	32656.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carrriage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	14.50	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	88110.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carrriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.44	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	117722.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carrriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	37.20	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	156592.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carrriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	8.16	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	11575.00
Total in words :-Four lac thirty one thousand five hundred seventy three only.							431573.00

Percentage %

Executive Engineer
 Banjar Division
 HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Mangalore to Panthar road Km. 0/00 to 8/00.
(SH :- Construction of PCC Toe wall alongwith Retaining wall at RD.2/200 to 2/208.50).(Under PDNA).

Estimated Cost:- Rs.415196/- only.
Earnest Money :-Rs.8400/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		Figures	Words	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3	4	5	6	7	8
		35.23	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	18806.00
2	Providing and laying concrete for plain/reinforced concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.12	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	29049.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	18.95	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	115151.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702,704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	25.94	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	130277.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	26.96	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	113487.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	5.94	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	8426.00
		Total in words :- Four lac fifteen thousand one hundred ninety six only.		Total:-		415196.00	

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Khundan to Shatyaugi road km. 0/00 to 6/500.
(SH :-Construction of Hume pipe culvert 900 mm dia at RD.1/565),(under PDNA).

Estimated Cost:- Rs.245623/- only.
Earnest Money :-Rs.5000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax or any other Taxes imposed by the Government but excluding GST.	55.71	Cubic Metre	533.81	Rupees five hundred thirty three paise eighty one only.	7	8.00 29739.00
2	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clause 702.704,1202 and 1204 in cement mortar 1:5 (one cement: five sand) including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.59	Cubic Metre	6268.81	Rupees six thousand two hundred sixty eight paise eighty only.	Per cubic metre	41311.00
3	Providing and laying reinforced cement concrete pipe WP3 (900mm dia for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work and back filling and concrete work in head wall and parapets clause 1106. Including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.50	Running metre	4423.95	Rupees four thousand four hundred twenty three paise ninety five only.	Per Running metre.	28756.00
4	Providing and laying of dry rubble flooring complete as per drawings and technical specification clause 1303.3 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	1.17	Cubic Metre	2325.85	Rupees two thousand three hundred twenty five paise eighty five only.	Per cubic metre	2721.00
5	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.86	Cubic Metre	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre	32561.00
6	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704,1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	11.94	Cubic Metre	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre	59966.00
7	Construction of dry rubble stone masonry for retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation. with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.80	Cubic Metre	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre	45462.00
8	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.60	Cubic Metre	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre	5107.00
						Total:-	245623.00

Total in words :-Two lac forty five thousand si hundred twenty three only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Khundan to Shatyaugi road km. 0/00 to 6/500.
(SH:-Construction of Hume pipe culvert 900 mm dia at RD.1/100)(under PDNA).

Estimated Cost:- Rs.127250/- only.
Earnest Money :-Rs.2600/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount	
		3	4	Figures	Words			
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock-hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earths in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	26.30	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	7 Per cubic metre.	8.00 14039.00	
2	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clause 702.704.1202 and 1204 in cement mortar 1:5 (one cement: five sand) including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	2.83	Cubic Metre.	6268.81	Rupees six thousand hundred sixty eight paise eighty only.	Per cubic metre.	17741.00	
3	Providing and laying reinforced cement concrete pipe NP3 (900mm dia for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work and back filling and concrete work in head wall and parapets clause 1106. including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.50	Running metre.	4423.95	Rupees four thousand two hundred twenty three paise ninety five only.	Per Running metre.	28756.00	
4	Providing and laying of dry rubble flooring complete as per drawings and technical specification clause 1303.3 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	1.17	Cubic Metre.	2325.85	Rupees two thousand three hundred twenty five paise eighty five only.	Per cubic metre.	2721.00	
5	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification &MORD technical specification and curing complete including the cost of form work and including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.65	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	17325.00	
6	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.68	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	46668.00	
Total in words :-One lac twenty seven thousand two hundred fifty only.							Total:-	127250.00

Percentage %


Executive Engineer
Banjar Division
HPPAWD Banjar.

SCHEDULE OF QUANTITY

Name of work :- Restoration of rain damages on Jhiri to Airport Gate Bhunter Km. 253/790 to 258/440.
(SH :-Providing and laying WBM-III for repair of Pot Holes km. 255/200 to 255/300)

Estimated Cost:- Rs.321445/- only.
Earnest Money :-Rs.6500/- only.
Time :- Two Month.

Sr.N o.	Description of items	Quantity	Rate with all taxes excluding GST		Unit	Amount
			Figures	Words		
1	Providing,laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 KN in stages proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading III as per Technical specification Clause 405. (By Mechanical means) including hauling/carriage of materials, labour and equipments to various location through all modes of transportation within all leads lifts and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	93.75	3428.75	Rupees two thousand nine hundred fifty nine paise twenty only.	Per Square metre	321445.00
Total in words :-Three lac twenty one thousand four hundred forty five only.						321445.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Approach road Govt. Degree College at Banjar Tehsil Banjar Distt. Kullu (HP).

Estimated Cost:- Rs. 470080/- only.

(SH :-Construction of PCC Retaining wall at RD. 0/018 to 0/028 damaged during the disaster 2025) (Deposit).

Earnest Money :-Rs.9500/- only.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST Figures	Time :- Three Month.		Unit	Amount
		3	4		Words	6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles,agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in- charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	45.85	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	24475.00	
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification &MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana,Toll Tax, or any other Taxes imposed by the Government but excluding GST.	4.30	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	20410.00	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	65.60	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	398624.00	
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20(H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	32.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	13379.00	
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carryage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	9.30	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	13192.00	
Total in words :-four lac seventy thousand Eighty only.							Total:-	470080.00

Total in words :-four lac seventy thousand Eighty only.

Percentage %

Executive Engineer,
Banjar Division

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Naglari to Sarchi road Km. 0/00 to 16/500.

(SH :- Construction of PCC Toe wall alongwith Retaining wall at RD.1/557.50 to 1/564). (Under PDNA).

Estimated Cost:- Rs.288034/- only.

Earnest Money :-Rs.5800/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST Figures	Words	Unit	Amount
		3	4				
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost . including dressing of slopes and beds setting out conforming to required lines, grades , side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in- charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	30.00	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	16014.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification &MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	2.80	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	13290.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	29.26	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	177801.00
4	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.54	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	52935.00
5	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation, with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	5.40	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise fourty five only.	Per cubic metre.	22731.00
6	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.71	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	5263.00
						Total:-	288034.00

Total in words :-Two lac eighty eight thousand thirty four only.

Total in words :- Two lac eighty eight thousand thirty four only.

Percentage %

Executive Engineer
Banjar Division
HPPWD Bangur

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Gushani to Pekhari road Km. 0/00 to 9/060.
(SH :-Construction of Hume pipe culvert 900 mm dia at RD. 2/215)(under PDNA).

Estimated Cost:- Rs.250725/- only.
Earnest Money :-Rs.5100/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST Figures	Unit		Amount
		3	4		Words	7	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and hauling out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	57.46	Cubic Metre.	533.81	Rupees five hundred thirty three hundred eighty one only.	Per cubic metre.	8.00 30673.00
2	Stone masonry in cement mortar for sub structure complete as per drawing and technical specification clause 702.704.1202 and 1204 in cement mortar 1:5 (one cement: five sand) including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.59	Cubic Metre.	6268.81	Rupees six thousand two hundred sixty eight paise eighty only.	Per cubic metre.	41311.00
3	Providing and laying reinforced cement concrete pipe NP3 (900mm dia for culverts on 1st class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation protection work and back filling and concrete work in head wall and parapets clause 1106. including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	7.50	Running metre.	4423.95	Rupees four thousand four hundred twenty three paise ninety five only.	Per Running metre.	33180.00
4	Providing and laying of dry rubble flooring complete as per drawings and technical specification clause 1303.3 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	1.17	Cubic Metre.	2325.85	Rupees two thousand three hundred twenty five paise eighty five only.	Per cubic metre.	2721.00
5	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand : twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawing and H.P.P.W.D specification & MORD technical specification and curing complete including the cost of form work and including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.86	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	32561.00
6	Random rubble stone masonry in cement mortar 1:6 (one cement: six sand) for sub structure as per drawing and technical specification of Ministry of Rural Development for Rural road clause 702.704.1202 and 1204 including carriage of all labour equipment and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	11.94	Cubic Metre.	5022.25	Rupees five thousand twenty two paise twenty five only.	Per cubic metre.	59966.00
7	Construction of dry rubble stone masonry for Retaining walls, breast walls, revetment walls and parapets etc for sub-structure and super structure complete as per drawing and technical specification of Ministry of Rural Development for Rural road clause 704.6 and 1302.5 including hauling/ carriage of all labour equipment and materials to various location through all modes of transportation with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.80	Cubic Metre.	4209.45	Rupees four thousand two hundred nine paise forty five only.	Per cubic metre.	45462.00
8	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.42	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	4851.00
						Total:-	250725.00

Total in words :- Two lac fifty thousand seven hundred twenty five only.

Percentage %


Executive Engineer
Banjar Division
HPPWD Bagar.

11

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Helpad with approach road to Dhameuli (Banjar) Distt. Kullu Km 0/00 to 2/115.
(SH :-Construction of PCC Retaining wall at RD.0/157 to 0/166.50),(under PDNA).

Estimated Cost:- Rs.494632/- only.
Earnest Money :-Rs.9900/- only.

Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures	Words		
1	2 Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.including hauling/carrriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in- charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	39.09	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	20867.00
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.P.W.D.specification & MORD technical specification and curing complete including the cost of form work and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3.70	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	17562.00
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carrriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	71.62	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	435205.00
4	Providing weep holes in brick masonry / stone masonry/ plain reinforced concrete abutment/wing wall/return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1% (1:100) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carrriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	28.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	11707.00
5	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carrriage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	6.55	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	9291.00
						Total:-	494632.00

Total in words :-Four lac ninety four thousand six hundred thirty two only.

Percentage %


Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Helipad with approach road to Dhameuli (Banjar) Distt. Kulhu Km 0/00 to 2/115.
(SH : Construction of U-shape drain at Km. 0/020 to 0/100) (Under PDNA).

Estimated Cost:- Rs.281632/- only.
Earnest Money :-Rs.5700/- only.

Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST Figures	Words		Unit	Amount
		3	4		5	6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades , side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other Incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.Including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	104.00	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	55516.00	
2	Providing and laying cement concrete for plain/reinforcement concrete 1:6:12 (One cement : Six sand :twelve graded stone aggregate 40mm (forty millimetre nominal size) mechanically mixed in open foundations and plinths complete as per drawings and H.P.W.D.specification &MORD technical specification and curing complete including the cost of form work and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	10.00	Cubic Metre.	4746.53	Rupees four thousand seven hundred forty six paise fifty three only.	Per cubic metre.	47465.00	
3	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	29.40	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	178651.00	
Total in words :-Two lac eighty one thousand six hundred thirty two only.								281632.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of rain damages on Garsa to Khora aage road Km. 0/00 to 6/00.
(SH :-Construction of PCC wire crated alongwith Retaining wall at RD. 5/666 to 5/680),(Under PDNA).

Estimated Cost:- Rs.398192/- only.
Earnest Money :-Rs.8000/- only.
Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST Figures	Unit		Amount
		3	4		5	6	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rockhard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials such as stone shingles, egg and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carriage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	42.00	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	22420.00
2	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802.803.1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carriage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	23.52	Cubic Metre.	6076.58	Rupees six thousand seventy six paise fifty eight only.	Per cubic metre.	142921.00
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire confirming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carriage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	65.66	Cubic Metre.	2843.20	Rupees two thousand eight hundred forty three paise twenty only.	Per cubic metre.	186685.00
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	28.42	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	40313.00
5	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1 v:20 (H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	14.00	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	5853.00
Total in words :-Three lac ninety eight thousand one hundred ninety two only.		Total:-		398192.00			

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Garsa to Khora aage road Km. 0/00 to 6/00.
(SH :- Construction of PCC wire crated alongwith Retaining wall at RD.5/650 to 5/665.50)(Under PDNA).

Estimated Cost:- Rs.440517/- only.
Earnest Money :-Rs.8900/- only.
Time :- Three Month.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST	Unit	Amount
		3	4	Figures	Words	
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials, such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects including hauling/carryage of materials and labour equipment to various location through all modes of transportation within all leads and lifts of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	46.50	Cubic Metre.	533.81	Per cubic metre.	24822.00
2	Providing concrete for plain reinforced concrete in open foundation complete as per drawing and technical specification clause 802,803,1202 and 1203 1:3:6 (one cement : three sand : six graded stone aggregate graded stone aggregate 40mm (forty millimetre nominal size) including the cost of form work and curing complete and hauling/carryage of all labour, equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	26.04	Cubic Metre.	6076.58	Per cubic metre.	158234.00
3	Providing and laying of boulder upon laid in wire crates with 4mm (four millimetre) dia G-I wire conforming to IS 280 and IS 4826 in 100mmx100mm (one hundred millimetre x one hundred millimetre) mesh woven diagonally including ten percent extra for laps and joints laid with stone boulder weighting not less than 25 kg (twenty five kilogramme) each as per drawing and technical specification clause 1301 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	72.50	Cubic Metre.	2843.20	Per cubic metre.	206132.00
4	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carryage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	31.47	Cubic Metre.	1418.49	Per cubic metre.	44640.00
5	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20 (H) towards draining face complete as per drawing and technical specifications clause 614,709,1206.6 including hauling/ carryage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	16.00	Each	418.09	Each	6689.00
Total in words :- Four lac forty thousand five hundred seventeen only.						440517.00

Percentage %


Executive Engineer
Banjar Division
HPTWID Banjar.

SCHEDULE OF QUANTITY

Name of Work:-Restoration of Demolition prortion of Ayush Sowa Rigpa Hospital at Bahaura Distt.Kullu (H.P).
 (SH :-Construction of PCC Toe wall for protection of footing damaged due to flood along the river beas at RD. 0/00 to 0/010).
 Estimated Cost:- Rs.400168/- only.
 Earnest Money :-Rs.8100/- only.
 Time :- Three Month.

Sr. No	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock/hard rock (Requiring blasting, hard rock/blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost. Including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, aggs and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	54.45	Cubic Metre.	533.81	Rupees five hundred thirty three paise eighty one only.	Per cubic metre.	8.00 29066.00
2	Providing and laying Concrete for plain /reinforced concrete 1:2:4 (one cement: two sand: four graded stone aggregate) in open foundation complete as per drawing and technical specifications clause 802.803.1202 and 1203.PCC Grade M-20 including haulage/carrriage of all labour equipments and materials to various locations through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	50.09	Cubic Metre	6687.35	Rupees six thousand six hundred eighty seven paise thirty five only.	Per cubic metre.	334969.00
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	13.86	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	19660.00
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment/wing wall/return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope off (v)20(H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	39.40	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	16473.00
Total in words :-Four lac one hundred sixty eight only.							400168.00

Percentage %


 Executive Engineer
 Banjar Division
 HPPWD Banjar.

16

SCHEDULE OF QUANTITY

Name of Work:- Restoration of Demolition portion of Ayush Sowa Riepa Hospital at Bahaura Distt. Kullu (H.P.)
(SH :- Construction of PCC Toe wall for protection of footing damaged due to flood along the river beas at RD. 0/010 to 0/020 damaged during the disaster 2023. (Deposit).

Estimated Cost:- Rs.409195/- only.
Earnest Money :- Rs.8200/- only.

Sr. No	Description of Items	Quantity		Rate with all taxes excluding GST		Unit	Amount	
		Time :- Three Month.		Rate with all taxes excluding GST				
		Figures	Words	Figures	Words			
1	Excavation in earth work for structure in all heights and depths in all kinds of soil including ordinary rock,hard rock (Requiring blasting), hard rock(blasting prohibited), marshy soil and their intermediate classification. If water is met due to stream flow, seepage, rain and other causes it shall be removed by suitable diversion, pumping and bailing out and the excavation shall be kept dry whenever so required by the contractor at his own cost, including dressing of slopes and beds setting out conforming to required lines, grades, side slopes as shown in the drawing and as per direction of Engineer-in-charge and transportation of soil to road way after back filling and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites including its stacking, leveling and dressing in all leads and lifts through all modes of transportation including head load animal load or mechanical means or other incidentals to complete the work as per technical specifications clause 305.1. All useful materials,such as stone shingles, agg. and slates shall be sorted out and stacked along road sides to the maximum possible extent in all leads and lifts. Any loss to the public and private property during the course of execution of disposal of serviceable and un-serviceable materials shall be absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	3 54.45	4 Cubic Metre.	5 533.81	6 Rupees five hundred thirty three paise eighty one only.	7 Per cubic metre.	8.00 29066.00	
2	Providing and laying Concrete for plain/reinforced concrete 1:2:4 (one cement: two sand: four graded stone aggregate) in open foundation complete as per drawing and technical specifications clause 802.803.1202 and 1203.PCC Grade M-20 including haulage/carryage of all labour equipments and materials to various locations through all modes of transportations in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge. The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	50.09	Cubic Metre	6687.35	Rupees six thousand six hundred eighty seven paise thirty five only.	Per cubic metre.	334969.00	
3	Back filling behind abutment wing wall and return wall complete as per drawing and technical specification of Ministry of Rural Development for rural road clause 1204.3.8 including hauling/ carriage of all labour equipment and materials to various location through,with in all leads and lift of materials and as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	20.46	Cubic Metre.	1418.49	Rupees one thousand four hundred eighteen paise forty nine only.	Per cubic metre.	29022.00	
4	Providing weep holes in brick masonry /stone masonry/ plain reinforced concrete abutment,wing wall,return wall with 100 mm (one hundred millimetre) dia PVC pipe extending through the full width of the structure with slope of 1:20(H) towards draining face complete as per drawing and technical specifications clause 614.709.1206.6 including hauling/ carriage of all labour, equipments and materials to various location through all modes of transportation in all leads and lifts to the entire satisfaction as per direction of Engineer-in-charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	38.60	Each	418.09	Rupees four hundred eighteen paise nineteen only.	Each	16138.00	
Total in words :-Four lac nine thousand one hundred ninety five only.							Total:-	409195.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sapangni to Kandha road Km. 0/00 to 9/900.
(SH :- Removal of slips / Land Slide at various reaches).(Under PDNA).

Estimated Cost:- Rs.499907/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along the road side as per direction of Engineer-in-Charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3767.20	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	499907.00
Total in words :-Four lac ninety nine thousand nine hundred seven only.							499907.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar

18

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sainj Ghat Parganoo road Km. 0/00 to 9/00.
(SH :- Removal of slips / Land Slide at various reaches). (Under PDNA).

Estimated Cost:- Rs.498129/- only.
Earnest Money :-Rs.10000/- only.
Time :-Three Month.

Sr.No.	Description of items	Quantity		Rate with all taxes excluding GST		Unit	Amount
		3	4	Figures 5	Words 6		
1	Removal of slips/land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slope and disposal of material with in all lift upto any lead as per technical specification. Any loss to the public property or any accidents etc .During the execution of work the contractor will be fully responsible. The fuel/POL charges and operational staff for the machine will be provided by the owner. The repair and other incidental charges of machinery will be borne by the contractor. The useful meterial shall be stacked along,the road side as per direction of Engineer-in-Charge.The rate is including octroi, Royalty, Malkana, Toll Tax, or any other Taxes imposed by the Government but excluding GST.	3753.80	Cubic Metre.	132.70	Rupees one hundred thirty two paise seventy only.	Per cubic metre.	498129.00
Total in words :-Four lac ninety eight thousand one hundred twenty nine only.							498129.00

Percentage %


Executive Engineer
Banjar Division
HPPWD Banjar