

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

No.PWD/JMD/CB/Tender/2026-27:- 599- 613

Dated:- 11/09/26

To

The Chief Engineer (KZ)
Dharmshala HP,PWD
Dharamshala

Subject:- Tender notice

Sir,

Enclosed kindly find herewith the tender notice for the various works as given in the notice inviting tender for uploading on Department website as per notification of Principal Secretary (PWD) to the Govt. of HP vide NO PBW(B)A(3) 1/2024 dated 03.01.2024 as the works mentioned in the notice inviting tender are ugent / emergent nature of works in public interest.

DA/As above


Executive Engineer,
Jawaamukhi Division/HPPWD.,
Jawalamukhi.

Endst. No.PWD/JMD/CB/Tender/2025-26:-

Dated:-

Copy forwarded to the following:-

- 1 The FC-Cum Secy. (PW) to the Govt. of HP Shimla-2
- 2 The Engineer-in-Chief, HPPWD., Shimla.
- 3 The Superintending Engineer, Dehra Circle HP.PWD. Dehra
- 4 All the Executive Engineers under North Zone.
- 5 All the Assistant Engineers under Dehra Division.
- 6 The Deputy Commissioner Kangra at Dharamshala.
- 7 The SDM/Tehsildar/President NAC Jawalamukhi.
- 8 Notice Board.


Executive Engineer,
Jawalamukhi DivisionHP.PWD.,
Jawalamukhi

P. P. W. D. TENDER

Sealed item rate tenders on the fom 6&8 are invited by the Executive Engineer Jawalamukhi Division HPPWD., Jawalamukhi on behalf of the Governor of HP for the following works from the approved and eligible contractors (C&D Class) enlisted in HPPWD.

TENDER SCHEULE

1. Date and time of receipt of application for tender form: 21.09.2026 upto 12.00 AM
2. Date and time of issue of tender form: 21.09.2026 upto 2.00 PM
3. Date and time of receipt of tenders: 22.09.2026 upto 11.00 AM
4. Date and time of opening of tenders: 22.09.2026 at 11.30 AM

The tender forms will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Jawalamukhi Division HPPWD Jawalamukhi must accompany with each tender.

Job No.	Name of work	Estimated cost	Earnest money	Time limit
1	C/O Link Road to House of Subhash Chand shivpur km 0/000 to 0/100 (SH:- Construction of Cement Concrete pavement at Km 0/000 to 0/035 (BSP/2024/71)	Rs 83,699/-	Rs 2,000/-	One month
2	C/O Link Road to House of Ramesh Chand Lower Tikker km 0/000 to 0/200 (SH:- Construction of Cement Concrete pavement at Km 0/000 to 0/035 (BSP/2024/72)	Rs 83,919 /-	Rs 2,000/-	One month
3	Construction of Pacca path main road Kalru to Matyal Dadwal House G.P.Sehorpiyan Tehsil Jawalamukhi Distt Kangra (H.P.) (SH:- Providing and Laying Interlocking Paver Block Pavement at RD-000 to 0/065 (SDP/2022/907)	Rs 1,63,480 /-	Rs 2000/-	One month
4	Restoration of rain Damages on(i) Baroh Chowk Dehrian jandrah Talli Tikka Lagru Dolla Khryana Khundian Nahallian road at Km 9/135 to 35/300 (ii) Baggi Lagru road at Km 0/000 to 4/000 (SH:-Unlined drains in Various RDs.)	Rs 84,490/-	Rs 2,000/-	One month
5	Restoration of rain damages on sapri to pankhar road at Km 0/000 to 24/800 (SH:- Resoration of Roadway/Carriageway.	Rs 87,540/-	Rs 2,000/-	One month
1	The contractors/firms should possess the following documents(Photocopy to be attached): (i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.) (iii) Registration under HP GST/ (TIN No.). (iv) EPF(Employee Provident Fund Account No.) (v) GST registration			


Executive Engineer
Jawalamukhi Division HP, PWD
Jawalamukhi Distt Kangra H.P.
on behalf of Governor of Himachal Pradesh

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 83,699.00

Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name Of work:-C/O Link Road to House of Subhash Chand shivpur km 0/000 to 0/100 (SH:- Construction of Cement Concrete pavement at Km 0/000 to 0/035 (BSP/2024/71)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains of soil in all kinds of soils . soft and hard rocks and saturated soil . de-watering. including wedging out rocks where blasting work is prohibited . chiseling or any other mixed variety of soil. including shoring, strutting or bailing out water upto any depth or any height quantum of water including de -watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as per direction of Engineer -in-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths . sides of foundation etcetera consolidating each deposited layer by ramming . watering and then disposing of all excavated earth including carriage of material within all leads . lifts and other incidentals as per approved drawing . design and as directed by the Engineer -in-charge The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	21.43 Cubic meter	245.00	Two Hundred Forty Five Rupees	Per Cubic meter	5,250.00
2	Providing and laying cement concrete for plain / reinforced concrete in . open foundation complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. PCC Grade (M-20) (M-Twenty) nominal mix 1:2:4 (One cement: Two sand: Four Graded/crushed stone aggregate) 20mm and curing complete as per drawing and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads . lifts and other incidentals. The rates including Royalty, Malkana, Octroi, toll tax, sale tax or any other taxes imposed by the Government but excluding GST.	16.01 Cubic metre	4900.00	Four Thousand Nine Hundred Rupees	Per Cubic metre	78,449.00
Total						83,699.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

DMT No - Percentage Bill of Quantity
Checked & Approved for Rs 83,699/-

Executive Engineer,
Jawalamukhi Division,
PPWD Jawalamukhi.

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 83,919.00
 Earnest Money :-Rs. 2,000.00

Time Limit :- One Month.

Name Of work:-C/O Link Road to House of Ramesh Chand Lower Ticker km 0/000 to 0/200 (SH:- Construction of Cement Concrete pavement at Km 0/000 to 0/035 (BSP/2024/72)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains of soil in all kinds of soils, soft and hard rocks and saturated soil, de-watering, including wedging out rocks where blasting work is prohibited, chiseling or any other mixed variety of soil, including shoring, strutting or bailing out water upto any depth or any height quantum of water including de-watering removal of slush and stacking the serviceable and un-serviceable material clear from the edge of excavation as per direction of Engineer -in-Charge and returning the stacked soil in 15cm (Fifteen centimeter) layers, when required into plinths, sides of foundation etcetera consolidating each deposited layer by ramming, watering and then disposing of all excavated earth including carriage of material within all leads, lifts and other incidentals as per approved drawing, design and as directed by the Engineer -in-charge. The rate is inclusive of octroi, royalty, Malkana, Toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	21.45 Cubic meter	255.00	Two Hundred Fifty Five Rupees	Per Cubic meter	5,470.00
2	Providing and laying cement concrete for plain / reinforced concrete in, open foundation complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. PCC Grade (M-20) (M-Twenty) nominal mix 1:2:4 (One cement: Two sand: Four Graded /crushed stone aggregate) 20mm and curing complete as per drawing and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkana, Octroi, toll tax, sale tax or any other taxes imposed by the Government but excluding GST.	16.01 Cubic metre	4900.00	Four Thousand Nine Hundred Rupees	Per Cubic metre	78,449.00
Total						83,919.00
		% Above/below				
		Quoted Amount in Figures				
		Quoted Amount in Words				

DNIT NO - Percentage Bill of Quantity sheet
 Approved for Rs 83,919/-

Executive Engineer,
 Jawalamukhi Division,
 HPPWD Jawalamukhi.

JOB NO: 4403

PERCENTAGE BILL OF QUANTITY

Estimate Cost :- Rs 1,63,480.00

Earliest Money :- Rs. 4,000.00

Time Limit :- One Month.

(H.P.)

Name Of work:-Construction of Pacca path main road Kalru to Matyal Dadwal House G.P.Sehorplan Tehsil Jawalamukhi Distt Kangra (H.P.)
(SH:- Providing and Laying Interlocking Paver Block Pavement at RD-000 to 0/065 (SDP/2022/907)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
1	Providing and laying ISI marked factory made chamfered edge Cement Concrete paver blocks having thickness 60 mm of M -30 grade with approved color design and pattern in footpath, parks, lawns, drive ways or light traffic parking etc. of required strength, thickness & size/ shape, made by table vibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper embedding /laying of inter locking paver blocks into the sand bedding layer through vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand complete as per the direction and the entire satisfaction of Engineer -in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government but excluding GST.	167.50	780.00	Seven Hundred Eighty Rupees	Per Square Metre	130650.00
2	Providing and laying cement concrete for plain / reinforced concrete in, open foundation complete as per drawing and technical specifications clause 802, 803, 1202 & 1203. PCC Grade (M-20) (M-Twenty) nominal mix 1:2:4 (One cement : Two sand : Four Graded /crushed stone aggregate) 20mm and curing complete as per drawing and the entire satisfaction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidentals. The rates including Royalty, Malkhana, Octroi, toll tax, sale tax or any other taxes imposed by the Government but excluding GST.	6.70	4900.00	Four Thousand Nine Hundred Rupees	Per Cubic metre	32830.00
Total						1,63,480.00
					% Above/below	
					Quoted Amount in Figures	
					Quoted Amount in Words	

DNIT No - Percentage Bill of Quantity checked
Approved for Rs 1,63,480.00

Executive Engineer,
Jawalamukhi Division,
HPWD Jawalamukhi.

Name of work:- Restoration of rain Damages on(i) Baroh Chowk Dehrian jandrah Talli Tikka Lagru Dolla Khryana Khundian Nahallian road at Km 9/135 to 35/300 (ii) Baggi Lagru road at Km 0/000 to 4/000 (SH:-Unlined drains in Various RDs.)

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Construction of unlined surface drains of average cross sectional area 0.40 sqm in soil to specified lines, grades levels and dimension. Excavated material to be used in embankment with a lift upto 3m and lead of 50m (average lead 25m) as per Technical Specification Clause 307. (Manual Means) and the entire satisfaction of Engineer-in-Charge, including carriage of material with in all leads lifts and other incidentals. The rates including Royalty, Malkana, Octroi, Toll tax, Sale tax or any other taxes imposed by the Government but excluding GST.	1420.00 Running Metre	59.50	Fifty Nine Rupees Fifty Paise	Per Running Metre	84,490.00
Total						84,490.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

DDT rate - Percentage 1% of Quantity

Amount in Words	
DNIT No - Percentage	Bill of Quantity
Checked & Approved for Rs 84,430/-	

Executive Engineer,
Jawalamukhi Division,
HPPVD Jawalamukhi.

JOB NO:-05

Earnest Money :-Rs. 2,000.00

Name of work:- Restoration of rain damages on sapri to pankhar road at Km 0/000 to 24/800 (SH:- Restoration of Carriage/Carriageawy.

Sr. No.	Description of Item	Quantity	Rate in		Unit	Amount
			Figures	Words		
3	Removal of Land Slide in Hilly area ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with all leads and lifts as per direction of the Engineer-in-charge as per HPPWD specification as per HPPWD Specification, including carriage of all labour equipments and materials to various location through all modes of transportation in all leads of, lifts and other incidentals. The rate is including Royalty, Malkana, Octroi, toll tax, sales tax or any other taxes imposed by the Government but excluding GST.	729.50 Cubic Metre	120.00	One Hundred Twenty Rupees	Per Cubic metre	87,540.00
	Total					87,540.00
	% Above/below					
	Quoted Amount in Figures					
	Quoted Amount in Words					

Unit in Words
DNT No - Percentage Bill of Quantity checked & approved for Rs 87,500/-

Executive Engineer,
Jawalamukhi Division,
FPPWD Jawalamukhi.