

Himachal Pradesh
Public Works Department

No. PWP/Agr. Asstt./Tender/2026/ 11095-11114

Dated/ 12-10-2026

To

The Chief Engineer (KZ),
HP.PWD Dharamshala.

Subject:- Publication of Tender Notice.

Enclosed please find herewith Tender Notice of works as given in the Notice inviting Tenders alongwith schedule of quantities for uploading on departmental website as per directions received through e-mail dated 22.05.2026 of worthy Engineer-in-Chief, HP.PWD Nigam Vihar Shimla

It is certified that the work mentioned in the Notice inviting tenders are urgent in nature and in Public interest.

DA/ Stated as above

~~Executive Engineer~~
~~Palampur Division~~
~~HPPWD Palampur~~


Copy along with copy of Tender Notice is forwarded to the following for information and necessary action:-

1. The Superintending Engineer, 5th Circle, HPPWD., Palampur.
2. The Drawing /Accounts Branch in this office.
3. All Assistant Engineers working under this division.
4. Notice Board.

Executive Engineer
Palampur Division
HPPWD Palampur

CERTIFICATE

Certified that the tenders invited vide this office
NIT No. PWP/ Agr. Asstt/ NIT/ 2026/- 11095-1114
Dated 12-10-26 are urgent in nature and in public interest.


Executive Engineer
Palampur Division
HPPWD Palampur

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
'NOTICE INVITING TENDERS'**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Palampur Division HP.PWD., Palampur on behalf of the Governor of H.P for the following work from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under the H.P General Sales Tax Act 1968 so as to reach in his office on or before **19.10.2026** up to 11.00 AM. And the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender documents can be had from his office against cash payment (Nonrefundable) on 17.10.2026 up to 4.00 P.M and the application for issue of tender form shall be received 16.10.2026 up to 12.00 noon.

The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons.

S.No.	Name of work.	Estimated Cost.	Earnest Money	Time Limit
1	Restoration of rain damages on Spedu to Goarth road (SW:- C/o R/Wall at RD 1/310 to 1/315 & 1/340 to 1/345 (PDNA-2025)	Rs. 4,22,580.00	Rs. 8,500.00	Three Months
2	Restoration of rain damages on Spedu to Goarth road (SW:- C/o R/Wall at RD 1/319 to 1/332 (PDNA-2025)	Rs. 4,22,561.00	Rs. 8,500.00	Three Months
3	Link road Chowki Patwar khana Kesar Bag Colony road (SW:- P/L GSB, GII, G III & CC Pavement from RD 0/850 to 0/966.30 (PDNA-2025)	Rs. 4,23,548.00	Rs 8,500.00	Three Months
4	Link road Chowki Patwar khana Kesar Bag Colony road (SW:- P/L GSB, GII, G III & CC Pavement from RD 1/150 to 1/265 (PDNA-2025)	Rs. 4,23,007.00	Rs 8,500.00	Three Months
5	Restoration of rain damages on Palampur to Lohna Langha road (SW:- C/o 6.00 mtrs Span RCC Culvert (LHS abutment work (Near Sai Garden) (PDNA-2025)	Rs. 3,56,417.00	Rs 7,100.00	Three Months
6	C/o U-Shape drain alongwith grating from PCCN Chowk towards Butail Chowk (SW:- C/o U-shape drain 0/400 to 01/454.10 (MC Deposit)	Rs. 84,470.00	Rs 1,700.00	Three Months
7	Restoration of rain damages on Link road Bandla Ghuggar Thakurdwara road (SW:- P/L Bituminous Concrete on both side berm 1/095 to 1/170 & CC on both side berms at RD 1/350 to 1/433 (PDNA-2025)	Rs. 3,51,086.00	Rs 7,000.00	Three Months
8	Restoration of Rain damages on Palampur to Lohna Langha road (SW:- C/o 6.00 mtrs Span RCC Culvert (RHS Abutment) (Near Sai Garden) (PDNA-2025)	Rs. 3,54,637.00	Rs 7,100.00	Three Months
9	C/o link road Toran to Katoch Basti KM 0/00 to 0/200 (SW:- C/o 3.00 mtr Span Culvert (MMGSY)	Rs. 84,156..00	Rs. 1,700.00	Three Months
10	C/o link road Toran to Katoch Basti KM 0/00 to 0/200 (SW:- C/o 3.00 mtr Span Culvert (MMGSY)	Rs. 83,975.00	Rs. 1,700.00	Three Months

11	Restoration of Rain damages on Link road Kandi to Thalla Malenta road Km 0/00 to 4/500 (SW:- C/o R/Wall at RD 3/580 to 3/594) (PDNA-2025)	Rs. 2,11,511.00	Rs 4,200.00	Three Months	
12	Restoration of rain damages on Dharaman to Kandwari road 0/00 to 5/000 (SW:- C/o CC Pavement RD 4/100 to 4/130 & U-shape drain with E/Wall (PDNA-2025)	Rs. 1,74,968.00	Rs. 3,500.00	Three Months	
13	Restoration of rain damages on Dharaman to Kandwari road 0/00 to 5/00 (SW:- C/o 1.00 mtrs Span RCC Slab Culvert at RD 4/780 (PDNA-2025)	Rs. 2,47,998.00	Rs. 5,000.00	Three Months	
14	Restoration of rain damages on Palampur to Lohna Langha road (SW:- C/o R/Wall 0/075 to 0/08/2, P/L Stone Soling & P/L Cement Concrete 0/030 to 0/105 (Near Panchayat Ghar Om Prakash House (PDNA-2025)	Rs. 2,71,028.00	Rs. 5,400.00	Three Months	
15	Restoration of rain damages on Link road Ghuggar to Nachhir (SW:- C/o Retaining Wall from 2/450 to 2/2/461.10 (PDNA-2025)	Rs. 84,261.00	Rs. 1,700.00	Three Months	
16	Restoration of rain damages on link road from Ghuggar Nallah Haar via Mansimbal (SW:- P/L Cement Concrete Pavement 0/090 to 0/119, 0/130 to 0/158.80 (PDNA-2025)	Rs. 1,68,699.00	Rs. 3,400.00	Three Months	
17	Construction of Indoor Stadium (Multipurpose Skill Development Centre) at Palampur Tehsil Palamplur (SW:- Geotechnical Investigation and preparation of Toplograpical Survey)	Rs. 84,718.00	Rs. 1,700.00	Three Months	
18	Restoration of Rain damages on Dharamshala Yol Dadh Holta Chadiyar Sandhole road Km 33/00 to 40/500 (SW:- C/o U-shape drain at RD 39/100 to 39/188, R/Wall at RD 39/250 to 39/260 (PDNA-2025)	Rs. 2,62,919.00	Rs. 5,700.00	Three Months	
19	Restoration of rain damages on Spedu to Goarth road (SW:- C/o Edge Wall in Km 1/400 to 1/500 & P/L CC Pavement at RD 1/385 to 1/500 (PDNA-2025)	Rs. 4,20,567.00	Rs. 8,400.00	Three Months	
20	Restoration of rain damages on Kand to Tikkar via Kalohi Mata (SW:- P/L CC Pavement at RD 0/540 to 0/780, 1/00 to 1/032 and C/o U-shape drain at RD 1/00 to 1/032 (PDNA-2025)	Rs. 1,57,110.00	Rs. 3,100.00	Three Months	
21	Restoration of rain damages on Kaloond to Balehar Road Km 0/00 to 2/500 (SW:- P/L Interlocking Tile at RD 0/000 to 0/015 ,C/o U-shape drain at RD 0/800 to 0/880, V-Shape drain at RD 2/100 to 2/204 & R/Wall at RD 2/140 to 2/151) (PDNA-2025)	Rs. 3,17,695.00	Rs. 6,400.00	Three Months	

22	C/o Jeepable road from Main road Sh. Karam Chand house towards Sh. Atma Ram house Ward No. 3 (SW:- P/L Stone Soling at RD 0/00 to 0/040, CC Pavement at RD 0/00 to 0/019 & Grating at RD 0/00 (DC Deposit (VKVNY)	Rs. 84,599.00	Rs. 1,700.00	Three Months	
23	Gopalpur to Gopalpur Via Gujreda KM 0/00 to 2/300 (SW:- P/L Interlocking Tile at RD 1/322 to 1/341)	Rs. 83,858.00	Rs. 1,700.00	Three Months	
24	Restoration of rain damages on Parour Lahla Gopalpur Rakh Sukeri Kandi Palamplur road Km 0/00 to 33/00 (SW:- Hiring of JCB for removal of slips, Dressing of berms and clearance of drain)	Rs. 83,816.00	Rs. 1,700.00	Three Months	

Terms & Conditions-

Following documents should accompany the application for tenders.

1. G.S.T. No.
2. Valid copy of Registration
3. Machinery will be of the contractor where required.
4. Certificate regarding possession of machinery.
5. Telegraphic/Fax tenders are not acceptable.
6. The tender documents can be received by registered/ Insured post which should be received in this office on or before the date of opening of tender by 11.00 A.M positively.
7. Contractor should have successfully executed two works of similar nature of 1/3 amount of estimated cost or similar single work of amount equal to estimated cost during the last preceding three years

Executive Engineer
Palampur Division
HPPWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Spedu to Gorath road (SH:-C/o R/wall at RD 1/310 to 1/315 & 1/340 to 1/345) (PDNA-2025)

Estimated Cost :- Rs. 4,22,580/-

Earnest Money :- Rs. 8500/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	44.50	228.80	Rupees Two Hundred Twenty Eight And Paise Eighty Only	Per Cubic metre	10182.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government ~~but excluding GST.~~	101.02	3856.00	Rupees Three Thousand Eight Hundred Fifty Six Only	Per cubic metre.	389533.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	21.09	593.20	Rupees Five Hundred Ninety Three And Paise Twenty Only	Per cubic metre.	12511.00
4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	47	220.30	Rupees Two Hundred Twenty And Paise Thirty Only	Each	10354.00
Total :-						422580.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Patiala

Schedule of Quantity

Name of work:- Restoration of rain damages on Spedu to Gorath road (SH:-C/o R/wall at RD 1/319 to 1/332) (PDNA-2025)

Estimate No 254
2

Estimated Cost :- Rs. 4,22,561/-
Earnest Money :- Rs. 8500/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	53.50	228.80	Rupees Two Hundred Twenty Eight And Paise Eighty Only	Per Cubic metre	12241.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, GST or other taxes imposed by the Government but excluding GST.	102.31	3856.00	Rupees Three Thousand Eight Hundred Fifty Six Only	Per cubic metre.	394507.00
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	22.20	593.20	Rupees Five Hundred Ninety Three And Paise Twenty Only	Per cubic metre.	13169.00
4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12	220.30	Rupees Two Hundred Twenty And Paise Thirty Only	Each	2644.00
Total :-						422561.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work :- Link road Chowki Patwar Khana Kesar bag colony road.(SH:- P/L GSB, Gil, GIII & CC Pavement from Rd 0/850 to 0/966.30)/(PDNA 2025)

S. No		Description of Item	Quantity	Rate		Unit	Amount Rs.
				In figure	In Words		
1		Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	53.61	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	12722.00
2		Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel roller 80-100 (Eighty to hundred) KN static roller to achieve the desired density, complete as per MORD Technical Specification clause 401 for grading-I material and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	22.34	1313.60	Rupees One Thousand Three Hundred Thirteen And Paise Sixty Only	Per Cubic metre.	29346.00
3		macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.40	1906.80	Rupees One Thousand Nine Hundred Six And Paise Eighty Only	Per Cubic metre.	25551.00

Estimated Cost :- Rs. 4,23,548/-
Earnest Money :- Rs. 8500/-

Time Limit :- Three Months

3

3

J. Wearing 53 to 22.4mm (Fifty three to twenty two point four milimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.					13.40	1949.15	Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only	Per Cubic metre	26119.00
5	Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.				51.89	6355.95	Rupees Six Thousand Three Hundred Fifty Five And Paise Ninety Five Only	Per Cubic metre	329810.00
Quoted rates percentage in figures					Total :-				423548.00
Quoted rates percentage in words									

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- Link road Chowki Patwar Khana Kesar bag colony road (SH- P/L GSB, GII, GIII & CC Pavement from Rd 1/150 to 1/265.15)(PDNA 2025)

Estimated Cost :- Rs. 4,23,007/-
Earnest Money :- Rs. 8500/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	53.54	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	12705.00
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel roller 80-100 (Eighty to hundred) KN static roller to achieve the desired density, complete as per MORD Technical Specification clause 401 for grading-1 material and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	22.31	1313.60	Rupees One Thousand Three Hundred Thirteen And Paise Sixty Only	Per Cubic metre.	29306.00
3	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.39	1906.80	Rupees One Thousand Nine Hundred Six And Paise Eighty Only	Per Cubic metre.	25532.00

4

ing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including cartage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	13.39	1949.15	Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only	Per Cubic metre.	26099.00
Providing and laying mechanically mixed and vibrated reinforced cement concrete Grade- M-25 (M-Twenty Five) in open foundation design mix with cement contents not less than 400 kg (Four hundred kilogram) per cubic metre using graded crushed stone aggregate 20mm (twenty millimetre) nominal size complete as per drawings and MORD technical specification section 800, 900 and 1400, including the cost of form work and curing complete including hauling of materials with in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	51.82	6355.95	Rupees Six Thousand Three Hundred Fifty Five And Paise Ninety Five Only	Per Cubic metre	329365.00
Total :-					423007.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Restoration of Rain Damages on Palampur to Lohna Langha road, (SW:- CIO 6.00 mtr span RCC Culvert (LHS abutment work)(Near Sai Garden)(PDNA 2025)

Estimated Cost :- Rs. 3,56,417/-
Earnest Money :- Rs. 7100/-
Time Limit :- Three Months

	Description of Item	Quantity	In figure	Rate In Words	Unit	Amount Rs.
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	136.40	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	32368.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	7.21	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per Cubic metre.	28718.00
3	Providing /Laying Concrete Cradle bedding with Cement concrete 1:2.5:5 (One Cement : Two point five Sand : five crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-Fifteen) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	62.23	4745.80	Rupees Four Thousand Seven Hundred Forty Five And Paise Eighty Only	Per Cubic metre.	295331.00
					Total :-	356417.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- C/O U-Shape drain along with grating from PCCN Chowk towards Butail Chowk.(SW:- C/O U-Shape drain 0/400 to 0/454,10)(MC Deposit)

Estimated Cost :- Rs. 84,470/-
Earnest Money :- Rs. 1700/-

S. No	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of slumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	20.83	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	Rs. 4943.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	12.33	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per Cubic metre.	49111.00
3	Steel work welded in built up sections including cutting, hoisting, fixing, in position and applying a priming coat of red lead paint in grating, Framed guards, bars, ladders railings, brackets & similar works complete as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	377.60	80.55	Rupees Eighty And Paise Fifty Five Only	Per Kilogram	30416.00
Total :-						84470.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of work:- Restoration of rain damages on Link road Bandla Guggar Thakurdwara road (SH:-P/L Bituminous concrete on both side berm 1/095 to 1/170 & CC on both side berms at RD 1/350 to 1/433) (PDNA-2025)

Estimated Cost :- Rs. 3,51,086/-
Earnest Money :- Rs. 7000/-
Time Limit :- Three Months

S. No	Description of item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	79.00	237.00	Rupees Two Hundred Thirty Seven Only	Per Cubic metre	18723.00
2	Construction of Granular Sub Base by providing well graded material, spreading in uniform layers with tractor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with three wheel roller 80-100 (Eighty to hundred) KN static roller to achieve the desired density, complete as per MORD Technical Specification clause 401 for grading-I material and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	39.50	1313.60	Rupees One Thousand Three Hundred Thirteen And Paise Sixty Only	Per Cubic metre	51887.00
3	Providing, laying, Wearing 53 to 22.4mm (Fifty three to twenty two point four millimetre) nominal size Grading-3, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 3 as per technical specification Clause 405 including carriage of materials within all leads and lift and other incidentals as per the direction of Engineer-in- Charge. The rates are inclusive octroi, royalty, Malkana, toll tax, or any other taxes imposed by the Government but excluding GST.	34.95	1949.15	Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only	Per Cubic metre	68123.00
4	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	24.90	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per cubic metre.	132941.00
5	Providing and applying primer coat with Bitumen emulsion (SS-1) on prepared surface of granular base including cleaning of road surface with hydraulic broom and spraying primer at the rate of 0.85 Kg. (Zero decimal eight five Kilogram) per Square metres using mechanical means as per technical specification clause 502, and as per the directions of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	166.00	47.45	Rupees Forty Seven And Paise Forty Five Only	Per Cubic metre	7877.00

7	Spreading and applying tack coat with Bitumen emulsion (RS-1) using emulsion pressure distributor at the rate of 0.275 Kg. (Zero decimal part seven five Kilogramme) per Square metres on the prepared granular surface treated with primer and cleaned with Hydraulic broom as per technical specification clause 503, as per directions of Engineer-in-charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	166.00	17.80	Rupees Seventeen And Paise Eighty Only	Per Cubic metre	2955.00
8	Spreading and laying 25mm (Twenty five millimetre) compacted thick Bituminous Concrete with crushed stone aggregate of grading -II (Ten), 13.2 (Thirteen point two) millimetre nominal size, using bitumen VG-10 (VG-Ten) minimum 5.5% (Five point five percent) of weight of mix and filler on thoroughly cleaned surface by mechanical broom and dust removed by compressed air, mixed in computerised batch plant of 80-100 (Eighty to hundred) TPH capacity calibrated from time to time, mixing the bituminous concrete, transporting the mix material in clean insulated vehicles covered while in transit or awaiting, tipping and laying with hydrostatic paver finisher with sensor control to the required level alignment and grade, rolling with smooth wheeled, vibratory and tandem power road roller to achieve the desired compaction as per MORT&H specification clause 507(5th revision) complete , within all leads and lifts including carriage of materials, plants and equipments by mechanical transport, as per the direction of Engineer-in- Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	4.15	16525.40	Rupees Sixteen Thousand Five Hundred Twenty Five And Paise Forty Only	Per Cubic metre	68580.00
Total :-						351086.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of Rain Damages on Palampur to Lohna Langha road.(SW:- C/O 6.00 mtr span RCC Culvert (RHS abutment)(Near Sai Garden)(PDNA 2025)

Estimated Cost :- Rs. 3,54,637/-

Earnest Money :- Rs. 7100/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	In figure	Rate In Words	Unit	Amount Rs.
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	128.90	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	30588.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	7.21	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per Cubic metre.	28718.00
3	Providing /Laying Concrete Cradle bedding with Cement concrete 1:2.5:5 (One Cement : Two point five Sand : five crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-Fifteen) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	62.23	4745.80	Rupees Four Thousand Seven Hundred Forty Five And Paise Eighty Only	Per Cubic metre.	295331.00
					Total :-	354637.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- C/O Link road Toran to Katoch Basti Km 0/00 to 0/200.(SW:- C/O 3m Spain Culvert)(MMGSY)

Estimated Cost :- Rs. 84,156/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing Plain/ reinforced Cement concrete 1:1.5:3 (One Cement : One and half Sand : three crushed stone aggregate) Nominal Mix P.C.C. grade M-25 (M-Twenty five) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	9.31	6700.00	Rupees Six Thousand Seven Hundred Only	Per Cubic metre.	62377.00
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	279.22	78.00	Rupees Seventy Eight Only	Per Kilogram	21779.00
Total :-						84156.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- C/O Link road Toran to Katoch Basti Km 0/00 to 0/200.(SW:- C/O 3m Spain Culvert)(MMGSY)

Estimated Cost :- Rs. 83,975/-
Earnest Money :- Rs. 1700/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Providing Plain/ reinforced Cement concrete 1:1.5:3 (One Cement : One and half Sand : three crushed stone aggregate) Nominal Mix P.C.C. grade M-25 (M-Twenty five) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental . as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	9.29	6700.00	Rupees Six Thousand Seven Hundred Only	Per Cubic metre.	62243.00
2	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. Mild steel and Medium Tensile steel bars with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	278.62	78.00	Rupees Seventy Eight Only	Per Klogram	21732.00
Total :-						83975.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Name of work:- Restoration of rain Damages on Link road Kandli to Thalla Malenta road Km 0/00 to 4/500 (SH):- Clo R/wall at RD 3/580 to 3/594
(PDNA-2025)

Schedule of Quantity

Estimated Cost :- Rs. 2,11,511/-
Earnest Money :- Rs. 4200/-
Time Limit :- Three Months

Estimated Cost :- Rs. 2,11,511/- Earnest Money :- Rs. 4200/- Time Limit :- Three Months							
S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.	
			In figure	In Words			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock , hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated materials and disposal of materials strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including shoring and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.60	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre	2990.00	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	54.52	3644.06	Rupees Three Thousand Six Hundred Forty Four And Paise Six Only	Per Cubic metre	198674.00	
3	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	10.50	576.27	Rupees Five Hundred Seventy Six And Paise Twenty Seven Only	Per cubic metre.	6051.00	
4	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	16	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Each	3796.00	
Quoted rates percentage in figures							
Quoted rates percentage in words							
Total :-						211511.00	

Executive Engineer
Palampur Division
HP PWD, Palampur

Schedule of Quantity

Work :- Restoration of rain damages on Dharaman to Kandwari road 0/00 to 5/00, (SW:- CC Pavement Rd 4/100 to 4/130 & U-Shape drain with E/Wall) (PDNA 2025)

Estimated Cost :- Rs. 1,74,968/-
Earnest Money :- Rs. 3500/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	13.50	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	3204.00
2	Big Boulder breaking with silent blast Eco friendly chemical using compressure drill machine medling Lab (all rateper hole) as per thr direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental .Recovery of stones to the tune of 3.5 cubicmeter (three point five cubicmeter) quantity at the rate of Rupees 300/- only (Rupees Three hundred only) per cubic meter shall be effected from the contractor's running bill on pro-rata basis as per actual quantity executed .Any loss to the Public/Private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	10.00	635.60	Rupees Six Hundred Thirty Five And Paise Sixty Only	PHole	6356.00

		7.34	3813.57	Rupees Three Thousand Eight Hundred Thirteen And Paise Fifty Seven Only	Per Cubic metre	27992.00
ing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 20mm (Twenty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.						
4	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	18.00	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	96102.00
5	Steel work welded in built up sections trusses and frame work including cutting hoisting and fixing in position and applying a primer coat of red lead paint in in gratings framed guard bars,ladders,railing,brackets and similar works. and the like. The rates are inclusive cost and carriage of materials with in all leads, lifts and other incidentals, as per the direction and entire satisfaction of Engineer-In-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	530.00	77.95	Rupees Seventy Seven And Paise Ninety Five Only	Per Kilogram	41314.00
Total :-						174968.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD, Palampur

Schedule of Quantity

Name of Work :- Restoration of rain damages on Dharaman to Kandwari road 0/00 to 5/00.(SW:- C/O 1.00 mtr span RCC slab Culvert at Rd 4780)(PDNA 2025)

Estimated Cost :- Rs. 2,47,998/-
Earnest Money :- Rs. 5000/-

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	17.71	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	4203.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 as per the direction of the Engineer-in-Charge. Including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	8.86	3813.57	Rupees Three Thousand Eight Hundred Thirteen And Paise Fifty Seven Only	Per Cubic metre	33788.00
3	Providing /Laying Concrete Cradle bedding with Cement concrete 1:2.5:5.5 (One Cement : Two point five Sand : five crushed stone aggregate) Nominal Mix P.C.C. grade M-15 (M-Fifteen) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	27.31	4830.50	Rupees Four Thousand Eight Hundred Thirty And Paise Fifty Only	Per Cubic metre	131921.00
4	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	3.84	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	20502.00

12

13

	Plain/ reinforced Cement concrete 1:1.5:3 (One Cement : One and half Sand : three crushed stone aggregate) Nominal Mix P.C.C. grade M-25 (M-Twenty five) for plain/ reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803 1202 & 1203 including carriage of materials with in all leads, lifts and other incidentals, as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	3.20	5677.98	Rupees Five Thousand Six Hundred Seventy Seven And Paise Ninety Eight Only	Per Cubic metre	18170.00
6	Supplying, fitting and placing HYSD bar reinforcement in sub structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORTH technical specification section 1600 and 2300 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	230.40	77.95	Rupees Seventy Seven And Paise Ninety Five Only	Per Kilogram	17960.00
7	Supplying, fitting and placing HYSD bar reinforcement in super structure complete with straightening, bending, binding of bars including the cost of binding wire in all heights / depths as per drawing and MORTH technical specification section 1000 and 1400 and as per direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	240.00	77.95	Rupees Seventy Seven And Paise Ninety Five Only	Per Kilogram	18708.00
8	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.00	228.81	Rupees Two Hundred Twenty Eight And Paise Eighty One Only	Each	2746.00
					Total :-	247998.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work :- Restoration of rain damages on Palampur to Lohna Langha road.(SW:- C/O RWall 0075 to 0/082, P/L Stone Soling & P/L Cement Concrete 0/030 to 0/105
 Nayat Ghar Om Parkash House)(PDNA 2025)

Estimated Cost :- Rs. 2,71,028/-
 Earnest Money :- Rs. 5400/-
 Time Limit :- Three Months

	Description of Item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	5.46	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	1296.00
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and combor including spreading watering and rolling of binding materials moonum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	35.52	1127.15	Rupees One Thousand One Hundred Twenty Seven And Paise Fifteen Only	Per Cubic metre	40036.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 20mm (twenty millimetre) nominal size in open foundation as per drawing and M.O.R.D. technical specifications section 800, 900 and 1200, including the cost of form work, curing complete and hauling of materials in all leads, lifts and other incidental and as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	33.75	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	180191.00

14

laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.02	3644.10	Rupees Three Thousand Six Hundred Forty Four And Paise Ten Only	Per Cubic metre	47446.00
Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	3.00	228.85	Rupees Two Hundred Twenty Eight And Paise Eighty Five Only	Each	687.00
Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	2.38	576.30	Rupees Five Hundred Seventy Six And Paise Thirty Only	Per Cubic metre	1372.00
Total :-					271028.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of Work :- Restoration of rain damages on Link road Ghuggar to Naccchir.(SW:- C/O Retaining Wall from 2/450 to 2/461.10)(PDNA 2025)

Estimated Cost :- Rs. 84,261/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	0.87	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	206.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	20.65	3644.10	Rupees Three Thousand Six Hundred Forty Four And Paise Ten Only	Per Cubic metre	75251.00
3	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	8.00	228.85	Rupees Two Hundred Twenty Eight And Paise Eighty Five Only	Each	1831.00

15

Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.10	576.30	Rupees Five Hundred Seventy Six And Paise Thirty Only	Per Cubic metre	6973.00
Total :-					84251.00
Quoted rates percentage in figures					
Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Item of Work :- Restoration of rain damages on Link road from Ghuggar Nallah haar via mansimble, (SW: P/L Cement Concrete Pavement 0/090 to 0/119, 0/130 to 0/158.80)/(PDNA

Estimated Cost :- Rs. 1,68,699/-
Earnest Money :- Rs. 3400/-

Time Limit :- Three Months

No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In Figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	43.35	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre.	10287.00
2	Stone soling properly hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm (Hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	17.34	1127.15	Rupees One Thousand One Hundred Twenty Seven And Paise Fifteen Only	Per Cubic metre.	19545.00
3	Providing and laying concrete for plain/ reinforced Cement concrete 1:2:4 (One Cement : Two Sand : four crushed stone aggregate) Nominal Mix, P.C.C. grade M-20 (M-Twenty) in open foundations complete as per drawing and technical specifications clause 802, 803, 1202 & 1203 including carriage of materials with in all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, or other taxes imposed by the Government time to time but excluding GST.	26.01	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre.	138867.00
Total :-						168699.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:-Construction of Indoor Stadium (Multipurpose Skill Development Centre) at palampur in Tehsil Palampur , District Kangra
 Himachal Pradesh (Sh. Geotechnical Investigation and Preparation of Topographical Survey)

Estimated Cost :- Rs. 84,718/-
 Earnest Money :- Rs. 1700/-
 Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Investigation Boreing capacity of soil at Site at two locations i.e. 6 mtr (Six Meter) depth of each bore and submitted the test result complete in all respect The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.00	5932.20	Rupees Five Thousand Nine Hundred Thirty Two And Paise Twenty Only	Per Running Meter	71186.00
2	Topographical Survey on Contouring by total station and collection of data at interval of 1 mtr with actual offset, including result complete in all respect The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1.00	13532.00	Rupees Thirteen Thousand Five Hundred Thirty Two And Paise Twenty Only	Nbs	13532.00
Total :-						84718.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
 Palampur Division
 HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Dharamshala Yol Dadh Holta Chadiar Sandhole road Km 33/00 to 40/500 (SH:- Clo U shape drain at 39/100 to 39/188, R/wall at RD 39/250 to 39/260) (PDNA-2025)

Estimated Cost :- Rs. 2,62,919/-
Earnest Money :- Rs. 5700/-
Time Limit :- Three Months

No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	46.18	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	10959.00
2	Providing and laying 80mm (Eighty millimetre) thick factory made cement concrete interlocking paver block of M -30 (M-Thirty) grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm (Fifty millimetre) thick compacted bed of coarse sand, filling the joints with line sand etc. all complete as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental . The rate is including of octroi, royalty, Malkana, toll tax, sale tax or other taxes imposed by the Government.	13.80	1169.50	Rupees One Thousand One Hundred Sixty Nine And Paise Fifty Only	Per Square metre	16139.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	4.92	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	26268.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	32.85	3644.10	Rupees Three Thousand Six Hundred Forty Four And Paise Ten Only	Per cubic metre	119709.00
5	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer- in-Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	16.00	228.85	Rupees Two Hundred Twenty Eight And Paise Eighty Five Only	Each	3662.00

7	Back filling with granular material behind abutments, wing walls, return walls complete and retaining walls complete as per drawing and MORD technical specifications clause 1203 and 1604 and as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	10.90	576.30	Rupees Five Hundred Seventy Six And Paise Thirty Only	Per cubic metre.	6282.00
	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement :Three sand :Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water ,dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	20.06	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per cubic metre	79900.00
		Total :-				
						262919.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Spedu to Gorath road (SH:-C/o edge wall in Km 1/400 to 1/500 & P/L CC Pavement at RD 1/385 to 1/400) (PDNA-2025)

Estimated Cost :- Rs. 4,20,567/-
Earnest Money :- Rs. 8400/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.00	237.30	Rupees Two Hundred Thirty Seven And Paise Thirty Only	Per Cubic metre	2848.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	27.52	3813.55	Rupees Three Thousand Eight Hundred Thirteen And Paise Fifty Five Only	Per cubic metre	104949.00
3	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn. in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interslices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per directions of Engineer-in-charge including carriage of materials, within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	26.74	1949.15	Rupees One Thousand Nine Hundred Forty Nine And Paise Fifteen Only	Per Cubic metre	52120.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	48.82	5339.00	Rupees Five Thousand Three Hundred Thirty Nine Only	Per Cubic metre	260650.00
Total :-						420567.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain damages on Kand to Tikker via Kalohi Mata (SH-P/L CC Pavement at RD 0/540 to 0/780, 1/00 to 1/032 & C/o U-shape drain at RD 1/00 to 1/032) (PDNA-2025)

Estimated Cost :- Rs.1,57,110/-
Earnest Money :- Rs.3100/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling/wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification section 300 and 1600 as per direction of the Engineer-in-Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.32	229.60	Rupees Two Hundred Twenty Nine And Paise Sixty Only	Per Cubic metre	2829.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depts including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	5.28	3854.00	Rupees Three Thousand Eight Hundred Fifty Four Only	Per cubic metre	20349.00
3	Providing, laying, Wearing 63 to 45mm (Sixty three to forty five millimetre) nominal size Grading-2, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel 80-100 Kn in stages to proper grade and camber, applying and brooming, stone screening/ binding materials to fill-up the interstices of coarse aggregate, watering and compacting to the required density grading 2 as per technical specification Clause 405 as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	13.96	1845.00	Rupees One Thousand Eight Hundred Forty Five Only	Per Cubic metre	25756.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	20.94	5166.00	Rupees Five Thousand One Hundred Sixty Six Only	Per Cubic metre	108176.00
Quoted rates percentage in figures						
Quoted rates percentage in words						
Total:-						157110.00

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Restoration of rain Damages on Kaloond to Balehar road Km 0/00 to 2/500 (SH:- P/L Interlocking tile at RD 0/00 to 0/015, C/O U-shape drain at RD 0/800 to 0/880, V-shape drain at RD 2/100 to 2/204 & R/wall at RD 2/140 to 2/151) (PDNA-2025)

Estimated Cost :- Rs. 3,17,695/-
Earnest Money :- Rs. 6400/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	In figure	In Words	Unit	Amount Rs.
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chiseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	47.25	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre	11211.00
2	Providing and laying 60mm (Sixty millimetre) thick factory made cement interlocking paver block of M-30 (M-Thirty) grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm (Fifty millimetre) thick compacted bed of coarse sand, filling the joints with fine sand etc. all complete as per drawings and M.O.R.D. technical specification section 800, 900 and 1200 and as per direction of Engineer-in-Charge Including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	60.00	1084.74	Rupees One Thousand Eighty Four And Paise Seventy Four Only	Per Square metre	65084.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement : Three sand : Six graded crushed / broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	28.31	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per cubic metre	112760.00
4	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement : five sand : ten graded crushed/broken stone aggregate 20mm (twenty millimeter) nominal size including curing complete in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clause 802, 803, 1202 and 1203 as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	34.65	3644.06	Rupees Three Thousand Six Hundred Forty Four And Paise Six Only	Per Cubic metre	126267.00
5	Providing and laying 100mm dia (One Hundred millimetre) diameter P.V.C. pipe weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20 (H) (one vertical: twenty horizontal) towards draining face complete as per drawing and M.O.R.D. technical specifications clause 709 and 1206.6 and as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	10	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Each	2373.00
Total :-						317695.00
Quoted rates percentage in figures						
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of work:- C/o (Construction of) Jeepable road from Main Road Sh. Karam Chand house towards Sh. Alma Ram house Ward No. 3 (SH:- P/L Stone soling at RD 0/00 to 0/040, CC Pavement at RD 0/00 to 0/019 & grating at RD 0/00) (DC Deposit VKVNY)

Estimated Cost :- Rs. 84,599/-
Earnest Money :- Rs. 1700/-
Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Excavation in Hilly Area in all heights and depths and in all kinds of soil by manual/ mechanical means including saturated soil comprising of ordinary soil soft Rock,Hard rock, chisseling/wedging out of rock (where blasting is prohibited) and their intermediate classification of soil setting out true to the required line grades cutting and trimming of side slopes and level as shown in the drawings and as directed by the Engineer in charge at site according to the technical specification clause 302.1603.1 and 1603.2 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of unuseful material for filling in road way, camber, embankments for grade improvement and disposal of all surplus material to required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its levelling fine dressing and carriage of machineries, materials, tools equipments and safety measures and incidentals necessary to complete the 1.40 cubic metre quantity at the Rate of Rupees 300/- only (Rupees Three hundred only) per cubic metre shall be effected from the contractor's running bills on pro-rata basis as per actual quantity executed. Any loss to the public private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be compensated by him in all cases as per entire the satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	60.00	133.89	Rupees One Hundred Thirty Three And Paise Eighty Nine Only	Per cubic metre.	8033.00
2	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetera in all type of classification of soil, comprising of ordinary soil, ordinary rock, hard rock chisseling / wedging out rocks (where blasting is prohibited) as per drawings and MORD technical specification clause 305.1 and as per the directions of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable / approved materials to the original surface in layers not exceeding 150mm one hundred fifty millimeters) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering or as per directions of Engineer-in-Charge including carriage of materials within all leads, lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1.62	237.28	Rupees Two Hundred Thirty Seven And Paise Twenty Eight Only	Per Cubic metre	384.00
3	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in open foundations for all types of structure complete of plain cement concrete nominal mix 1:3:6 (one cement : Three sand : Six graded crushed /broken stone aggregate 20 mm (Twenty Millimeters) nominal size on ground or under water including curing complete, pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying concrete complete for all heights/depths including the cost of form work in drain as per drawings and MORD technical specifications section 800, 900 and 1200 and as per the direction of Engineer-in-Charge including carriage of material within all leads and lifts and other incidentals. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	1.16	3983.05	Rupees Three Thousand Nine Hundred Eighty Three And Paise Five Only	Per cubic metre	4620.00
4	Steel work welded in built up sections including cutting,hoisting, fixing, in position and applying a priming coat of red lead paint in grating, Framed guards, bars, ladders railings,brackets & similar works complete as per the entire satisfaction and direction of Engineer-in-Charge including carriage of materials within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	152.85	83.05	Rupees Eighty Three And Paise Five Only	per Kilogram	12694.00
5	Stone soling property hand-packed filling interstices with spalls and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per H.P.PWD specification. 100 mm (hundred millimetre) spread thickness (finished work including materials and labour) complete as per the direction of Engineer-in-Charge including carriage of material within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	12.00	1101.69	Rupees One Thousand One Hundred One And Paise Sixty Nine Only	Per Cubic metre	13220.00

6	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal mix 1:2:4 (one cement : two sand : four graded crushed stone aggregate 40mm (forty millimetre) nominal size using cement contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or boiling out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer-in-Charge. The rate is including octrai, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	8.55	5338.98	Rupees Five Thousand Three Hundred Thirty Eight And Paise Ninety Eight Only	Per Cubic metre	45648.00
Total :-						
	Quoted rates percentage in figures					
	Quoted rates percentage in words					

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Work:- Gopalpur to Gopalpur via gujreda Km 0/00 to 2/300(SH:-P/L Interlocking tile at Rd 1/322 to 1/341)

Estimated Cost :- Rs. 83,858/-
Earnest Money :- Rs. 1700/-

S.No	Description of item	Quantity	Rate		Unit	Amount
			In figure	In Words		
1	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement : four sand : eight graded crushed/ broken stone aggregate 40mm (forty millimetre) nominal size on ground or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying concrete complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification section 800, 900 and 1200 and as per the entire satisfaction and direction of the Engineer -in-Charge including carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	4.56	3855.95	Rupees Three Thousand Eight Hundred Fifty Five And Paise Ninety Five Only	Per cubic metre.	17583.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete Grade- M-20 (M-Twenty) in open foundation nominal contents not less than 330 Kg (Three hundred thirty kilogram) per cubic metre on ground or under water and curing complete including pumping or bailing out water, dewatering, removal of slush which may arise at the time of laying concrete complete for all height/ depths including cost of form work in open foundation as per drawing and MORD technical specification section 800, 900, 1200 including carriage of material with in all leads, lifts and other incidentals as per the entire satisfaction and directions of Engineer -in-Charge. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	0.76	5338.98	Rupees Five Thousand Three Hundred Thirty Eight And Paise Ninety Eight Only	Per cubic metre.	4058.00
3	Providing and Laying of Interlocking Concrete Block Pavements having thickness 80 mm (Eighty millimetre) as per drawings and Technical Specification Clause 1504 and as per the directions of Engineer-In-Charge including carriage of materials within all leads, lifts and other incidental. The rate is including octroi, royalty, Malkana. toll tax, sale tax, or other taxes imposed by the Government but excluding GST.	53.20	1169.49	Rupees One Thousand One Hundred Sixty Nine And Paise Forty Nine Only	Per square metre.	62217.00
	Quoted rates percentage in figures					
	Quoted rates percentage in words					
			Total:-			83858.00

Executive Engineer
Palampur Division
HP PWD Palampur

Schedule of Quantity

Name of work:- Restoration of rain damages on Parour Lahla Gopalpur Rakh Suikeri Kandi Palampur road Km 0/00 to 33/00
(SH:- Hiring of JCB for removal of slips, Dressing of berms & Clearance of drain)

Estimated Cost :- Rs. 83,816/-
Earnest Money :- Rs. 1700/-

Time Limit :- Three Months

S. No	Description of Item	Quantity	Rate		Unit	Amount Rs.
			In figure	In Words		
1	Hiring of excavator cum loader for maintenance of berms, clearance of side drain, removal of slip etc. including cost of fuel oil lubricants and wages of operating staff, any repair/ breakage during operation will be carried out by the contractor on risk, shifting machinery from one place to other place will be absolute responsibility of the contractor, only actual working hours will be accounted for the payment. Earth cutting in all kinds of soils, including loading into tipper/ truck and disposal of all excavated earth in all leads and lifts to the entire satisfaction of Engineer-in- Charge. Rate is inclusive of toll tax and any other taxes imposed by the government but excluding GST.	86.00	974.60	Rupees Nine Hundred Seventy Four And Paise Sixty Only	Per Hour	83816.00
Quoted rates percentage in figures				Total :-		83816.00
Quoted rates percentage in words						

Executive Engineer
Palampur Division
HP PWD Palampur