

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT

NO. PWF/CB/2nd C /Tender/2026:-
To,

6159-66

Dated:-

11/10/2026

The Chief Engineer (KZ),
HPPWD Dharamshala (HP)
e-mail:- hp-kan1@nic.in


Subject:

Publication of Tender Notice.

Dear Sir,

Enclosed please find herewith the Tender Notice of work as given in the Notice Inviting Tender for uploading on department website as per notification Pr. Sec.(PW) to the Govt. of HP letter No. PBW (B) A(3)1/2020 dated Shimla-2 the 16th July,2021 and further in compliance of the Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICT Wing/website dated 22/5/2026 as the work mentioned in the tender notice are urgent in nature and in public interest. You are requested to kindly get it published on departmental website on or before 03.10.2026.

DA/ Notice Inviting Tender.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

Copy forwarded for information to:-

1. The Superintending Engineers 9th Circle, HPPWD, Nurpur.
2. All the Assistant Engineers working under this Division.
3. Copy to AB/DB of this Division.
4. Notice Board.


Executive Engineer,
Fatehpur Division HPPWD,
Fatehpur.

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
*NOTICE INVITING TENDER***

Scaled item rate tenders on the form 6&8 are invited by the Executive Engineer Fatehpur Division HPPWD, Fatehpur on behalf of the Governor of HP for the following works from the approved and eligible contractors enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|-------------------------|
| 1. Date and time of receipt of application for tender form: | 12.10.2026 upto 5.00 PM |
| 2. Date and time of issue of tender form: | 13.10.2026 upto 5.00 PM |
| 3. Date and time of receipt of tenders: | 14.10.2026 upto 11.00AM |
| 4. Date and time of opening of tenders: | 14.10.2026 at 11.30 AM |

The tenders form will be issued against cash payment (non refundable). The earnest money in the shape of NSC/FDR/Deposit at call of any of Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Fatehpur Division HPPWD Fatehpur must accompany with each tender. The Tender shall remain valid for 90 days from the date of opening of the tenders. If any of the date mentioned above happens to be local/Gazetted Holiday the same shall be process on next date.

Sr. No	Name of work	Estimated cost (in Rs.)	Earnest money (in Rs.)	Time limit	Cost Tender Form (in Rs.)	Eligible class of Contractor
1.	Repair of path from Shaheed Ashok Kumar road to Rajinder House Ward No.7 Under SDF (D.C. Deposit) (SH:- Providing and laying cement concrete pavement at R.D. 0/000 to 0/026.40)	Rs.84502/-	Rs.1700/-	One month	350/-	Class D&C
2.	Re-construction of RW near house of Kamal Kumar Ward No.4 Village Hara Under SDF (D.C. Deposit) (SH:-Construction of 19.00mtr. Retaining wall)	Rs.84541/-	Rs.1700/-	One month	350/-	Class D&C
3.	Re-construction of RW near house of Shaukat Ali Ward No.6 Manoh Sihal Under SDF (D.C. Deposit) (SH:- Construction of 9.20mtr. Breast wall)	Rs.84341/-	Rs.1700/-	One month	350/-	Class D&C
4.	Re-construction of RW near house and Gaushala of Balwinder Singh Jeewan Rakesh etc. Ward No.4 Village Bheda Harsariyan Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/008.40)	Rs.62914/-	Rs.1300/-	One month	350/-	Class D&C
5.	R/O (Repair of) Path Ramesh Kumar to Ranjit Singh House Ward No.4 G.P. Barot khas Under SDF (D.C. Deposit) (SH:- Providing and laying cement concrete pavement at R.D. 0/0 to 0/039)	Rs.84289/-	Rs.1700/-	One month	350/-	Class D&C
6.	Re-construction of RW (retaining wall) near house of Nazia Begum Ward No.3 G.P. Fatehpur Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/007)	Rs.84530/-	Rs.1700/-	One month	350/-	Class D&C
7.	Re-construction of RW (retaining wall) near house of Balwinder Singh Ward No.1 Village Bankehar G.P. Kutwasi Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/009.50)	Rs.83953/-	Rs.1700/-	One month	350/-	Class D&C
8.	Re-construction of RW (retaining wall) near house of Washilo Devi Village Bhatoli Samiyala G.P. Diana Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/007)	Rs.84432/-	Rs.1700/-	One month	350/-	Class D&C
9.	Re-construction of RW (retaining wall) near house of Pritam Singh Ward No.2 Village Bhatti Riyallan G.P. Bhattian Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/009.50)	Rs.84329/-	Rs.1700/-	One month	350/-	Class D&C
10.	Re-construction of RW (Retaining wall) near house of Prem Singh Village Baned G.P. Bagroli Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/004)	Rs.84061/-	Rs.1700/-	One month	350/-	Class D&C
11.	Re-construction of RW (Retaining wall) near house of Asha Devi Village Houru Devi G.P. Bagroli Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/008.10)	Rs.84500/-	Rs.1700/-	One month	350/-	Class D&C
12.	Re-construction of RW (Retaining wall) near house of Jaswant Singh Village Sanaurth G.P. Bagroli Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/150 to 0/155)	Rs.84154/-	Rs.1700/-	One month	350/-	Class D&C
13.	R/O (Repair of) Path near house of Jagdish Singh to Rajinder house Ward No.7 G.P. Sunet Under SDF (D.C. Deposit) (SH:- Providing and laying cement concrete pavement at R.D. 0/0 to 0/036).	Rs.84562/-	Rs.1700/-	One month	350/-	Class D&C
14.	Restoration of Rain Damages on Jagnoli Bhatta Bhawara road km. 0/00 to 5/000 Under SDF (D.C. Deposit) (SH:- Construction of Edge wall at R.D.0/695 to 0/700, V-shape drain at R.D. 0/655 to 0/700 and providing and laying cement concrete pavement at R.D.0/700 to 0/710)	Rs.75890 /-	Rs.1600/-	One month	350/-	Class D&C
15.	Restoration of Rain Damages on Malahri Kothi Bartiyal road km.0/000 to 4/200 Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 3/980 to 3/989.40)	Rs.84416/-	Rs.1700/-	One month	350/-	Class D&C
16.	Construction of Retaining wall near the house of Praveen Kumar Dile Ram etc. Ward No.2 Mohal Bari Under SDF (D.C. Deposit) (SH:-	Rs.84596/-	Rs.1700/-	One month	350/-	Class D&C

	Construction of Retaining wall)					
17.	Construction of Retaining wall near the house of Girdhari Lal Ward No.3 Mohal Baroona Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63348/-	Rs.1300/-	One month	350/-	Class D&C
18.	Construction of Retaining wall near the house of Kalyan Chand Ward No.5 Mohal Sathana Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63526/-	Rs.1300/-	One month	350/-	Class D&C
19.	Construction of Retaining wall near the house of Pyar Chand Ward No.5 Village Bhanoli Mohal Kudal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63427/-	Rs.1300/-	One month	350/-	Class D&C
20	Construction of Retaining wall near the house of Amarjeet Singh Dilbagh etc.Ke Khet Ward No.3 Village Bhanoli Mohal Kudal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63427/-	Rs.1300/-	One month	350/-	Class D&C
21	Construction of Retaining wall near the land of Ruldu Ram Kuldeep etc.Ward No.3 Village Dhanuna Mohal Machhot Under SDF (D.C. Deposit) (SH:- Construction of Breast wall)	Rs.63460/-	Rs.1300/-	One month	350/-	Class D&C
22	Construction of Retaining wall near the house of Kewal Singh Rai Singh etc. Ward No.3 Village Mohal Machhot Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63500/-	Rs.1300/-	One month	350/-	Class D&C
23	Construction of Retaining wall near the house of Baldev Singh Ward No.5 Mohal Bari Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63500/-	Rs.1300/-	One month	350/-	Class D&C
24	Construction of Retaining wall near the house of Parshotam Singh Ward No.4 Village Kohlari Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63500/-	Rs.1300/-	One month	350/-	Class D&C
25	Construction of Retaining wall near the house of Dhayam Singh Ward No.3 SC Basti Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63423/-	Rs.1300/-	One month	350/-	Class D&C
26	Construction of Retaining wall near the house of Mohinder Singh Ward No.3 Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63486/-	Rs.1300/-	One month	350/-	Class D&C
27	Construction of Retaining wall near the house of Kuldeep Singh Ward No.3 Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63423/-	Rs.1300/-	One month	350/-	Class D&C
28	Construction of Retaining wall near the house of Saleem Ward No.3 Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63501/-	Rs.1300/-	One month	350/-	Class D&C
29	Construction of Retaining wall near the house of Narinder Kumar Ward No.3 Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)	Rs.63304/-	Rs.1300/-	One month	350/-	Class D&C

Certified that tender of above works are being called of emergent nature in exigency of public interest.

TERMS AND Conditions:-

1. The Contractor/Firm shall have his GST NO. & Copy of same be attached with the application.
2. The intending Contractor /Firm should have attached copy of registration/renewal.
3. The earnest money & cost of tender form for the above works should be submitted with the application for the purchase of the tender forms the application received without earnest money & cost of tender from shall summarily be rejected.
4. The tender form will be issued to those contractors who have not more than two works at the time of issue of tender forms. In this regard contractor has to submit an affidavit that he is not having more two works.
5. **Only two tenders form will be issued to the contractor/ firms which may be noted.**
6. The intending contractors are requested to see the site of the work before submitting the tender.
7. The Offer of the tender shall remain valid up to 75 days after the opening of tender.
8. The tender amount after negotiation should be **within limit of (+) 5%** otherwise the tender will be cancelled.
9. The Executive Engineer reserves the right to reject/accept any or all the tenders without assessing any reason.

Executive Engineer,
Fatehpur Division HRPWD,
Fatehpur.

On behalf of Governor of Himachal Pradesh

①

SCHEDULE OF QUANTITY

Name of work:- Repair of path from Shaheed Ashok Kumar road to Rajinder House Ward No.7 Under SDF (D.C. Deposit) (SH:- Providing and laying cement concrete pavement at R.D. 0/000 to 0/026.40)				Estimated cost:- Rs.84502/- only		
				Earnest Money : Rs.1700/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	15.84	5334.75	Rupees Five Thousand Three Hundred Thirty Four And Paise Seventy Five Only	Per cubic meter	84502.00
					Total:-	84502.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)

2

SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW near house of Kamal Kumar Ward No.4 Village Hara Under SDF (D.C. Deposit) (SH:- Construction of 19.00mtr. Retaining wall)							Estimated cost:- Rs.84541/- only	
							Earnest Money : Rs.1700/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.60	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	3011.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	24.23	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	76940.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	17.00	270.00	Rupees Two Hundred Seventy Only	Each	4590.00		
					Total:-	84541.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								

Executive Engineer
Fatehpur Division HPPW
Fatehpur Distt. Kangra (HP)

SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW near house of Shaukat Ali Ward No.6 Manoh Sihal Under SDF (D.C. Deposit) (SH):- Construction of 9.20mtr. Breast wall)									
Estimated cost:- Rs.84341/- only									
Earnest Money : Rs.1700/- only									
Time limit:- One month									
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	4.78	350.35	Rupees Three Hundred Fifty And Paise Thirty Five Only	Per cubic meter	1675.00			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	20.98	3850.14	Rupees Three Thousand Eight Hundred Fifty And Paise Fourteen Only	Per cubic meter	80776.00			
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi. royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	7.00	270.00	Rupees Two Hundred Seventy Only	Each	1890.00			
					Total:-	84341.00			
Note:- 18% GST shall be paid separately									
Amount quoted by the contractor in % Above/Below									


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW near house and Gaushala of Balwinder Singh Jeewan Rakesh etc. Ward No.4 Village Bheda Harsariyan Under SDF (D.C. Deposit) (SH):- Construction of. Retaining wall at R.D. 0/0 to 0/008.40)						
Estimated cost:- Rs.62914/- only						
Earnest Money : Rs.1300/- only						
Time limit:- One month						
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	4.03	350.25	Rupees Three Hundred Fifty And Paise Twenty Five Only	Per cubic meter	1412.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.41	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	59342.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	8.00	270.00	Rupees Two Hundred Seventy Only	Each	2160.00
					Total:-	62914.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

(5)

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Path Ramesh Kumar to Ranjit Singh House Ward No.4 G.P. Barot khas Under SDF (D.C. Deposit) (SH:- Providing and laying cement concrete pavement at R.D. 0/0 to 0/039)						Estimated cost:- Rs.84289/- only	
						Earnest Money : Rs.1700/- only	
						Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802.803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	15.80	5334.75	Rupees Five Thousand Three Hundred Thirty Four And Paise Seventy Five Only	Per cubic meter	84289.00	
					Total:-	84289.00	
Note:- 18% GST shall be paid separately							
Amount quoted by the contractor in % Above/Below							

Executive Engineer
Fatehgarh Division HPPWD
Fatehgarh
Kangra (H)

SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW (retaining wall) near house of Nazia Begum Ward No.3 G.P. Fatehpur Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/007)							Estimated cost:- Rs.84530/- only	
							Earnest Money : Rs.1700/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.89	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	3112.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	25.13	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	79798.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204,3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	6.00	270.00	Rupees Two Hundred Seventy Only	Each	1620.00		
					Total:-	84530.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Disu. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW (retaining wall) near house of Balwinder Singh Ward No.1 Village Bankehar G.P. Kutwasi
Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/009.50)

Estimated cost:- Rs.83954/- only


Earnest Money : Rs.1700/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.65	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	3028.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts in Retaining walls and breast wall and in parapets and the like etcetera including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	24.89	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	79036.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204,3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	7.00	270.00	Rupees Two Hundred Seventy Only	Each	1890.00
					Total:-	83954.00


Note:- 18% GST shall be paid separately

Amount quoted by the contractor in % Above/Below


Engineer
Fatehpur Division HPPW
Fatehpur Distt. Kangra (H.P.)


SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW (retaining wall) near house of Washilo Devi Village Bhatoli Samiyala G.P. Diana Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall at R.D. 0/0 to 0/007)							Estimated cost:- Rs.84432/- only	
							Earnest Money : Rs.1700/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.61	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	3014.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	25.13	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	79798.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	6.00	270.00	Rupees Two Hundred Seventy Only	Each	1620.00		
					Total:-	84432.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW (retaining wall) near house of Pritam Singh Ward No.2 Village Bhatti Riyallan G.P. Bhattian Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/009.50)							Estimated cost:- Rs.84329/- only	
							Earnest Money : Rs.1700/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.27	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	2895.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802. 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	25.05	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	79544.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204,3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	7.00	270.00	Rupees Two Hundred Seventy Only	Each	1890.00		
					Total:-	84329.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								


 Engineer
 Division HPPWD
 District Kangra (H)

SCHEDULE OF QUANTITY

Name of work:- Re-construction of RW (Retaining wall) near house of Prem Singh Village Baned G.P. Bagroli Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall at R.D. 0/0 to 0/004)				Estimated cost:- Rs.84061/- only		
				Earnest Money : Rs.1700/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.60	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	3011.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of 24.20 plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	24.20	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	76845.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	7.00	270.00	Rupees Two Hundred Seventy Only	Each	1890.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	3.56	650.30	Rupees Six Hundred Fifty And Paise Thirty Only	Per cubic meter	2315.00
					Total:-	84061.00
	Note:- 18% GST shall be paid separately					
	Amount quoted by the contractor in % Above/Below					


 Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Re-construction of RW (Retaining wall) near house of Asha Devi Village Hourri Devi G.P. Bagroli Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/0 to 0/008.10)				Estimated cost:- Rs.84500/- only		
				Earnest Money : Rs.1700/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	5.91	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	2069.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	23.10	3310.20	Rupees Three Thousand Three Hundred Ten And Paise Twenty Only	Per cubic meter	76466.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204,3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	7.00	270.00	Rupees Two Hundred Seventy Only	Each	1890.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	5.99	680.30	Rupees Six Hundred Eighty And Paise Thirty Only	Per cubic meter	4075.00
					Total:-	84500.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						


 Executive Engineer
 Treasury Division HPPWD
 District Durgam Changanu (H.P.)

12

SCHEDULE OF QUANTITY

Name of work:-Re-construction of RW (Retaining wall) near house of Jaswant Singh Village Sanaurth G.P. Bagroli Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 0/150 to 0/155)				Estimated cost:- Rs.84154/- only		
				Earnest Money : Rs.1700/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.65	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	3028.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	23.50	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	74622.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	10.00	270.00	Rupees Two Hundred Seventy Only	Each	2700.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer – in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	5.85	650.30	Rupees Six Hundred Fifty And Paise Thirty Only	Per cubic meter	3804.00
					Total:-	84154.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						

Executive Engineer
 Flood Control Division HPPW
 Ferozepur, Distt. Kangra (P.)

13

SCHEDULE OF QUANTITY

Name of work:- R/O (Repair of) Path near house of Jagdish Singh to Rajinder house Ward No.7 G.P. Sunet Under SDF (D.C. Deposit) (SH):- Providing and laying cement concrete pavement at R.D. 0/0 to 0/036).			Estimated cost:- Rs.84562/- only			
			Earnest Money : Rs.1700/- only			
			Time limit:- One month			
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Granular sub-base/surface course with local materials (Table 400.13) by mix in place method normal Construction of granular sub-base by providing local material spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at once and compacting with smooth wheel roller to achieve the desired density complete as per Clause 401.4 as per Technical Specification Clause 408. Using naturally occurring gravel as per the direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	7.29	730.20	Rupees Seven Hundred Thirty And Paise Twenty Only	Per cubic meter	5323.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	14.58	5434.75	Rupees Five Thousand Four Hundred Thirty Four And Paise Seventy Five Only	Per cubic meter	79239.00
Note:- 18% GST shall be paid separately					Total:-	84562.00
Amount quoted by the contractor in % Above/Below						

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Jagnoli Bhatta Bhawara road, km. 0/00 to 5/000 Under SDF (D.C. Deposit) (SH:- Construction of Edge wall at R.D.0/695 to 0/700, V-shape drain at R.D. 0/655 to 0/700 and providing and laying cement concrete pavement at R.D.0/700 to 0/710)						
				Estimated cost:- Rs.75890/- only		
				Earnest Money : Rs.1600/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.90	350.10	Rupees Three Hundred Fifty And Paise Ten Only	Per cubic meter	3466.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-10 (M Ten) nominal mix 1:3:6 (One cement : 3 sand : 6 graded crushed/ broken stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work in toe walls as per drawings and M.O.R.D. technical specification sections 800, 900 & 1200 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	6.37	4590.60	Rupees Four Thousand Five Hundred Ninety And Paise Sixty Only	Per cubic meter	29242.00
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	5.06	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	19486.00

4.	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	3.00	270.00	Rupees Two Hundred Seventy Only	Each	810.00
5	Providing and laying mechanically mixed and vibrated concrete for plain/ reinforced concrete in open foundation for all type of structure complete of plain cement concrete grade M-20 (M- twenty) nominal mix 1:2:4 (One cement isto two sand isto four graded stone aggregate 20mm (twenty millimeter) nominal size in or under water and curing complete including pumping or bailing out water , dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work as per drawings and M.O.R.D. technical specification Clause 802,803,1202 and 1203 as per the direction of the Engineer-in-Charge . Including carriage of material within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	4.29	5334.75	Rupees Five Thousand Three Hundred Thirty Four And Paise Seventy Five Only	Per cubic meter	22886.00
					Total:-	75890.00
	Note:- 18% GST shall be paid separately .					
	Amount quoted by the contractor in % Above/Below					


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Bangra (P.)


SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Malahri Kothi Bartiya road km.0/000 to 4/200 Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 3/980 to 3/989.40)							Estimated cost:- Rs.84416/- only	
							Earnest Money : Rs.1700/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.50	352.60	Rupees Three Hundred Fifty Two And Paise Sixty Only	Per cubic meter	4055.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	23.45	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	74463.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	7.00	270.00	Rupees Two Hundred Seventy Only	Each	1890.00		
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	6.11	656.00	Rupees Six Hundred Fifty Six Only	Per cubic meter	4008.00		
					Total:-	84416.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Restoration of Rain Damages on Malahri Kothi Bartiyal road km.0/000 to 4/200 Under SDF (D.C. Deposit) (SH:- Construction of. Retaining wall at R.D. 3/980 to 3/989.40)							Estimated cost:- Rs.84416/- only	
							Earnest Money : Rs.1700/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	11.50	352.60	Rupees Three Hundred Fifty Two And Paise Sixty Only	Per cubic meter	4055.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of plain cement concrete nominal mix 1:5:10 (One cement isto five sand isto ten graded crushed/broken stone aggregate 40mm (Forty millimeter) nominal size in or under water including curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths in Retaining walls and breast wall and in parapets and the like etcetra including the cost of form work as per drawing and M.O.R.D technical specification clauses 802, 803, 1202 and 1203 as per the entire satisfaction and direction of Engineer-in-charge including carriage of material within all leads and lifts and other incidental. The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	23.45	3175.40	Rupees Three Thousand One Hundred Seventy Five And Paise Forty Only	Per cubic meter	74463.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	7.00	270.00	Rupees Two Hundred Seventy Only	Each	1890.00		
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	6.11	656.00	Rupees Six Hundred Fifty Six Only	Per cubic meter	4008.00		
					Total:-	84416.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Praveen Kumar Dile Ram etc. Ward No.2 Mohal Bari Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)

Estimated cost:- Rs.84596/- only

Earnest Money : Rs.1700/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	10.47	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3555.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	20.55	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	79136.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	4.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	1068.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	1.32	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	837.00
					Total:-	84596.00
	Note:- 18% GST shall be paid separately					
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Fatehpur Division HPPV
Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Girdhari Lal Ward No.3 Mohal Baroona Under SDF (D.C. Deposit)							Estimated cost:- Rs.63348/- only
(SH):- Construction of Retaining wall)							Earnest Money : Rs.1300/- only
							Time limit:- One month
Sr. No	Description of items	Quantity	Rate		Unit	Amount	
			In words	In figures			
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In – Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.50	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3225.00	
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer –in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	14.85	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	57186.00	
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer – in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	11.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	2937.00	
					Total:-	63348.00	
Note:- 18% GST shall be paid separately							
Amount quoted by the contractor in % Above/Below							


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Kalyan Chand Ward No.5 Mohal Sathana Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)							Estimated cost:- Rs.63526/- only	
							Earnest Money : Rs.1300/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.36	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3178.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	14.98	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	57686.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	7.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	1869.00		
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	1.25	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	793.00		
					Total:-	63526.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								


 Engineer
 Fatehpur Division H.P.P.W.
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Pyar Chand Ward No.5 Village Bhanoli Mohal Kudal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)									
Estimated cost:- Rs.63427/- only									
Earnest Money : Rs.1300/- only									
Time limit:- One month									
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification. clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.22	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2791.00			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.07	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	58033.00			
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	4.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	1068.00			
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.42	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1535.00			
					Total:-	63427.00			
Note:- 18% GST shall be paid separately									
Amount quoted by the contractor in % Above/Below									


Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (H.P.)


SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Amarjeet Singh Dilbagh etc. Ke Khet Ward No.3 Village Bhanoli Mohal Kudal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)							Estimated cost:- Rs.63427/- only	
							Earnest Money : Rs.1300/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	8.22	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	2791.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.07	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	58033.00		
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709.1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	4.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	1068.00		
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer -in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.42	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1535.00		
					Total:-	63427.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								


Executive Engineer
 Fatehpur Division HPPW
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the land of Ruldu Ram Kuldeep etc. Ward No.3 Village Dhanuna Mohal Machhot Under SDF (U.C. Deposit) (SH:- Construction of Breast wall)									
Estimated cost:- Rs.63460/- only									
Earnest Money : Rs.1300/- only									
Time limit:- One month									
Sr No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Excavation in hilly area for road ways in all heights and depths and in all kind of soil by manual/mechanical means including saturated soil comprising of ordinary soil, soft rock, hard rock, chiselling, wedging out of rock (where blasting is prohibited) and their intermediate classification of soil, setting out true to the required lines, grades, cutting and trimming of side slopes and level as shown in the drawing and as directed by Engineer-in-charge at site according to the MORD technical specification section 1600 and 300 and sorting out useful materials and stacking the same in all leads and lifts in acquired width of road and transportation of useful material for filling in road ways, camber, embankments for grade improvements and disposal of all surplus material in required width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanical means along with its leveling, fine dressing and carriage of machineries, materials, tools, equipment and safety measures and other incidentals necessary to complete the work by mechanical means and labour if required. Any loss to the public, private property during the course of execution shall be the absolute responsibility of the contractor, which shall have to be compensated by him in all cases. The rate is including octroi, royalty, Malkana, Toll Tax, Sale tax, GST, or any other taxes imposed by the Government.	17.27	155.50	Rupees One Hundred Fifty Five And Paise Fifty Only	Per cubic meter	2685.00			
2	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental.	4.93	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	1674.00			
3	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	15.07	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	58033.00			
4	Providing and laying 100mm dia (Hundred millimeter) diameter P V C pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V). 20(1)(one vertical. twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	4.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	1068.00			
					Total:-	63460.00			
Note:- 18% GST shall be paid separately									
Amount quoted by the contractor in % Above/Below									


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Kewal Singh Rai Singh etc. Ward No.3 Village Mohal Machhot Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)

Estimated cost:- Rs.63500/- only
Earnest Money : Rs.1300/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.52	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3232.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.07	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	58033.00
3	Providing and laying, 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	3.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	801.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.26	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1434.00
					Total:-	63500.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						


Executive Engineer
Fatehpur Division HPPW
Fatehpur Distt. Kangra (HP.)

SCHEDULE OF QUANTITY

SCHEDULE OF QUANTITY									
Name of work:-Construction of Retaining wall near the house of Parshotam Singh Ward No.4 Village Kohlari Mohal Nagal Under									
SDF (D.C. Deposit) (SH:- Construction of Retaining wall)									
Estimated cost:- Rs.63500/- only									
Earnest Money : Rs.1300/- only									
Time limit:- One month									
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.52	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3232.00			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.07	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	58033.00			
3	Providing and laying, 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	3.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	801.00			
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.26	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1434.00			
					Total:-	63500.00			
Note:- 18% GST shall be paid separately									
Amount quoted by the contractor in % Above/Below									


 Executive Engineer
 Fatehpur Division HPPWT
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Construction of Retaining wall near the house of Dhayam Singh Ward No.3 SC Basti Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)

Estimated cost:- Rs.63423/- only

Earnest Money : Rs.1300/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.52	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3232.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.05	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	57956.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	3.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	801.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.26	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1434.00
					Total:-	63423.00

Note:- 18% GST shall be paid separately

Amount quoted by the contractor in % Above/Below


Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (P.)

29

SCHEDULE OF QUANTITY

Name of work:- Construction of Retaining wall near the house of Baldev Singh Ward No.5 Mohal Bari Under SDF (D.C. Deposit)					Estimated cost:- Rs.63500/- only	
(SH:- Construction of Retaining wall)					Earnest Money : Rs.1300/- only	
					Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.52	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3232.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.07	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	58033.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	3.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	801.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.26	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1434.00
					Total:-	63500.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra (P.)

86

SCHEDULE OF QUANTITY						
Name of work:-Construction of Retaining wall near the house of Mohinder Singh Ward No.3 Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)				Estimated cost:- Rs.63486/- only		
				Earnest Money : Rs.1300/- only		
				Time limit:- One month		
Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.05	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3072.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer-in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	15.07	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	58033.00
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614.709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	4.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	1068.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST.	2.07	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1313.00
					Total:-	63486.00
Note:- 18% GST shall be paid separately						
Amount quoted by the contractor in % Above/Below						

Executive Engineer
Fatehpur Division HPD/D
Fatehpur Distt. Kangra

SCHEDULE OF QUANTITY

Name of work:-Construction of Retaining wall near the house of Kuldeep Singh Ward No.3 Mohal Nagal Under SDF (D.C. Deposit)									
(SH:- Construction of Retaining wall)									
Estimated cost:- Rs.63423/- only									
Earnest Money : Rs.1300/- only									
Time limit:- One month									
Sr. No	Description of items	Quantity	Rate		Unit	Amount			
			In words	In figures					
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.52	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3232.00			
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.05	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	57956.00			
3	Providing and laying 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	3.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	801.00			
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.26	634.40	Rupees Six Hundred Thirty Four And Paise Fortv Only	Per cubic meter	1434.00			
					Total:-	63423.00			
Note:- 18% GST shall be paid separately									
Amount quoted by the contractor in % Above/Below									

Executive Engineer


Fatehpur Division HPPWD

Fatehpur Distt. Kangra



SCHEDULE OF QUANTITY

Name of work:-Construction of Retaining wall near the house of Saleem Ward No.3 Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)							Estimated cost:- Rs.63501/- only	
							Earnest Money : Rs.1300/- only	
							Time limit:- One month	
Sr. No	Description of items	Quantity	Rate		Unit	Amount		
			In words	In figures				
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing , removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.45	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3208.00		
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.04	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	57918.00		
3	Providing and laying, 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abutment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer - in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	4.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	1068.00		
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.06	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1307.00		
					Total:-	63501.00		
Note:- 18% GST shall be paid separately								
Amount quoted by the contractor in % Above/Below								


 Executive Engineer
 Fatehpur Division HPPWD
 Fatehpur Distt. Kangra (H.P.)

SCHEDULE OF QUANTITY

Name of work:-Construction of Retaining wall near the house of Narinder Kumar Ward No.3 Mohal Nagal Under SDF (D.C. Deposit) (SH:- Construction of Retaining wall)

Estimated cost:- Rs.63304/- only
Earnest Money : Rs.1300/- only

Time limit:- One month

Sr. No	Description of items	Quantity	Rate		Unit	Amount
			In words	In figures		
1	Earth work in excavation for foundation of structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rock chiseling /wedging out rocks (Where blasting is prohibited) as per drawings and M.O.R.D. technical specification clause 305.1 section 300 and as per direction of the Engineer- In - Charge including setting out, shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto any lead and upto any lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (one hundred fifty millimeter) compacted thickness of each layers including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per entire satisfaction and the direction of Engineer-in-Charge. Including carriage of materials within all leads and lifts and other incidental .	9.17	339.50	Rupees Three Hundred Thirty Nine And Paise Fifty Only	Per cubic meter	3113.00
2	Providing and laying mechanically mixed and vibrated plain cement concrete in open foundation for all type of structure complete of nominal mix 1:4:8 (One cement isto four sand isto eight graded crushed/ broken stone aggregate 40mm (forty millimeter) nominal size in or under water including curing complete and pumping or bailing out water, dewatering, removal of slush as required at site which may arise at the time of laying under water complete for all heights/ depths including the cost of form work complete in all respect as per drawing and M.O.R.D. technical specification sections and as per the entire satisfaction and direction of the Engineer -in-Charge and carriage of materials within all lead, and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	15.05	3850.90	Rupees Three Thousand Eight Hundred Fifty And Paise Ninety Only	Per cubic meter	57956.00
3	Providing and laying, 100mm dia (Hundred millimeter) diameter P.V.C. pipe having pressure not less than 4.5 kilogram (four point five kilogram) per centimetre square weep holes in brick masonry/ stone masonry, plain/reinforced concrete abatment, wing wall, return wall and retaining/breast walls through the full width of the structures with slope of 1(V): 20(H)(one vertical: twenty horizontal) towards drainage face complete as per drawing and M.O.R.D. technical specifications clause 614,709,1204.3.7 and as per direction of Engineer in- Charge including carriage of materials within all leads and lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	3.00	267.00	Rupees Two Hundred Sixty Seven Only	Each	801.00
4	Back filling with granular material behind abutments, wing wall and return wall complete as per drawing and M.O.R.D. technical specifications section 1200 and 1600 as per direction of Engineer - in- Charge including carriage of materials within all leads, lifts and other incidental . The rate is including octroi, royalty, Malkana, toll tax, sale tax and any other taxes imposed by the Government but excluding GST .	2.26	634.40	Rupees Six Hundred Thirty Four And Paise Forty Only	Per cubic meter	1434.00
					Total:-	63304.00
	Note:- 18% GST shall be paid separately					
	Amount quoted by the contractor in % Above/Below					

Executive Engineer
Fatehpur Division HPPWD
Fatehpur Distt. Kangra

11/11-27
2026-27

29