



HIMACHAL PRADESH PUBLIC WORKS DEPARTMENT

Office of the Executive Engineer National Highway Division HPPWD Theog.

Email: eeenh-theog-hp@gov.in Phone/ Fax No.: 01783-238900

NO.PW.TH.D/CB/TENDER/Tender Notice/2026

3080-82

Dated:- 01-10-2026

To

The Executive Engineer,(IT)
Nigam Vihar Shimla 2

Subject:- Publication of tender Notice.

Enclosed please find herewith the Tender Notice of the works as given in the Notice inviting Tender for uploading on department website as per Notification Pr. Secy. (PW)) to the Govt. of HP letter No PBW(B)A(3)1/2024 dated 03.01.2024 as the work mentioned in the tender notice are urgent in nature and in public interest.

Encl:- Schedule of Quantity.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Copy forwarded to the Superintending Engineer NH Circle Shimla HP PWD for information please.

Copy forwarded to the Computer Cell O/O Executive Engineer(IT) Cell), Nigam Vihar Shimla-2 for information and further necessary action please.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Himachal Pradesh
Public Works Department
Notice Inviting Tender

Executive Engineer NH Division HP PWD Theog for the following works on behalf of the Governor of Himachal Pradesh from the eligible contractors enlisted in HP PWD so as to reach in this office as per time schedule Given below:-

1	Date of receipt of Applications for tender forms:	09.10.2026 upto 12:00 PM
2	Date of issue/sale of Tender forms:-	09.10.2026 upto 4:00 PM
3	Date of receipt of Tender:-	12.10.2026 upto 10:30 AM
4	Date of opening of Tender	12.10.2026 upto 11:00 AM

Sr. No	Job No.	Name of Works	Estimated Cost	Earnest Money	Cost of form	Time Period for completion
1	1	R/R damages on NH 705 Theog Kotkhai Hatkoti Road Km 0/00 to 69/0(SH: C/o R/wall in PCC M15 at 29/513 to 29/515)	97801/-	2000/-	350/-	1 Month
2	2	R/R damages on NH 705 Theog Kotkhai Hatkoti Road Km 0/00 to 69/0(SH: C/o R/wall in PCC M15 at 29/510 to 29/512)	97830/-	2000/-	350/-	1 Month
3	3	R/R damages on NH 705 Theog Kotkhai Hatkoti Road Km 0/00 to 69/0(SH: C/o B/Wall in PCC M 15 at 0/870 to 0/875)	95562/-	2000/-	350/-	1 Month
4	4	R/R damages on NH 705 Theog Kotkhai Hatkoti Road Km 0/00 to 69/0(SH: C/o B/Wall in PCC M 15 at 0/876 to 0/881)	95317/-	2000/-	350/-	1 Month
5	5	R/R damages on NH 705 Theog Kotkhai Hatkoti Road Km 0/00 to 69/0(SH: C/o V-shape drain in PCC M15 at 0/510 to 0/571)	97926/-	2000/-	350/-	1 Month
6	6	R/R damages on NH 705 Theog Kotkhai Hatkoti Road Km 0/00 to 69/0(SH: C/o V-shape drain in PCC M15 at 4/700 to 4/760)	96339/-	2000/-	350/-	1 Month

Terms & Conditions:- The tender documents shall be issued to those contractors/firms who fulfill the following documents with the application:

- 1 The valid enlistment/ registration of contractor in appropriate class.
- 2 Permanent Account Number(PAN)
- 3 GST Number and EPF No.
- 4 Earnest Money in the shape of National saving certificate/Time deposit account in any of the Post office in HP FDR from Tender form for the above works should be submitted with the application for the purchase of the tender forms. The application received without earnest money & Cost tender form shall summarily be rejected.
- 5 Ambiguous/telegraphic/Conditional tender of tender by fax/ E-mail shall not be entertained/considered and will summarily be rejected.
- 6 Executive Engineer reserves the right to reject or cancel any or all the tenders without assigning any reasons.
- 7 The offer of the tender shall remain valid upto 120 days after the opening of tender.
- 8 If the date given above happens to be a holiday, the same shall be processed on next working days.
- 9 The Contractors/firm must quote their rates in words as well as in figures failing which Xen reserves the right to accept/reject any or all tenders.
- 10 The Tender form will not be issued to those contractors/firms whose previous performance is not found satisfactory and who have not executed/completed the previous awarded works within the stipulated period of completion.
- 11 One Contractor should not have more than two works in hand at a time.
- 12 Works should be completed by the contractor within the stipulated period.

No/PW/NH/CB/Tender/2026-27-

3076-79

Copy forwarded for information and necessary actions to:

- 1 The Superintending Engineer NH Circle HP PWD Shimla .
- 2 All the Assistant Engineer working under this Division
- 3 The Drawing Branch/Account Branch in this office.
- 4 Notice Board.

Shakun
Executive Engineer,
NH Division,
H.P.P.W.D., Theog

Dated - 01-10-2026

Executive Engineer,
NH Division,
H.P.P.W.D., Theog



NATIONAL HIGHWAY (NH-05)
HIMACHAL PRADESH PUBLIC WORKS DE
PARTMENT DIVISION THEOG

Certificate

Certified that the tenders of works as called
vide this office NIT No/PW/NH/CB/Tender/2026-27-3076-79 Dated - 01-10-2026
are urgent nature and public interest.


Executive Engineer,
NH Division,
H.P.P.W.D., Theog

SCHEDULE OF QUANTITY

		Estimated Cost:		Rs. - 97801		
		Earnest Money		Rs. - 2000.00		
		Time.		1 Month		
Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 Km 0/00 to 69/00 (SH: C/O R/Wall in PCC M15 at 29/513 to 29/515)						
Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	5.55	Per Cum.	201.15	(RsFive Hundred Forty Three & Paisa Five)Only	1116.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	11.39	Per Cum.	7720.55	Rupees Three Hundred Fifty Only	87937.00
3	Providing and layingof filter mdia with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	4.00	Per Rmt.	2064.00	Rupees Five Thousand Five Hundred Eighty Five and Paisa eighty Six Only)	8256.00
4	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	2.04	Per Cum.	241.00	Rupees Nine Thousands	492.00
Total						97801.00
(Quoted Rates in Figures)(+/-%)				(.....%)		
(Quoted Rates in words)(+/-%)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


Executive Engineer,
NH Division HPPWD,
Theog.

SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:-	97830
				Earnest Money	Rs:-	2000.00
				Time.		1 Month
Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 Km 0/00 to 69/00 (SH: C/O R/Wall in PCC M15 at 29/510 to 29/512)						
Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining eath locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	5.55	Per Cum.	201.15	(RsFive Hundred Forty Three & Paisa Five)Only	1116.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	11.39	Per Cum.	7720.55	Rupees Three Hundred Fifty Only	87937.00
3	Providing and layingof filter mdia with granular material/stone crushed aggregate satisfying the requirements laid down in clause 2504.2.2 of MoRTH specifications to a thickness of not less than 600 mm (six hundred millimetre) with smaller size towards the soil and bigger size towards the wall and provided over the entire surface behind retaining walls abutment , wing wall and return walls to the full height compacted to a firm condition complete as per drawing and technical Specification, as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport etc.	4.00	Per Rmt.	2064.00	Rupees Five Thousand Five Hundred Eighty Five and Paisa eighty Six Only)	8256.00
4	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	2.16	Per Cum.	241.00	Rupees Nine Thousands	521.00
Total						97830.00
(Quoted Rates in Figures)(+/ -)				(.....%)		
(Quoted Rates in words)(+/ -)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

				Estimated Cost:		Rs. -	95562
				Earnest Money		Rs. -	2000.00
				Time.		1 Month	
Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 Km 0/00 to 69/00 (SH: C/O B/Wall in PCC M15 at 0/870 to 0/875)							
Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount	
				In figure	In words		
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	12.20	Per Cum.	201 15	Rupees Two Hundred one and Paisa Fifteen only)	2454.00	
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	11.81	Per Cum.	7720.55	Rupees Seven Thousands Seven Hundred Twenty and Paisa Fifty Five only	91180.00	
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge.etc.	8.00	Per Cum.	241.00	RupeesTwo Hundred Forty One Only	1928.00	
Total						95562.00	
(Quoted Rates in Figures)(+-)				(.....%)			
(Quoted Rates in words)(+-)				(.....%)			

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

				Estimated Cost:	Rs:- 95317
				Earnest Money	Rs:- 2000.00
				Time.	1 Month
Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 Km 0/00 to 69/00 (SH: C/O B/Wall in PCC M15 at 0/876 to 0/881)					
Sr.N o.	Description of item	Quantity	Unit.	Rate	
				In figure	In words
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private property during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	10.98	Per Cum.	201.15	Rupees Two Hundred one and Paise Fifteen only)
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	11.81	Per Cum.	7720.55	Rupees Seven Thousands Seven Hundred Twenty and Paise Fifty Five only
3	Providing weep holes in Brick masonry/plain /reinforced concrete abutment,wing wall/return wall with 100 mm dia.AC pipe extending through the full width of the structure with slop of IV : 20 H towards drawing complete as per drawing and Technical Specifications and as per direction of the Engineer-in-Charge in all leads and lifts and carriage of materials by all means of transport as per the direction by the Engineer-in-charge etc.	8.00	Per Cum.	241.00	Rupees Two Hundred Forty One Only
Total					95317.00
(Quoted Rates in Figures)(+/-)				(..... %)	
(Quoted Rates in words)(+/-)				(..... %)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

Estimated Cost: Rs:- 97926
 Earnest Money Rs:- 2000.00
 Time. 1 Month

Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 Km 0/00 to 69/00 (SH: C/O V-shape drain in PCC M15 at 0/510 to 0/571)

Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	12.81	Per Cum.	201.15	Rupees Two Hundred one and Paise Fifteen only)	2577.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	12.35	Per Cum.	7720.55	Rupees Seven Thousands Seven Hundred Twenty and Paise Fifty Five only	95349.00
	Total					97926.00
	(Quoted Rates in Figures)(+/-)				(.....%)	
	(Quoted Rates in words)(+/-)				(.....%)	

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.

SCHEDULE OF QUANTITY

		Estimated Cost:		Rs.:-	96339	
		Earnest Money		Rs.:-	2000.00	
		Time.		1 Month		
Name of Work: R/R Damages on Theog Kotkhai Hatkoti Road NH-705 Km 0/00 to 69/00 (SH: C/O V-shape drain in PCC M15 at 4700 to 4760)						
Sr.N o.	Description of item	Quantity	Unit.	Rate		Amount
				In figure	In words	
1	Excavation for Structures .Earth work in excavation of foundation of structures as per drawings and technical specifications clause 304, including setting out, construction of shoring and bracing ,removal of slumps and other deleterious matter ,dressing of sides and bottom , back filling the excavation earth to the extent required and utilising the remaining earth locally for road work Ordinary Soil Manual Means , stacking the useful materials and disposal of unserviceable materials in all leads & lifts . Any loss to public /private poperty during course of excavation shall be the whole responsibility of the contractor including carriage of materials and equipment in all leads and lifts by all modes of transportation as per the direction by the Engineer-in-charge.	12.60	Per Cum.	201.15	Rupees Two Hundred one and Paise Fifteen only)	2534.00
2	Providing and laying Plain Cement Concrete in M15 Grade in open Foundation complete as per Drawing and technical specifications clause 1500,1700,2100 , in all leads, lifts and carriage of materials by all means of transport etc. as per direction of the Engineer-in-Charge.	12.15	Per Cum.	7720.55	Rupees Seven Thousands Seven Hundred Twenty and Paise Fifty Five only	93805.00
Total						96339.00
(Quoted Rates in Figures)(+/ -)				(.....%)		
(Quoted Rates in words)(+/ -)				(.....%)		

Conditions

- 1 Rates shall be Quoted for all heights including all leads and lifts.
- 2 The Contractor shall procure all the materials conforming to the specification of MORTH at his own risk and cost


 Executive Engineer,
 NH Division HPPWD,
 Theog.