

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-DPD-CB-Tender/2026-27-
To

15816

Dated:- 9.10.2026

The Chief Engineer (HZ),
Himachal Pradesh, PWD,
Hamirpur (HP).


Subject: Publication of tender Notice on departmental site.

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification of Secretary (PW) to the Govt. of HP vide notification No. PBW(B)A(3)1/2024 Dated 03/01/2025 and further in compliance of Engineer-inChief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICTWing/website dt. 22/05/2026 as the matter is of urgent nature and in public interest,

It is therefore requested to kindly get it published on departmental website before 17.10.2026.

Certified that the work mentioned in the Tender Notice are urgent in nature.

DA:- As above


Executive Engineer,
Dharampur Division,
HP.PWD. Dharampur.

H.P P W D NOTICE INVITING TENDER

The **percentage** rate off line tender notice on the form 6 & 8 are invited by the Executive Engineer, Dharampur Division, HPPWD Dharampur on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|--------------------------|
| 1 Date and time of receipt of application for the tender form : | 17-10 -2026 upto 4.00 PM |
| 2 Date and time of issue of tender form : | 19-10 -2026 upto 4.00 PM |
| 3 Date and time of receipt of tenders: | 21-10-2026 upto 11.00 AM |
| 4. Date and time of opening of tenders: | 21-10-2026 at 11.30 AM |

The tender form will be issued against cash payment (non refundable), the **earnest money in the shape of NSC/FDR/Deposit** at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dharampur Division, HPPWD Dharampur must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.

Sr. No	Name of Works	Estimated Cost (in Rs)	EMD (in Rs.)	Time Limit
1	R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- Providing and fixing " W" Metal beam crash at 19/600 to 19/720)PDNA 25	4,87,415/-	10,000/-	Two Months
2	R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- C/O wire crate wall at RD 21/345 to 21/360) PDNA 25	2,85,575/-	10,000/-	Two Months
3	R Damages on Kun to Kamlah road Km 0/00 to 6/00 (SH :- C/O PCC R/Wall at RD 2/450 to 2/465) PDNA 25	4,49,013/-	10,000/-	Two Months
4	R/R Damages on Khudi to Gwella Road Km 0/00 to 2/00 (SH :- Providing and laying C.C Pavement at RD 1/400 to 1/480) PDNA 25	2,84,071/-	6,000/-	Two Months
5	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- C/O Wire crate at RD 23/990 to 24/00) PDNA 25	1,90,513/-	4,000/-	Two Months
6	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- Providing and laying C.C. Pavement at RD 24/525 to 24/610 & 27/105 to 27/130) PDNA 25	4,99,906/-	10,000/-	Two Months
7	R/R Damage on Trohla Richali Manudhar Road Km 0/00 to 4/900 (SH: C/O pCC R/wall at RD 1/100 to 1/112)	3,02,040/-	6,100/-	Two Months
8	R/R damages on various road under Sandhole Section Sub Division Marhi (SH:- Removal of slips, Maintenance of Earthen shoulder and C/O of unlined Surface Drains).	1,04,384/-	2,200/-	Two Months
9	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlahgaloo Road Km 0/00 to 33/00(SH :- Repair of Pot holes in Km 14/700 to 19/300)PDNA 25	4,98,559/-	10,000/-	Two Months
10	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 8/765 to 19/300(SH:- Removal of slips & Construction of unlined surface drain in Km 14/00 to 19/300)PDNA 25	4,92,580/-	10,000/-	Two Months
11	R/R Damages on Pump House to Sidhpur to Khair road Km 0/0 to 1/0 (SH :- C/O Road Embankment at RD 0/190 to 0/497)PDNA25	4,98,561/-	10,000/-	Two Months
12	R/R Damages on Narwalka to Kheri Road Km 0/00 to 5/200 (SH :- C/O PCC Wing walls for hume pipe culvert both side at Rds 3/045) NDF 2026/106	2,19,504/-	4,500/-	Two Months

13	R/R damages on various road under Sandhole Section Sub Division Marhi (SH:- Hriing of tractor).	87,750/-		Two Months
14	R/R Damages on Deyol Lassani Gowella Road Km 0/00 to 8/670 (SH :- C/O R/Wall at RD 1/970 to 1/980)	4,73,842/-	2,000/-	Two Months
15	R/R Damages on Kothwan to neri via chatron road Km 0/0 to 7/0 (SH :- Providing and laying C.C. Pavement at RD4/460 to 4/590)	4,61,615/-	10,000/-	Two Months
16	R/R Damages on Gorat Chamehar Road Km 0/0 to 4/0 and Proun Rangar Khroon Saklana Dodar Km 0/00 to 10/585 (SH :- Deployment/ Hiring of Excavator cum loader & Tipper for removal of slips hiring of Tipper in various RDs)	2,83,500/-	10,000/-	Two Months
17	R/R Damages on Sarkaghat Rissa Mandap Baroti Road Km 12/0 to 24/0 (SH :- C/O 2.00 x 2.00 mtrs span box culvert at RD 16/825) PDNA	4,78,668/-	6,000/-	Two Months
18	R/R Damages on Tihra to Kot Road Km 0/00 to 4/00 (SH :- C/O R/Wall at RD 2/330 to 2/348.50) PDNA	4,88,921/-	10,000/-	Two Months

Terms and Conditions:-

1. The contractors/firms should posses the following documents at the time of application (Photocopy to be attached):- i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.), (iii) Copy of GST registration. (iv) Copy of EPF Number, (v) Owned/Hired documentary proof of the machinery required for the work. (Vi) Cost of tender, (vii) Earnest Money.
2. The Contractors/firms are required to quote their rates both in figures and words, failing which under- signed reserve the right to accept/reject any or all tenders without assigning any reasons.
3. 1% cess charges on the amount of work awarded will be recovered from the contractor and the contractor has to get registered with Labour Officer-cum-Registering Officer-cum- Cess Collector within one month from the issue of the award letter.
4. Cost of tender form will be Rs. 350/-
5. The contractor shall furnish an affidavit stating that he/she has not more than two works in hand for execution..
6. The offer of the tender shall remain valid upto 60 days after the opening.
7. The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).

Executive Engineer,
Dharampur Division,
HP.PWD, Dharampur,
Distt: Mandi (H.P).

No.PW-DPD-CB-Tender/2026-27/

158/2-20

Dated:- 9/10/2026

Copy forwarded to the following for information and necessary action to:-

1. The Chief Engineer , Hamirpur Zone HP.PWD ,Hamirpur H.P.
2. The Superintending Engineer Dharampur Circle HP.PWD Dharampur .
3. Notice Board.
4. A/B, D/B. Of this office.

Executive Engineer,
Dharampur Division,
HP.PWD

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- Providing and fixing " W" Metal beam crash at 19/600 to 19/720)

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Estimated Cost	
				Words	Time Limit:-		Earnest Money	Two Months
1	2	3	4	5	6	7	8	9
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.59	350.2	Rupees Three Hundred Fifty Paise Twenty Only	Per cubic metre	4759	487415	10000.00
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in drains and open foundation for all type of structures complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed stone aggregate 40 (forty) millimetres) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work as per drawings and MORD technical specification 2014 clause 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.59	5444.4	Rupees Five Thousand Four Hundred FortyFour Paise Forty Only	Per Cubic Metre	73989		
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre)thick corrugated sheet metal beam rail, 70 cm(seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m(two metre) centre to centre, 1.80 m(one point eight zero metre) high, 1.10 m (one point one zero metre)below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) , 330 mm (three hundred thirty millimetre) long complete as per MORD technical specification 2014clause 810including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	120	3405.55	Rupees Three Thousand Four Hundred Five Paise FiftyFive Only	Running Metre	408666		
Total							487415	

DNIT amount approved for Rs. 487415/- vide No. 212/202627

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

214
34.3

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- C/O wire crate wall at RD 21/345 to 21/360) PCNA

Sr. No.	Description of Items	Qty.	Fig.	Rate in Words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by	32.4	350	Rupees Three Hundred Fifty Only	Per cubic metre	11340
2	Providing and laying boulder apron laid in wire crate with 4 mm dia wire confirming to IS 280 and 4826 in 100x100 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification including carriage of materials with in all leads and lifts and direction of Engineer in Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	84.38	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per Cubic Metre	274235
	Total					285575

DNIT. Amount approved for Rs 285575
Vide 88 No-214/2026-29

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

Executive Engineer,
Dharanpur Division
H.P.P.W.D., Dharam

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Khudi to Gwella Road Km 0/00 to 2/00 (SH :- Providing and laying C.C Pavement at RD 1/400 to 1/480)			Estimated Cost		284071
			Earnest Money		1000.00
			Time Limit:-		Three Months
Sr. No.	Description of Items	Qty.	Fig.	Rate in	
				Words	Amount
1	Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre) nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mn ² and minimum cement not less than 400 kg/ cum(Four hundred kilogramme per cubic metre) (with plasticizer) , coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and wa ter finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	36.00	7890.85	Rupees Seven Thousand Eight Hundred Ninety Paise EightyFive Only	284071
		Total			284071

*DNIT. amount approved for Rs. 284071/-
Vides No. 217/2026-27*

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

218
40.8

DRAFT SCHEDULE OF QUANTITY									
Name of Work:- R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- C/O Wire crate at RD 23/990 to 24/00)				Estimated Cost			190513		
				Earnest Money			4000.00		
				Time Limit:-			Two Months		
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount			
			Fig.	Words					
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by	22	4	350	Per cubic metre	7700			
2	Providing and laying boulder apron laid in wire crate with 4 mm dia wire conforming to IS 280 and 4826 in 100x100 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification including carriage of materials with in all leads and lifts and direction of Engineer in Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.25	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per Cubic Metre	182813			
		Total				190513			

DNIT amount approved for Rs 190513/-
Vides No 218/2026-27

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- Providing and laying C.C. Pavement at RD 24/525 to 24/610 & 27/105 to 27/130)				Estimated Cost		499906	
				Earnest Money		10000.00	
				Time Limit:-		Three Months	
r. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	2	3	4	5	6	7	
1	Stone soling properly hand packed filling interstices with kharanja stone and consolidating complete to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 100mm (one hundred millimetre)spread thickness (finished workincluding materials and labour) including the hauling of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	44.55	1576.85	Rupees One Thousand Five Hundred SeventySix Paise EightyFive Only	Per Cubic Metre	70249	
2	Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre)nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mn2 and minimum cement not less then 400 kg/ cum(Four hundred kilogramme per cubic metre) (with plasticizer) , coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and wa ter finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	54.45	7890.85	Rupees Seven Thousand Eight Hundred Ninety Paise EightyFive Only	Per Cubic Metre	429657	
Total							499906

*PNIT. amount approved for Rs. 499906/-
vide No. 219/2026-29*

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

220
1.3

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Trohla Richali Manudhar Road Km. 0/0 to 4/900 (SH:- C/O PCC R/Wall at RD Km. 1/100 to 1/112)			Estimated Cost		302040
			Earnest Money		6000
			Time Limit:-		Three Months

No.	Description of Items	Qty.	Rate in		Unit	Amount	
			Fig.	Words			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	27.6	350	Rupees Three Hundred Fifty Only	Per cubic metre	9660	
2	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	63.54	4463.05	Rupees Four Thousand Four Hundred Sixty Three Paise Five Only	Per cubic metre	283582	
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614.709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30	293.25	Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	8798	
Total						302040	

*DNIT. amount approved for Rs. 302040/-
Vidya No 220/ 20 26-27*

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY						
Name of Work :-R/R Damages on various roads under Sandhole Section Sub Division Marhi(SH:- Removal of slips,maintenance of earthen shoulder & Construction of unlined surface drain)				Estimated cost :- Earnest Money:- Time Limit		
Description of item/Sub Head				Rates		
Sr.No	Quantity	In Figure	In words	Unit	Amount	Two Months
1	3	4	5	6	7	
1	233.40	110.00	Rupees One Hundred Ten Only	Per Cubic Metre	25674	
2	3110.25	21.50	Rupees twenty one point five Only	Per Square Metrer	66870	
3	320.00	37.00	Rupees ThirtySeven Only	Per Square Metre	11840	
				Total:-	104384	

DN17 amount approved for Rs. 104384/-
Vide Sr No 222/202629

Executive Engineer,
Dharanpur Division
H.P.P.W.D. Dharampur

222
34.4

DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/R Damages on Baroti Rakhara Dharampur Marhi Kamlahgaloo Road Km 0/00 to 33/00(SH :- Repair of Pot holes in Km 14/700 to 19/300)

Estimated cost :-
Earnest Money:-
Time Limit

498559
12000

Two Months

Sr.No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Repair of Pot Holes and removal of loose material trimming of sides , cleaning of surface by providing tack Coat, 20 mm (twenty millimetre) thick premix carpet and seal coat TYPE -B specification Clause 1904.2. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , 1 GST or other taxes imposed by the Govt.	2	3	4	5	7
		1131.02	425	Rupees Four Hundred TwentyFive Only	Per Square Metre	480684
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and key aggregates and rolling with a three wheel 80-100 kN static roller to achieve the desired degree of compaction as per Technical Specification Clause 506.The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Govt.	65.00	275	Rupees Two Hundred SeventyFive Only	Per Square Metre	17875
					Total	498559

*DNIT amount approved for Rs. 498559/-
vide No. 24/2026-27*

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

[Signature]

223
40.11

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY							
Name of Work :-R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 14/00 to19/300 (SH:- emoval of slips & Construction of unlined surface drain in Km 14/00 to 19/300)			Estimated cost :- Earnest Money:-		492580 10000		
Sr.No	Description of item/Sub Head	Quantity	Time Limit		Unit	Two Months	
			In Figure	Rates		Amount	
				In words			
1	2	3	4	5	6	7	
1	Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer - in -Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4175.27	110.00	Rupees One Hundred Ten Only	Per Cubic Metre	459280	
2	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site. The rates are inclusive of royalty, GST or other taxes imposed by the Government	900.00	37.00	Rupees ThirtySeven Only	Per Square Metre	33300	
					Total:-	492580	

DNIT amount approved for Rs. 492580/-

Vide No. 223/2026-27

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

[Signature]

226

DRAFT SCHEDULE OF QUANTITY									
ame of Work:- R/R Damages on Pump House to Sidhpur to Khair road Km 0/0 to 1/0 (SH :- C/O Road Embankment at RD									
/190 to 0/497)									
				Estimated Cost		498561			
				Earnest Money		10000.00			
				Time Limit:-		Two Months			
Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount		
				Words	5				
1	2 Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including carriage of materials with in all leads and lifts and direction of Engineer in Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1988.28	4 250.75	Rupees Two Hundred Fifty Paise SeventyFive Only	6	Per Cubic Metre	498561		
		Total					498561		

Duit amount approved For Rs 498561/-
vide S.O. 226
Executive Engineer,
Dharanpur Division
H.P.W.D., Dharampur.

me of Work:- R/R Damages on Narwalka to Kheri Road Km 0/00 to 5/200 (SH :- CIO PCC Wing walls for hume pipe culvert both side at						
Estimated Cost				219504		
Earnest Money				4500		
Time Limit:-				Three Months		
No.	Description of Items	Qty.	Fig.	Rate in		Amount
				Words	Unit	
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.05	350	Rupees Three Hundred Fifty Only	Per cubic metre	6318
2	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	46.19	4463.05	Rupees Four Thousand Four Hundred SixtyThree Paise Five Only	Per cubic metre	206148
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24	293.25	Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	7038
Total						219504

D.N.T. amount approved for Rs. 219504/-
Vide Sr No. 216/2026-27
 Executive Engineer,
 Dharampur Division
 H.P.P.W.D., Dharampur

144
30

DRAFT SCHEDULE OF QUANTITY

Name of Work: R/R Damages on various road under Sandhole Section Sub Division HPPWD Marhi (SH :-		Estimated cost :-		2000	
Description of Item/Sub Item		Earnest Money:-		2000	
Sl. No.	Description of Item/Sub Item	Quantity	Rates		Amount
			In Figure	In Words	
1	Hiring of tractor for disposal of excavated material from cutting per day. The contractor / Owner of tractor shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer - in- Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax. GST or other taxes imposed by the Government.	45.00	1950.00	(Rupees:- One thousand eight hundred and paise zero only)	87750
Total:-					87750

Unit amount approved For Rs 87750

Duit amount approved For Rs 87750/-
vide Sr No. 144

Executive Engineer
B&R Division HPPWD
Dharampur

231
117.1

DRAFT SCHEDULE OF QUANTITY									
Name of Work:- R/R Damages on Deyol Lassani Gowella Road Km 0/00 to 8/670 (SH :- C/O R/Wall at RD 1/970 to 1/980)					Estimated Cost		473842		
					Earnest Money		10000		
					Time Limit:-				
Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2	39.8	350 Rupees Three Hundred Fifty Only	Per cubic metre	7	13930		
2	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand isto Ten graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.		95	4463.05 Rupees Four Thousand Four Hundred Sixty Three Paise Five Only	Per cubic metre		423990		
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.		36	293.25 Rupees Two Hundred Ninety Three Paise Twenty Five Only	Each		10557		
4	Back filling behind abutment , wing walls and return walls complete as per drawings and MORD technical specification 2014 Clause 1204.3.8. with Granular Material and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.		25.2	1006.55 Rupees One Thousand Six Paise Fifty Five Only	Per Cubic Metre		25365		
Total							473842		

Unit amount approved for Rs 473842/- vide No 231

Executive Engineer,
Dharanpur Division
H.P.W.D., Dharampur.

(40.1)

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Kothwan to neri via chatron road Km 0/0 to 7/0 (SH :- Providing and laying C.C. Pavement at RD4/460 to 4/590)

Estimated Cost

461615

Earnest Money

40000.00

9500

Three Months

Time Limit:-

Sr. No.

Description of Items

Qty.

Fig.

Rate in Words

Unit

Amount

1

2

3

4

5

6

7

Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre)nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mm² and minimum cement not less than 400 kg/cum(Four hundred kilogramme per cubic metre) (with plasticizer) , coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and wa ter finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.

Total

461615

DNIT amount approved for 20-461615/-
Vide SS No. 224/2026-27.

Executive Engineer,

Dharampur Division

H.P.P.W.D., Dharampur

170
26.103.10

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Gorat Chamehar Road Km 0/0 to 4/0 and Proun Rangar Khroon Saklana Dodar Km 0/00 to 10/500 (S.M. Deployment/Hiring of Excavator cum loader & Tipper for removal of slips hiring of Tipper in various PDs)					Estimated Cost	
					Earnest Money	283500
					Time Limit:-	6000 00
Sl. No.	Qty	Fig	Rate in Words	Unit	Two Months	
					Amount	
1	150	4	1250.00	Per Hours	6	7
Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.					Rupees One Thousand Two Hundred Fifty Only	187500
2	30		3200.00	Per Day		96000
Hiring of tipper for disposal of excavated material from cutting having capacity of 150 cubic feet Per trip and minimum 70 Km of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.					Rupees Three Thousand Two Hundred Only	
Total						283500

*Nil amount approved for Rs. 283500/-
vide S. No 140*

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur.

227
Lab.1

DRAFT SCHEDULE OF QUANTITY									
Name of Work : R/R Damages on Sarkaghat Rissa Mandap Baroti Road Km 12/0 to 24/0 (SH :- C/O 2.00 x 2.00					Estimated cost :-				
Time span box culvert at RD 16/825) PDNA					Earnest Money:-				
					Time Limit				
Sr.No	Description of item/Sub Head	Quantity	Rates			Unit	Amount		
			In Figure	In words					
1	2	3	4	5	6	7			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of waterincluding entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	67.5	350	Rupees Three Hundred Fifty Only	Per cum	23625			
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in drains and open foundation for all type of structures complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 40 (forty) millimetres) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work as per drawings and MORD technical specification 2014 clause 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.5	4805.45	Rupees Four Thousand Eight Hundred Five Paise FortyFive Only	Per cum	21625			
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.45	4463.05	Rupees Four Thousand Four Hundred SixtyThree Paise Five Only	Per cubic metre	42176			
4	Providing and laying mechanically mixed and vibrated cement concrete for plain/reinforced concrete in super structure for all type of structures complete reinforced cement concrete 1:1.5:3 (one cement : one point five sand : three graded stone aggregate twenty millimetre nominal size) grade M-25 (M-Twenty five) design mix upto minium cement contents 406(Four hundred six) Killograme per Cubic metre for all heights/depts including the cost of form work and curing complete as per technical specification clause 802, 1205.4 & 1205.5 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.62	7652.9	Rupees Seven Thousand Six Hundred FiftyTwo Paise Ninety Only	Per cum	165456			
5	Supplying, fitting, and placing HYSD bar reinforcement (Fe 415) in substructure including binding wire complete as per technical specifications clauses 1002, 1005, 1010 & 1202 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2378.53	92.25	Rupees NinetyTwo Paise TwentyFive Only	Per Killograme	219419			

7	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogram) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614.709, 1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4	293.25	Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	1173
	Back filling behind abutment , wing walls and return walls complete as per drawings and MORD technical specification 2014 Clause 1204.3.8. with Granular Material and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.16	1006.55	Rupees One Thousand Six Paise FiftyFive Only	Per Cubic Metre	5194
Total:-						478668

Unit amount approved for Rs 478668/- vide Sr.No. 227

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY						
Name of Work:- R/R Damages on Thira to Kot Road Km 0/00 to 4/00 (SH :- C/O R/Wall at RD 2/330 to 2/348.50) PDNA			Estimated Cost		488921	
			Earnest Money		10000	
Sl. No.	Qty	Rate in Fig.	Words	Two Months		Amount
				Unit	Unit	
1	2	40.15	350	Rupees Three Hundred Fifty Only	Per cubic metre	14053
Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.						
2	97.87	4463.05		Rupees Four Thousand Four Hundred SixtyThree Paise Five Only	Per cubic metre	436799
Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.						
3	46	293.25		Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	13490
Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.						
4	24.42	1006.55		Rupees One Thousand Six Paise FiftyFive Only	Per Cubic Metre	24580
Back filling behind abutment , wing walls and return walls complete as per drawings and MORD technical specification 2014 Clause 1204.3.8. with Granular Material and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.						
Total						488921

Don't amount approved for Rs 488921/-
vide 8.6.18/85

Executive Engineer,
Dharanpur Division
H.P.P.W.D., Dharampur

H.P P W D NOTICE INVITING TENDER

The **percentage** rate off line tender notice on the form 6 & 8 are invited by the Executive Engineer, Dharampur Division, HPPWD Dharampur on behalf of Governor of HP for the following works from the approved and eligible contractor enlisted in HPPWD.

TENDER SCHEDULE:

- | | |
|---|--------------------------|
| 1 Date and time of receipt of application for the tender form : | 17-10 -2026 upto 4.00 PM |
| 2 Date and time of issue of tender form : | 19-10 -2026 upto 4.00 PM |
| 3 Date and time of receipt of tenders: | 21-10-2026 upto 11.00 AM |
| 4. Date and time of opening of tenders: | 21-10-2026 at 11.30 AM |

The tender form will be issued against cash payment (non refundable), the **earnest money in the shape of NSC/FDR/Deposit** at call of any Post Office/Bank in H.P duly pledged in the name of the Executive Engineer, Dharampur Division, HPPWD Dharampur must accompany with each tender. Conditional tender and tender received without earnest money will summarily be rejected.

Sr. No	Name of Works	Estimated Cost (in Rs)	EMD (in Rs.)	Time Limit
1	R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- Providing and fixing " W" Metal beam crash at 19/600 to 19/720)PDNA 25	4,87,415/-	10,000/-	Two Months
2	R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- C/O wire crate wall at RD 21/345 to 21/360) PDNA 25	2,85,575/-	10,000/-	Two Months
3	R Damages on Kun to Kamlah road Km 0/00 to 6/00 (SH :- C/O PCC R/Wall at RD 2/450 to 2/465) PDNA 25	4,49,013/-	10,000/-	Two Months
4	R/R Damages on Khudi to Gwella Road Km 0/00 to 2/00 (SH :- Providing and laying C.C Pavement at RD 1/400 to 1/480) PDNA 25	2,84,071/-	6,000/-	Two Months
5	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- C/O Wire crate at RD 23/990 to 24/00) PDNA 25	1,90,513/-	4,000/-	Two Months
6	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- Providing and laying C.C. Pavement at RD 24/525 to 24/610 & 27/105 to 27/130) PDNA 25	4,99,906/-	10,000/-	Two Months
7	R/R Damage on Trohla Richali Manudhar Road Km 0/00 to 4/900 (SH: C/O pCC R/wall at RD 1/100 to 1/112)	3,02,040/-	6,100/-	Two Months
8	R/R damages on various road under Sandhole Section Sub Division Marhi (SH:- Removal of slips, Maintenance of Earthen shoulder and C/O of unlined Surface Drains).	1,04,384/-	2,200/-	Two Months
9	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlahgaloo Road Km 0/00 to 33/00(SH :- Repair of Pot holes in Km 14/700 to 19/300)PDNA 25	4,98,559/-	10,000/-	Two Months
10	R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 8/765 to 19/300(SH:- Removal of slips & Construction of unlined surface drain in Km 14/00 to 19/300)PDNA 25	4,92,580/-	10,000/-	Two Months
11	R/R Damages on Pump House to Sidhpur to Khair road Km 0/0 to 1/0 (SH :- C/O Road Embankment at RD 0/190 to 0/497)PDNA25	4,98,561/-	10,000/-	Two Months
12	R/R Damages on Narwalka to Kheri Road Km 0/00 to 5/200 (SH :- C/O PCC Wing walls for hume pipe culvert both side at Rds 3/045) NDF 2026/106	2,19,504/-	4,500/-	Two Months

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

No. PW-DPD-CB-Tender/2026-27- 15816
To

Dated:- 9.10.2026

The Chief Engineer (HZ),
Himachal Pradesh, PWD,
Hamirpur (HP).


Subject: Publication of tender Notice on departmental site.

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification of Secretary (PW) to the Govt. of HP vide notification No. PBW(B)A(3)1/2024 Dated 03/01/2025 and further in compliance of Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No. PWD/ICTWing/website dt. 22/05/2026 as the matter is of urgent nature and in public interest,

It is therefore requested to kindly get it published on departmental website before 17.10.2026.

Certified that the work mentioned in the Tender Notice are urgent in nature.

DA:- As above


Executive Engineer,
Dharampur Division,
HP.PWD. Dharampur.

13	R/R damages on various road under Sandhole Section Sub Division Marhi (SH:- Hriing of tractor).	87,750/-		Two Months
14	R/R Damages on Deyol Lassani Gowella Road Km 0/00 to 8/670 (SH :- C/O R/Wall at RD 1/970 to 1/980)	4,73,842/-	2,000/-	Two Months
15	R/R Damages on Kothwan to neri via chatron road Km 0/0 to 7/0 (SH :- Providing and laying C.C. Pavement at RD4/460 to 4/590)	4,61,615/-	10,000/-	Two Months
16	R/R Damages on Gorat Chamehar Road Km 0/0 to 4/0 and Proun Rangar Khroon Saklana Dodar Km 0/00 to 10/585 (SH :- Deployment/ Hiring of Excavator cum loader & Tipper for removal of slips hiring of Tipper in various RDs)	2,83,500/-	10,000/-	Two Months
17	R/R Damages on Sarkaghat Rissa Mandap Baroti Road Km 12/0 to 24/0 (SH :- C/O 2.00 x 2.00 mtrs span box culvert at RD 16/825) PDNA	4,78,668/-	6,000/-	Two Months
18	R/R Damages on Tihra to Kot Road Km 0/00 to 4/00 (SH :- C/O R/Wall at RD 2/330 to 2/348.50) PDNA	4,88,921/-	10,000/-	Two Months

Terms and Conditions:-

1. The contractors/firms should posses the following documents at the time of application (Photocopy to be attached):- i) Latest renewal of enlistment. (ii) PAN (Permanent Account No.), (iii) Copy of GST registration. (iv) Copy of EPF Number, (v) Owned/Hired documentary proof of the machinery required for the work. (Vi) Cost of tender, (vii) Earnest Money.
2. The Contractors/firms are required to quote their rates both in figures and words, failing which under- signed reserve the right to accept/reject any or all tenders without assigning any reasons.
3. 1% cess charges on the amount of work awarded will be recovered from the contractor and the contractor has to get registered with Labour Officer-cum-Registering Officer-cum- Cess Collector within one month from the issue of the award letter.
4. Cost of tender form will be Rs. 350/-
5. The contractor shall furnish an affidavit stating that he/she has not more than two works in hand for execution..
6. The offer of the tender shall remain valid upto 60 days after the opening.
7. The Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason(s).

Executive Engineer,
Dharampur Division,
HP.PWD, Dharampur,
Distt: Mandi (H.P).

No.PW-DPD-CB-Tender/2026-27/

158/2-20

Dated:- 9/10/2026

Copy forwarded to the following for information and necessary action to:-

1. The Chief Engineer , Hamirpur Zone HP.PWD ,Hamirpur H.P.
2. The Superintending Engineer Dharampur Circle HP.PWD Dharampur .
3. Notice Board.
4. A/B, D/B. Of this office.

Executive Engineer,
Dharampur Division,
HP.PWD

216
331

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- Providing and fixing " W" Metal beam crash at 19/600 to 19/720)

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Estimated Cost	
				Words	Time Limit:-		Earnest Money	Two Months
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.59	350.2	4	5	6	7	487415
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in drains and open foundation for all type of structures complete of plain cement concrete nominal mix 1:3:6 (One cement : three sand : six graded crushed stone aggregate 40 (forty) millimetres) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depths including the cost of form work as per drawings and MORD technical specification 2014 clause 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	13.59	5444.4			Per Cubic Metre	73989	
3	Providing and erecting a "W" metal beam crash barrier comprising of 3 mm (three millimetre)thick corrugated sheet metal beam rail, 70 cm(seventy centimetre) above road/ground level, fixed on ISMC series channel vertical post, 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) spaced 2 m(two metre) centre to centre, 1.80 m(one point eight zero metre) high, 1.10 m (one point one zero metre)below ground/road level, all steel parts and fitments to be galvanised by hot dip process, all fittings to conform to IS:1367 and IS:1364, metal beam rail to be fixed on the vertical post with a spacer of channel section 150 x 75 x 5 mm (one hundred fifty into seventy five into five millimetre) , 330 mm (three hundred thirty millimetre) long complete as per MORD technical specification 2014clause 810including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	120	3405.55			Running Metre	408666	
Total							487415	

DNIT amount approved for Rs. 487415/-
vide No. 212/202627

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

214
34.3

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Sandhole Marhi Dharampur Road Km 0/00 to 23/0 (SH :- C/O wire crate wall at RD 21/345 to 21/360) PCNA

Sr. No.	Description of Items	Qty.	Fig.	Rate in Words	Unit	Amount
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by	32.4	350	Rupees Three Hundred Fifty Only	Per cubic metre	11340
2	Providing and laying boulder apron laid in wire crate with 4 mm dia wire confirming to IS 280 and 4826 in 100x100 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification including carriage of materials with in all leads and lifts and direction of Engineer in Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	84.38	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per Cubic Metre	274235
Total						285575

DNIT. Amount approved for Rs 285575
Vide 88 No-214/2026-29

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Khudi to Gwella Road Km 0/00 to 2/00 (SH :- Providing and laying C.C Pavement at RD 1/400

to 1/480)

Estimated Cost

Earnest Money

Time Limit:-

284071

1000.00

Three Months

Sr. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words	5		
1	Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre)nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mn ² and minimum cement not less than 400 kg/ cum(Four hundred kilogramme per cubic metre) (with plasticizer) , coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and wa ter finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	36.00	7890.85	Rupees Seven Thousand Eight Hundred Ninety Paise EightyFive Only	Per Cubic Metre	284071	
Total							284071

*DNIT. amount approved for Rs. 284071/-
vide No. 217/2026-27*

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

218
40.8

DRAFT SCHEDULE OF QUANTITY									
Name of Work:- R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- C/O Wire crate at RD 23/990 to 24/00)				Estimated Cost			190513		
				Earnest Money			4000.00		
				Time Limit:-			Two Months		
Sr. No.	Description of Items	Qty.	Rate in		Unit	Amount			
			Fig.	Words					
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by	22	4	350 Rupees Three Hundred Fifty Only	Per cubic metre	7700			
2	Providing and laying boulder apron laid in wire crate with 4 mm dia wire conforming to IS 280 and 4826 in 100x100 mm mesh (Woven diagonally) including 10% extra for laps and joints laid with stone boulder weighing not less than 25 Kg each as per drawing and technical specification including carriage of materials with in all leads and lifts and direction of Engineer in Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	56.25	3250.00	Rupees Three Thousand Two Hundred Fifty Only	Per Cubic Metre	182813			
		Total				190513			

DNIT amount approved for Rs 190513/-
Vides No 218/2026-27

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY

ame of Work:- R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 0/00 to 30/375 (SH :- Providing and ying C.C. Pavement at RD 24/525 to 24/610 & 27/105 to 27/130)				Estimated Cost		499906	
				Earnest Money		10000.00	
				Time Limit:-		Three Months	
r. No.	Description of Items	Qty.	Fig.	Rate in		Unit	Amount
				Words			
1	2	3	4	5	6	7	
1	Stone soling properly hand packed filling interstices with kharanja stone and consolidating complete to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD. specification. 100mm (one hundred millimetre)spread thickness (finished workincluding materials and labour) including the hauling of materials in all leads and lifts as per the entire satisfaction and direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	44.55	1576.85	Rupees One Thousand Five Hundred SeventySix Paise EightyFive Only	Per Cubic Metre	70249	
2	Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre)nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mn2 and minimum cement not less then 400 kg/ cum(Four hundred kilogramme per cubic metre) (with plasticizer) , coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and wa ter finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.	54.45	7890.85	Rupees Seven Thousand Eight Hundred Ninety Paise EightyFive Only	Per Cubic Metre	429657	
Total							499906

DNIT amount approved for Rs. 499906/-
Vide No. 219/2026-29

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY

Work:- R/R Damages on Trohla Richali Manudhar Road Km. 0/0 to 4/900 (SH:- C/O PCC R/Wall at RD Km. 1/100 to 1/112)

Estimated Cost	302040
Earnest Money	6000
Time Limit:-	Three Months

No.	Description of Items	Qty.	Rate in		Unit	Amount	
			Fig.	Words			
1		2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the	27.6	350	Rupees Three Hundred Fifty Only	Per cubic metre	9660	
2	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	63.54	4463.05	Rupees Four Thousand Four Hundred SixtyThree Paise Five Only	Per cubic metre	283582	
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614.709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	30	293.25	Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	8798	
	Total						302040

*DNIT. amount approved for Rs. 302040/-
Vidya No 220/ 20 26-27*

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY						
Name of Work :-R/R Damages on various roads under Sandhole Section Sub Division Marhi(SH:- Removal of slips,maintenance of earthen shoulder & Construction of unlined surface drain)				Estimated cost :- Earnest Money:- Time Limit		
Description of item/Sub Head				Two Months		
Sr.No	Quantity	In Figure	In words	Unit	Amount	
1	3	4	5	6	7	
1	233.40	110.00	Rupees One Hundred Ten Only	Per Cubic Metre	25674	
2	3110.25	21.50	Rupees twenty one point five Only	Per Square Metrer	66870	
3	320.00	37.00	Rupees ThirtySeven Only	Per Square Metre	11840	
				Total:-	104384	

DN17 amount approved for Rs. 104384/-

Vide Sr No 222/202629
Executive Engineer,
Dharanpur Division
H.P.P.W.D. Dharampur

2

222
34.4

DRAFT SCHEDULE OF QUANTITY

Name of Work :- R/R Damages on Baroti Rakhara Dharampur Marhi Kamlaahgaloo Road Km 0/00 to 33/00(SH :- Repair of Pot holes in Km 14/700 to 19/300)

Estimated cost :-
Earnest Money:-
Time Limit

498559
12000
Two Months

Sr.No	Description of item/Sub Head	Quantity	Rates		Unit	Amount
			In Figure	In words		
1	Repair of Pot Holes and removal of loose material trimming of sides , cleaning of surface by providing tack Coat, 20 mm (twenty millimetre) thick premix carpet and seal coat TYPE -B specification Clause 1904.2. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , 1 GST or other taxes imposed by the Govt.	2	3	4	5	7
		1131.02	425	Rupees Four Hundred TwentyFive Only	Per Square Metre	480684
2	Construction of penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate using chips spreader with alternate applications of bituminous binder and key aggregates and rolling with a three wheel 80-100 kN static roller to achieve the desired degree of compaction as per Technical Specification Clause 506.The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Govt.	65.00	275	Rupees Two Hundred SeventyFive Only	Per Square Metre	17875
					Total	498559

*DN.IT. amount approved for Rs. 498559/-
Vide No. 24/2026-27*

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

[Signature]

*221
40.9*

223
40.11

DRAFT SCHEDULE OF QUANTITY

DRAFT SCHEDULE OF QUANTITY							
Name of Work :-R/R Damages on Baroti Rakhera Dharampur Marhi Kamlah Road Km 14/00 to19/300 (SH:- emoval of slips & Construction of unlined surface drain in Km 14/00 to 19/300)			Estimated cost :- Earnest Money:-		492580 10000		
Sr.No	Description of item/Sub Head	Quantity	Time Limit		Unit	Two Months	
			In Figure	Rates		Amount	
				In words			
1	2	3	4	5	6	7	
1	Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer - in -Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4175.27	110.00	Rupees One Hundred Ten Only	Per Cubic Metre	459280	
2	Construction of unlined surface drain of average cross-sectional area 0.4 sqm in ordinary rock to specified lines, grades, levels and dimensions as per approved design and Technical Specification Clause 307. Excavated material to be used in embankment at site. The rates are inclusive of royalty, GST or other taxes imposed by the Government	900.00	37.00	Rupees ThirtySeven Only	Per Square Metre	33300	
					Total:-	492580	

DNIT amount approved for Rs. 492580/-
vide s/n No. 223/2026-27

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur

226

DRAFT SCHEDULE OF QUANTITY									
ame of Work:- R/R Damages on Pump House to Sidhpur to Khair road Km 0/0 to 1/0 (SH :- C/O Road Embankment at RD									
/190 to 0/497)									
				Estimated Cost		498561			
				Earnest Money		10000.00			
				Time Limit:-		Two Months			
				Rate in					
				Fig.	Words	Unit	Amount		
				4		6	7		
r. No.	Description of Items	Qty.							
1	2	3	4	5	6	7			
1	Construction of embankment with approved materials deposited at site from roadway cutting and excavation from drain and foundation of other structures graded and compacted to meet requirement of tables 300.1 and 300.2 as per Technical Specification Clause 301.5 including carriage of materials with in all leads and lifts and direction of Engineer in Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	1988.28	250.75	Rupees Two Hundred Fifty Paise SeventyFive Only	Per Cubic Metre	498561			
		Total	498561						

Rs. 498561 / -

For

Received

Duit amount approved For Rs 498561/-
vide S.O. 226
Executive Engineer,
Dharanpur Division
H.P.W.D., Dharampur.

me of Work:- R/R Damages on Narwalka to Kheri Road Km 0/00 to 5/200 (SH :- C/O PCC Wing walls for hume pipe culvert both side at s 3/045) NDF 2026/106										Estimated Cost		219504	
										Earnest Money		4500	
										Time Limit:-		Three Months	
No.	Description of Items	Qty.	Fig.	Words	Unit	Amount							
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	18.05	350	Rupees Three Hundred Fifty Only	Per cubic metre	6318							
2	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	46.19	4463.05	Rupees Four Thousand Four Hundred SixtyThree Paise Five Only	Per cubic metre	206148							
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolux/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogrammm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24	293.25	Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	7038							
Total						219504							

41

219504

2026/106

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

219504

D.N.T. amount approved for Rs. 219504/-
Vide No. 216/2026-27
 Executive Engineer,
 Dharampur Division
 H.P.P.W.D., Dharampur

144
30

DRAFT SCHEDULE OF QUANTITY

Name of Work: R/R Damages on various road under Sandhole Section Sub Division HPPWD Marhi (SH :-		Estimated cost :-		2000	
Description of Item/Sub Item		Earnest Money:-		Time Limit	
Sl. No.	Description of Item/Sub Item	Quantity	Rates		Amount
			In Figure	In Words	
1	Hiring of tractor for disposal of excavated material from cutting per day. The contractor / Owner of tractor shall bear the expensive of P.O.L charges, repair of machineries. Any accident and other damages to private and Govt. property occur during the working hours is the whole responsibility of the contractor and debris disposal with in all leads and lifts as per direction of Engineer - in- Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax. GST or other taxes imposed by the Government.	3	45.00	(Rupees:- One thousand eight hundred and paise zero only)	87750
Total:-					87750

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Rs 87750/-

Duit amount approved For Rs 87750/-
vide Sr No. 144

Executive Engineer
B&R Division HPPWD
Dharampur

231
117.1

DRAFT SCHEDULE OF QUANTITY									
Name of Work:- R/R Damages on Deyol Lassani Gowella Road Km 0/00 to 8/670 (SH :- C/O R/Wall at RD 1/970 to 1/980)					Estimated Cost		Earnest Money		
					Time Limit:-		Three Months		
Sr. No.	Description of Items	Qty.	Rate in Fig.	Words	Unit	Amount			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2	39.8	350 Rupees Three Hundred Fifty Only	Per cubic metre	13930			
2	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand isto Ten graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.		95	4463.05 Rupees Four Thousand Four Hundred Sixty Three Paise Five Only	Per cubic metre	423990			
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.		36	293.25 Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	10557			
4	Back filling behind abutment , wing walls and return walls complete as per drawings and MORD technical specification 2014 Clause 1204.3.8. with Granular Material and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.		25.2	1006.55 Rupees One Thousand Six Paise FiftyFive Only	Per Cubic Metre	25365			
Total									

231
117.1

Unit amount approved for Rs 473842/- vide No. 231

Executive Engineer,
Dharanpur Division
H.P.W.D., Dharampur.

(40.1)

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Kothwan to neri via chatron road Km 0/0 to 7/0 (SH :- Providing and laying C.C. Pavement at RD4/460 to 4/590)

Estimated Cost

461615

Earnest Money

40000.00

4500

Three Months

Time Limit:-

Sr. No.

Description of Items

Qty.

Fig.

Rate in Words

Unit

Amount

1

2

3

4

5

6

7

Construction of un-reinforced and construction joint only, plain cement concrete pavement in 1:1.5:3 (one cement : one and half sand : three graded stone aggregate 20 mm (Twenty millimetre)nominal size), thickness as per design, over a prepared sub base, with 43 (Forty three) grade cement or any other type as per Clause 1501.2.2 to be ensure minimum strength of 25N/mm² and minimum cement not less than 400 kg/cum(Four hundred kilogramme per cubic metre) (with plasticizer) , coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm,(Twenty five millimetre) mixed in a concrete mixer of not less than 0.2 cum (Zero point two cubic metre) capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, , wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including provision of contraction and expansion, construction joints, applying debonding strips, primer, sealant, dowel bars, near approaches to bridge/culvert and construction joints, admixtures as approved, curing of concrete slabs for 14-days, using curing compound (where specified) and wa ter finishing to lines and grade as per drawing and Technical specification clause 1501 including hauling of material within all leads and lifts and other incidental charges and as per direction of Engineer-In-Charge. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax , GST or other taxes imposed by the Government.

Total

461615

DNIT amount approved for 20-461615/-
Vide SS No. 224/2026-27.

Executive Engineer,

Dharampur Division

H.P.P.W.D., Dharampur

170
26.103.10

DRAFT SCHEDULE OF QUANTITY

Name of Work:- R/R Damages on Gorat Chamehar Road Km 0/0 to 4/0 and Proun Rangar Khroon Saklana Dodar Km 0/00 to 10/500 (S.M. Deployment/Hiring of Excavator cum loader & Tipper for removal of slips hiring of Tipper in various P.Ds)					Estimated Cost	
					Earnest Money	283500
					Time Limit:-	6000 00
		Qty	Fig	Rate in Words	Unit	Two Months Amount
		3	4	5	6	7
		150	1250.00	Rupees One Thousand Two Hundred Fifty Only	Per Hours	187500
1		Deployment/Hiring of Excavator-cum-loader 0.90cum bucket capacity @ 20.00 cubic metre per hour for removal of slips, Road side berms, katcha drain and boulder in all kinds of soils including rocky portion and saturated soil and disposing of all excavated earth of unserviceable material from the road surface including cost of fuel oil lubricant and wages of operating staff Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.				
2		30	3200.00	Rupees Three Thousand Two Hundred Only	Per Day	96000
		Hiring of tipper for disposal of excavated material from cutting having capacity of 150 cubic feet Per trip and minimum 70 Km of trip per day. The contractor / Owner of tipper shall bear the expensive of P.O.L charges, repair of machineries. Any repair /breakage during operation will be carried out by the contractor / owner at his own risk. Shifting of machinery from one place to another place will be absolute responsibility of the contractor and no payment will be made for the same only actual working hours will be accounted for the payment. The rate should be inclusive of POL and all other charges. The payment will be made for the exact hour for which the machine will work at site. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Govt.				
		Total				283500

*Nil amount approved for Rs. 283500/-
vide S.No 140*

Executive Engineer,
Dharampur Division
H.P.P.W.D., Dharampur.

227
Lab.1

DRAFT SCHEDULE OF QUANTITY									
Name of Work : R/R Damages on Sarkaghat Rissa Mandap Baroti Road Km 12/0 to 24/0 (SH :- C/O 2.00 x 2.00					Estimated cost :-				
Time span box culvert at RD 16/825) PDNA					Earnest Money:-				
					Time Limit				
Sr.No	Description of item/Sub Head	Quantity	Rates			Unit	Amount		
			In Figure	In words					
1	2	3	4	5	6	7			
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of waterincluding entire carriage of materials within all leads lifts and other incidentals and per direction of Engineer-in-Charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	67.5	350	Rupees Three Hundred Fifty Only	Per cum	23625			
2	Providing and laying mechanically mixed and vibrated concrete for plain/reinforced concrete in drains and open foundation for all type of structures complete of plain cement concrete nominal mix 1:4:8 (One cement : four sand : eight graded crushed stone aggregate 40 (forty) millimetres) on ground or under water and curing complete including pumping or bailing out water, dewatering removal of slush as required at site which may arise at the time of laying under water complete for all heights/depts including the cost of form work as per drawings and MORD technical specification 2014 clause 802, 803, 1202 and 1203 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4.5	4805.45	Rupees Four Thousand Eight Hundred Five Paise FortyFive Only	Per cum	21625			
3	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundation retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	9.45	4463.05	Rupees Four Thousand Four Hundred SixtyThree Paise Five Only	Per cubic metre	42176			
4	Providing and laying mechanically mixed and vibrated cement concrete for plain/reinforced concrete in super structure for all type of structures complete reinforced cement concrete 1:1.5:3 (one cement : one point five sand : three graded stone aggregate twenty millimetre nominal size) grade M-25 (M-Twenty five) design mix upto minium cement contents 406(Four hundred six) Killograme per Cubic metre for all heights/depts including the cost of form work and curing complete as per technical specification clause 802, 1205.4 & 1205.5 as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	21.62	7652.9	Rupees Seven Thousand Six Hundred FiftyTwo Paise Ninety Only	Per cum	165456			
5	Supplying, fitting, and placing HYSD bar reinforcement (Fe 415) in substructure including binding wire complete as per technical specifications clauses 1002, 1005, 1010 & 1202 including hauling of material in all leads, lifts as per the entire satisfaction and direction of Engineer-in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	2378.53	92.25	Rupees NinetyTwo Paise TwentyFive Only	Per Killograme	219419			

7	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogram) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614.709, 1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	4	293.25	Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	1173
	Back filling behind abutment , wing walls and return walls complete as per drawings and MORD technical specification 2014 Clause 1204.3.8. with Granular Material and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	5.16	1006.55	Rupees One Thousand Six Paise FiftyFive Only	Per Cubic Metre	5194
			Total:-			478668

Unit amount approved for Rs 478668/- vide Sr.No. 227

Executive Engineer,
Dharampur Division
H.P.W.D., Dharampur

DRAFT SCHEDULE OF QUANTITY						
Name of Work:- R/R Damages on Thira to Kot Road Km 0/00 to 4/00 (SH :- C/O R/Wall at RD 2/330 to 2/348.50) PDNA			Estimated Cost		488921	
			Earnest Money		10000	
Sl. No.	Qty	Rate in Fig.	Words	Two Months		Amount
				Unit	Time Limit:-	
1	2	3	4	5	6	7
1	Earth work in excavation for all type of road structure such as retaining walls, breast walls, culverts, drains and parapets etcetra in all type of classification of soil comprising of ordinary soil, ordinary rock, hard rocks, chiseling/wedging out of rocks (where blasting is prohibited) as per drawings and technical specification clause 305.1 and as per direction of the Engineer-in-Charge including setting out, construction of shoring and bracing, removal of stumps and other deleterious materials and disposal of materials upto all leads and lift including dressing of sides and bottom and back filling in trenches with excavated suitable approved material to the original surface in layers not exceeding 150mm (One hundred fifty millimetre) compacted thickness including shoring and strutting and pumping and bailing out water (surface and sub soil water) upto any depth and any quantum of water including cleaning of slush which may arise out during dewatering as per the direction of the Engineer-in-Charge and carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	40.15	350	Rupees Three Hundred Fifty Only	Per cubic metre	14053
2	Providing concrete for plain/reinforced concrete mechanically mixed and vibrated in open foundations retaining walls, breast walls etcetra complete as per drawings and MORD technical specifications 2014 clause 800 and 1200 nominal mix 1:5:10 (One cement isto five sand istoTen graded crushed stone aggregate) 40mm (Forty millimetre) nominal size including cost of form work and curing complete without plum as per HPPWD specification 2014 clause complete in all respect including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	97.87	4463.05	Rupees Four Thousand Four Hundred SixtyThree Paise Five Only	Per cubic metre	436799
3	Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in abutment retaining walls, breast walls and the like with 100mm (One hundred millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm ² (four kilogramm) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete as per drawing and technical specification 2014 clause 614,709,1204.3.7 in all leads and lifts and carriage of material by all modes of transportation as per the direction of Engineer- in-charge. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	46	293.25	Rupees Two Hundred NinetyThree Paise TwentyFive Only	Each	13490
4	Back filling behind abutment , wing walls and return walls complete as per drawings and MORD technical specification 2014 Clause 1204.3.8. with Granular Material and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.	24.42	1006.55	Rupees One Thousand Six Paise FiftyFive Only	Per Cubic Metre	24580
Total						488921

Don't amount approved for Rs 488921/-
vide 8.6.18/85

Executive Engineer,
Dharanpur Division
H.P.P.W.D., Dharampur