

REGISTERED

Office of the Executive Engineer, B&R Division, HP PWD Kalpa District Kinnaur (HP)

Web:- www.hppwd.gov.in E mail:- hp-kin@nic.in

Phone No:- 01786-226027 Fax:- 01786-226027.

No:- PW/KNR-E-Tender/2026- 10216 - 18
To

Dated:- 08/10/2026

The Executive Engineer (IT Cell),
HP.PWD. Shimla-2.

Subject:- Publication of Tender Notice (OFFLINE)

Enclosed please find herewith the Tender of works costing above 1 upto 5.00 Lakh as given in the Notice Inviting Tender for uploading on the departmental website as per notification vide Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B) 1/2020 dated 16-07-2021 and even file No. 1/2024 dated 03-01-2024, 03-01-2025 and 1/2024-241828 dated 17-07-2025 and PWD-B-A 0(3)/8/2025-300858 dated 09-10-2025, even file No. 300858 dated 13-11-2025, 08-12-2025 and even file No. 241828 dated 02-02-2026. The works mentioned in the tender notice are urgent in nature and public interest.

Encl:- NIT, Schedule of Quantity
& Certificate.

Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

Copy forwarded for information to:-

1. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
2. Copy to Drawing Branch in this office.

Executive Engineer,
Kalpa Division,
HP. PWD, Kalpa.

HP.P.W.D. TENDER NOTICE (offline)

Scaled item rate offline tender on form PWD-6 & 8 are hereby invited on behalf of Governor of Himachal Pradesh by the Executive Engineer, Kalpa Division, HP.PWD; Kalpa for the following works from the approved and eligible contractors enlisted in HP.PWD; so as to reach in the office of the Executive Engineer Kalpa Division HP.PWD, Kalpa on or before **15-10-2026 up to 11.00 A.M.** and shall be opened on the same day at **11:30 AM** in presence of intending contractors or their authorized representatives. The tender form documents can be had from this office (Kalpa Division, HP.PWD Kalpa) against cash payment (Non-refundable) on **14-10-2026 up to 4:00 P.M.** No application for issue of tender forms will be received on **14-10-2026 after 4:00 PM.** If the office happens to be closed on the above mentioned dates, the tenders will be sold/opened on the next working day at the same time and venue. The Earnest Money in the shape of National Saving Certificate, F.D.R.s any Post office/Bank in H.P. duly pledged in the name of Executive Engineer, Kalpa Division, HP.PWD, Kalpa must accompany with each tenders. Conditional tenders and application (For purchase of tender forms) received without Earnest Money summarily be rejected. The officer of the tenders shall be kept open for 75 days. The Executive Engineer Reserves (Right to accept or to reject any) or all the tenders without assigning any reasons.

Sr. No	Name of work	Estimated cost	Earnest Money	Time allowed	Cost of form	Eligible class of contractor
1	Restoration of rain damages on link road from Rushkulang to Giabong Km. 0/00 to 2/00 (SH:- C/O R/wall in R.R. Masonry at RD. 0/130 to 0/185)	3,91,363/-	8,000/-	One Month	350/-	"C" & "D" Class
2	C/O Link road from Peo Karchham Shilti road to Shagro Kotang in G.P. Shudarang Km. 0/00 to 0/630 (SH:- C/O R/wall in G.I. wire crate at RD. 0/105 to 0/120 and 0/139 to 0/180)	4,15,554/-	8,500/-	One Month	350/-	"C" & "D" Class
3	C/O Link road from Peo Karchham Shilti road to Shagro Kotang in G.P. Shudarang Km. 0/00 to 0/630 (SH:- C/O B/wall in G.I. wire crate at RD. 0/061 to 0/065 and R/wall at RD. 0/300 to 0/318)	4,23,441/-	8,500/-	One Month	350/-	"C" & "D" Class
4	C/O Link road from Peo Karchham Shilti road to Shagro Kotang in G.P. Shudarang Km. 0/00 to 0/630 (SH:- C/O R/wall in G.I. wire crate at RD. 0/180 to 0/207)	4,09,996/-	8,500/-	One Month	350/-	"C" & "D" Class
5	Restoration of rain damages (PDNA) on link road from Kankani to Pakchey in G.P. Nako Km. 0/00 to 2/110 (SH:- C/O B/wall in G.I. wire crate at RD. 1/720 to 1/756)	3,94,809/-	8,000/-	One Month	350/-	"C" & "D" Class
6	Restoration of rain damages (PDNA) on Jeepable road from Panchayat Ghar Shudarang to Banglang via Rang School Km. 0/00 to 2/050 (SH:- Providing and laying soling from Km. 0/00 to 0/400) (On Banglang road)	2,15,160/-	4,500/-	One Month	350/-	"C" & "D" Class
7	Restoration of rain damages on link road from Hango Bus Stand to Hango Village Km. 0/00 to 1/750 (SH:- C/O R/wall in R.R. Masonry at RD. 0/880 to 0/900)	3,13,745/-	6,500/-	One Month	350/-	"C" & "D" Class
8	C/O Link road from Kalpa Pangri to Tarkhawa in G.P. Telangi Km. 0/00 to 2/00 (SH:- C/O E/wall in R.R. Masonry at RD. 1/420 to 1/480)	3,60,187/-	7,500/-	One Month	350/-	"C" & "D" Class
9	Restoration of rain damages on link road to Village Dabling Km. 0/00 to 4/900 (SH:- C/O G.I. wire crate R/wall at RD. 2/550 to 2/595)	4,04,160/-	8,500/-	One Month	350/-	"C" & "D" Class

10	C/O Jeepable road from Holdang to Mollam Chhosten G.P. Ribba Km. 0/00 to 1/500 (SH:- F/C from Km 0/00 to 0/510 and providing protection work from Km. 0/035 to 0/055) Under SASCI)	4,17,972/-	8,500/-	One Month	350/	"C" & "D" Class
11	C/O Jeepable road from Holdang to Mollam Chhosten G.P. Ribba Km. 0/00 to 1/500 (SH:- Providing protection work from Km. 0/105 to 0/125 and 0/135 to 0/170)) Under SASCI)	4,12,503/-	8,500/-	One Month	350/	"C" & "D" Class
12	C/O Jeepable road from Holdang to Mollam Chhosten G.P. Ribba Km. 0/00 to 1/500 (SH:- Providing protection work from Km. 0/170 to 0/225) Under SASCI)	4,07,208/-	8,500/-	One Month	350/	"C" & "D" Class
13	C/O Jeepable road from Holdang to Mollam Chhosten G.P. Ribba Km. 0/00 to 1/500 (SH:- Providing protection work from Km. 0/240 to 0/255 & 0/270 to 0/276) Under SASCI)	4,20,300/-	8,500/-	One Month	350/	"C" & "D" Class
14	R/R damages on link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- C/O B/wall in G.I. wire crate at RD. 3/200 to 3/311)	4,23,586/-	8,500/-	One Month	350/	"C" & "D" Class
15	R/R damages on link road from Leo Bridge to Hango Km. 0/00 to 16/00 (SH:- C/O B/wall in G.I. wire crate at RD. 3/312 to 3/425)	4,23,405/-	8,500/-	One Month	350/	"C" & "D" Class

Terms and conditions:-

Following documents should accompany the application for tenders:-

1. Copy of valid enlistment/renewal order.
2. Copy of GST Registration No.
3. Proof of Valid E.P.F accounts Number allotted by the Provident Fund Commissioner Shimla and copy of PAN Number.
4. Ambiguous/Telegraphic/conditional tenders or tenders by fax/E-Mail shall not been entertained/considered in any case.
5. The contractors should quote the rates of each items in words as well as figures in the Schedule of quantity.
6. The earnest money must also accompany with the application for the tender documents.
7. The tender shall be issued to those contractors who have not more than two works in Hand.

[Signature]

Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

Dated:- 08/09/2026

No.:- PW/KNR-E-Tender/NIT/2026- 10200-15

Copy forwarded for information to:-

1. The Engineer-in-Chief, HP.PWD. Shimla-2.
2. The Deputy Commissioner, Kinnaur District at Reckong Peo.
3. The Sub Divisional Officer (Civil) Kalpa at Reckong Peo.
4. The Superintending Engineer, 11th Circle, HP.PWD. Rampur Bushahr.
5. The Block Development Officer, Kalpa at Reckong Peo.
6. The Chairman, Zila Parishad, Kinnaur District at Reckong Peo.
7. The Chairman, Panchayat Samiti Kalpa at Reckong Peo.
8. Drawing Branch in this office.
9. All the Contractors under this Division.
10. Notice Board.

Executive Engineer,
Kalpa Division,
HP. PWD. Kalpa.

CERTIFICATE

Certified that the Tender for works called vide this office Letter No. PW/KNR/E-Tender/2026- ~~10200~~ -15 dated 08/10/2026 and Fifteen numbers of works are of urgent nature and essential for public safety or restoration of infrastructure and public interest.


Executive Engineer,
Kalpa Division,
HP.PWD. Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Rushkulang to Giabong Km. 0/00 to 2/00		Estimated Cost	:- 3,91,363/-
(SH:- C/O R/Wall in RR Masonry at RD 0/130 to 0/185).		Earnest Money	:- 8,000/-
		Time	:- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	8.25	₹ 230.25	Rupees Two Hundred Thirty Paise TwentyFive Only	Per Cubic meter	₹ 1,900.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(One Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	8.25	₹ 3,575.00	Rupees Three Thousand Five Hundred SeventyFive Only	Per Cubic meter	₹ 29,494.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	74.25	₹ 4,495.00	Rupees Four Thousand Four Hundred NinetyFive Only	Per Cubic meter	₹ 333,754.00
4	Providing weepholes in brick masonry / stone masonry /plain reinforced concrete aboutment, wing wall, return wall with 100 mm dia (One hundred millimeter diameter) pvc pipe extending through the full with of the structures with stop of 1 (V) : 20 (H) towards drawings face complete as per drawing and technical specification clauses 614,709,1204.3.7, ncluding carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	107.00	245.00	Rupees Two Hundred FortyFive Only	Each	₹ 26,215.00
Total in figures:-						₹ 391,363.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						

Executive Engineer
KALPA D. Phine
H/P PWD KALPA

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Peo Karcham Shiliti road to Shangro Kotang in G.P. Shudharang Km. 0/00 to 0/630
(SH:- C/O R/Wall in G.I. wire crate at RD 0/105 to 0/120 and 0/139 to 0/180).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including cartage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	72.90	₹ 230.25	Rupees Two Hundred Thirty TwentyFive Only	Per Cubic meter	₹ 16,785.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301, including cartage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	155.52	₹ 2,546.80	Rupees Two Thousand Five Hundred FourSix Paise Eighty Only	Per Cubic meter	₹ 396,078.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 with good earth, including cartage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	16.20	₹ 166.10	Rupees One Hundred SixtySix Paise Ten Only	Per Cubic meter	₹ 2,691.00
Total in figures:-						₹ 415,554.00
Total in Words:-		Rupees Four Lakh Fifteen Thousand Five Hundred FiftyFour Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				

Executive Engineer,
Kalpa Division (B&R),
HP. PWD, Kalpa.

SCHEDULE OF QUANTITY

(1)

(2)

Name of work: C/O Link road from Peo Karcham Shilti road to Shangro Kolang in G.P. Shudharang Km. 0/00 to 0/630

(SH:- C/O B/Wall in G.I. wire crate at RD 0/061 to 0/065 and R/Wall at RD 0/300 to 0/318).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	34.54	₹ 230.25	Rupees Two Hundred Thirty Five Paise TwentyFive Only	Per Cubic meter	₹ 7,953.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	8.98	₹ 3,575.00	Rupees Thousand Hundred SeventyFive Only	Per Cubic meter	₹ 32,104.00
3	Providing and laying in position cement concrete of seecified grade excluding the cost of centering and shuttering -All work up to plinth level 1:4:8 (One cement : Four coars sand) : Eight graded stone aggregate 40 mm (Forty millimeter) nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	78.98	₹ 4,490.00	Rupees Four Thousand Four Hundred Ninety Only	Per Cubic meter	₹ 354,620.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	18.74	₹ 505.00	Rupees Five Hundred Five Only	Per Cubic meter	₹ 9,464.00

5	Providing weepholes in brick masonry / stone masonry /plain reinforced concrete aboutment , wing wall, return wall with 100 mm dia (One hundred millimeter diameter) pvc pipe extending through the full with of the structures with stop of 1 (v) : 20 (H) towards drawings face complete as per drawing and technical specification clauses 614,709,1204.3.7, ncluding carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	43.00	245.00	Rupees Two Hundred FortyFive Only	Each	₹ 10,535.00
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more,including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	100.00	₹ 87.65	Rupees EightySeven Paise SixtyFive Only	Per Kilogram	₹ 8,765.00
Total in figures:-						₹ 423,441.00
Total in Words:-		Rupees Four Lakh TwentyThree Thousand Four Hundred FortyOne Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Peo Karcham Shilt road to Shangro Kotang in G.P. Shudharang Km. 0/00 to 0/630
(SH:- C/O R/Wall in G.I. wire crate at RD 0/180 to 0/207).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	32.40	₹ 230.25	Rupees Two Hundred Thirty Two Five Only	Per Cubic meter	₹ 7,460.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogram each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	155.52	₹ 2,546.80	Rupees Two Thousand Five Hundred FourtySix Paise Eighty Only	Per Cubic meter	₹ 396,078.00
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8 with good earth, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	38.88	₹ 166.10	Rupees One Hundred SixtySix Paise Ten Only	Per Cubic meter	₹ 6,458.00
Total in figures:-						₹ 409,996.00
Total in Words:-		Rupees Four Lakh Nine Thousand Nine Hundred NinetySix Only				
Quoted Percentage rate upto three Digits :-		(+)/(-)				

Executive Engineer,
Kalpa Division (B&R),
HP.PWD Jammu.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages (PDNA) on link road from Kankani to Pakkhey in G.P. Nako Km 0/00 to 2/110

(SH:- C/O B/Wall in G.I. wire catte at RD 1/720 to 1/756).

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	32.76	₹ 230.25	Rupees Two Hundred Thirty Paise TwentyFive Only	Per Cubic meter	₹ 7,543.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	152.06	₹ 2,546.80	Rupees Two Thousand Five Hundred FourtySix Paise Eighty Only	Per Cubic meter	₹ 387,266.00
Total in figures:-						₹ 394,809.00
Total in Words:-			Rupees Three Lakh NinetyFour Thousand Eight Hundred Nine Only			
Quoted Percentage rate upto three Digits :-		(+)/(-)				

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

1

6

Name of work:- Restoration of rain damages (PDNA) on Jeepable road from Panchyat Ghar Shudarang to Banglang via Rang School Km 0/00 to 2/050 (SH:- Providing and laying soling from Km. 0/00 to 0/400 (On Banglang road).		Estimated Cost	:- 2,15,160/-
		Earnest Money	:- 4,500/-
		Time	:- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	198.00	₹ 230.00	Rupees Two Hundred Thirty Only	Per Cubic meter	₹ 45,540.00
2	Providing and laying stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the required gradient and comber including spreading watering and rolling of binding materials moorum or earth etc, 100mm (One hundred millimeter) spread thickness, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	132.00	₹ 1,285.00	Rupees One Thousand Two Hundred EightyFive Only	Per Cubic meter	₹ 169,620.00
Total in figures:-						₹ 215,160.00
Total in Words:-			Rupees Two Lakh Fifteen Thousand One Hundred Sixty Only			
Quoted Percentage rate upto three Digits :-		(+)/(-)				


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

(1)

(7)

Name of work:- Restoration of rain damages on link road from Hango Bus Stand to Hango Village Km. 0/00 to 1/750		Estimated Cost	3,13,745/-
(SH:- C/O R/Wall in RR Masonry at RD 0/880 to 0/900).		Earnest Money	:- 6,500/-
		Time	:- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	20.25	₹ 230.25	Rupees Two Hundred Thirty TwentyFive Only	Per Cubic meter	₹ 4,663.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12(One Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	4.05	₹ 3,575.00	Rupees Thousand Hundred SeventyFive Only	Per Cubic meter	₹ 14,479.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	63.36	₹ 4,495.00	Rupees Four Thousand Four Hundred NinetyFive Only	Per Cubic meter	₹ 284,803.00
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall,with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/Wall),including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	40.00	₹ 245.00	Rupees Two Hundred FortyFive Only	Each	₹ 9,800.00
Total in figures:-						₹ 313,745.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						

Executive Engineer,
Kalpa Division,
DWR, Kalpa

SCHEDULE OF QUANTITY

Name of work:- C/O Link road from Kalpa Pangli to Tarkhawa In G.P. Telangal Kin 0/00 to 2/00
(SH:- C/O E/Wall in RR Masonry at Rd 1/420 to 1/480)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	67.80	₹ 221.23	Rupees Two Hundred TwentyOne Paise TwentyThree Only	Per Cubic meter	₹ 14,999.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (One cement : five coarse sand:ten graded stone aggregate 40 mm nominal size), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, GST or other taxes imposed by the Government.	12.00	₹ 4,380.45	Rupees Four Thousand Three Hundred Eighty Paise FourFive Only	Per Cubic meter	₹ 52,565.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand,) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	61.20	₹ 4,473.64	Rupees Four Thousand Four Hundred SeventyThree Paise SixtyFour Only	Per Cubic meter	₹ 273,787.00
4	Providing weep holes in brick masonry /stone masonry/plain reinforced concrete abutments, wing wall, return wall, with 100mm (One hundred millimeter) dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7 (For R/wall) including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	80.00	₹ 235.45	Rupees Two Hundred ThirtyFive Paise FourtyFive Only	Each	₹ 18,836.00
Total in figures:-						₹ 360,187.00
Total in Words:-				Rupees Three Lakh Sixty Thousand One Hundred EightySeven Only		
Quoted Percentage rate upto three Digits :-		(+)/(-)				

Executive Engineer,
Kalpa Division,
H.P. PWD: Kalpa

SCHEDULE OF QUANTITY

(1)

Estimated Cost :- 4,04,160/-

Name of work:- RR Damages on link road to village Dabbling KM. 0/00 to 4/900(SH:- C/O G.I wire crate R/wall at RD. 2/550 to 2/595)

Earnest Money :- 8500/-
Time:- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) /manual means in foundation trenches or drains (within all lead and lift including dressing of sides and ramming of bottoms, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	35.10	₹ 230.25	Two Hundred Thirty Rupees and Twenty Five Paise Only	Per Cubic Meter	₹ 8,082.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301,	155.52	₹ 2,546.80	Two Thousand Five Hundred Forty Six Rupees and Eighty Paise Only	Per Cubic Meter	₹ 396,078.00
Total in figures:-					Total =	404160.00
Total in Words:-		Four Lakh Four Thousand One Hundred Sixty Rupees Only				
Quoted percentage rate upto three Digits:-		(+)/(-)				

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:-

C/O Jeepable road from Holdang to Mollam Chhosten in G.P. Ribba Km. 0/00 to 1/500

(SH:- Formation cutting from Km. 0/00 to 0/510 and Providing Protection work from Km. 0/035 to 0/055).

Estimated Cost

4,17,972/-

Earnest Money

8,500/-

Sr. No.

Description of items

Qty.

In Fig.

Rate

Unit

Amount

1	Cutting in earth work in all heights and depths and in all kinds of soils including saturated soil comprising of Pick, Jumper, blasting work both in soft and hard rock with chiseling, wedging-out of rock where blasting is prohibited, their intermediate classification of soil, setting-out true to the required lines, grades, side slopes, trimming bottoms to levels as shown on the drawing and as directed by the Engineer-in-charge at site according to HP.PWD, specification of 1990 Vol-I and sorting-out useful/ un-useful materials and stacking the same in all leads and lifts in acquired width of the road and transportation of useful/ un-useful materials for filling in road ways camber, embankments for grades, improvement and leveling to required grade and disposing of all surplus excavated earth in acquired width of the road or on approved dumping sites through all modes of transportation including head load or animal transport or mechanically means along with its leveling, fine dressing and all labour, machineries, tools, equipments and safety measures and other incidental, necessary to complete the work by mechanised means and labour if required. All useful materials such as stones, shingles, aggregates and slates shall be sorted-out and stacked along road side, the quantity of which shall not be less than 153.13 cum, failing which recovery @ Rupees 300/cum. (Three hundred per cubic metre) shall be effected from the bill of the contractor. Any loss of the public/ private property during the course of execution shall be absolute responsibility of the contractor which shall to be duly compensated by him in all respect, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge. The rates are excluding GST.	1351.13	₹ 195.11	Rupees One Hundred NinetyFive Eleven Only Paise	Per Cubic meter	₹ 263,619.00
2	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	2.80	₹ 230.00	Rupees Two Hundred Thirty Only	Per Cubic meter	₹ 644.00

SCHEDULE OF QUANTITY

Name of work:- C/O Jeepable road from Holdang to Mollam Chhosten in G.P. Ribba Km. 0/00 to 1/500

(SH:- Providing protection work from Km. 0/105 to 0/125 and 0/135 to 0/170). (Under SASCI)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	9.03	₹ 230.00	Rupees Two Hundred Thirty Only	Per Cubic meter	₹ 2,077.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12 (one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	4.20	₹ 3,575.00	Rupees Thousand Hundred SeventyFive Only	Per Cubic meter	₹ 15,015.00
3	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	29.20	₹ 4,495.00	Rupees Four Thousand Four Hundred NinetyFive Only	Per Cubic meter	₹ 131,254.00
4	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	100.80	₹ 2,546.80	Rupees Two Thousand Five Hundred FourtySix Paise Eighty Only	Per Cubic meter	₹ 256,717.00

5	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment , wing wall, return wall with 100 mm dia (One hundred millimeter diameter) pvc pipe extending through the full with of the structures with stop of 1 (v) : 20 (H) towards drawings face complete as per drawing and technical specification clauses 614.709,1204.3.7, including carriage of materials through all modes, of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	18.00	245.00	Rupees Two Hundred FourtyFive Only	Each	₹ 4,410.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	6.00	₹ 505.00	Rupees Five Hundred Five Only	Per Cubic meter	₹ 3,030.00
Total in figures:-						₹ 412,503.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-		(+)/(-)		Rupees Four Lakh Twelve Thousand Five Hundred Three Only		


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work:- C/O Jeepable road from Holdang to Mollam Chhosten in G.P. Ribba Km. 0/00 to 1/500

(SH:- Providing protection work from Km. 0/170 to 0/225). (Under SASCI)

Estimated Cost :- 4,07,208/-

Earnest Money :- 8,500/-

Time :- One Month

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	16.50	₹ 230.00	Rupees Two Hundred Thirty Only	Per Cubic meter	₹ 3,795.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighting not less than 25kg (twenty five kilogramme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	158.40	₹ 2,546.80	Rupees Two Thousand Five Hundred FourtySix Paise Eighty Only	Per Cubic meter	₹ 403,413.00
Total in figures:-						₹ 407,208.00
Total in Words:-			Rupees Four Lakh Seven Thousand Two Hundred Eight Only			
Quoted Percentage rate upto three Digits :-		(+)/(-)				


Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

SCHEDULE OF QUANTITY

Name of work: C/O Jeepleable road from Holdang to Mollam Chhosten in G.P. Ribba Km. 0/00 to 1/500

(SH:- Providing protection work from Km. 0/240 to 0/255 & 0/270 to 0/276). (Under SASCI)

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	9.15	₹ 230.00	Rupees Two Hundred Thirty Only	Per Cubic meter	₹ 2,105.00
2	Providing and Laying concrete for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203. PCC 1:6:12 (one Cement : six coarse sand) : twelve graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	3.00	₹ 3,575.00	Rupees Thousand Hundred SeventyFive Only	Per Cubic meter	₹ 10,725.00
3	Providing concrete for plain / reinforced concrete in open foundations complete as per drawing and technical specification Clause: 802,803,1202 & 1203. P.C.C grade M10 Nominal mix 1:3:6 (one Cement : three coarse sand) : six graded stone aggregate), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	18.90	₹ 5,130.00	Rupees Five Thousand One Hundred Thirty Only	Per Cubic meter	₹ 96,957.00
4	Stone masonry in cement mortar for substructure complete as per drawing & technical specification Clauses 702, 704, 1202 and 1204. Random rubble masonry in cement mortar 1:6 (One cement: Six sand), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	66.90	₹ 4,495.00	Rupees Four Thousand Four Hundred NinetyFive Only	Per Cubic meter	₹ 300,716.00

(13)

Providing weepholes in brick masonry / stone masonry /plain reinforced concrete abutment , wing wall, return wall with 100 mm dia (One hundred millimeter diameter) pvc pipe extending through the full width of the structures with stop of 1 (v) : 20 (H) towards drawings face complete as per drawing and technical specification clauses 614.709,1204.3.7, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.		27.00	245.00	Rupees Two Hundred FourtyFive Only	Each	₹ 6,615.00
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification clause 1204.3.8. Granular material (For R/wall), including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	6.30	₹ 505.00	Rupees Five Hundred Five Only	Per Cubic meter	₹ 3,182.00
Total in figures:-						
Total in Words:-						₹ 420,300.00
Quoted Percentage rate upto three Digits :-		(+)/(-)	Rupees Four Lakh Twenty Thousand Three Hundred Only			


 Executive Engineer,
 Kalpa Division (B&R),
 HP.PWD; Kalpa.

SCHEDULE OF QUANTITY

Name of work:- Restoration of rain damages on link road from Leo Bridge to Hango Km. 0/00 to 16/00
(SH:- C/O B/Wall in G.I. wire cart at RD 3/200 to 3/311).

Estimated Cost :- 4,23,586/-
Earnest Money :- 8,500/-

Sr. No.	Description of items	Qty.	Rate		Unit	Amount
			In Fig.	In Words		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, including dressing of sides and ramming of bottoms, with in all lifts, including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads in all kind of soil, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	81.20	₹ 230.25	Rupees Two Hundred Thirty Two Hundred Paise TwentyFive Only	Per Cubic meter	₹ 18,696.00
2	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter) diameter GI wire conforming to IS: 280 and IS: 4826 in 100mm x 100mm (Hundred millimeter into hundred millimeter) mesh (woven diagonally) including 10 percent extra for laps and joints laid with stone boulders weighing not less than 25kg (twenty five kilograme each as per drawing and technical specification Clause 1301, including carriage of materials through all modes of transportation with in all leads and lifts, as per PWD specifications and as per direction of the Engineer-in-charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax or other taxes imposed by the Government. The rates are excluding GST.	158.98	₹ 2,546.80	Rupees Two Thousand Five Hundred FourtySix Paise Eighty Only	Per Cubic meter	₹ 404,890.00
Total in figures:-						₹ 423,586.00
Total in Words:-						
Quoted Percentage rate upto three Digits :-						

Rupees Four Lakh TwentyThree Thousand Five Hundred EightySix Only

Executive Engineer,
Kalpa Division (B&R),
HP.PWD, Kalpa.

①

Estimated Cost	:- 4,23,405/-
Earnest Money	:- 8,500/-

**Executive Engineer,
Kalpa Division (B&R),
HP.PWD; Kalpa.**