

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
NO.PW- GHD-EA-I- /Tender/2026-
To

7515-16 Dated:- 09/10/2026

The Chief Engiener (HZ),
HPPWD Hamirpur(HP).

Publication of Tender Notice.

SUBJECT: -

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 and further in compliance of Engineer-in-Chief,HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICTWing/website dt. 22/5/2026 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before 12.10.2026.

DA:-As above.

Executive Engineer,
Ghumarwin, Division,
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- One No.

Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.
On behalf of Governor of Himachal Pradesh

***NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under O,the H.P General Sales Tax Act 1968 so as to reach in his office on or before **19-10-2026 up to 11.00 AM(if holiday then next working day)**, and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 17-10-2026 up to 4.00 P.M and the application for issue of tender form shall be received on **17-10-2026 up to 11.30 AM(if holiday then next working day)**. The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	Repair of Indoor Ward and old pH Building at CH Ghumarwin (SH: Providing and laying Granite stone in 20mm (health Deposit)	Rs.47766/-	Rs.1000/-	Rs.350/-	One Month
2.	Restoraton of rain damages on Rohal Khad Lehri Sarail Domehar Ghandalwin road km 0/00 to 13/00(SH: Removal of slips,maintenance of earthen shoulder and maintenance of drain at varous Rds under PDNA year 2025	Rs.130021/-	Rs.1700/-	Rs.350/-	One Month
3.	Link Road to house of Sh.Gian Chand S/o Shiv Ram GP Kotlu Brahmna (SH:Providing and laying Cement concrete pavement at varous damaged Rds under SDP).	Rs.253892/-	Rs.5100/-	Rs.350/-	One Month
4.	Restoration of rain damages on link road from GTB road to village Baloh km 0/00 to 1/510 (SH: Balance work of link road Khanger Bari Thalotu village Padal,B/wall at RD 0/460 to 0/500 and R/wall at RD 0/286 to 0/300 under PDNA year 2023	Rs. 421167/-	Rs.8500/-	Rs.350/-	One Month
5.	Restoration of rain damages on link road from GTB road to village Baloh km 0/00 to 1/510 (SH: Balance work of link road Khanger Bari Thalotu village Padal,B/wall at RD 0/560 to 0/590 and R/wall at RD 0/338 to 0/350 under PDNA year 2023	Rs. 423111/-	Rs.8500/-	Rs.350/-	One Month
6.	Restoration of rain damages on Kursai chatter Barota road km 0/00 to 4/00 (SH: Balance work of CC work in 1:1.5:3 in km 2/779 to 2/879 and drain in between 2/700 to 2/779 at varous RDs under PDNA year 2023.	Rs. 349274/-	Rs.8200/-	Rs.350/-	One Month
7.	Restoration of rain damages on Kursai chatter Barota road km 0/00 to 4/00 (SH: Balance work of CC work in 1:1.5:3 in km 2/779 to 2/879 and drain in between 2/700 to 2/779 and at Km 3/00 to 3/030 and Drain in between 2/600 to 2/700 under PDNA year 2023.	Rs. 408152/-	Rs.8200/-	Rs.350/-	One Month
8	Restoration of rain damages on varous road under Sub Division Bharari HPPWD Bharari (SH: Removal of slips maintenance of earthen shoulder and drain in varous roads under section Bharari -1 sub division Bharari.	Rs. 84514/-	Rs.1700/-	Rs.350/-	One Month

Certificate of Exigencies:- Certified that tenders are being called for due to exigencies of works (landslide and road singking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division , HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The Contractor/Firm shall quote the rate in percentage only, both in words and in figures. The percentage rate quoted shall be exclusive of GST. The contractor shall ensure that the rate quoted by him is inclusive of all other applicable costs, duties, royalties, labour cess, transportation, overheads, profits, etc., as applicable, but excluding GST.

Executive Engineer,
Ghumarwin Division
HP.PWD, Ghumarwin

Draft Schedule of Quantity

Draft Schedule of Quantity				Estimated Cost (Excluding GST):- Rs.		47,766.00
				Earnest Money:- Rs.		1,000.00
				Time :-		One Month
Name of Work:- Repair Indoor Ward and old P.H.C. Building at CH Ghumarwin (SH:- Providing and laying Granite stone in 20 mm) . (Health Deposit work)						
Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
	Providing and laying Leather finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge :Leather finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	16.28	Per square metre	2934.00	Rupees Two Thousand Nine Hundred Thirty Four Only	47766
	Total					47766

Name of Work:- Repair Indoor Ward and old P.H.C. Building at CH Ghumarwin (SH:- Providing and laying Granite stone in 20 mm) . (Health Deposit work)

Estimated Cost
(Excluding GST):- Rs. 47,766.00

Earnest Money:- Rs. 1,000.00

Time :- One Month

Draft Schedule of Quantity No-171 for the year 2026-27 approved for Rs 47,766/- only

Executive Engineer
G. S. Division
H.P. PWD, Gumarwin

(Signature)

Draft Schedule of Quantity

Draft Schedule of Quantity				Estimated Cost		
				(Excluding GST):- Rs.		
				Earnest Money:- Rs.		
				Time :-		
Name of Work:- Restoration of rain damages on Rohal Khad Lehri Sarail Domehar Ghandalwin road km 0/00 to 13/00 (SH:- Removal of slips . maintenance of earthen oudder and maintenance of drain at various RD's). (Under PDNA 2025).						
No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Removal of land slides in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of material with in all leads and lifts as per technical specification 302.3.5 and 1611. The dumping site for throwing debris be arranged by the contractor at his own level and no debris be thrown in the forest land or along the nallah, culverts etc. including carriage of materials, within all leads and lifts as per direction of Engineer-in-Charge. Any damage occurred to government or private property during execution of work will be the sole responsibility of the contractor. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	386.18	Per cubic metre	101.69	Rupees One Hundred One and Sixty Nine Paise	39271
2	The maintenance of unline drains include erosion, repair, clearing cleaning, reshaping, regarding, deepening of side drains as well as catch water drains as per technical specification clause 1907as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	3356.00	Per Running Metre	10.17	Rupees Ten and Seventeen Paise	34131
3	Maintenance of earthen shoulder (Stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and Technical Specification Clause 1903 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	3037.50	Per square metre	18.64	Rupees Eighteen and Sixty Four Paise	56619
Total						130021

Draft Schedule of Quantity No 149 for
the year 2026-27 approved for Rs. 1,30,021/-

Executive Engineer
CUMMUTARIAN Division
T.P.D. D. Ghumard
(Signature)

Draft Schedule of Quantity

Estimated Cost	2,53,892.00
(Excluding GST):- Rs.	
Earnest Money:- Rs.	5,100.00
Time :-	One Month

Name of Work:- Construction of link road to House of Sh. Gian Chand S/o Shiv Ram G.P. Kotlu Brahmna (SH:- Providing and laying Cement concrete pavement at various damaged RD's). (Under SDP Deposit).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm (fifteen centimetre) deep and disposal of rubbish, all lead and lift up to in All kinds of soil as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	262.80	Per square metre	16.95	Rupees Sixteen and Ninety Five Paise	4454
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre) spread thickness (finished work including materials and labour) as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	39.42	Per cubic metre	1313.56	Rupees One Thousand Three Hundred Thirteen and Fifty Six Paise	51781
3	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5 :3 (One cement is to one point five coarse sand is to three graded crushed stone aggregate 20 mm (twenty millimetre) nominal size as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	32.85	Per cubic metre	6016.95	Rupees Six Thousand Sixteen and Ninety Five Paise	197657
Total:-						2,53,892.00

Draft Schedule of Quantity No 143 for
the year 2026-27 approved for
Rs 2,53,892/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.

(Signature)

Draft Schedule of Quantity

Work:- Restoration of rain damages on link road from G.T.B. road to village Baloh km 0/00 to 1/510 (SH :- Balance work of link road Khanger Thalolu Village Padal. B/wall at RD 0/460 to 0/500 and R/wall at RD 0/286 to 0/300). (Under PDNA Year 2023).

Sr. No.		Description Item	Quantity	Unit	Estimated Cost		Amount
					(Excluding GST):- Rs.	Earnest Money:- Rs.	
						Time :-	One month
1		Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	179.03	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	37929
2		Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate) 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	81.33	Per Cubic Metre	4110.20	Rupees Four Thousand One Hundred Ten and Twenty Paise	334283
3		Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614.709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	94.00	Each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	25889
4		Back filling with granular material behind retaining walls, abutment wing wall and return wall complete as per drawings and MORD technical specification 2014 Clause 1204.3.8 and as per direction of Engineer-In-Charge including carriage of materials with in all leads and lifts and other incidental. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	21.76	Per cubic metre	1060.00	Rupees One Thousand Sixty Only	23066
Total							421167

Draft Schedule of Quantity No 177 for the year 2024-27 approved for Rs 421167/- only

HP, PWD, G. T. B. Road to Village Baloh, Khanger Thalolu, Dist. Balasore, Odisha

Draft Schedule of Quantity

Draft Schedule of Quantity									
Line of Work:- Restoration of rain damages on link road from G.T.B. road to village Baloh km 0/00 to 1/510 (SH :- Balance work of link road Khangeri Thalotu Village Padal. B/wall at RD 0/560 to 0/590 and R/wall at RD 0/338 to 0/350) .(Under PDNA Year 2023).									
Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount			
				In figure	In words				
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead .All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	128.05	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	27129			
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate) 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	86.48	Per Cubic Metre	4110.20	Rupees Four Thousand One Hundred Ten and Twenty Paise	355450			
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	74.00	Each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	20381			
4	Back filling with granular material behind retaining walls, abutment wing wall and return wall complete as per drawings and MORD technical specification 2014 Clause 1204.3.8 and as per direction of Engineer-in-Charge including carriage of materials with in all leads and lifts and other incidental. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	19.01	Per cubic metre	1060.00	Rupees One Thousand Sixty Only	20151			
Total						423111			

Draft Schedule of Quantity No 178 for the year 2026-27 approved for Rs 423111/- only

Executive Engineer,
Ghumarwis Division,
H.P. PWD, Ghumarwis

Draft Schedule of Quantity

Estimated Cost (Excluding GST):- Rs.	3,49,274.00
Earnest Money:- Rs.	7,000.00
Time :-	One month

Item of Work:- Restoration of rain damages on Kursai Chatter Barota road km 0/00 to 4/00 (SH:-Balance work of C.C. work in 1:1.5:3 in km 2/779 to 2/879 and Drain in Between 2/700 to 2/779 at various RD's). (Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre) spread thickness (finished work including materials and labour) as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	9.15	Per cubic metre	1313.56	Rupees One Thousand Three Hundred Thirteen and Fifty Six Paise	12019
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5:3 (One cement is to one point five coarse sand is to three graded crushed stone aggregate 20 mm (twenty milimetre) nominal size as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	38.13	Per cubic metre	6016.95	Rupees Six Thousand Sixteen and Ninety Five Paise	229426
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	22.52	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	4771
4	Providing and laying cement concrete 1:3:6 (one cement is to three sand is to six graded crushed stone aggregate 40mm (forty millimetre) nominal size) including cost of centring and shuttering in Foundations and plinth as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	22.52	Per Cubic metre	4576.27	Rupees Four Thousand Five Hundred Seventy Six and Twenty Seven Paise	103058
Total						349274

Draft Schedule of Quantity No 179 for the year 2026-27 approved for Rs 349274/- only

Executive Engineer,
Gh. Division,
HP. PWD

Draft Schedule of Quantity

Estimated Cost (Excluding GST):- Rs.	4,08,152.00
Earnest Money:- Rs.	8,200.00
Time :-	One month

me of Work:- Restoration of rain damages on Kursai Chatter Barota road km 0/00 to 4/00 (SH:- Balance work of C.C. work in 1:1.5:3 at KM 2/700 to 779 & at KM 3/00 to 3/030 and Drain in Between 2/600 to 2/700). (Under PDNA Year 2023).

Sr. No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
1	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 150 mm (One Hundred fifty millimetre) spread thickness (finished work including materials and labour) as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	13.73	Per cubic metre	1313.56	Rupees One Thousand Three Hundred Thirteen and Fifty Six Paise	18035
2	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level. 1:1.5:3 (One cement is to one point five coarse sand is to three graded crushed stone aggregate 20 mm (twenty milimetre) nominal size as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	41.56	Per cubic metre	6016.95	Rupees Six Thousand Sixteen and Ninety Five Paise	250064
3	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever	29.25	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	6197
4	Providing and laying cement concrete 1:3:6 (one cement is to three sand is to six graded crushed stone aggregate 40mm (forty millimetre) nominal size) including cost of centring and shuttering in Foundations and plinth as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	29.25	Per Cubic metre	4576.27	Rupees Four Thousand Five Hundred Seventy Six and Twenty Seven Paise	133856
	Total					408152

Draft Schedule of Quantity No 180 for the year 2026-27 approved for Rs 4,08,152/- only

Executive Engineer,
G. M. Division,
H.P. P.O., G. M. Division.

Draft Schedule of Quantity

				Estimated Cost:- Rs.	184,514.00
				Earnest Money:- Rs.	1,700.00
				Time :-	One Month
Work:- Restoration of rain damages on various road under Sub-Division Bharari HPPWD Bharari (SH:- Removal of slips, Maintenance of earthen drain and drain in various roads under Section Bharari-I, Sub-division Bharari). (Under NDRP)					
Sl. No.	Description Item	Quantity	Unit	Rates	
				In figure	In words
1	Removal of land slide/slips in hilly area in all kinds and classification of soil by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 mtrs and lead upto 5000 mtrs/soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	516.00	Per cubic metre	101.69	Rupees One Hundred One and Sixty Nine Paise
2	Maintenance of earthen shoulder (Stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawing and Technical Specification Clause 1903 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	798.00	Per square metre	18.64	Rupees Eighteen and Sixty Four Paise
3	The maintenance of unline drains include erosion, repair, clearing cleaning, reshaping, deepening of side drains as well as catch water drains as per technical specification clause 1907 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	1688.00	Per Running Metre	10.17	Rupees Ten and Seventeen Paise
Total:-					84,514.00

*Draft Schedule of Quantity No 181 for
the year 2026-27 approved for Rs 84514/- only*

Executive Engineer,
Chunaboti Sub-Division,
H.P.W.D., Guwahati.

(Signature)