

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NO.PW- GHD-EA-I- /Tender/2026-

To

7228-31 Dated:- 05/10/26

**The Chief Engiener (HZ),
HPPWD Hamirpur(HP).**

SUBJECT: -

Publication of Tender Notice.

Sir,

Jai Hind

Enclosed please find herewith the Tender Notice for the work as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary(PW) to the GOVT of HP vide No. PBW(B)A(3)1/2024 Dated 03/01/2025 and further in compliance of Engineer-in-Chief,HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICTWing/website dt. 22/5/2026 as the matter is of urgent nature and in public interest , you are requested to kindly get it published on departmental website before 06.10.2026.

DA:-As above.

**Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin**
On behalf of Governor of Himachal Pradesh

Copy along with copy of e-Procurement Notice forwarded to the following for information please: -

1. The Superintending Engineer, 10th Circle, HP.PWD., Bilaspur.
2. All the Assistant Engineer, working under this Division
3. Notice Board of this office.

DA:- One No.

**Executive Engineer,
Ghumarwin, Division.
HP.PWD. Ghumarwin.**
On behalf of Governor of Himachal Pradesh

***NOTICE INVITING TENDER**

Sealed percentage rate tenders on form 6 & 8 are hereby invited by the Executive Engineer, Ghumarwin Division HP.PWD. Ghumarwin on behalf of the Governor of H.P for the following works from the approved and eligible contractors enlisted in HP.PWD, (B&R) whose registration stood renewed as per revised rules and also registered under O.the H.P General Sales Tax Act 1968 so as to reach in his office on or before **13-10-2026 up to 11.00 AM(if holiday then next working day)**, and the same shall be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The tender form/documents can be had from his office against cash payment (Non refundable) on 12-10-2026 up to 4.00 P.M and the application for issue of tender form shall be **received on 12-10-2026 up to 11.30 AM(if holiday then next working day)**. The earnest money in the shape of NSC/FDR/saving account of the Post office/Bank in H.P duly pledged in favour of the XEN must accompany with each tender. Conditional/ incomplete tenders & tender without earnest money will be summarily rejected. The XEN reserves the right to accept or reject any or all tenders or drop the proposal of tenders without assigning any reasons. The offer of the tender shall be kept open for 75 days.

The draft NIT, other specifications and conditions of the tender can be seen by the contractors in the office of the undersigned on any working day during the office hours.

S. No.	Name of work	Estimated of cost	Earnest Money	Cost of form	Time limit
1.	Restoraton of rain damages on Ghumarwin to Tikker Silh via Marhol, Soi Ropari km 0/00 to 6/190 (SH: C/o R/wall at RD 1/040 to 1/044 under NDRF.	Rs.84587/-	Rs.1700/-	Rs.350/-	One Month
2.	Restoraton of rain damages on Ghumarwin to Tikker Silh via Marhol, Soi Ropari km 0/00 to 6/190 (SH: C/o R/wall at RD 1/050 to 1/054 under NDRF.	Rs.84626/-	Rs.1700/-	Rs.350/-	One Month
3.	C/o Link road from samshanghat Ropari to village Lower Ropari km 0/00 to 0/500(SH: C/o R/wall at RD 0/200 to 0/210 under SDP.	Rs.105908/-	Rs.2200/-	Rs.350/-	One Month
4.	Restoration of rain damages on Silh to Nanin road km 0/00 to 3/285 (SH: C/o B/wall at RD 2/650 to 2/270 and Removal of land slide 2/650 to 2/680 under PDNA year 2023.	Rs. 339246/-	Rs.6800/-	Rs.350/-	One Month
5.	Resotration of rain damages on link road Jaswal Basti Padyalag GP Padyalag Tehsil Ghumarwin Distt Bilaspur HP (SH: Balance work for Providing and laying cement concrete pavement at damaged reaches under NDRF	Rs. 36475/-	Rs.800/-	Rs.350/-	One Month

Certificate of Exigencies:- Certified that tenders are being called for due to exigencies of works (landslide and road singking etc.) in the public interest.

Terms and Conditions:-

1. The Contractor should produce a copy of enlistment/renewal letter at time of application.
2. Executive Engineer reserves the right to reject/cancel any or all the tenders without assigning any reason.
3. The Contractor/firm must have his registration and GST No. The copy of same be attached with the application.
4. The earnest money shall be deposited duly pledged in favour of Executive Engineer, Ghumarwin Division , HP.PWD, Ghumarwin and cost of tender form for the above works should be submitted with the application for the purchase of tender forms. The application received without earnest money and cost of tender form shall be rejected straight way.
5. The Contractor/Firm shall quote the rate in percentage only, both in words and in figures. The percentage rate quoted shall be **exclusive of GST**. The contractor shall ensure that the rate quoted by him is inclusive of all other applicable costs, duties, royalties, labour cess, transportation, overheads, profits, etc., as applicable, **but excluding GST**.

Executive Engineer,
Ghumarwin Division
HP.PWD, Ghumarwin

Draft Schedule of Quantity

Draft Schedule of Quantity		Estimated Cost (Excluding GST):- Rs.		84,587.00	
		Earnest Money:- Rs.		1,700.00	
		Time :-		One Month	
of Work:- Restoration of rain damages on Ghumarwin to Tikker Silh via Marhol, Soi Ropari km 0/00 to 6/190 (SH:-C/o R/wall at RD 1/040 to 1/044). (per NDRF).					
Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
			In figure	In words	
Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), within any lead .All kinds of soil as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	8.55	Per Cubic Metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	1811
2 Providing and Laying concrete 1:4:8 (One cement is to four coarse sand is to eight graded crushed stone aggregate) 40mm (forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	18.95	Per cubic metre	4237.29	Rupees Four Thousand Two Hundred Thirty Seven and Twenty Nine Paise	80297
3 Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full width of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	9.00	each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	2479
Total					84587

Draft Schedule of Quantity No 163 for the
Year 2026-27 approved for Rs 84,587/- only

Executive Engineer,
Ghumarwin Division,
PWD, Ghumarwin.

[Signature]

Draft Schedule of Quantity

Estimated Cost	84,626.00
(Excluding GST):- Rs.	
Earnest Money:- Rs.	1,700.00
Time :-	One Month

**ne of Work:- Restoration of rain damages on Ghumarwin to Tikker Silh via Marhol . Soi Ropari km 0/00 to 6/190 (SH:-C/o R/wall at RD 1/050 to 1/054).
nder NDRF).**

No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto 1.5 m (one point five metre), within any lead .All kinds of soil as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals . The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	7.13	Per Cubic Metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	1511
	Providing and Laying concrete 1:4:8 (One cement is to four coarse sand is to eight graded crushed stone aggregate) 40mm (forty millimetre) for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	19.03	Per cubic metre	4237.29	Rupees Four Thousand Two Hundred Thirty Seven and Twenty Nine Paise	80636
3	Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge including carriage of material with in all leads and lifts and other incidentals as directed by the Engineer-In-Charge. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	9.00	each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	2479
Total						84626

Draft Schedule of Quantity No 165 for the
Year 2026-27 approved for Rs 84,626/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.

(Signature)

Draft Schedule of Quantity

Estimated Cost (Excluding GST):- Rs.	1,05,908.00
Earnest Money:- Rs.	2,200.00
Time :-	One month

Line of Work:- Construction of link road from Samshanghat Ropari to village Lower Ropari km 0/00 to 0/500 (SH:- C/o R/wall at RD 0/200 to 0/210 under SDPL)

Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
			In figure	In words	
Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead .All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	10.50	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise	2225
Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level :1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate) 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	23.60	Per Cubic Metre	4229.95	Rupees Four Thousand Two Hundred Twenty Nine and Ninety Five Paise	99827
3 Providing weep holes in brick masonry /stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre). dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614,709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	14.00	Each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise	3856
Total					105908

Draft Schedule of Quantity No 166. for the year 2026-27 approved for Rs 1,05,908/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin.

(Signature)

Draft Schedule of Quantity

Work:- Restoration of rain damages on Silh to Nain road km 0/00 to 3/285 (SH- C/o B/wall at RD 2/650 to 2/270) and Removal of land Slide 50 to 2/680. (Under PDNA Year 2023).

Description Item		Estimated Cost	
		(Excluding GST):- Rs.	
		Earnest Money:- Rs.	Time:- One months
Unit			
Quantity	Unit	Rates (Excluding GST)	
		In figure	In words
Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains not exceeding 1.5 m (one point five metre) in width or 10 sqm (ten square metre) on plan, including dressing of sides and ramming of bottoms, lift upto any lead. All kinds of soil as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	Per cubic metre	211.86	Rupees Two Hundred Eleven and Eighty Six Paise
Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level 1:4:8 (One Cement is to four coarse sand is to eight crushed graded stone aggregate) 40 mm (forty millimetre) nominal size as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	Per Cubic Metre	4237.29	Rupees Four Thousand Two Hundred Thirty Seven and Twenty Nine Paise
Providing weep holes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm (one hundred millimetre), dia PVC pipe white in colour extending through the full with of the structures with slop of 1(V): 20(H) towards drawing face complete as per HPPWD specification clauses 614.709,1204.3.7 as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	Each	275.42	Rupees Two Hundred Seventy Five and Forty Two Paise
Removal of land slide/slips in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut materials with in lift upto 1.50 mtrs and lead upto 1000 mtrs/soil with in all leads and lifts as per technical specification 302.3.5 and 1611 and as per direction of Engineer-In-Charge with in all leads and lifts and other incidentals. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	Per cubic metre	101.69	Rupees One Hundred One and Sixty Nine Paise
Total			339246

Draft Schedule of Quantity No 167 for the year 2026-27 approved for Rs. 339,246/- only

Executive Engineer,
Ghumarwin Division,
HP, PWD, Ghumarwin

Draft Schedule of Quantity

Work:- Repair Indoor Ward and old P.H.C. Building at CH Ghumarwin (SH:- Providing and laying Granite stone in 20 mm). (Health Deposit work)

Estimated Cost
(Excluding GST):- Rs. 47,766.00
Earnest Money:- Rs. 1,000.00
Time :- One Month

No.	Description Item	Quantity	Unit	Rates (Excluding GST)		Amount
				In figure	In words	
10.	Providing and laying Leather finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge :Leather finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent. The rate includes octroi, Malkana, Toll Tax, Building and Other Construction Worker Welfare Cess, royalty or any other tax, levy or cess in respect of input for or output by this contract, which shall be payable by the Contractor. Goods and Services Tax (GST) shall be excluded from the rate and shall be payable separately as per applicable rules. Government shall not entertain any claim whatsoever in this respect of the same.	16.28	Per square metre	2934.00	Rupees Two Thousand Nine Hundred Thirty Four Only	47766
	Total					47766

Draft Schedule of Quantity No-17.. for
the year 2026-27 approved for Rs 47,766/- only

Executive Engineer
G... Division
H.P. PWD, Ghumarwin...

Ⓢ