

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT  
Office of the Executive Engineer Hamirpur Division HPPWD Hamirpur**  
Web:- www.hppwd.gov.in Email:- ee-ham-hp@nic.in Phone No:- 01972-222510

No:- PW-HMR/Tender/GA-I/2026-27-  
To

7771-77

Dated:- 07/10/2026

**The Chief Engineer (HZ).  
HPPWD Hamirpur (H.P.).**

**Subject:- Publication of Tender Notice.**

Sir,

Enclosed please find herewith the Tender Notice of various works as given in the Notice Inviting Tender for uploading on department website as per Notification Secretary (PW) to the Govt. of HP vide No. PBW(B)A(23)1/2024 Dated 03-01-2025 and further in compliance of Engineer-in-Chief, HPPWD Nigam Vihar Shimla-2 letter No.PWD/ICTWing/website dt 22/05/2026 as the matter is of urgent nature and in public interest, you are requested to kindly get it published on departmental website.

DA/- As above

  
**Executive Engineer  
Hamirpur Division  
HPPWD Hamirpur**  


Copy forwarded with its enclosures for information to:-

1. The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
2. The Assistant Engineer, Sub Division, HPPWD Hamirpur and Lambloo.
3. Drawing Branch in this office.
4. Accounts Branch in this office.
5. Notice Board.

/  
**Executive Engineer  
Hamirpur Division  
HPPWD Hamirpur.**

**HIMACHAL PRADESH  
PUBLIC WORKS DEPARTMENT**

**NOTICE INVITING TENDER**

Scaled item rate tenders are hereby invited by the Executive Engineer, Hamirpur Division HPPWD., Hamirpur in form No. 6 & 8 on behalf of Governor of H.P. for the following works from the contractors of appropriate class enlisted with HP.PWD. The tender shall be opened in the presence of the contractors / firms or their representative who wish to be present.

**TIME SCHEDULE OF TENDER:-**

- |                                                              |                             |
|--------------------------------------------------------------|-----------------------------|
| 1. Date and time of receipt of application for tender form:- | 12-10-2026 up to 10.30 A.M. |
| 2. Date and time of issue of tender form :-                  | 12-10-2026 up to 3.30 P.M.  |
| 3. Date and time of receipt of tenders:-                     | 13-10-2026 up to 10.30 A.M. |
| 4. Date and time of opening of tenders:-                     | 13-10-2026 at 03.30 P.M.    |

The request for issue of tenders should be on the **PRESCRIBED APPLICATION FORM** which can be obtained from the office of undersigned and tenders will be issued to only those contractors who qualify the criteria after the scrutiny of application forms by the Committee constituted for this purpose.

| Sr. No. | Name of Work                                                                                                                                                                           | Estimated cost | EMD      | Cost of tender | Time Limit | Eligible class of contractor |
|---------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------|----------|----------------|------------|------------------------------|
| 1       | Restoration of rain damages on link road from Baffrin Harner road km 0/0 to 1/200. (SH:- Repair of pot hole at RD 0/0 to 1/200 under PDNA-2025)                                        | 491829.00      | 10000.00 | One Month      | 350/-      | Class C, D                   |
| 2       | Restoration of rain damages on link road from harsan Langwan road km 0/0 to 2/285. (SH:- Repair of pot hole at RD 0/0 to 2/0 under PDNA-2026)                                          | 472818.00      | 9500.00  | One Month      | 350/-      | Class C, D                   |
| 3       | Restoration of rain damages on Mair Bhagetu road km 0/0 to 1/700. (SH:- Providing and laying WMM & Repair to pot holes). (Total Length = 470 metre) other than AMP) (Under PDNA-2025). | 499688.00      | 10000.00 | One Month      | 350/-      | Class C, D                   |
| 4       | Restoration of rain damages on Mair Bhagetu road km 0/0 to 1/700. (SH:- Providing and laying WMM & Repair to pot holes). (Total Length = 460 metre) other than AMP) (Under PDNA-2025). | 499400.00      | 10000.00 | One Month      | 350/-      | Class C, D                   |
| 5       | Restoration of rain damages on link road to Beri to Talasi km 0/0 to 1/0. (SH:- Construction of retaining wall with wire crates at km 0/0 to 0/025 and edging).                        | 476320.00      | 9600.00  | One Month      | 350/-      | Class C, D                   |
| 6       | Restoration of rain damages on link road to Beri to Talasi km 0/0 to 1/0. (SH:- Construction of Hume pipe culvert and retaining wall at km 0/620).                                     | 488541.00      | 9800.00  | One Month      | 350/-      | Class C, D                   |

- The earnest money in the shape of National Saving Certificate, Time deposit account in any of the post office in HP / FDR of any Bank duly pledged in favour of Executive Engineer, Hamirpur Division, HP.PWD., Hamirpur must be accompanied with the application for receipt of tender form along with cost of form. Tender application received without earnest money will summarily be rejected.
- The contractors / firms should possess the following documents (photo copy to be attached with application for obtaining the tenders documents):-
  - Latest enlistment / renewal orders with application for obtaining the tenders documents.
  - GST Number issued by the Income Tax Department.
  - PAN (Permanent Account Number) issued by the Income Tax Department.
  - Shall contain scanned copies of EPF issued from competent authority.
- The Executive Engineer, Hamirpur Division HPPWD., Hamirpur reserves the right to reject any tender without assigning any reasons(s).
- The Cess Charges @ 1% will be deducted from the gross amount of work done by the Contractor.
- A contractor enlisted in a particular class shall be eligible to tender for his own class and one step below.
- If 13-10-2026 happens to be holiday the tender shall be opened on next working day at 11.00.
- GST will be deducted as per rates fixed by the Govt.

Executive Engineer,  
Hamirpur Division,  
HPPWD, Hamirpur.

Dated :- 07/10/2026

No. PWH/HMR/CB/GA-I/Tender/2026-27-  
Copy forwarded to the following:-

- The Superintending Engineer, 8th Circle, HPPWD, Hamirpur.
- The Assistant Engineer, Sub Division, HPPWD Hamirpur and Lambloo.
- Drawing Branch in this office.
- Accounts Branch in this office.
- Notice Board.

Executive Engineer,  
Hamirpur Division,  
HPPWD, Hamirpur.

# DRAFT SCHEDULE OF QUANTITY

Name Of Work :- Restoration of rain damages on link road from Baffrin Harner road km 0/0 to 1/200. (SH:- Repair of pot hole at RD 0/0 to 1/200 under PDNA-2025)

Estimated Cost:-Rs. 491829.00  
Earnest Money:- Rs. 10000.00  
Time Limit:- One Month

| Sr. No.      | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.    | Fig.    | Rate in                                                         | Unit             | Amount           |
|--------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|---------|-----------------------------------------------------------------|------------------|------------------|
|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |         |         | Words                                                           |                  |                  |
| 1            | Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) (fifty three millimetres to zero point zero seven five millimetres) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne ( eight to ten tonne) capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge as pr direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                                                                                                                                                                | 18.80   | 2207.26 | Rupees Two Thousand Two Hundred Seven and Paise Twenty Six Only | Per cubic metre  | 41496.00         |
| 2            | Repair to patch/pot holes (any depth) in connection with repainting including sweeping free from dust and mud, scoring sunken surfaces in road, paths etcetera cutting around edges to atleast 25mm (Twenty five millimetres) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm (Zero point three zero zero kilogramme per square metre) and then providing 20mm (Twenty millimetres) thick premix carpet using VG-10 bitumen @1.46kg/sqm (One point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @0.68kg/sqm (Zero point six eight kilogramme per square metre) as per technical specification clause 1904.2, 503 and 508.2 including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, Malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 1106.47 | 407.00  | Rupees Four Hundred Seven and Paise Zero Only                   | Per square metre | 450333.00        |
| <b>Total</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |         |         |                                                                 |                  | <b>491829.00</b> |

## Conditions:-

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure Cement from Civil Supply Depot, VG-30 & Emulsion RS-1 & SS-1 from HPC/IOCL/BPCL at their own level after the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 491829. only  
Rupees Four Lakhs Ninety One Thousand Eight Hundred Twenty Nine and Paise Zero Only

Executive Engineer,  
Hamirpur Division,  
HPPWD, Hamirpur

# DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on link road from Harsan Langwan road km 0/0 to 2/285. (SH:- Repair of pot hole at RD 0/0 to 2/0 under PDNA-2025).

Estimated Cost:-Rs. 472818.00

Earnest Money:- Rs. 9500.00

Time Limit:- One Month

| Sr. No.      | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.    | Time Limit:- One Month |                                                                 |                  |           |
|--------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|------------------------|-----------------------------------------------------------------|------------------|-----------|
|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |         | Rate in Words          | Unit                                                            | Amount           |           |
| 1            | Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm ) ( fifty three millimetres to zero point zero seven five millimetres ) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base /base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne ( eight to ten tonne) capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge as pr direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                                                                                                                                                              | 27.51   | 2207.26                | Rupees Two Thousand Two Hundred Seven and Paise Twenty Six Only | Per cubic metre  | 60722.00  |
| 2            | Repair to patch/pot holes (any depth) in connection with repainting including sweeping free from dust and mud, scoring sunkeda surfaces in road, paths etcetera cutting around edges to atleast 25mm (Twenty five millimetres) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm (Zero point three zero zero kilogramme per square metre) and then providing 20mm (Twenty millimetres) thick premix carpet using VG-10 bitumen @1.46kg/sqm (One point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @0.68kg/sqm (Zero point six eight kilogramme per square metre) as per technical specification clause 1904.2, 503 and 508.2 including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 1012.52 | 407.00                 | Rupees Four Hundred Seven and Paise Zero Only                   | Per square metre | 412096.00 |
| Conditions:- |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Total   |                        |                                                                 |                  | 472818.00 |

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure Cement from Civil Supply Depot, VG-30 & Emulsion RS-1 & SS-1 from HPCL/IOCL/BPCL at their own level after the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP, vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 472818/- only  
Rupees Four Lakhs Seventy Two Thousand Eight Hundred Eighteen and Paise Zero Only

Executive Engineer,  
Hamirpur Division,  
HPPWD, Hamirpur

# DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on Mair Bhagetu road km 0/0 to 1/700. (SH:- Providing and laying WMM & Repair to pot holes). (Total Length = 470 metre) other than AMP) (Under PDNA-2025).

Estimated Cost:-Rs. 499688.00  
Earnest Money:- Rs. 10000.00  
Time Limit:- One Month

| Sr. No. | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                | Qty.    | Rate in | Unit                                                            | Amount           |           |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------|---------|-----------------------------------------------------------------|------------------|-----------|
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |         | Words   |                                                                 |                  |           |
| 1       | Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm ) ( fifty three millimetres to zero point seven five millimetres ) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base /base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne ( eight to ten tonne) capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge as pr direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                                                                                                                                                                   | 29.81   | 2207.26 | Rupees Two Thousand Two Hundred Seven and Paise Twenty Six Only | Per cubic metre  | 65798.00  |
| 2       | Repair to patch/pot holes (any depth) in connection with repainting including sweeping free from dust and mud, scoring sunken surfaces in road, paths etcetera cutting around edges to atleast 25mm (Twenty five millimetres) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm (Zero point three zero zero kilogramme per square metre) and then providing 20mm (Twenty millimetres) thick premix carpet using VG-10 bitumen @1.46kg/sqm (One point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @0.68kg/sqm (Zero point six eight kilogramme per square metre) as per technical specification clause 1904.2, 503 and 508.2 including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 1066.07 | 407.00  | Rupees Four Hundred Seven and Paise Zero Only                   | Per square metre | 433890.00 |
| Total   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |         |         |                                                                 |                  | 499688.00 |

## Conditions:-

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure Cement from Civil Supply Depot., VG-30 & Emulsion RS-1 & SS-1 from HPCL/IOCL/BPCL at their own level after the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499688.- only  
Rupees Four Lakhs Ninety Nine Thousand Six Hundred Eighty Eight and Paise Zero Only

Executive Engineer,  
Hamirpur Division,  
HPPWD, Hamirpur

# DRAFT SCHEDULE OF QUANTITY

Name Of Work:- Restoration of rain damages on Mair Bhagetu road km 0/0 to 1/700. (SH:- Providing and laying WMM & Repair to pot holes). (Total Length = 460 metre) other than AMP) (Under PDNA-2025).

Estimated Cost:-Rs. 499400.00  
Earnest Money:- Rs. 10000.00

Time Limit:- One Month

| Sr. No.             | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | Qty.         | Fig.    | Rate in                                                           |       | Unit             | Amount           |
|---------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------|---------|-------------------------------------------------------------------|-------|------------------|------------------|
|                     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |              |         | Words                                                             | Words |                  |                  |
| 1                   | Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm) (fifty three millimetres to zero point seven five millimetres) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub-base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne (eight to ten tonne) capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                                                                                                                                                                      | 28.72        | 2207.26 | Rupees Two Thousand Seven Hundred Seven and Paise Twenty Six Only |       | Per cubic metre  | 63393.00         |
| 2                   | Repair to patch/pot holes (any depth) in connection with repainting including sweeping free from dust and mud, scoring sunken surfaces in road, paths etcetera cutting around edges to atleast 25mm (Twenty five millimetres) in depth and removal of loose material, trimming of sides, cleaning of surface and making good by providing tack coat with emulsion bitumen @ 0.300kg/sqm (Zero point three zero zero kilogramme per square metre) and then providing 20mm (Twenty millimetres) thick premix carpet using VG-10 bitumen @1.46kg/sqm (One point four six kilogramme per square metre) and seal coat type-B with VG-10 bitumen @0.68kg/sqm (Zero point six eight kilogramme per square metre) as per technical specification clause 1904.2, 503 and 508.2 including entire carriage of material with in all leads, lifts, drawings, technical specifications as per direction by Engineer-in-Charge including other incidentals. The rates are inclusive of octroi, royalty, malikana, toll tax, sale tax, GST or other taxes imposed by the Government. | 1071.27      | 407.00  | Rupees Four Hundred Seven and Paise Zero Only                     |       | Per square metre | 436007.00        |
| <b>Conditions:-</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | <b>Total</b> |         |                                                                   |       |                  | <b>499400.00</b> |

- The work will be strictly executed as per HPPWD specifications
- The contractor will procure Cement from Civil Supply Depot, VG-30 & Emulsion RS-1 & SS-1 from HPCL/IOCL/BPCL at their own level after the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 499400/- only  
Rupees Four Lakhs Ninety Nine Thousand Four Hundred and Paise Zero Only

Executive Engineer,  
Hamirpur Division  
HPPWD, Hamirpur

**DRAFT SCHEDULE OF QUANTITY**

**Name Of Work:-** Restoration of rain damages on link road to Beri to Talasi km 0/0 to 1/0. (SH:- Construction of retaining wall with wire crates at km 0/0 to 0/025 and edging).

**Estimated Cost:-** Rs. 476320.00  
**Earnest Money:-** Rs. 9600.00  
**Time Limit:-** One Month

| Sr. No.      | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Qty.   | Fig.    | Rate in                                                     | Unit            | Amount           |
|--------------|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------|---------|-------------------------------------------------------------|-----------------|------------------|
|              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |        |         | Words                                                       |                 |                  |
| 1            | Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed; within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malakana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                                                        | 31.25  | 300.00  | Rupees Three Hundred and Paise Zero Only                    | Per cubic metre | 9375.00          |
| 2            | Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm (forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures including the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malakana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                                                                    | 27.00  | 4400.00 | Rupees Four Thousand Four Hundred and Paise Zero Only       | Per cubic metre | 118800.00        |
| 3            | Providing and laying of boulder apron laid in wire crates with 4mm (Four millimetres) dia G.I. wire conforming to IS:280 and IS:4826 in 100mmx100mm (One hundred into one hundred millimetre) mesh (woven diagonally) including 10% (Ten percent) extra for laps and joints laid with stone boulders weighing not less than 25kg (Twenty five kilogramme) each as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malakana, toll tax, sale tax or other taxes imposed by the Government.                                                                                                                                                  | 105.46 | 3250.00 | Rupees Three Thousand Two Hundred Fifty and Paise Zero Only | Per cubic metre | 342745.00        |
| 4            | Providing weep holes in brick masonry / Stone masonry / Plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm <sup>2</sup> (four kilogramme ) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malakana, toll tax, sale tax, GST or other taxes imposed by the Government. | 18.00  | 300.00  | Rupees Three Hundred and Paise Zero Only                    | Each            | 5400.00          |
| <b>Total</b> |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |        |         |                                                             |                 | <b>476320.00</b> |

**DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 476320/-**  
Rupees Four Lakhs Seventy Six Thousand Three Hundred Twenty and Paise Zero Only

- 1 **Condition**  
The work will be strictly executed as per HPPWD specifications
- 2 The contractor will procure cement/steel at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August 2018 and all other condition are liable & carriage will be born by the contractor.
- 3 The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

  
**Executive Engineer,**  
Hamirpur Division  
HPPWD, Hamirpur

Name Of Work:- Restoration of rain damages on link road to Beri to Talasi km 0/0 to 1/0. (SH:- Construction of Hume pipe culvert and retaining wall at km 0/620).

**DRAFT SCHEDULE OF QUANTITY**

Estimated Cost:-Rs. 488541.00  
Earnest Money:- Rs. 9800.00  
Time Limit:- One Month

| Sr. No. |  | Description of Items                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | Qty.  | Rate in |                                                       | Unit               | Amount           |
|---------|--|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-------|---------|-------------------------------------------------------|--------------------|------------------|
|         |  |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |       | Fig.    | Words                                                 |                    |                  |
| 1       |  | Excavation work by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms within all leads including getting out the excavated soil and disposal of surplus excavated soil as directed, within all leads and lifts ordinary rock and all kinds of soil including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                                                                                | 54.09 | 300.00  | Rupees Three Hundred and Paise Zero Only              | Per cubic metre    | 16227.00         |
| 2       |  | tax, sale tax, GST or other taxes imposed by the Government.<br>Providing and laying in position cement concrete of specified grade 1:5:10 (one cement : five coarse sand : ten graded stone aggregate) 40mm ( forty millimetre) nominal size graded stone aggregate in retaining wall, breast wall, walls of any thickness and like structures including the cost of centering and shuttering including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.                                                                           | 83.26 | 4400.00 | Rupees Four Thousand Four Hundred and Paise Zero Only | Per cubic metre    | 366344.00        |
| 3       |  | Providing and laying cement concrete 1:3:6 (One cement : three coarse sand : six graded stone aggregate) 20 mm (Twenty millimetre) nominal size in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, filets, sunken floor etcetera <b>excluding the cost of centering, shuttering and finishing</b> as per direction of Engineer-in-Charge including entire carriage of material within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.                                     | 10.24 | 5500.00 | Rupees Five Thousand Five Hundred and Paise Zero Only | Per cubic metre    | 56320.00         |
| 4       |  | taxes imposed by the Government.<br>Providing weep holes in brick masonry / Stone masonry / plain/reinforced concrete in retaining walls, breast walls and the like with 110mm (One hundred ten millimetre) dia PVC pipe Finolex/ Supreme having pressure not less than 4.00 Kg/Cm² (four kilogramme ) per centimetre square extending through the full width of the structure with slope of 1(V):20(H) (one vertical : twenty horizontal) towards drawing face complete including entire carriage of materials within all leads and lifts and as per drawings and technical specifications as per the direction of Engineer-in-Charge including all incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government. | 28.00 | 300.00  | Rupees Three Hundred and Paise Zero Only              | Each               | 8400.00          |
| 5       |  | Providing and laying 900mm (Nine hundred millimetre diameter) ( to level and slopes) reinforced cement concrete non pressure pipe I.S.I class NP-3 (Medium duty) for culverts on 1st class bedding of granular material in single row including collar with cement mortar 1:2 (One cement : two coarse sand) but excluding the cost of excavation protection work, back filling, concrete and masonry work in head walls and parapets as per drawing and MORD technical specification and as per direction of Engineer-in-Charge including entire carriage of materials within all leads and lifts and other incidentals. The rates are inclusive of octroi, royalty, malkana, toll tax, sale tax, GST or other taxes imposed by the Government.                                         | 7.50  | 5500.00 | Rupees Five Thousand Five Hundred and Paise Zero Only | Per Running metre. | 41250.00         |
|         |  | <b>Total</b>                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |       |         |                                                       |                    | <b>488541.00</b> |

- Condition**
- The work will be strictly executed as per HPPWD specifications
  - The contractor will procure cement/steel at their own level from Civil Supply Depot. After the approval of permit from the competent authority and other material from market as per Department specification issued by the Addition Chief Secretary PW to the Govt. of HP vide No. PBW (B) C (17) 2/2012 dated 07 August, 2018 and all other condition are liable & carriage will be born by the contractor.
  - The bills of all materials procured by the contractor M-form of mining materials used for execution of work must be submitted to the authority concerned alongwith contractor bill.

Executive Engineer,  
Hamirpur Division,  
HPPWD, Hamirpur

DRAFT SCHEDULE OF QUANTITY APPROVED FOR RS. 488541/-  
Rupees Four Lakhs Eighty Eight Thousand Five Hundred Forty One and Paise Zero Only