



**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

Telephone No:-01782-240075
e-mail:-ee-kum-hp@nic.in

No. PW-KMS-AB-NIT/2026-27- 4838-40

Dated: - 08.10.2026

To

The Executive Engineer (IT Cell),
HP, PWD, Nirman Bhawan,
Nigam Vihar Shimla-2

Subject: -

Publication of Tender Notice


Enclosed please find herewith the tender of works as given in the Notice Inviting tender for uploading on department website as per notification Pr. Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW(B)1/2020 dated 16.07.2021 as the works mentioned in the tender notice are urgent in nature and public interest.

**Encl: - Notice Inviting tender &
Schedule of Quantity and certificate.**


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

Copy to the Supertntending Engineer, 11th Circle,
HP.PWD., Rampur Bsr. for information please.

Copy to Drawing Branch in this office.


Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

CERTIFICATE

CERTIFIED THAT THE TENDERS OF WORKS, AS CALLED
VIDE THIS OFFICE LETTER NO. PWKMS-AB-NIT/2026-27-⁴⁸³⁸⁻⁴⁰-----DATED^{08.10.2026}-----
ARE URGENT NATURE AND PUBLIC INTEREST.



Executive Engineer,
Kumarsain Division,
HPPWD Kumarsain

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

"NOTICE INVITING TENDER"

Sealed percentage rate tenders are hereby invited by the Executive Engineer, Kumarsain Division, and HP.PWD. Kumarsain from the experienced contractors enlisted with PWD for B&R works, so as to reach in this office on or before 17.10.2026 up to 12:00 PM and will be opened on same day at 02:00 PM. in the presence of intending contractors or their authorized representatives who may wish to be present.

The application for issue of tender form shall be received on 16.10.2026 up to 1:00 PM. The tender form can be had from this office against cash payment (Non-refundable) on 16.10.2026 upto 5:00 PM.

The earnest money in the shape of National saving certificate/Time deposit receipt of any recognized Bank in H.P. duly pledged in the name of XEN must accompany with each application for obtaining the tender form. The Executive Engineer reserves the right to reject the tenders without assigning any reasons.

1. **Name of work:-** Construction of link road from Barogi Khaltudhar road to Kehri GP Deeb Km.0/000 to 0/750 (SH:-Formation cutting 5/7 mtr. wide road in Km.0/525 to 0/630).Estimated Cost:-3,98,032/-(Excluding GST) Earnest Money: 8,000/- Time allowed: -One Months.
2. **Name of work:-** Restoration of rain damages on link road to village Aroth Km. 0/000 to 2/840 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips at various RD's)..Estimated Cost:-2,85,600/-(Excluding GST) Earnest Money: 5,750/- Time allowed: -Two Months.
3. **Name of work:-** Restoration of rain damages on link road to village Aroth Km. 0/000 to 2/840 (under PDNA)(SH:-Hiring of Tipper for carriage of removal slips/debris)).Estimated Cost:-1,86,400/- Earnest Money: 3,750/- Time allowed: -Two Month.
4. **Name of work:-** A/R & M/O on various roads under Kumarsain Sub-Division (SH:-Supplying and stacking stone aggregate 13.2mm to 6.7mm size).Estimated Cost:-96,000/-(Excluding GST) Earnest Money: -1,950/- Time allowed: -One Month.
5. **Name of work:-** Restoration of rain damages on Malendi Section (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips at various roads under Malendi Section).Estimated Cost:-99,960/-(Excluding GST) Earnest Money: -2,000/- Time allowed: -One Month.
6. **Name of work** Restoration of rain damages on link Nog Kirti road Km. 0/000 to 9/165 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips at various RD's).Estimated Cost:-99,960/-(Excluding GST) Earnest Money: -2,000/- Time allowed: -One Month.
7. **Name of work:** A/R & M/O link road Kachoti Khad to Odi Nalla G.P. Khaneti Km.0/000 to 2/453 (SH:-Construction of P.C.C V-shape side drain and Providing and laying of hot applied Thermoplastic compound 2.5mm thick in Km. 1/600 to 2/453).Estimated Cost:-3,33,354/-(Excluding GST) Earnest Money: 6,700/- Time allowed: -One Month.
8. **Name of work:** A/R & M/O link road Kachoti Khad to Odi Nalla G.P. Khaneti Km.0/000 to 2/453 (SH:-Construction of P.C.C V-shape side drain and Providing and laying of hot applied Thermoplastic compound 2.5mm thick in Km. 0/000 to 0/800).Estimated Cost:-3,14,115/-(Excluding GST) Earnest Money:-6,300/- Time allowed: -One Month.

Terms and conditions:-

1. The contractors shall produce their latest registration/renewal of their registration/GST No/EPF No./ PAN No. along with their application.
2. The single/conditional tender will be rejected.
3. The offer shall remain valid up to 75 days.
4. The amount should be within the 5% above.
5. The work should be started within fifteen days from the opening of tender.

Note:- Since the work involves mass concrete. Hence 20mm dia needle vibrator is mandatory at site during concrete pouring

Executive Engineer,
Kumarsain Division
HP.PWD, Kumarsain

No.PW-KMS-AB-N.I.T/2026-27- 4838-40

Dated:- 08.10.2026

Copy to the Engineer-in-Chief, HP.PWD., Shimla-2.
Copy to the Deputy Commissioner Shimla, District Shimla (H.P)
Copy to the Sub-Divisional Officer © Kumarsain, Distt. Shimla (H.P.)
Copy to the Superintending Engineer, XIth Circle, HP.PWD., Rampur.
Copy to Block Development office, Narkanda Distt. Shimla, (H.P.)
Copy to all Assistant Engineers under this Division for information & n.a.
Copy to various contractors for information.
Copy to Notice Board of this office.

Executive Engineer,
Kumarsain Division,
HP.PWD. Kumarsain

DRAFT SCHEDULE OF QUANTITY.

Estimated Cost:-Rs.398032/-

Earnest money:-8000/-

Time allowed:-One month.

Name of work:-Construction of link road from Barogi Khaltudhar road to Kehri GP Deeb Km.0/000 to 0/750 (SH:-Formation cutting 5/7 mtr. wide road in Km.0/525 to 0/630)

S.No.	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	5/7 meters wide (5 meters wide in straight and 7 meters on curves) Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposal of excavated earth in all height and depths in all kinds of soil, including saturated soil comprising of pick work, jumper work and blasting work both in soft and hard rock with chiseling and wedging out of rock where blasting is prohibited and their intermediate classification of soils including dewatering wherever required, setting out true to the required lines, grades, side, slopes, trimming of bottom and levels as shown on the drawing and as directed by the Engineer.-in Charge. at site according to the HP.PWD specification of 1990 volume-I and sorting out useful and un-useful material and stacking the same in all leads and lifts and transportation of the un serviceable materials for filling in roadways, embankment s for grade improvement and leveling to required grades and then disposing of all surplus excavated materials in acquired width of the road or on approved dumping site /sites through all labours machineries materials, tools, equipments and safety measures and other incidental necessary to complete the work by mechanical means and or labour if any required. The recovery for stones, whether useful or not for 278.38 (Two hundred seventy eight point thirty eight) Cubic Meter in all cases at the rate of Rupees 300/- only (Rupees three hundred only) per cubic meter shall be effected on pro rata basis in all circumstances. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1360.28 m3	292.61	(Rupees two hundred ninety two and paise sixty one only).	Per cubic metre.	398032.00
	G.Total:-					398032.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

The following materials will be issued from P.W.D Store at Kumarsain.

- | | | |
|---|-----------------------------|------------------------|
| 1 | Gelatine @ Rs.88.53/Per Kg. | } +3% storage charges. |
| 2 | Detonator @ Rs.3.39/Each. | |
| 3 | S.F coil @ Rs.31/Coil | |

Draft schedule of quantity approved for
Rs. 3,98,032/- only

Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

(51)
1st copy

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.285600/-

Earnest money:-Rs.5750/-

Time allowed:-Two Months.

Name of work:-Restoration of rain damages on link road to village Aroth Km. 0/000 to 2/840 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips at various RD's).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compansated to the full extent by him in all respect and in all cases .	280.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	285600.00
Total:-						285600.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Draft schedule of quantity approved for
Rs. 2,85,600/- only.

Executive Engineer,
Kumarsain Division,
H.P.W.D., Kumarsain.

S2
1st copy

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.186400/-

Earnest money:-Rs.3750/-

Time allowed:-Two Months.

Name of work:-Restoration of rain damages on link road to village Aroth Km. 0/000 to 2/840 (under PDNA)(SH:-Hiring of Tipper for carriage of removal slips/debries)

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of tipper for carriage of slips/muck including boulders etc. in all leads and lifts as direction of Engineer-in-Charge.	40 Days	4660.00	(Rupees four thousand six hundred sixty only).	Per Day.	186400.00
	Total:-					186400.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Draft schedule of quantity approved for
Rs. 186400/- only


Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

53

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.96000/-

Earnest money:-Rs.1950/-

Time allowed:-One Month.

Name of work:-A/R & M/O on various roads under Kumarsain Sub-Division (SH:-Supplying and stacking stone aggregate 13.2mm to 6.7mm size).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Supplying and stacking at site broken/crushed aggregate chipping of hard stones of following nominal size free of disintegrated pieces deleterious and organic materials 13.2mm to 6.7mm size crushed stone aggregate including stacking the material including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge.	80.00 m3	1200.00	(Rupees one thousand two hundred only).	Per cubic metre.	96000
Total:-						96000.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Draft schedule of quantity approved for
Rs. 99,600/- only

Executive Engineer,
Kumarsain Division,
HP PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

1st copy (7/)

Estimated cost:-Rs.99960/-

Earnest money:-Rs.2000/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on Malendi Section (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips at various roads under Malendi Section).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compansated to the full extent by him in all respect and in all cases .	98.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	99960.00
Total:-						99960.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Draft schedule of quantity approved for
Rs. 99960/- only

Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

1st copy (72)

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.99960/-

Earnest money:-Rs.2000/-

Time allowed:-One Month.

Name of work:-Restoration of rain damages on link Nog Kirti road Km. 0/000 to 9/165 (under PDNA) (SH:-Hiring of JCB front end loader for removal of slips at various RD's).

S. No	Sub-Head/Items of work.	Quantity.	Rate.(Excluding GST)		Unit.	Amount.
			In fig.	in words.		
1	Hiring of (J.C.B) front end loader for removal of slips including P.O.L. as per direction Engineer- in-Charge. Any loss to public and private property during the course of excution and disposal of secviceable / unserviceable material shall be the abolute responsibility of the contractor which shall also be duly compansated to the full extent by him in all respect and in all cases .	98.00 Hours	1020.00	(Rupees one thousand twenty only).	Per Hour	99960.00
	Total:-					99960.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

Draft schedule of quantity approved for
Rs. 99,960/-

Executive Engineer,
Kumarsain Division,
HP.PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.333354/-

Earnest money:-Rs.6700/-

Time allowed:-One month.

Name of work:-A/R & M/O link road Kachoti Khad to Odi Nalla G.P. Khaneti Km.0/000 to 2/453 (SH:-Construction of P.C.C V-shape side drain and Providing and laying of hot applied Thermoplastic compound 2.5mm thick in Km. 1/600 to 2/453).

S.N o.	Sub-Head/Items of work.	Quantity.	Rate (excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	70.80 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	15576.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 P.C.C grade M 10 Nominal mix 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate of 20mm nominal size) including entire carriage of materials plants and equipments by all modes of transportation with in all leads and lifts and as per direction of Engineer-in-Charge.	61.42 m3	4660.00	(Rupees four thousand six hundred sixty only).	Per cubic metre.	286217.00
3	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications., including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge.	85.30 m2	370.00	(Rupees three hundred seventy only).	Per square metre.	31561.00
Total:-						333354.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for
Rs. 3,33,354/- only

Executive Engineer,
Kumarsain Division,
HR PWD., Kumarsain.

DRAFT SCHEDULE OF QUANTITY

Estimated cost:-Rs.314115/-

Earnest money:-Rs.6300/-

Time allowed:-One month.

Name of work:-A/R & M/O link road Kachoti Khad to Odi Nalla G.P. Khaneti Km.0/000 to 2/453 (SH:-Construction of P.C.C V-shape side drain and Providing and laying of hot applied Thermoplastic compound 2.5mm thick in Km. 0/000 to 0/800).

S.No.	Sub-Head/Items of work.	Quantity.	Rate (excluding GST)		Unit.	Amount.
			In fig.	In words.		
1	Earth work in excavation for structures as per drawing and technical specifications clause 305.1 including setting out, construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom backfilling in trenches with excavated suitable materials upto all leads and lifts as per directions of the Engineer-in-Charge.	66.40 m3	220.00	(Rupees two hundred twenty only).	Per cubic metre.	14608.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 P.C.C grade M 10 Nominal mix 1:3:6 (1 cement : 3 sand : 6 graded stone aggregate of 20mm nominal size) including entire carriage of materials plants and equipments by all modes of transportation with in all leads and lifts and as per direction of Engineer-in-Charge.	57.92 m3	4660.00	(Rupees four thousand six hundred sixty only).	Per cubic metre.	269907.00
3	Providing and applying 2.5 mm thick road marking strips (retro- reflective) of specified shade/ colour using hot thermoplastic material by fully/semi automatic thermoplastic paint applicator machine fitted with profile shoe, glass beads dispenser, propane tank heater and profile shoe heater, driven by experienced operator on road surface including cost of material, labour, T&P, cleaning the road surface of all dirt, seals, oil, grease and foreign material etc. complete as per direction of Engineer-in-charge and accordance with applicable specifications., including entire carriage of materials in all leads and lifts as per direction of Engineer-in-Charge.	80.00 m2	370.00	(Rupees three hundred seventy only).	Per square metre.	29600.00
Total:-						314115.00

Note:-(i) Rates derived for the purpose of estimation are excluding GST.

(ii) GST @ 18% shall be payable separately.

(iii) Since the work involves mass concrete work. Hence use of 40mm dia needle vibrator is mandatory at site during concrete pouring.

Draft schedule of quantity approved for
Rs. 3,14,115/- only

Executive Engineer,
Kumarsain Division,
H.B.W.D. Kumarsain