

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2026-27-14706-36

Dated:- 05/10/2026

To

✓ The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 dated 03-01-2024, letter No.300858 dated 09-10-2025 and even letter dated 21.09.2026 and as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

Copy forwarded for the following information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

/

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dhami
Ph. 0177-2790534

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Sealed percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. -Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **13.10.2026 up to 10:30 A.M** and the same shall be opened on the same day at **11:00 A.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **12.10.2026 up to 4.00 P.M** and the application for issue of tender form shall be received on **12.10.2026 up to 12:00 P.M.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R damages on Galog Halog Road km. 0/00 to 2/300 (SH: - Providing and Laying G-III & Bitumen penetration macadam for correction of road surface in km. 0/00 to 2/300) Job No.1.	423039/-	8000/-	One Month	Rs.350/-
2	R/R damages on Rattanpur Bathmana Road km. 0/00 to 1/600 (SH:- Providing and Laying G-III & Bitumen penetration macadam for correction of road surface in km. 0/00 to 1/600)	420580/-	8000/-	One Month	Rs.350/-
3	R/R damages on Gharog Nalta Road km. 0/00 to 7/00 (SH: - Providing and Laying G-III & Bitumen penetration macadam for correction of road surface in km. 0/00 to 7/00) Job No.1.	421614/-	8000/-	One Month	Rs.350/-
4	R/R damages on Gharog Nalta Road km. 0/00 to 7/00 (SH: - Providing and Laying G-III & Bitumen penetration macadam for correction of road surface in km. 0/00 to 7/00) Job No.2.	411113/-	8000/-	One Month	Rs.350/-
5	R/R damages on Thachi Seri Shalli Road km. 0/00 to 3/285 (SH:- Providing and Laying G-III & Bitumen penetration macadam for correction of road surface in km. 0/00 to 3/285) Job No.1.	405411/-	8000/-	One Month	Rs.350/-
6	R/R damages on Galog Nehra Okhroo road km. 0/00 to 11/135 (SH:- Providing and Laying WBM G-III and Bitumen Penetratin Macadam for correction of road surface in km. 1/00 to 2/00).	421902/-	8000/-	One Month	Rs.350/-

7	R/R damages on Galog Nehra Okhroo road km. 0/00 to 11/135(SH:- Providing and Laying WBM G-III and Bitumen Penetratin Macadam for correction of raod surface in km. 4/00 to 5/00).	422772/-	8000/-	One Month	Rs.350/-
8	R/R damages on Galog Nehra Okhroo road km. 0/00 to 11/135(SH:- Providing and Laying WBM G-III and Bitumen Penetratin Macadam for correction of raod surface in km.0/00 to 1/00).	423376/-	8000/-	One Month	Rs.350/-
9	A/R & M/O various Roads under Sunn-I Section under Sunni Sub-Division (SH:- Repair of Pot holes, P/L 20mm Premix carpet & seal coat on (i) Link road to village Chebri in km. 0/00 to 1/00(ii) Link road Chebri to Sarkadi in km. 0/00 to 0/500).	422462/-	8500/-	One Month	Rs.350/-
10	R/R damages on Thachi Seri Shalli Road km. 0/00 to 3/285 (SH:- Providing and Laying G-III & Bitumen penetration macadam for correction of road surface in km. 0/00 to 3/285) Job No.2.	405411/-	8000/-	One Month	Rs.350/-
11	Repair & Maintenance of Judicial Academy at Ghandal Distt. Shimla H.P (SH:- Providing & Fixing Granite Stone, Painting, Steel Work and Red Stone etc.)	406339/-	8000/-	One Month	Rs.350/-
12	Preparation of Detail Project Report for various roads under HPPWD Dharni Division Distt. Shimla (H.P) (SH:- C/o link road to Chaili Khurd km 0/00 to 1/500 (ii) C/o link road to village Dargot km. 0/00 to 5/00).	385593/-	7800/-	One Month	Rs.350/-
13	Preparation of Detail Project Report for various roads under HPPWD Dharni Division Distt. Shimla (H.P) (SH:- C/o link road Jawaharnagar Shanahu Shyalti in km. 0/00 to 2/800).	166102/-	3500/-	One Month	Rs.350/-
14	Preparation of Detail Project Report for various roads under HPPWD Dharni Division Distt. Shimla (H.P) (i) C/o Link road Garkhan to Berti road km. 0/00 to 4/7/00).	278814/-	5600/-	One Month	Rs.350/-
15	C/O Link road from Nehwat Nayaser Ghaini Devidhar road Km. 0/000 to 13/691 (SH: - C/O 24 meter span RCC T-Beam Bridge (CH: 4/813 to 4/837) (Sub-work: Dewatering/Pumping out water from excavated pit) Job-1.	411185/-	10000	One Month	Rs.350/-
16	C/O Link road from Nehwat Nayaser Ghaini Devidhar road Km. 0/000 to 13/691 (SH: - C/O 24 meter span RCC T-Beam Bridge (CH: 4/813 to 4/837) (Sub-work: Dewatering/Pumping out water from excavated pit) Job-2.	411185/-	10000	One Month	Rs.350/-
17	Preparation of Detail Project Report for various roads under HPPWD Dharni Division, Distt. Shimla (H.P) (i) C/o Link road to Karyali to Shara Nallah 0/00 to 8/300).	492373/-	10000/-	One Month	Rs.350/-
18	R/R damages on Dharni Bainsh Road km. 0/00 to 6/00 (SH:- Providing and Laying G-III & Bitumen penetration macadam for correction of road surface in km. 4/00 to 6/00).	419881/-	8000/-	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhani

Certificate

Certified that the tenders called vide this notice inviting tender for 18 (Eighteen) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dhani

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Galog Halog Road Km. 0/00 to 2/300 (Sh: Providing and laying G-III & bitumen penetration macadam for correction of road surface in km. 0/000 to 2/300) Job No. 1

Estimated Cost:- Rs. 423039/- only
Earnest Money:- Rs. 8000/- only
Time:- One Month

S. No.	Sub head and items of work	Qty.	Rate			Unit	Amount
			figures	5	6		
1	Providing laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 KN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum, (Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 By mechanical means and as per intire satispction direction by the Engineer-In-Charge including carriage of materials all leads and lifts as per the direction of Engineer in Charge	32.63	Cum	2076.27	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre	57749.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bitumenous surface cleaned with Hydraulic broom as per Technical Specification Clause 503 including entire carriage of materials upto all leads and lifts and as per thedirection of Engineer in Charge	543.83	Sqm	29.52	Rupees Twenty Nine and Paise Fifty Two Only	Per cubic metre	15054.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	543.83	Sqm	623.79	Rupees Six Hundred Twenty Three and Paise Seventy Nine Only	Per cubic metre	309236.00
0						Total:	423039.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharmu

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Ratanpur Bathmana Road Km. 0/000 to 1/600 Sh: Providing and laying G-III & bitumen penetration macadam for correction of road surface in km. 0/000 to 1/600)

Estimated Cost: - Rs. 420580/- only
Earnest Money: - Rs. 8000/-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum/(Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 By mechanical means and as per intire satispsection direction by the Engineer-In-Charge, including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	32.44	Cum	2076.27	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre 67354.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bitumenous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per thedirection of Engineer in Charge.	540.67	Sqm	29.52	Rupees Twenty Nine and Paise Fifty Two Only	Per cubic metre 15961.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ lipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	540.67	Sqm	623.79	Rupees Six Hundred Twenty Three and Paise Seventy Nine Only	Per cubic metre 337265.00
0						Total: 420580.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Gharog Nalta Road Km. 0/000 to 7/000 (Sh: Providing and laying G-III & bitumen penetration macadam for correction of road surface in Km. 0/000 to 7/000) Job No. 1

Estimated Cost:- Rs 421614 /- only
Earnest Money :- Rs. 8000 /-only
Time:- One Month

S. No.	Sub head and items of work	Qty.	Rate			Unit	Amount
			4	5	figures		
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using Template, hand packing, rolling with three wheel 80-100 kN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum.(Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405. By mechanical means and as per intire satispction direction by the Engineer-In-Charge. including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	32.52 Cum	2076.27	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only		Per cubic metre	67520.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bitumenous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per thedirection of Engineer in Charge.	542.00 Sqm	29.52	Rupees Twenty Nine and Paise Fifty Two Only		Per cubic metre	16000.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	542.00 Sqm	623.79	Rupees Six Hundred Twenty Three and Paise Seventy Nine Only		Per cubic metre	338094.00
0						Total:	421614.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Charog Nalta Road Km. 0/000 to 7/000 (Sh: Providing and laying G-III & bitumen penetration macadam for correction of road surface in km. 0/000 to 7/000) Job No. 2

Estimated Cost:- Rs 411113/- only
Earnest Money :- Rs. 8000 /-only
Time:- One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm/fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum/(Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405.By mechanical means and as per intire satisfaction direction by the Engineer-In-Charge. including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	31.71 Cum	2076.27	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre	65839.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bitumenous surface cleaned with Hydanrlic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per thedirection of Engineer in Charge	528.50 Sqm	29.52	Rupees Twenty Nine and Paise Fifty Two Only	Per cubic metre	15601.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	528.50 Sqm	623.79	Rupees Six Hundred Twenty Three and Paise Seventy Nine Only	Per cubic metre	329673.00
0					Total:-	411113.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Thachi Seri Shaili Road Km. 0/000 to 3/285 (Sh: Providing and laying G-III & bitumen penetration macadam for correction of road surface in km. 0/000 to 3/285) Job No. 2

Estimated Cost:- Rs 405411/-, only
Earnest Money:- Rs. 8000/- only
Time:- One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			figures	5		
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 KN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum (Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405. By mechanical means and as per intire satlspection direction by the Engineer-In-Charge. including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	31.27	Cum	2076.27	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre 54925.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bitumenous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per thedirection of Engineer in Charge.	521.17	Sqm	29.52	Rupees Twenty Nine and Paise Fifty Two Only	Per cubic metre 15385.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	521.17	Sqm	623.79	Rupees Six Hundred Twenty Three and Paise Seventy Nine Only	Per cubic metre 325101.00
0						
					Total:	405411.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

SCHEDULE OF QUANTITY

Time: -

One Month

0

Amount Quoted by the Contractor in Percentage excluding GST

RS

~~Executive Engineer~~
~~Shimla Rural Division~~
~~HPPWD, Dharmi~~

Name of Work:- Restoration of rain damages on Galog Nehra Okhroo Road Km. 0/000 to 11/135. (Sh: Providing and laying WBM G-III and Bitumen Penetration Macadam for correction of road surface in Km. 4/000 to 5/000)

Estimated Cost: - Rs. 422772/- only
Earnest Money: - Rs. 8000/- only

One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount	
1	2	3	4	5	6	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 14.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum (Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 By mechanical means and as per intire satisfaction direction by the Engineer-In-Charge including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	32.77	Cum	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre	68039.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bituminous surface cleaned with Hydraulic broom as per Technical Specification Clause 503, including entire carriage of materials upto all leads and lifts and as per the direction of Engineer in Charge.	546.17	Sqm	Rupees Twenty Nine Only	Per Square Meter	15839.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper/tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.50 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm, including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	540.50	Sqm	Rupees Six Hundred Twenty Seven Only	Per Square Meter	338894.00
Total:					422772.00	

Note : (i) All the material will be procured by the contractor himself.

Amount Quoted by the Contractor in Percentage excluding GST

RS.

Executive Engineer
Shimla Rural Division
HPPWD, Dharmi

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Galog Nehra Okhroo Road Km. 0/000 to 11/135 (Sh: Providing and laying WBM G-III and Bitumen Penetration Macadam for correction of road surface in Km. 0/00 to 1/000)

Estimated Cost: - Rs 423376/- only
Earnest Money : - Rs. 8000/-only
Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate figures	Unit	Amount
1	2	3	4	5	6
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 KN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum (Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405. By mechanical means and as per intire satispction direction by the Engineer In-Charge including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	35.13	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre	72939.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bitumenous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per the direction of Engineer in Charge.	585.50	Rupees Twenty Nine Only	Per Square Metter	5960.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy. For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	531.83	Rupees Six Hundred Twenty Seven Only	Per Square Metter	103457.00
0	Total				423376.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

Schedule of Quantity

N.O.W:- AR/MO various roads under Sunni-I section under Sunni Sub-Division .(SH:-Repair to pot holes,P/L 20 mm Premix carpet & seal coat on (i) Link road to village chebri in km 0/000 to 1/000(ii) Link road Chebri to Sarkadi in km 0/000 to 0/500)

S. No	Description of Work	Nos of Qty	4	In Figure	Rate		Unit	Amount
					6	In word		
1	2	3	4	5	6		7	8
1	Repair to pot holes and removal of loose material, trimming of sides, cleaning of surface by providing tack coat, 20 mm thick pre-mix carpet and seal coat type B specification Clause 1904.2	589.75	Per Sqm	716.34	Rupees Seven Hundred Sixteen and Paise Thirty Four Only		Per Sqm	422462.00
	Amount Quoted by the Contractor in Percentage				Total			422462.00
	Note :- All the material will procured by the contractor himself							

Executive Engineer
Shimla Rural Division
HP.PWD, Jhansi

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Thachi Seri Shaili Road Km. 0/000 to 3/285 (Sh: Providing and laying G-III & bitumen penetration macadam for correction of road surface in Km. 0/000 to 3/285) Job No. 1

Estimated Cost :- Rs 405411 /- only
Earnest Money :- Rs. 8000 /-only
Time :- One Month

S. No.	Sub head and items of work	Qty.	Rate			Unit	Amount
			4	5	figures		
1	2	3	4	5	6	7	
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum/(Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405. By mechanical means and as per intire satisfaction direction by the Engineer-In-Charge, including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	31.27	Cum	2076.27	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre	64925.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-1) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm On the prepared bitumenous surface cleaned with Hydanulic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per thedirection of Engineer in Charge	521.17	Sqm	29.52	Rupees Twenty Nine and Paise Fifty Two Only	Per cubic metre	15385.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm, including carriage of material upto all leads and lifts as per the direction of Engineer-In-Charge.	521.17	Sqm	623.79	Rupees Six Hundred Twenty Three and Paise Seventy Nine Only	Per cubic metre	325101.00
0						Total:	405411.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharni

SCHEDULE OF QUANTITY
Name of Work:- Repair & Maintenance of Judicial Academy at Ghandal District Shimla H.P. (Sh: Providing & Fixing Granite Stone, painting, Steel Work and red stone etc.)

Estimated Cost - Rs 406339 /- only
 Earnest Money :- Rs. 8000 /-only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures				
1	2	3	4	5	6	7	
1	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	450.00	Sqm.	80.51	Rupees Eighty and Paise Fifty One Only	Per Square Meter	36230.00
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete including carriage of material in all leads and lifts as per direction of the Engineer in Charge.	587.28	Kg	93.22	Rupees Ninety Three and Paise Twenty Two Only	Per Kilogram	54746.00
3	Providing & fixing Red sand stone sun shade (chisel dressed) supported on red sand stone brackets, fixed in walls with cement mortar 1:4 (1 Cement : 4 Coarse sand), including finishing complete as per the direction of Engineer in Charge.	22.50	Sqm.	1271.19	Rupees One Thousand Two Hundred Seventy One and Paise Nineteen Only	Per Square Meter	28602.00
4	Providing and laying gang saw cut 18 mm thick, mirror polished pre moulded and pre polished machine cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring cut granite stone of required size and shape of approved shade, colour and texture in footpath, flooring in road side plazas and similar locations, laid over 20mm thick base of cement mortar 1:4 (1cement : 4 coarse sand) including grouting the joints with white cement mixed with matching pigment, epoxy touch ups etc. complete as per direction of Engineer-in-Charge. With granite stone of area less than 0.50 sqm.	67.50	Sqm.	4248.31	Rupees Four Thousand Two Hundred Forty Eight and Paise Thirty One Only	Per Square Meter	286761.00
0						Total:	406339.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.


Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dharni

Schedule Of Quantity

Name Of Work :- Preparation of Detail Project report for various roads under HPPWD		Estimated Cost:- 3,85,593.00
Dhami Division , Distt Shimla (HP) (i) C/o link road to Chahli Khurd km. 0/000 to 1/500.		Earnest Money:- 7,800.00
(ii) C/o link road to village Darkot Km. 0/000 to 5/00.)		Time:- One Months.

S.No	Description of Work	No.of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	Preparation of detailed project report which include the following provision as given Topography survey by digital total station with two second accuracy, showing all features on survey pain like tress, culverts, bridge, electric poles, telephone poles, hand pumps, schools, Habitants Villages etc. Draw cross-sections at 15 m (fifteen meter) intervals. L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provision and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Test Reports must include atleast following field test per Km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii) Optimum Moisture Content (iv) Maximum Dry Dentity (v) Grain Size Analysis. Detailed Project Report and working drawings (Draft and Final). Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR Copy (Soft & hard copy) and as per the direction and entire satisfaction of Engineer-in-Charge complete. The rate are excluding of GST as applicable.	6.50	Km	59322.03	Rupees Fifty Nine Thousand Three Hundred Twenty Two and Paise Three Only	Per Kilometer	385593.00
	Total Rs.						385593.00
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						


 Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhami

Schedule Of Quantity

**Name Of Work :- Preparation of Detail Project report for various roads under HPPWD
Dhami Division , Distt Shimla (HP) (i) C/o link road Jawaharnagar Sanahu shyalti km.
0/000 to 2/800)**

**Estimated Cost:- 1,66,102.00
Earnest Money:- 3,500.00
Time:- One Months.**

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5 In figures	6 In words		
1	Preparation of detailed project report which include the following provision as given Topography survey by digital total station with two second accuracy, showing all features on survey pain like tress, culvests, bridge, electric poles, telephone poles, hand pumps, schools, Habitants Villages etc. Draw cross-sections at 15 m (fifteen meter) intervals, L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provision and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Test Reports must include atleast following field test per Km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii) Optimum Moisture Content (iv) Maximum Dry Dentity (v) Grain Size Analysis. Detailed Project Report and working drawings (Draft and Final), Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR Copy (Soft & hard copy) and as per the direction and entire satisfaction of Engineer-in-Charge complete, The rate are excuding of GST as applicable.	2.800	Km	59322.03	Rupees Fifty Nine Thousand Three Hundred Twenty Two and Paise Three Only	Per Kilometer	166102.00
Total Rs.							166102.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

**Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami**

Schedule Of Quantity

Name Of Work :- Preparation of Detail Project report for various roads under HPPWD
Dhami Division , Distt Shimla (HP) (i) C/o link road Garkhan to Berti km. 0/000 to 4/700)
Estimated Cost:- 2,78,814.00
Earnest Money:- 5,600.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Preparation of detailed project report which include the following provision as given Topography survey by digital total station with two second accuracy, showing all features on survey pain like tress, cuivests, bridge, electric poles, telephone poles, hand pumps, schools, Habitants Villages etc. Draw cross-sections at 15 m (fifteen meter) intervals, L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provision and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Test Reports must include atleast following field test per Km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii) Optimum Moisture Content (iv) Maximum Dry Dentity (v) Grain Size Analysis. Detailed Project Report and working drawings (Draft and Final), Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR Copy (Soft & hard copy) and as per the direction and entire satisfaction of Engineer-in-Charge complete. The rate are excuding of GST as applicable.	4.700	Km	59322.03	Rupees Fifty Nine Thousand Three Hundred Twenty Two and Paise Three Only	Per Kilometer	278814.00
Total Rs.							278814.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami.

Schedule of Quantity

Name of Work :- C/O Link road from Nehwat Nayaser Ghaini Devidhar road km 0/000 to 13/691 (SH: C/O 24 meter span RCC T-Beam Bridge){CH: 4/813 to 4/837}{Sub-Work: Dewatering/Pumping out water from excavated pit) Job-1

Estimated Cost: - Rs 411185 /- only
Earnest Money :- 10000/- Only
Time:- One Month

Sr. No.	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Dewatering / Pumping out water from excavated pit and laying of cement concrete 1:2:4 (1 cement 2 sand and 4 graded stone aggregate in abutment Ghani & Nayasair up to lowest water level and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	936	Per Hours	439.30	Four Hundred Ninety Three Rupees Thirty Paise only	Per Hours	411185.00
	Total (Rates excluding GST)						411185.00
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self and bills will be submitted						



 Executive Engineer,
 Shimla Rural Division,
 HP, PWD/Dyami.

Schedule of Quantity

Name of Work :- C/O Link road from Nehwat Nayaser Ghaini Devidhar road km 0/000 to 13/691 (SH: C/O 24 meter span RCC T-Beam Bridge{CH: 4/813 to 4/837})(Sub-Work: Dewatering/Pumping out water from excavated pit) Job-2

Estimated Cost: - Rs 411185 /- only
Earnest Money :- 100000/- Only
Time:- One Month

Sr. No.	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	Dewatering / Pumping out water from excavated pit and laying of cement concrete 1:2:4 (1 cement 2 sand and 4 graded stone aggregate in abutment Ghani & Nayasair up to lowest water level and including all leads and lifts and work will be executed as per the direction of Engineer in charge.	936	Per Hours	439.30	Four Hundred Ninety Three Rupees Thirty Paise only	Per Hours	411185.00
	Total (Rates excluding GST)						411185.00
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self and bills will be submitted						


Executive Engineer,
 Shimla Rural Division,
 HP, P.W.D., Dharauli

Schedule Of Quantity

Name Of Work :- Preparation of Detail Project report for various roads under HPPWD
Dhami Division , Distt Shimla (HP) (i) C/o link road Karyali to Shara Nallah 0/000 to 8/300)

Estimated Cost:- 4,92,373.00

Earnest Money:- 10,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Preparation of detailed project report which include the following provision as given Topography survey by digital total station with two second accuracy, showing all features on survey pain like tress, culvests, bridge, electric poles, telephone poles, hand pumps, schools, Habitants Villages etc. Draw cross-sections at 15 m (fifteen meter) intervals, L-Section & calculate the quantity of earth work in standard format of autocad showing all layer of pavement components as applicable Preparation of survey plan showing all provision and preparation of detailed project report as per PMGSY Guidelines. Preliminary Project Reports including all test reports, coloured Photographs at every 100.00 mtr of road and at prominent points. Test Reports must include atleast following field test per Km (i) C.B.R of soil soaked & un-soaked (ii) Plastic Limit/Liquid Limit (iii) Optimum Moisture Content (iv) Maximum Dry Denty (v) Grain Size Analysis. Detailed Project Report and working drawings (Draft and Final), Technical Sanction as per Approved DPR. Bid Documents with BOQ and three set of approved DPR Copy (Soft & hard copy) and as per the direction and entire satisfaction of Engineer-in-Charge complete, The rate are excuding of GST as applicable.	8.300	Km	59322.03	Rupees Fifty Nine Thousand Three Hundred Twenty Two and Paise Three Only	Per Kilometer	492373.00
Total Rs.							492373.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhami.

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Dhami Bainsh Road Km. 0/000 to 6/000 (Sh: Providing and laying G-III & bitumen penetration macadam for correction of road surface in km. 4/000 to 6/00)

Estimated Cost: - Rs 419881/- only
Earnest Money : - Rs. 8000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Providing, laying, spreading and compacting stone aggregates of specific sizes 55 mm to 22.4mm(fifty three millimetre to twenty point four millimetre) grading- III 75 mm (seventy five millimetre) Consolidating thick to water bound macadam specification including spreading in uniform thickness, using template, hand packing, rolling with three wheel 80-100 kN (Eighty to one hundred) static roller in stages to proper grade and camber, applying and brooming, stone screening type -B of size 11.2 mm (eleven point two millimetre) nominal size at the rate 0.18 cum/(Zero point eighteen cubic metre) per 10 square metre (ten) and to fill up the interstices of coarse aggregate, watering and compacting to the required density as per MORD Technical Specification Clause 405 By mechanical means and as per intire satisfaction direction by the Engineer-In-Charge. including carriage of materials all leads and lifts as per the direction of Engineer in Charge.	32.39 Cum	2076.27	Rupees Two Thousand Seventy Six and Paise Twenty Seven Only	Per cubic metre	67250.00
2	Providing and applying Tack Coat with Bitumen emulsion (RS-I) using emulsion distributor at the rate of 0.25 to 0.30 kg. per sqm. On the prepared bitumenous surface cleaned with Hydraulic broom as per Technical Specification Clause 503. including entire carriage of materials upto all leads and lifts and as per thedirection of Engineer in Charge.	539.76 Sqm	29.52	Rupees Twenty Nine and Paise Fifty Two Only	Per cubic metre	15934.00
3	Providing and laying Bitumen Penetration Macadam with hard stone aggregate of quality, size and grading as specified, with bitumen of suitable penetration grade, including required key aggregate as specified, spreading coarse aggregate with the help of self propelled/ tipper tail mounted aggregate spreader and applying bitumen by a pressure distributor and then spreading key aggregate with the help of aggregate spreader complete, including consolidation with road roller of minimum 8 to 10 tonne capacity to achieve specified values of compaction and surface accuracy : For 50 mm compacted thickness using coarse aggregate of size 50-20 mm graded @ 0.60 cum per 10 sqm key aggregate of size 12.5 mm graded @ 0.15 cum per 10 sqm. With paving asphalt grade VG - 10 @ 50 kg/ 10 sqm. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	539.76 Sqm	623.79	Rupees Six Hundred Twenty Three and Paise Seventy Nine Only	Per cubic metre	336697.00
0					Total:	419881.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhami