

HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT
No.PW-SRDD-CB-CTR-NIT-2026-27-15282-15311

Dated:- 07/10/2026

To

The Executive Engineer (IT Cell),
H.P.P.W.D. Nigam Vihar Shimla-2.

Subject:- **Notice Inviting Tender for uploading the same on departmental website.**

Enclosed please find herewith Notice Inviting Tender (NIT) of various works in respect of this office for uploading the same on departmental website as per notification Secy. (PW) to the Govt. of Himachal Pradesh letter No. PBW (B)A(3)1/2024 dated Shimla-2 dated 03-01-2024, letter No.300858 dated 09-10-2025 and even letter dated 21.09.2026 and as the works mentioned in the tender Notice are urgent in nature and in public interest.

Encl:-Copy of NIT

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dharni
Ph. 0177-2790534

Copy forwarded for the following for information and necessary action to:-

1. The Engineer-in-Chief, HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-2
2. The Chief Engineer, (SZ) HPPWD., Nirman Bhawan, Nigam Vihar, Shimla-
3. The Superintending Engineer, 4th Circle, HPPWD., Shimla-3.
4. All the Superintending Engineer, in HPPWD. (SZ)
5. The Deputy Commissioner Shimla Distt. Shimla.
6. The Sub Divisional Magistrate Shimla.
7. All the Executive Engineers in HPPWD, (SZ).
8. All the Assistant Engineer, working under this division.
9. All the heads of the branches in this office.
10. Notice Board.

Executive Engineer,
Shimla Rural Division
H.P.P.W.D. Dharni
Ph. 0177-2790534

**HIMACHAL PRADESH
PUBLIC WORKS DEPARTMENT**

NOTICE INVITING TENDER

Scaled percentage tenders on PWD Form 6 & 7/8 are hereby invited by the Executive Engineer Shimla Rural Division H.P.P.W.D. -Dhami on behalf of Governor of Himachal Pradesh for the followings works from the eligible contractors enlisted in H.P.PWD. (B&R) whose registration stood renewed as per revised rules and also registered under the Central Goods and Services Tax Act, 2017 so as to reach in this office on before **16.10.2026 up to 11:00 AM** and the same shall be opened on the same day at **11:30 A.M.** in the presence of intending contractors or their authorized representative who may like to be present. The Tenders documents can be had from this office against cash payment (Non-refundable) on **15.10.2026 up to 5.00 PM** and the application for issue of tender form shall be received on **14.10.2026 up to 4:00 PM.**

The amount of earnest money in the shape of NSCs/FDR deposit at call of any of the Post office/Bank duly pledged in favour of Executive Engineer Shimla Rural Division HPPWD Dhami must be accompanied with the application for tender documents. Please not any exemption order of earnest money will be entertained. Conditional tenders and the tenders received without earnest money as mentioned above will similarly be rejected. The offer of the tenders shall be kept open for 75 days. The Executive Engineer reserve right to reject any tender of all tenders without assigning any reasons. If it happens to be a holiday on the day of opening of tenders the same will be opened on next working day at the same time and venue.

Sr. No.	Name of Work	Estimated Cost (In Rs.)	EMD	Time	Cost of Form
1	R/R Damages on Devidhar Bhajyar road Km. 0/00 to 2/165 (SH:- C/O R/Wall at Rd. 1/130 to 1/150).	430357.00	9000.00	One Month	Rs.350/-
2	(i)C/O Link road from Sunni Luhri road to Village upper Jaishi / Dhar via Duganal Km. 0/000 to 2/750 (ii) C/O Link road from Majhiwar to Jabal Km. 0/000 to 1/800 (iii) Widening / Improvement of Slapper Tatapani Sunni Luhri road Km. 72/000 to 86/00 (SH:- Prepration of DPR, CBR Tests, Techincal Sanction, Working Estimate of Bridge).	415250.00	10000.00	One Month	Rs.350/-
3	A/R & Khel Ka Chaura Baggi Road portion 10/00 to 12/225 (SH:- Cutting of Shart Curves Between km. 10/380 to 10/460).	495546.00	10000.00	One Month	Rs.350/-
4	A/R & M/O Chailly Beaunt road Km. 0/00 to 10/000 (SH:- Rain Shelter at Rd. 0/300).	342269.00	8000.00	One Month	Rs.350/-
5	A/R & M/O Chailly Beaunt road Km. 0/00 to 10/000 (SH:- Rain Shelter at Rd. 0/900).	342269.00	8000.00	One Month	Rs.350/-
6	A/R & M/O Ghanahatti Devnagar Bhajol road Km. 0/00 to 15/300 (SH:- Improvement Work in Km. 1/662 to 1/818) Balance Work.	498038.00	8000.00	One Month	Rs.350/-
7	A/R & M/O Hiranagar Dhamoon road Km. 0/000 to 8/000 (SH:- Maintenance of Shoulder, Trimming of Grass and Cliaring of Drain etc. in Km. 4/000 to 8/000).	302376.00	8000.00	One Month	Rs.350/-
8	A/R & M/O Malog Jalgi road Km. 0/00 to 0/470 (SH:- C/O RCC Box Culvert (1.5x 1.5mtr) at Rd.0/470).	422346.00	7000.00	One Month	Rs.350/-

9	A/R & M/O NH-22 Judicial Complex via Chakkar road Km. 0/00 to 1/790 (SH: - C/O V-Shaped drain & CC Shoulder b/w Km. 0/300 to 0/700).	483612.00	6000.00	One Month	Rs.350/-
10	A/r & M/O Ghanhatti Kalihatti Arki road in km. 0/00 to 8/060 (SH:- Trimming of Grass, Drssing of shoulder, clearing of drain etc.)	270699.00	5000.00	One Month	Rs.350/-
11	A/R & M/O Old age Home at Basantpur, Tehsil Sunni Distt. Shimla H.P. (SH: - Balance Works thereof).	411304.00	10000.00	One Month	Rs.350/-
12	A/R & M/O Palkari Makdi road km. 0/00 to 1/60.0(SH:- C/o Edge wall at various Rds 0/120 to 0/135, 0/170 to 0/190, 0/200 to 0/215, 0/310 to 0/325, 0/400 to 0/415, 0/770 to 0/780 and 0/5810 to 0/825)	488168.00	8000.00	One Month	Rs.350/-
13	A/R & M/O Shakoh to Hanuman road km. 0/00 to 1/250 (SH:- C/o slab a/w bed block & dirt wall of slab culvert at Rd. 1/050)	498425.00	10000.00	One Month	Rs.350/-
14	A/R & M/O Shimla Mandi road km. 39/200 to 52/200 (SH:- Maintenance /Cleaning of side drain, Hume pipe culverts, Trimming of grass and maintenance of earthen shoulders/berms from km. 22/00 to 33/200) Job NO.2.	499950.00	10000.00	One Month	Rs.350/-
15	A/R & M/O Shimla Mandi Road km. 39/200 to 52/300(SH:- C/o Rain Shelter at Rd. 42/930).	423673.00	8000.00	One Month	Rs.350/-
16	A/R & M/O Shoghi Mehli road Km. 0/00 to 12/375 (SH- C/O V-Shape drain in Km. 3/00 to 3/400).	415507.00	10000.00	One Month	Rs.350/-
17	A/R & M/O Shoghi Mehli road Km. 0/00 to 12/375 (SH:- C/O R/Wall at Rd. 9/750 to 9/763).	487536.00	10000.00	One Month	Rs.350/-
18	A/R & M/O Thachi Rehana road Km. 0/000 to 2/645 (SH:- C/O wing wall along with D/S & U/S Toe wall, Catchpit of Exising pipe Culvert at Km. 1/510).	328710.00	10000.00	One Month	Rs.350/-
19	A/R & M/O Tutikand Shilgaon via Kiari road km. 0/00 to 3/370 (SH- C/o B/Wall km. 2/650 to 2/695).	453387/-	10000.00	One Month	Rs.350/-
20	C/O Link road from Chebri to Piplughat Km. 0/000 to 3/870 (SH:- C/O R/Wall (wire crate & PCC) at Rd. 1/460 to 1/476.80).	408296.00	10000.00	One Month	Rs.350/-
21	C/O Link Road from Kanda to Lunu Km. 0/00 to 2/300 (SH:- F/C 5/7 mtr wide road in Km. 1/285 to 1/390).	423573.00	10000.00	One Month	Rs.350/-
22	C/O Link Road from Kanda to Lunu Km. 0/00 to 2/300 (SH:- F/C 5/7 mtr wide road in Km. 1/180 to 1/285).	423139.00	10000.00	One Month	Rs.350/-
23	C/o Link road from Kufridhar to Shanol Road km. 0/00 to 2/120(SH:- C/o CD work in km. 1/360 with wing wall)	497196.00	10000.00	One Month	Rs.350/-
24	C/O Link road from Pahal to Ghat in Km. 0/00 to 2/00 (SH:- Formation Cutting in Km. 1/280 to 1/455).	498583.00	10000.00	One Month	Rs.350/-
25	C/O Link road Majhiwar to Jabal Km. 0/00 to 1/800 (SH:- Formation Cutting/widening in Km. 0/000 to 0/270).	420653.00	10000.00	One Month	Rs.350/-
26	C/O Link road Majhiwar to Jabal Km. 0/00 to 1/800 (SH:- Formation Cutting/widening in Km. 0/270 to 0/515).	417957.00	10000.00	One Month	Rs.350/-

27	C/O Link road to Harizen Basti Syalmu Badog Km. 0/000 to 1/600 (SH:- C/O PCC R/Wall at Rd. 0/720 to 0/740).	250974.00	10000.00	One Month	Rs.350/-
28	C/O Link road to Mandrech Km. 0/000 to 2/620 (SH:- Formation Cutting from Rd. 0/585 to 0/630, 0/675 to 0/720,0/915 to 0/960).	409110.00	10000.00	One Month	Rs.350/-
29	C/o link road to Village Majelu road km. 0/00 to 1/650(SH:- F/C 5/7 mtr wide road in km. .0/405 to 0/495)	421911.00	10000.00	One Month	Rs.350/-
30	C/o link road to Village Majelu road km. 0/00 to 1/650(SH:- F/C 5/7 mtr wide road in km. .0/495 to 0/630)	420789.00	4000.00	One Month	Rs.350/-
31	C/O Link road Totu to Kayar Km. 0/00 to 1/555 (SH:- C/O Hume Pipe Culvert 900 mm dia at Rd. 0/405 along with wing walls).	376637.00	10000.00	One Month	Rs.350/-
32	C/O Link road Totu to Kayar Km. 0/00 to 1/555 (SH:- C/O Hume Pipe Culvert 900 mm dia at Rd. 0/555 along with wing walls).	376637.00	10000.00	One Month	Rs.350/-
33	C/o Science Learning and creativity Centre at Village Bhog Anandpur Shoghi (SH:- C/o Boundary Wall a/w Planetorium (Balance Work) Job No.1	494244.00	10000.00	One Month	Rs.350/-
34	C/O Two Nos Type-II Ouarter at Sunni Tehsil Sunni Distt. Shimla H.P (SH:- Providing and Fixing Prepainted Sheet Roofing).	423582.00	10000.00	One Month	Rs.350/-
35	C/O Two Nos Type-II Ouarter at Sunni Tehsil Sunni Distt. Shimla H.P (SH:- Providing and Fixing Structural Steel, Painting and finishing work).	422592.00	10000.00	One Month	Rs.350/-
36	R/R damages on Airport Road km. 0/00 to 1/150 (SH:- C/o B/Wall at Rd. 0/680 to 0/690).	204972.00	10000.00	One Month	Rs.350/-
37	R/R Damages on Badmain Basantpur road km. 0/000 to 7/000 (SH: - C/O R/Wall at Rd. 0/720 to 0/735.50).	409001.00	8000.00	One Month	Rs.350/-
38	R/R Damages on Badmain Basantpur road km. 0/000 to 7/000 (SH:- C/O R/Wall at Rd. 0/870 to 0/885.50).	409001.00	8000.00	One Month	Rs.350/-
39	R/R Damages on Badmain to Basantpur road Km. 0/00 to 7/000 (SH: - C/O R/Wall at Rd. 5/285 to 5/293).	472550.00	6000.00	One Month	Rs.350/-
40	R/R Damages on Bangora Kalihatti Bastigunana road (SH:- C/O R/Wall Between Rd. 11/420 to 11/430).	418573.00	6000.00	One Month	Rs.350/-
41	R/R Damages on Bangora Kalihatti Bastigunana road (SH:- C/O R/Wall Between Rd. 11/430 to 11/440).	418634.00	5000.00	One Month	Rs.350/-
42	R/R damages on Banogra Kalihatti Bastigunana Road km. 0/00 to 11/675 (SH:- C/o R/Wall at rd. 11/240 to 11/254).	422742.00	7000.00	One Month	Rs.350/-
43	R/R damages on Banuti Pahal road via Nehwat in Km. 0/00 to 17/105 (SH: C/O R/Wall at Rd. 1/753 to 1/770).	483149.00	8000.00	One Month	Rs.350/-
44	R/R damages on Chauri ki Ghatti to Yaan via Bhad road km. 0/00 to 9/600 (SH:- C/o R/Wall at km. 2/900 to 2/905 & Removal of slips.	254976.00	6000/-	One Month	Rs.350/-
45	R/R damages on Chauri ki Ghatti to Yaan via Bhad road km. 0/00 to 9/600 (SH:- C/o R/Wall at km. 9/345 to 9/360).	416484.00	6500.00	One Month	Rs.350/-

46	R/R Damages on Chauri ki Ghatti to Yan via Bhad road Km. 0/00 to 9/600 (SH:- C/O R/Wall at Rd. 2/830 to 2/840 and C/O B/Wall at Rd. 2/980 to 2/995).	408600.00	8000.00	One Month	Rs.350/-
47	R/R Damages on Badheri Section under Jutogh Sub Division (SH:- Hiring of JCB for Removal of Slips)	399675.00	8000.00	One Month	Rs.350/-
48	R/R Damages on Dhami Bainsh road Km. 0/000 to 6/000 (SH:- C/O PCC R/Wall at Rd. 5/015 to 5/045).	499219.00	9900.00	One Month	Rs.350/-
49	R/R Damages on Gallu to Palged road Km. 0/000 to 9/600 (SH:- C/O PCC R/Wall at Rd. 2/355 to 2/362, 2/395 to 2/405 & 2/840 to 2/850.90).	499848.00	10000.00	One Month	Rs.350/-
50	R/R Damages on Gallu to Palged road Km. 0/000 to 9/600 (SH:- C/O R/Wall at Rd. 1/505 to 1/512.90, 1/535 to 1/545, 1/890/ to 1/898 & 2/235 to 2/245).	499848.00	9800.00	One Month	Rs.350/-
51	R/R Damages on Gallu to Palged road Km. 0/000 to 9/600 (SH:- C/O R/Wall at Rd. 3/470 to 3/482, 3/665 to 3/675 & 3/705 to 3/715).	497343.00	9800.00	One Month	Rs.350/-
52	R/R Damages on Gallu to Palged road Km. 0/000 to 9/600 (SH:- C/O Wire Crate R/Wall at Rd. 2/605 to 2/634)	493433.00	9700.00	One Month	Rs.350/-
53	R/R damages on Sangti Neri road km., 0/00 top 6/465 (SH:- C/o PCC R/Wall at Rd. 1/020 to 1/030).	330941.00	7000.00	One Month	Rs.350/-
54	R/R damages on Hiranagar Jutogh road km. 0/00 to 1/200 (SH:- C/o R/Wall at Rd. 0/845 to 0/855)	255975.00	8300.00	One Month	Rs.350/-
55	R/R Damages on Hiranagar Sharog road Km. 0/000 to 5/000 (SH:- C/O R/Wall Between Rd. 1/580 to 1/591).	283294.00	8100.00	One Month	Rs.350/-
56	R/R damages on Hiranagar Sharog road km.0/00 to 5/500 (SH:-C/O B/Wall at Rd. 0/211 to 0/236).	316981.00	6000.00	One Month	Rs.350/-
57	R/R Damages on Jalog Himri Naltu Reog road Km. 0/00 to 2/150 (SH:- P/L Kharanja Stone Soling at Rd. 00/250 to 00/600 & 1/330 to 1/505).	499807.00	8200.00	One Month	Rs.350/-
58	R/R Damages on Jalog to Gadheri road Km. 0/00 to 10/500 (SH:- Removal of Land Slide / Slips at Various Rds Between Km. 0/000 to 4/00).	498501.00	8500.00	One Month	Rs.350/-
59	R/R Damages on Jalog to Gadheri road Km. 0/00 to 10/500 (SH:- Removal of Land Slide / Slips at Various Rds Between Km. 04/00 to 10/500).	485247.00	8200.00	One Month	Rs.350/-
60	R/R Damages on Kadharghat to Palag Serikedi road Km. 0/00 to 7/030 (SH: - C/O B/Wall at Km. 4/353 to 4/380) (PCC).	490087.00	8200.00	One Month	Rs.350/-
61	R/R damages on Khel ka Chaura Baggi road km. 0/00 to 10/0 (SH:- C/o R/Wall at Rd. 8/340 to 8/362) Under PDNA	415847.00	8300.00	One Month	Rs.350/-
62	R/R damages on link road Bag to Kayalu km. 0/00 to 10/500 (SH:- C/o R/Wall in between km. 7/445 to 7/487.5) Under PDNA 2025	499931.00	9100.00	One Month	Rs.350/-
63	R/R damages on link road from Hiranagar Petrol Pum to Jalog in km. 0/00 to 0/760 (SH:- C/o R/Wall at Rd. 0/363 to 0/391)	484308.00	10000.00	One Month	Rs.350/-
64	R/R Damages on Link road from Khatnol to Dandibag km. 0/00 to 6/150 (SH: - C/O B/Wall at Rd. 5/327 to 5/354).	497345.00	8305.00	One Month	Rs.350/-

65	R/R damages on link road to Kayalu road km. 0/00 to 10/500 (under PDNA 2025) (SH:- C/o R/Wall in between km. 7/795 to 7/804.3).	499935.00	10000.00	One Month	Rs.350/-
66	R/R Damages on Nehra Shaltu Dargot road Km. 0/00 to 5/450 (SH:- C/O R/Wall at Rd. 0/345 to 0/356).	401281.00	10000.00	One Month	Rs.350/-
67	R/R damages on Nehra Shaltu Dargot road km. 0/00 to 5/450 (SH:- C/o R/Wall between Rd. 2/285 to 2/307)	417971.00	10000.00	One Month	Rs.350/-
68	R/R Damages on NH-22 to Judicial Complex via Chakker road Km. 0/00 to 1/790 (SH:- C/O U-Shaped Drain b/w 1/630 to 1/730 & P/F RCC Drain Covers Km. 1/630 to 1/730).	382830.00	10000.00	One Month	Rs.350/-
69	R/R damages on Okhroo Nehra via Keru road km. 0/00 to 2/00 (SH:- C/o B/Wall at Rd. 1/400 to 1/420)	215467.00	10000.00	One Month	Rs.350/-
70	R/R damages on Pakki Bawari Shakrah Sedan road Km. 0/00 to 5/700 (SH: C/O R/Wall at Rd. 3/648 to 3/655.50).	275122.00	10000.00	One Month	Rs.350/-
71	R/R damages on Shakoli Koti Hanuman Mandir road km. 0/00 to 1/450 (SH:- C/o R/Wall at Rd. 1/336.10 to 1/343.10).	421436.00	10000.00	One Month	Rs.350/-
72	R/R damages on Shal Chanog road Km. 0/00 to 7/330 (SH: C/O R-Wall at Rd. 3/820 to 3/825).	491326.00	10000.00	One Month	Rs.350/-
73	R/R damages on Shaltu Nehra Dargot Road km. 0/00 to 5/450 (SH:- C/o PCC R/Wall at Rd. 3/895 to 3/905.50).	498531.00	10000.00	One Month	Rs.350/-
74	R/R Damages on Shimla Mandi road Km. 22/000 to 33/200 (SH:- Removal of Slips on various Rds of Road).	418447.00	10000.00	One Month	Rs.350/-
75	R/R damages on Shimla Mandi road road km. 39/200 to 52/300 (SH:- C/o R/Wall at Rd. 46/400 to 46/405.80).	495442.00	10000.00	One Month	Rs.350/-
76	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: C/O R-Wall at Rd. 4/080 to 4/097).	496994.00	1000.00	One Month	Rs.350/-
77	R/R damages on Shoghi Mehli road Km. 0/00 to 12/375 (SH: C/O R-Wall at Rd. 11/995 to 12/009).	490608.00	10000.00	One Month	Rs.350/-
78	R/R Damages on Totu Tara Devi road Km. 0/00 to 4/105 (SH:- C/O R/Wall b/w Km. 2/940 to 2/953).	404690.00	10000.00	One Month	Rs.350/-
79	R/R Damages on Totu Tara Devi road Portion Km. 0/00 to 4/105 (SH:- C/O R/Wall in Between Km. 2/900 to 2/912)	470719.00	10000.00	One Month	Rs.350/-
80	R/R Damages on Tutikandi Shilgaon via Kiari road, Portion Km. 0/000 to 3/870 (SH:- C/O R/Wall at Rd. 3/595 to 3/607.50).	412538.00	7000.00	One Month	Rs.350/-
81	R/R Damages on Various roads under Thaila Section under Sunni Sub-Division (SH:- Removal of Slips/Debris at Various Rds)	498087.00	7000.00	One Month	Rs.350/-
82	R/R damages on Shimla Nalagarh road km. 6/910 to 22/00 (SH:- C/o B/Wall at Rd. 8/525 to 8/545).	420626.00	8000.00	One Month	Rs.350/-

Followings documents should be attached with the application for tenders:-

- (i) The Contractors are requested to be produced a copy of their PAN No. GST No. copy of enlistment renewed letter and EPF certificate alongwith FDR against earnest money.
- (ii) Special care would be taken to write the rates both in figures and in word failing which tender is likely to be rejected.


Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni

Certificate

Certified that the tenders called vide this notice inviting tender for 82 (Eighty Two) jobs are due to exigencies/emergency of works in the larger public interest.


Executive Engineer
Shimla Rural Division
H.P.P.W.D. Dharni

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Devdhar Bhajyar Road Km. 0/00 to 2/165 (Sh: Construction of R-wall at Rd. 1/130 to 1/150)

Estimated Cost - Rs 430357 /- only
Earnest Money : - Rs 9000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	11.20	Cum	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	2514.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	41.40	Cum	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	14759.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	86.40	Cum	Rupees Four Thousand Six Hundred Only	Per cubic metre	397440.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	9.60	Cum	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	8081.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v).20(H-) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	43.90	Rmt.	Rupees One Hundred Seventy Only	Per Running Metre	7453.00
0					Total:	430357.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharami

Draft Schedule of Quantity

Estimated cost - ₹4,15,250
Earnest Money - ₹8,305
Time - Three months

Name of work : i) C/O Link road from sunni Luhri road to village upper Jaishi / Dhar via Duganal, km 0/000 to 2/750. ii) C/O Link road from Majhiwar to Jabal km 0/000 to 1/800. iii) Widening /Improvement of Slapper Tattapani Sunni Luhri road km 72/000 to Sub head: Preparation of DPR, CBR tests, Technical sanction , working Estimate of bridge.

Sr. No.	Description of item	Quantity	Units	Rate	Amount
1	Preparation of Detailed project report which include following provision as mentioned below : A) Topography survey by Digital total station with two second accuracy , showing all features on survey plan like trees, culvert, bridge, electric pole, telephone poles, hand pumps, school, habitant villages. B) Draw cross section at 15 m (fifteen meter) interval, L-section & calculate the quantity of earth work in standart format of autocad showing all layer of pavement components as applicable. C) Preparation of survey plan showing all provision and preparation of detailed project report as per MORD guidelines.	4.55	km	35000	159250
2	CBR test including grain size analysis , atterbergs limit , proctor compaction and CBR value Preparation of Technical sanction and Working Estimate of Bridge. Printing approved 2 set and submitting the same to the divisional office The Work will we carried in accordance with latest desgin specification, latest market rate and to satisfaction of Engineer -in - charge. Printing two set complete in all respect and submitting the same to division office and there after approval from competent authority	10	samples	1600	16000
		2	per bridges	120000	240000
3					
Conditions:-(1) All the materils will be procured by the contractor himself and bills will be submitted.				TOTAL	415250

Draft Schedule of quantity duly Checked and approved for Rs 415250- only (Rupees Four lac Fifteen thousand Two hundred fifty only) for the year 2025-2026, and entered at DNIT Register Sr no.

Executive Engineer,
Shimla Rural Division,
HP.PWD Dargani.

SCHEDULE OF QUANTITY

Name of Work: - A/R & M/O Khel Ka Chaura Baggi Road Portion 10/00 to 12/225 (Sh: Cutting of Sharp Curves Between Km. 10/380 to 10/460)

Estimated Cost: - Rs 495546 /- only
Earnest Money : - Rs. 10000 /-only

Time- One Month

S.No.	Sub head and items of work	Qty.		Rate	Unit	Amount
		3	In figure	In words	6	7
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil, ordinary rock and hard rock. All work of rock cutting by blasting shall be carried out by taking all necessary precautions against soil erosion, damages to hill side, water pollution etc. and to protect stability of hill side Rock shall be excavated with chiseling and wedging out of rock (where blasting is prohibited). All earth work in cutting/excavation including rock excavation shall be carried out true to lines, grades, sides slopes, width, camber, super-elevation and level as shown on the drawing and as directed by the Engineer-in-Charge in conformity with the requirement of technical specification for Rural Road, August 2004 and clause 16.2 of General conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites safe manner including arrangement of dumping site trimming, filling of unevenness blind age and finishing of the road to specified dimensions or as directed by the Engineer-in-charge for smooth riding. The recovery for stones, whether useful or not, for 355.60 cubic metre at the rate of Rs 300/-only (Rupees three hundred only) per cubic meter shall be effected on prorata basis in all circumstances. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor, which shall have to be duly compensated by him in all cases.	1502.52	Cum	Rupees Three Hundred Twenty Nine and Paise Eighty One Only	Per cubic metre	495546.00
					Total:	495546.00

Amount Quoted by the Contractor in Percentage

Executive Engineer,
Shimla Rural Division,
HPPWD Dhani

SCHEDULE OF QUANTITY

Name of Work: Annual Repair & Maintenance on Chailly Beant Road Km. 0/00 to 10/000 (Sh. Rain Shelter at RD. 0/ 300)

Estimated Cost : Rs. 342259 /- only
Earnest Money : Rs. 7000 /- only
Time : One Month

S. No.	Sub head and items of work	Qty.	Rate	Unit	Amount
1	2	3	4	5	6
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed within all leads and lifts as per the direction of Engineer in Charge, in all kinds of soil	11.24 Cum	Rupees Two Hundred Nine and Paise Ninety Three Only	Per cubic metre	2060.00
2	Providing and laying cement concrete 1:5:10 (1 cement: 5 coarse sand) 10 graded stone aggregate 40 mm nominal size) mechanical mixed and curing complete excluding cost of centring and shuttering in Foundation and Plinth as required complete including carriage of all labour equipments and materials to various location through all modes of transportation within all leads, lifts and other incidental charges as per direction of the Engineer in Charge.	1.25 Cum	Rupees Three Thousand Eight Hundred Ninety Seven and Paise Seventy Only	Per cubic metre	4872.00
3	Providing and laying cement concrete 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size) mechanical mixed and curing complete excluding cost of centring and shuttering in Foundation and plinths required complete including carriage of all labour equipments and materials to various location through all modes of transportation within all leads, lifts and other incidental charges as per the directions of Engineer-in-Charge.	18.74 Cum	Rupees Four Thousand One Hundred Twenty Three and Paise Sixty Only	Per cubic metre	77275.00
4	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete 40 mm thick with 20 mm nominal size stone aggregate including carriage of material within all leads and lifts as per direction of Engineer-in-charge	9.25 Sqm	Rupees Three Hundred Ninety One and Paise Fifty Only	Per Square Meter	3621.00
5	Providing and fixing precast/galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total/coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade; 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling/self tapping screws of size (6.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required including carriage of material within all leads and lifts as per direction of Engineer-in-charge	13.44 Sqm	Rupees Nine Hundred Seventy Four and Paise Fifty Eight Only	Per Square Meter	13098.00
6	Providing and fixing precast/galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total/coated thickness, Zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade; 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling/self tapping screws complete :	4.00 Rmt	Rupees Five Hundred Fifty Nine and Paise Thirty Only	Per Running Metre	2237.00
5(i)	Valley Plan (upto 600 mm)	13.44 Rmt	Rupees Five Hundred Twenty One Only	Per Running Metre	7002.00

6(iii)	Gutter 300 mm wide (900 mm over all girth)	13.60	Rmt.	907.80	Rupees Nine Hundred Seven and Paise Eighty Only	Per Running Metre	12346.00
7	Providing and fixing M.S. BP Sheet 2mm thick in eaves board/facias/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge including carriage of material upto all leads and lifts as per the direction of Engineer in Charge	29.30	Sqm	1698.90	Rupees One Thousand Six Hundred Ninety Eight and Paise Ninety Only	Per Square Metre	49778.00
8	Structural steel work including hollow section riveted, bolted or welded in built up sections, tusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1692.50	Kg	98.40	Rupees Ninety Eight and Paise Forty Only	Per Kilogramme	166542.00
9	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 lit/10 sqm over an under coat of primer applied @ 0.80 lit/10 sqm of approved brand and manufacture including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	32.08	Sqm	97.80	Rupees Ninety Seven and Paise Eighty Only	Per Square Metre	3137.00
0						Total:	342269.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will be procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharmi

SCHEDULE OF QUANTITY

Name of Work : Annual Repair & Maintenance on Chailly Beant Road Km. 0/00 to 10/000 (Sh. Rain Shelter at RD. 0/900)

Estimated Cost : - Rs. 342269/- only
 Earnest Money : - Rs. 7000/- only
 Time : - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	5		
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed within all leads and lifts as per the direction of Engineer in Charge. in all kinds of soil	11.24	Cum	209.93	Rupees Two Hundred Nine and Paise Nirey Three Only	Per cubic metre 22950.00
2	Providing and laying cement concrete 1:5:10 (1 cement 5 coarse sand). 10 graded stone aggregate 40 mm nominal size) mechanical mixed and curing complete excluding cost of centing and shuttering in Foundation and plinth as required complete including carriage of all labour equipments and materials to various location through all modes of transportation within all leads, lifts and other incidental charges as per direction of the Engineer in Charge.	1.25	Cum	3897.70	Rupees Three Thousand Eight Hundred Nirey Seven and Paise Seventy Only	Per cubic metre 4872.00
3	Providing and laying cement concrete 1:4:8 (1 Cement: 4 coarse sand: 8 graded stone aggregate 40 mm nominal size) mechanical mixed and curing complete excluding cost of centing and shuttering in Foundation and plinth as required complete including carriage of all labour equipments and materials to various location through all modes of transportation within all leads, lifts and other incidental charges as per the directions of Engineer-in-Charge.	18.74	Cum	4123.60	Rupees Four Thousand One Hundred Twenty Three and Paise Sixty Only	Per cubic metre 77276.00
4	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc., complete 40 mm thick with 20 mm nominal size stone aggregate including carriage of material within all leads and lifts as per direction of Engineer-in-charge	9.25	Sqm	391.50	Rupees Three Hundred Ninety One and Paise Fifty Only	Per Square Meter 3621.00
5	Providing and fixing precasted galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277. in 240 mpa steel grade. 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12 metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling / self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal vertical ocured surfaces, excluding the cost of purfins, rafters and trusses and including cutting to size and shape wherever required including carriage of material within all leads and lifts as per direction of Engineer-in-charge	13.44	Sqm	974.58	Rupees Nine Hundred Seventy Four and Paise Fifty Eight Only	Per Square Meter 13098.00
6	Providing sand fixing precasted galvanised steel sheet roofing accessories 0.50 mm (+0.05 %) total coated thickness Zinc coating 120 grams per sqm as per IS: 277. in 240 mpa steel grade. 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns using self drilling / self tapping screws complete.	4.00	Rmtl	559.30	Rupees Five Hundred Fifty Nine and Paise Thirty Only	Per Running Metre 2237.00
6(a)	Valley Plain (upto 600 mm)	13.44	Rmtl	521.00	Rupees Five Hundred Twenty One Only	Per Running Metre 7002.00

6(iii)	Gutter 300 mm wide (900 mm over all girth)	13.60	Rmtl	907.80	Rupees Nine Hundred Seven and Paise Eighty Only	Per Running Metre.	12346.00
7	Providing and fixing M.S. BP Sheet 2mm thick in eaves board/facia/soffit/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	29.30	Sqm	1698.90	Rupees One Thousand Six Hundred Ninety Eight and Paise Ninety Only	Per Square Metre	49778.00
8	Structural steel work, including hollow section riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1692.50	Kg.	98.40	Rupees Ninety Eight and Paise Forty Only	Per Kilogramme	156542.00
9	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufacture including carriage of material upto all leads and lifts as per the direction of Engineer in Charge.	32.08	Sqm	97.80	Rupees Ninety Seven and Paise Eighty Only	Per Square Metre	3137.00
0						Total:	242258.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharmi

SCHEDULE OF QUANTITY

Name of Work: - Annual Repair & Maintenance of Ghanahatti Devnagar Bhajol Road Km. 0/000 to 15/300 (Sh: Improvement *1500 Rs* in km. 1/662 to 1/818) Balance Work.

Estimated Cost: - Rs 498038 /- only
Earnest Money : - Rs. 10000 /- only
Time- One Month

S.No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			In figure	In words			
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including, dewatering where ever required, setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP.PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load , animal load or mechanical means along with its leveling line dressing and all labour , machineries, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required), the cost of useful materials such as stones,shingles,aggregates and slates shall be sorted out and stacked along road side,which shall not be less than one tenth of 1W,one sixth of SR and one third of HR. = 259.76 Cum Qty. which shall be proportionately increase/decrease as the qty. of earth work increase/ decrease in all cases recovered from the contracto @ 300/- (Three Hundred only) per cubic metre shall be effected any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	779.28	Cum	639.10	Rupees Six Hundred Thirty Nine and Paise Ten Only	Per cubic metre	498038.00

Amount Quoted by the Contractor in Percentage Excluding GST

Executive Engineer,
Shimla Rural Division,
HPPWD Dhani

Name of Work:- Annual Repair & Maintenance of Hiranagar Dhamoon Road Km. 0/000 to 8/000 (Sh. Maintenance of Shoulder, Trimming of Grass and clearing of drain etc. in km. 4/000 to 8/000)

SCHEDULE OF QUANTITY

clearing of drain etc. in km. 4/000 to 8/000)									
Maintenance of Shoulder, Trimming of Grass and									
S. No.	Sub head and items of work	Qty.	Rate	Unit	Amount	Estimated Cost - Rs 302376 /- only	Earnest Money - Rs 6000 /-only	Time -	One Month
1	2	3	4	5	6	7			
1	Maintenance of Earthen shoulder (stripping of excess soil) , Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per the direction of Engineer-in-Charge.	3200.00	Sqm	13.98	Rupees Thirteen and Paise Ninety Eight Only	Per Square Meter	44736.00		
2	Trimming of grass and weeds from shoulder / berms and disposing off the same to suitable locations as per technical specifications clause 1914 including carriage of material within all leads and lifts as per the directions of Engineer-in-charge.	72000.00	Sqm	3.39	Rupees Three and Paise Thirty Nine Only	Per Square Meter	244080.00		
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	4000.00	Rmt.	3.39	Rupees Three and Paise Thirty Nine Only	Per Running Meter	13560.00		
0.00						Total:	302376.00		

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

Schedule Of Quantity

Name Of Work :- A/R & M/O on Malog Zalagi road km 0/00 to 0/470 (SH:- C/O RCC Box Culvert

(1.5x 1.5 mtr) at Rd. 0/470)

Estimated Cost:- 4,22,346.00

Earnest Money:- 8,500.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		In words	Unit	Amount
		3	4	Excluding GST	5			
1	Earth work in excavation for structures as per drawing and technical specification clause 305.1 including setting out, construction of shoring the bracing, removal of stumps and other deleterious material and disposal upto a lead of 50 mtr. dressing of sides and bottom and back filling in trenches with excavated suitable material including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	61.77	Cum	302.12		Rupees Three Hundred Two and Paise Twelve Only	Per Cubic metre	18662
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 P.C.C. Grade M-10 Nominal mix 1:3:6 (1 cement :3sand :6graded stone agg./including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	39.60	Cum	4491.52		Rupees Four Thousand Four Hundred Ninety One and Paise Fifty Two Only	Per Cubic metre	177864
3	Providing and laying RCC M25 reinforced cement concrete in foundation as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	3.60	Cum	6830.00		Rupees Six Thousand Eight Hundred Thirty Only	Per Cubic metre	24588
4	Providing and laying RCC M25 reinforced cement concrete in substructure as per drawing and technical specifications Clauses 800, 1205.4 and 1205.5 including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	9.41	Cum	7241.53		Rupees Seven Thousand Two Hundred Forty One and Paise Fifty Three Only	Per Cubic metre	68143
5	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawing and technical specification clauses 1002, 1005, 1010 & 1202, including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	1.43	Tonne	\$3690.00		Rupees Eighty Three Thousand Six Hundred Ninety Only	per Tonne	119677
6	Providing and Laying filter media with granular crushed aggregates as per specification to a thickness of not less than 600mm with smaller size toward the soil and bigger size toward the all and providing over the entire surface behind abutment wing wall, return wall to the full height completed to firm condition complete as per drawing and technical specification clause 1204.3.8. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	8.40	Cum	1175.00		Rupees One Thousand One Hundred Seventy Five Only	Per Cubic metre	9870

7	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	22.00	Nos	161	Rupees One Hundred Sixty One Only	Each	3542
	Total Rs.						422346
	Note :- The Rates are excluding GST						
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm.

Schedule Of Quantity

Name of Work :- A/R & M/O NH-22 Judicial Complex via Chakkar road km 0/00 to 1/790
(SH:- C/O V-shaped drain & CC Shoulder b/w km 0/300 to 0/700

Estimated Cost:- 4,83,612.00

Earnest Money:- 9,700.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1.1	37.80	Cum	233.4	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	8823
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	129.00	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	45989
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and camber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification, 100 mm spread thickness (finished work including materials and labour) including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	60.00	Cum	1425.00	Rupees One Thousand Four Hundred Twenty Five Only	Per cubic metre	85500
4	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:3:6 (1 Cement : 3 sand : 6 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	21.00	Cum	5300.00	Rupees Five Thousand Three Hundred Only	Per cubic metre	111300
5	5. P/L Cement concrete 1:2:4 (one cement : Two sand : Four graded stone aggregate 20 millimeter nominal size (for plain/ reinforced concrete work in open foundation complete as per drawing and technical specification Clauses 802, 803, 1202 & 1203.	40.00	Cum	5800.00	Rupees Five Thousand Eight Hundred Only	Per cubic metre	232000
	Total Rs.						483612
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmu

SCHEDULE OF QUANTITY

Name of Work: Annual Repair & Maintenance of Ghanahatti Kalihatti Arki Road in Km. 0/000 to 8/060 (Sh: Trimming of Grass, Dressing of shoulder, clearing of drain etc.)

Estimated Cost : Rs 270699 /- only
 Earnest Money : - Rs 5000 /- only
 Time : - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount	
				figures			
1	2	3	4	5	6	7	
1	Maintenance of Earthen shoulder (stripping of excess soil) , Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 as per the direction of Engineer-in-Charge.	15801.00	Sqm	12.71	Rupees Twelve and Paise Seventy One Only	Per Square Meter	200831.00
2	Trimming of grass and weeds from shoulder / berms and disposing off the same to suitable locations as per technical specifications clause 1914 including carriage of material within all leads and lifts as per the directions of Engineer-in-charge.	13740.00	Sqm	3.39	Rupees Three and Paise Thirty Nine Only	Per Square Meter	46579.00
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 including carriage of material upto all leads and lifts as per the direction of Engineer-in-charge.	6870.00	Rmt.	3.39	Rupees Three and Paise Thirty Nine Only	Per Running Meter	23289.00
0.00						Total:	270699.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executing Engineer
 Shmita Rural Division
 HPPWD, Dhani

Schedule of Quantity
Name of Work : A/R & M/O Old age Home at Basantpur, Tehsil Suni Distt. Shimla H.P.
(SH : Balance works thereof).

Estimated Cost:- 4,11,304 /- Only
Earnest Money:- 10000 /- Only

Time:- One Month

Sr. No.	Description of Work	No. of Qty.	In figures	Rate		Unit	Amount
				In words	In figures		
1	Dismantling roofing including ridges, hips, valleys, gutters etc. stacking the serviceable materials and disposal of un-serviceable materials within 20 Metres lead.	80.50	Sqm	Eighty two Rupees only	82.00	Per Sqm	6601.00
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles above 25 mm and up to 40 mm	1.35	Sqm	Sixty nine rupees only	69.00	Per Sqm	93.00
3	Providing and fixing PVC water storage tank of ISI : 12701 marked, G.I. inlet and outlet connection, 15mm Nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting up to all heights above ground level 1000 litres(one thousand litres) net capacity tank as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.(including all fittings)	5.00	Nos.	Nine thousand eight hundred ninety nine rupees only	9899.00	Per Nos	49495.00
4	Providing and fixing PVC water storage tank of ISI : 12701 marked, G.I. inlet and outlet connection, 15mm Nominal bore ball valve and mosquito proof PVC cover with locking arrangement including hoisting up to all heights above ground level 500 litres(five hundred litres) net capacity tank as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.(including all fittings)	2.00	Nos.	Five thousand two hundred sixty five rupees only	5265.00	Per Nos	10530.00
5	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre long with S.S.triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	1.00	Nos.	Six hundred thirteen rupees only	613.00	Per Nos	613.00
6	Providing and fixing CP brass bib tap with capstan head & CP flange including carriage of materials within all leads and lifts :-	1.00	Nos.	Four hundred ninety six rupees only	496.00	Per Nos	496.00
7	Providing and fixing 15 mm (fifteen millimetre) dia C.P. Brass angle cock as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals..	10.00	Nos.	Three hundred seventy eight rupees only	378.00	Per Nos	3780.00
8	Providing and fixing P.V.C. connection with Brass unions 300/450 mm (three hundred/four hundred fifty millimetre) length 15 mm(fifteen millimetre) nominal size as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals. :	2.00	Nos.	Two hundred thirty five rupees only	235.00	Per Nos	470.00
9	Providing and fixing wall mixing faucet for shower and bath hand shower with angular and rest holder.	5.00	Each	Three thousand four hundred fifty five rupees only	3455.00	Each	17275.00
10	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.	1.00	Nos	Six thousand three hundred seventy five rupees only	6375.00	Per Nos	6375.00

11	Providing and laying Ceramic glazed wall tiles of size 300x300 mm (thickness to be specified by the manufacturer) of 1st quality conforming to IS : 15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., complete.	30.68	Sqm	1281.00	One thousand two hundred eighty one rupees only	Per Sqm	39301.00
12	Providing and laying 8 mm thick Anti Skid Ceramic tile 300 x 300 mm of AGI/Johnson/Kajaria/Orient Bell or equivalent manufactured of approved shade and colour in flooring, treads of steps and landing laid over 12mm thick cement mortar 1:3 (1 cement : 3 sand) jointed with cement slurry mixed with pigment to match the shade of tiles as required complete, as per direction of Engineer-in-Charge including carriage of materials with in all leads, lifts and other incidentals.	1.35	Sqm	1671.00	One thousand six hundred seventy one rupees only	Per Sqm	2256.00
13	Providing and laying 15mm (fifteen millimetre) cement plaster in single coat on the fair side of brick concrete stone wall for interior plastering upto floor all level including arises, internal rounded angles, chamfers and or rounded angles not exceeding 80mm (Eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement: six sand) including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	26.87	Sqm	250.00	Two hundred fifty rupees only.	Per Sqm	6718.00
14	Applying birla white wall care putty over plaster surface after thoroughly brushing the surface free mortar droppes, dust, loose materials and other foreign matters sand papered smooth to give final matter finish to the surface complete.	42.32	Sqm	93.00	Ninety three rupees only	Per Sqm	3936.00
15	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & fungal resistance, dirt resistance exterior paint of required shade (Company Depot Limited) with silicon additives.	42.32	Sqm	130.00	One hundred thirty rupees only	Per Sqm	5502.00
16	Providing and fixing polycarbonate transparent sheet 3 mm thick in roofing with galvanised J or L hooks bolts and nuts with G.I. Limpe and bitumen rubber washer complete with all accessories as required as per direction of Engineer-in-Charge.	80.50	Sqm	2678.00	Two thousand six hundred seventy eight rupees only	Per Sqm	215579.00
17	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end) :-						
17	25 mm nominal size	6.00	Nos	553.00	Five hundred fifty three rupees only	Per Nos	3318.00
17	20 mm Nominal Size	4.00	Nos	503.00	Five hundred three rupees only	Per Nos	2012.00
18	Supplying and fixing glass panes with putty and nails including removal of broken glass panes wherever necessary: Plain Glass: 4mm thick.	3.20	Sqm	868.00	Eight hundred sixty eight rupees only	Per Sqm	2778.00
19	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. Second class deodar wood 35 mm thick	2.46	Sqm	3951.00	Three thousand nine hundred fifty one rupees only	Per Sqm	9719.00
20	Applying priming coat over new wood and wood based surfaces after and including prepping the surface by thoroughly cleaning oil, grease, dirt and other foreign matter) sand papering and knotting, Ready mixed paint brushing with wood primer pink	2.46	Sqm	56.00	Fifty six rupees only	Per Sqm	138.00

21	Painting two coats excluding eart) on new wood and wood based surface with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter,sand papering & stoping With enamel paint other than white including entire carriage of materials in all leads and lifts.	2.46	Sqm	98.00	Twenty eight rupees only	Per Sqm	241.00
22	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 100 mm	5.00	Nos.	59.00	Fifty nine rupees only	Per Nos	295.00
23	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 150 X 10 mm	10.00	Nos.	83.00	Eighty three rupees only	Per Nos	830.00
24	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. i) Trusses and trussed purlins in buildings	178.11	Kg	102.00	One hundred rupees only	Per Kg	18167.00
25	Preparing the surface to receive waterproofing treatment by making surface ready to receive water proofing treatment, Cleaning the surface with wire brushes to clean,smooth & dry surface, free of any loose particles, reinforcement bars, debris etc. Providing and applying base coat on primer coat as per site requirement and complete in all respect including all leads, lifts and carriage of material at site as directed by engineer in charge allowing drying gap between successive coats. Providing and applying with paint brush two final coats of elastomeric liquid applied Polyurethane, Membrane, Multihane BK on the prepared surface as per site requirement and complete in all respect including all leads, lifts and carriage of material at site as directed by the Engineer in charge allowing drying gap between successive coats.	1.60	Sqm	1190.00	One thousand one hundred ninety rupees only	Per Sqm	1904.00
26	Providing and fixing PVC floor trap ISI marked of self cleaning design including fixing with approved adhesive, cost of cutting and making good the wall and floors etc. complete including carriage of materials within all leads and lifts :- 110 mm X 90 mm.	2.00	Nos.	354.00	Three hundred fifty four rupees only	Per Nos	708.00
27	Providing and fixing PVC 'P' or 'S' trap for water closet (squatting pan) including jointing the trap with the pan and PVC pipe with approved adhesive etc. complete.	2.00	Nos.	263.00	Two hundred sixty three rupees only	Per Nos	526.00
28	Providing and fixing high pressure uPVC spigot and socket waste and ventilating pipes including fixing with approved adhesive etc. complete. 110 mm dia	4.00	Rmt	412.00	Four hundred twelve rupees only	Per Rmt	1648.00
Total (Rates excluding GST)							
Amount Quoted by the Contractor in Percentage							
Note :- All the material will be procured by the contractor himself and bills will be submitted							
							411304.00


 Executive Engineer,
 Sanjiv Ranga Division,
 MPWD

Name of Work: - Annual Repair & Maintenance of Palkari Makri Road Km. 0/000 to 1/600 (SH:- Construction of Edge walls at various RDs. 0/120 to 0/135, 0/170 to 0/190, 0/200 to 0/215, 0/310 to 0/325, 0/400 to 0/415, 0/770 to 0/780 and 0/810 to 0/825)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs. 488168 /- only
Earnest Money: - Rs. 10000 /- only

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures	5			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	14.70	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3431.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	88.20	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	31443.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	95.29	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	438334.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	88.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	14960.00
0						Total:	488168.00

Amount Quoted by the Contractor in Percentage:

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhampur

Schedule Of Quantity

Name of Work :- A/R & M/O Shakoh to Hanuman road km 0/00 to 1/250 (SH:- C/O slab a/w bed block & dirt wall of slab culvert at Rd 1/050)

Estimated Cost:- 4,98,425 .00
Earnest Money:- 10,000.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and Technical Specification Clauses 802, 803, 1202 and 1203. Reinforced Cement concrete grade M15 Nominal mix 1:2:4.	16.70	Cum	6800.00	Rupees Six Thousand Eight Hundred Only	Per cubic metre	113560
2	Providing and laying reinforced cement concrete in superstructure complete as per drawings and Technical Specification Clauses 800, 1205.4 and 1205.5 Reinforced Cement Concrete Grade M20 (1:1.5:3) Nominal mix	12.00	Cum	8545.00	Rupees Eight Thousand Five Hundred Forty Five Only	Per cubic metre	102540
3	Supplying, fitting and placing HYSD bar reinforcement (Fe 415) in substructure complete as per drawings and technical specification Clauses 1002, 1005, 1010 & 1202	2.05	Tonne	99982.74	Rupees Ninety Nine Thousand Nine Hundred Eighty Two and Paise Seventy Four Only	per tonne	204965
4	Back filling behind abutment, wing wall and return wall complete as per drawings and Technical Specification Clause 1204.3.8 HPSR 2009 Item No. 12.14 (i)	30.00	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	25254
5	Plain/reinforced cement concrete in substructure complete as per drawings and Technical Specification Clauses 802, 804, 805, 806, 807, 1202 and 1204 upto 5.00 metre height. Plain Cement concrete grade nominal mix 1:2:5:5	7.63	Cum	6200.00	Rupees Six Thousand Two Hundred Only	Per cubic metre	47306

6	Providing and laying weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall return wall with 100 mm (one hundred) millimetre dia. PVC pipe extending through the full width of the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification MORD clause 614.709,1204.3.7 including carriage of material within all leads and lifts as per the direction of Engineer-in-charge.	24.00	Rmt	200.00	Rupees Two Hundred Only	Per running Metre	4800
	Total Rs.						498425
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm


Schedule of Quantity

Name of Work : A/R & M/O Shimla Mandi road Km 22/000 to 33/200.

(SH : Maintenance/Cleaning of side drain, Hume pipe culverts, Trimming of grass and maintenance of earthen shoulders/berms from Km 22/000 to 33/200.) (Job-2)

Name of work : A/R & M/Shimla Mandi road Km 22/000 to 33/200.								Estimated Cost:		499950.00	only /-
(SH : Maintenance/Cleaning of side drain, Hume pipe culverts, Trimming of grass and maintenance of earthen shoulders/berms from Km 22/000 to 33/200.) (Job-2)								Earnest Money		10000.00	only /-
								Time: - One month			
S. No	Description of Work	Nos of Qty		In Figure	Rate		Unit	Amount			
		3	4	5	6		7	8			
1											
2	Maintenance of Hume pipe Culvert by way of Clearing, Cleaning, Erosion repair, repairs to cracks, parapet wall and protection work as per drawing and technical specification Clause 1908	10.00	Each	2475.00	Two Thousand Four Hundred Seventy Five rupees only		Each	24750.00			
3	Cutting of branches of trees shrubs and trimming of grass and weeds. iii) Trimming of grass and weeds from the shoulders/berms and disposing off the same to suitable locations as per technical specifications Clause 1914	5760.00	Per Sqm	5.00	Five Rupees only		Per Sqm	28800.00			
4	Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903	7200.00	Per Sqm	62.00	Sixty two Rupees only		Per Sqm	446400.00			
	Amount Quoted by the Contractor in Percentage						Total	499950.00			
	Note :- All the material will procured by the contractor him self										

Executive Engineer
Shimla Rural Division
HP.PWD, Dham

A/R m/c

Name of Work: *Shimla Mandi road Km 39/200 to 52/300.*
SH: C/O Rain Shelter at RD 42/930

Schedule of Quantity

S. No	Description of Work	Nos of Qty		In Figure	Rate <i>Rs</i> ~~Rs~~ <i>G.S.T.</i> <i>In word</i>	Unit	Amount
		3	4	5	6	7	8
1	Excavation work by mechanical means (Hydraulic excavator)/ manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soils as directed, within a lead of 30 m	3	4	374.00	Rupees Three Hundred Seventy Four only	cum.	2339.00
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:10 (1 cement : 5 coarse sand) : 10 graded stone aggregate 40 mm nominal size)	1.251	4	4751.00	Rupees Four Thousand Seven Hundred Fifty One only	cum.	5944.00
3	Providing and laying reinforced cement concrete 1:2:4 (one cement : two Sand : four graded stone aggregate 20mm nominal size) mechanically mixed and vibrated to give an smooth and even surface including the cost of centering and shuttering etc.	7.96	4	6743.00	Rupees Six Thousand Seven Hundred Forty Three Only	cum.	53674.00
4	Brick work with common burnt clay F.P.S. (iron modular) bricks of class designation 7.5 in super structure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	2.52	4	9162.00	Rupees Nine Thousand One hundred Sixty Two only	cum.	23088.00
5	Providing and laying 15mm (fifteen millimetre) cement plaster in single coat on the fair side of brick concrete stone wall for interior plastering upto floor all level including arses, internal rounded angles, chasters and or rounded angles not exceeding 80mm (Eighty millimetre) in girth and finished even and smooth in cement mortar 1:6 (one cement: six sand) including carriage of materials with in all leads, lifts and other incidentals as per the directions of Engineer-in-Charge.	7.55	4	249.00	Rupees Two Hundred Forty Nine only	Sqm	1880.00
6	Providing and fixing 0.60 mm thick plain prepainted steel sheet roofing, with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts and nuts 6mm dia metre with prepainted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-Charge.	36.17	4	1284.00	Rupees One Thousand Two Hundred Eighty Four only	Sqm	46442.00
7	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick prepainted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with prepainted iron J or L hooks, bolts & nuts 6mm dia & prepainted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charge.	13.70	4	690.00	Rupees Six Hundred Ninety only	Rmt	9453.00
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 1) Trusses and trussed purlins in buildings	987.35	4	102.00	Rupees One hundred Two only	Kg	100710.00

Estimated Cost: 423673.00 only /-

Earnest Money 10000.00 only /-

Time: - One month

9	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	147.38	Kg.	109.00	Ruppes One hundred Nine only	Kg.	16664.00
10	Supplying and filling in plinth with sand under floors, including watering, ramming, consolidating and dressing complete.	1.61	cum.	2021.00	Ruppes Two thousand twenty one only	cum.	3254.00
11	Stone soling boulder filling dry hand packed in under floor as per the direction of Engineer-in-charge including carriage of materials with in all leads, lifts and other incidentals.	2.14	cum.	1374.00	Ruppes One thousand three hundred seventy four only	cum.	2940.00
12	Providing and laying in position cement concrete of specified grade including the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand) : 8 graded stone aggregate 20 mm nominal size)	2.26	cum.	3224.00	Ruppes Five thousand Two hundred twenty four only	cum.	11806.00
13	Steel reinforcement for R.C.C. work ready to use "cut and bend" rebars of approved make from factory/ workshop to construction site including placing in position and binding all complete upto plinth level.	355.20	Kg.	87.00	Ruppes Eighty Seven only	Kg.	30962.00
14	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) 25 mm thick	21.66	sqm.	1317.00	Ruppes One thousand five hundred seventeen only	sqm.	22858.00
15	Applying priming coat over new steel & other metal surfaces after & including preparing the surface by thoroughly cleaning oil grease dirt and other foreign matter and scoured with wire brushes (fine steel wool scrapers and sand paper complete. With ready mixed priming paint brushing red lead, Red-oxide/zinc oxide chrome.	35.37	sqm.	52.00	Ruppes Fifty two only	sqm.	1839.00
16	Painting two coats (excluding priming coat) on new steel and other metal surfaces with enamel paint brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matters :- With ready mixed paint	35.37	sqm.	108.00	Ruppes One hundred eight only	sqm.	2850.00
17	Providing and fixing M.S. BP Sheet 1.6mm to 2.00 mm thick in eaves board/facia/soffits (ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately)	40.39	sqm	1898.00	Ruppes One thousand Eight hundred ninety eight only	sqm	76660.00
Amount Quoted by the Contractor in Percentage					Total		423673.00
Note :- All the material will procured by the contractor him self							

Executive Engineer
Shimla Rural Division
HP P.W.D. Shimla

Schedule Of Quantity

Name Of Work :- A/R & M /O Shoghi Mehli road km 0/00 to 12/375 (SH:- C/O V-shape drain in km 3/00 to 3/400)

Estimated Cost:- 4,15,507.00
Earnest Money:- 8,300.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		In words	Unit	Amount
		3	4	Excluding GST	5			
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305 1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	175.95	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only		Per Cubic metre	53158
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:3:6 (1 Cement 3 sand: 6 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	79.18	Cum	4576.27	Rupees Four Thousand Five Hundred Seventy Six and Paise Twenty Seven Only		Per Cubic metre	362349
Total Rs.								415507
Note :- The Rates are excluding GST								
Amount Quoted by the Contractor in Percentage								
Note :- All the material will procured by the contractor him self								

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dharti

Schedule Of Quantity

Name of Work :- A/R & M/O Shoghi Mehli road km 0/000 to 12/375 (SH:- C/O R/wall at RD 9/750 to 9/763)

Estimated Cost:- 4,87,536.00

Earnest Money:- 9,800.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	2						
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	25.09	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5856
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	24.31	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	8667
3	Providing and Laying for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause 802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-Charge 1:3:6 (1 Cement 3 sand: 6 graded stone Aggregate 20 mm nominal mix)	85.41	Cum	5300.00	Rupees Five Thousand Three Hundred Only	Per cubic metre	452673
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	38.00	No	190.00	Rupees One Hundred Ninety Only	Each	7220
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	15.60	Cum	841.00	Rupees Eight Hundred Forty One Only	Per cubic metre	13120
	Total Rs.						487536
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhary

NAME OF WORK:- Annual Repair & Maintenance of Thachi Rehana Road Km. 0/000 to 2/645 (Sh: Construction of wing wall along with D/S & U/S Toe Wall, Catchpit of Existing pipe Culvert at Km. 1/510)

SCHEDULE OF QUANTITY

U/S Toe Wall, Catchpit of Existing pipe Culvert at Km. 1/510)									
Estimated Cost :- Rs 328710 /- only									
Earnest Money :- Rs. 7000 /-only									
Time :- One Month									
S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount			
			figures	figures					
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	43.70	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	13203.00		
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Millimetre size) concrete mix , including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	1.53	Cum	4406.78	Rupees Four Thousand Four Hundred Six and Paise Seventy Eight Only	Per cubic metre	6742.00		
3	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications, P.C.C grade M 15, Nominal mix (1:2.5:5) Clause 802, 803, 1202 & 1203 including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	14.78	Cum	4576.30	Rupees Four Thousand Five Hundred Seventy Six and Paise Thirty Only	Per cubic metre	67638.00		
4	Providing and Laying cement concrete for plain / reinforced concrete in open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	58.44	Cum	3890.31	Rupees Three Thousand Eight Hundred Ninety and Paise Thirty One Only	Per cubic metre	227350.00		
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	28.00	Rmt.	144.00	Rupees One Hundred Forty Four Only	Per Running Metre	4032.00		
6	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	13.66	Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per cubic metre	9745.00		
0						Total:	328710.00		

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will be procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharam

Schedule Of Quantity

Name of Work :- A/R M/O on Tutikandi Shilgaon via Kiari road km 0/00 to 3/370 (SH:- C/O B/wall km 2/650 to 2/695)

Estimated Cost:- 4,53,387 .00
Earnest Money:- 9,100.00
Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate	In words	Unit	Amount
		3	4	Excluding GST			
1	2 1 xccavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1	16.20	Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per running Metre	3204
2	Earth work in excavation for structures as per drawing and technical specifications clause No. 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead of 50m dressing of side and bottom and backfilling in trenches with excavated suitable materials	8.10	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per Square metre	2447
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802,803,1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix)	107.10	Cum	4067.80	Rupees Four Thousand Sixty Seven and Paise Eighty Only	Per Square metre	435661
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204,3,7.	75.00	No	161.00	Rupees One Hundred Sixty One Only	Each	12075
	Total Rs.						453387
	Note :- The Rates are excluding GST 18%						
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhanu.

Schedule of Quantity

Name of work: C/O Link road from Chebri to Piplughat Km 0/000 to 3/870.
(SH : C/O R/Wall/Wire crate & PCC) at RD 1/460 to 1/476.80).

Estimated Cost:	408296.00	only /-
Earnest Money	10000.00	only /-
Time: - One month		

S. No	Description of Work	Nos of Qty	Unit	Rate		Amount
				In Figure	In word	
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer-in-Charge.	13.44	Per Cum	233.40	Two hundred thirty three rupees forty Paise only	3137.00
2	Earth work in excavation for structures as per drawing and technical specifications clause No. 305.1 including setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of side and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-in-Charge.	22.76	Per Cum	356.50	Three hundred fifty six rupees fifty paise only	7906.00
3	Back filling behind Abutment, wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	17.47	Per Cum	841.80	Eight Hundred forty one rupees eighty paise only	14706.00
4	Providing and laying of boulder apron laid in wire crates with 4 mm dia GI wire conforming to IS:280 and IS:4826 in 100 mm x 100 mm mesh (woven diagonally) including 10 per cent extra for laps and joints laid with stone boulders weighing not less than 25 kg each as per drawing and technical specifications Clause 1301.	96.81	Per Cum	2852.00	Two thousand Eight Hundred fifty two rupees only	276102.00
5	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803.1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including cartage of material up to all leads and lifts as per the direction-in-Charge.	22.76	Per Cum	4800.00	Forty eight Hundred rupees only	106445.00
Amount Quoted by the Contractor in Percentage				Total		408296.00
Note :- All the material will procured by the contractor him self						

Executive Engineer
Shimla Rural Division
HP.PWD, Dehra

Schedule of Quantity	
----------------------	--

F/C 57 mtr wide road in Km 1/285 to 1/390)

Estimated Cost:-	4,23,573.00 Only.
Earnest Money:	10,000.00 Only

Time: - One month

No.	Description of Work	Time: - One month					
		Nos. of Qty.		Rate (excluding GST)		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour machines, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones, shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 276.91 cum qty which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course, of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	1449.40	cum	292.24	Rupees Two hundred Ninety Two and Twenty Four paise only	per cum	4,23,573.00
					Total		4,23,573.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machines/materials will be procured by the contractor himself and bills will be submitted.						
	Note: All the rates are excluding GST.						

~~Executive Engineer
Shimla Rural Division
HPWD Dharami~~

Schedule of Quantity

Name of work:- C/O link road from Kanda to Lunu Km 0/00 to 2/300 (SH: F/C 5/7 mtr wide road in Km 1/180 to 1/285)

Estimated Cost:- 4,23,139.00 Only.

Earnest Money: 10,000.00 Only.

Time:- One month

S. No.	Description of Work	Nos. of Qty.		Rate (excluding GST)		Unit	Amount
		3	4	In Figure 5	In word 6	7	8
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including: dewatering where ever required setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-1 and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour machines, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones, shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 277.63 cum qty which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundred only) per cubic meter shall be effected, any loss to the public and private property during the course. of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects.	1,435.10	cum	294.85	Rupees Two hundred Ninety Four and Eighty Five paise only	per cum	4,23,139.00
	Amount procured by the contractor in percentage						Rs.
	Conditions:- All the Machines/materials will be procured by the contractor himself and bills will be submitted.						
	Note: All the rates are excluding GST.						
					Total		4,23,139.00


 Executive Engineer
 Shimla Rural Division
 HP PWD Dary

Name of Work:- Construction of Link Road from Kufridhar to Shanol Road Km. 0/00 to 2/120 (Sh: Construction C.D. Work in Km. 1/360 with wing wall)

SCHEDULE OF QUANTITY

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			Figures	5		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	66.95 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	23968.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) C.C. 1:3:6 20 mm nominal mix (Twenty Millimetre size) concrete mix, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	25.49 Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	132548.00
3	Providing and laying reinforced cement concrete pipe NP2 as per design in single Row. Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, (c) 900 mm dia	7.50 Rmt.	3855.64	Rupees Three Thousand Eight Hundred Fifty Five and Paise Sixty Four Only	Per Running Metre	28917.00
4	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	65.50 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	301300.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	8.55 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	7197.00
6	Providing weepholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(V):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	19.80 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	3366.00
0					Total:	497196.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shanoli Rural Division
HPPW, Dhani

Name of Work: - Construction of Link Road from Pahal to Ghat in Km. 0/00 to 2/00 (SH: Formation Cutting in km. 1/280 to 1/455)

Name of Work: - Construction of Link Road from Pahal to Ghat in Km. 0/00 to 2/00 (SH: Formation Cutting in km. 1/280 to 1/455)

Estimated Cost: - Rs 498583 /- only

Earnest Money :- Rs. 10000 /-only

Time-One Month

Amount Quoted by the Contractor in Percentage

~~Executive Engineer,~~
Shimla Rural Division,
HPPW-3 Dhani

Name of work :- C/O Link road from Majhiwar to Jabal km 0/000 to 1/800.(SH:Formation Cutting/widening in km 0/000 to 0/270)

Schedule of Quantity

0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									
0/270)									

Executive Engineer
Shimla Rural Division
HP.PWD, Dhani

Name of Work:- Construction of Link Road to Hanzen Basti Sylmu Badog Km. 0/000 to 1/600 (Sh: Construction of PCC R/Wall at Rd. 0/720 to 0/740)

SCHEDULE OF QUANTITY

NAME OF WORK:- Construction of Link Road to Harizen Basti Syalmu Badoag Km. 0/000 to 1/600 (Sh. Construction of PCC R/Wall at Rd. 0/720 to 0/740)									
S. No.	Sub head and items of work	Qty.	Rate			Unit	Amount		
			4	5	6				
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	29.00	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6769.00		
2	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	51.80	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	238280.00		
3	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	3.00	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	2525.00		
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	20.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	3400.00		
0						Total:	250974.00		

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

Schedule of Quantity

Name of Work:- C/O Link road to Mandrech Km 0/000 to 2/620.

SH: Formation Cutting from RD 0/585 to 0/630, 0/675 to 0/720, 0/915 to 0/960.

Name of Work:- C/O Link road to Mandreesh Km 0/000 to 2/620.									
SH: Formation Cutting from RD 0/585 to 0/630, 0/675 to 0/720, 0/915 to 0/960.									
		Estimated Cost:		409110.00		only /-			
		Earnest Money		10000.00		only /-			
		Time: - One month							
S. No	Description of Work	Nos of Qty	4	In Figure	Rate		Unit	Amount	
					In word				
1	Excavation in soil in hilly area in all heights and depths in all kinds of soil including saturated soil comprising of mixed soil , ordinary rock and hard rock .All work of rock cutting by blastingshall be carried out by taking all necessary precautions against soil erosion ,damages to hill side ,water pollution etc. and to protect stability of hill side .Rock shall be excavated with chiseling and wedging out of rock (where blasting is prohibited) .All earth work in cutting /excavation including rock excavation shall be carried out true to lines ,grades ,sides /slopes ,width ,camber ,super-elevation and level as shown on the drawing and as directed by the Engineer-in-Charge in conformity with the requirement of technical specification for Rural Road,August 2004 and clause 16.2 of General conditions for contract to achieve designed formation width including hauling and stacking of materials useful for construction at suitable sites safe manner including arrangement of dumping site trimming ,filling of unevenness blind age and finishing of the road to specified dimensions or as directed by the Engineer-in-Charge for smooth riding .The recovery for stones ,whether usefule or not ,for 309.14 cubic metre at the rate of Rs 300/-only (Rupees three hundred only) per cubic meter shall be effected on pro rata basis in all circumstances. Any loss to the public and private property during the course of excavation shall be the absolute responsibility of the contractor ,which shall have to be duly compensated by him in all cases.	1081.70	Per Cum	378.21	Three Hundred Seventy Eight rupees Twenty one Paise only		Per Cum	409110.00	
						Total		409110.00	
Amount Quoted by the Contractor in Percentage									
Note :- All the material will procured by the contractor himself									

Name of work:- C/O Link road to village Majelu km 0/000 to 1/650 (SH-Formation Cutting 5/7 Mtr wide road in km 0/405 to 0/495)

Time: - One month							
S. No	Description of Work	Nos of Qty		Rate (excluding GST)		Unit	Amount
1	2	3	4	In Figure	In word	7	8
				5	6		
1	Cutting in earth work in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper, blasting work both in soft and hard rock with chiseling/ wedging out of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where ever required setting to the required line, grades, side slopes trimming bottoms and level as shown on the drawing as directed by the Engineer-in-Charge at site according to HP PWD specifications of 1990 (One thousand Nine hundred Ninety) Volume-I and sorting out useful/un-useful materials and stacking the same in all leads and lifts and transportation of the unuseful materials for filling in road ways, embankments for grades improvements and leveling to the required grades and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load, animal load or mechanical means along with its leveling fine dressing and all labour machines, materials, tools equipments and safety measures and incidentals necessary to complete the work by mechanized means and labour (if any required). The cost of all useful materials such as stones, shingles, aggregates, and slates shall be sorted out and stacked along road side, which shall not be less than one tenth of the jumper work and one sixth of ballasting work (soft rock) one third of blasting work (Hard rock) 288.63 cum qty which shall be proportionately increases/decreases as the antity of earth work increase/decrease in all cases recovered from the contractor at the rate of Rupees 300/- (Three hundreded only) per cubic meter shall be effected, any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor which shall have to be duly compensated by him in all respects	1043.25	per cum	₹ 404.42	Four hundred Four rupees and forty two paisa only.	per cum	421911.00
					Total		421911.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted .						
	Note: All rates are excluding GST.						

Executive Engineer
Shimla Road Division
HPPWD District

Schedule of Quantity

420789.00 Only.

1000.00 Only.

h

Executive Engineer
Shimla Rural Division
HPPWD District

SCHEDULE OF QUANTITY
Name of Work: Construction of Link Road Totu to Kayar Km. 0/00 to 1/555 (Sh: Construction of Hume Pipe Culvert 900 mm dia at Rd. 0/405 along with wing walls)

Estimated Cost - Rs. 376637 /- only
 Earnest Money - Rs. 8000 /- only
 Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures	figures		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	26.38	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre 6157.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) Nominal Mix 1:3:6, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	15.78	Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre 82056.00
3	Providing and laying reinforced cement concrete pipe NP2 as per design in single Row. Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108 (c) 900 mm dia	7.50	Rmt	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Running Metre 28875.00
4	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	54.33	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre 249918.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204 3.8, (i) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	7.20	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre 5061.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(h) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	21.00	Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre 3570.00
0					Total:	376637.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will be procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Bham

Name of Work: Construction of Link Road Totu to Kayar Km. 0/00 to 1/555 (Sh: Construction of Hume Pipe Culvert 900 mm dia at Rd. 0/555 along with wing walls)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 376637 /- only
Earnest Money : - Rs. 8000 /- only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures				
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	26.38	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6157.00
2	Providing concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203, P.C.C grade M 10, (i) Nominal Mix 1:3:6, including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	15.76	Cum	5200.00	Rupees Five Thousand Two Hundred Only	Per cubic metre	82056.00
3	Providing and laying reinforced cement concrete pipe NP2 as per design in single Row. Providing and laying reinforced cement concrete pipe NP2 for culverts on first class bedding of granular material in single row including fixing collar with cement mortar 1:2 but excluding excavation, protection work, back filling, concrete and masonry work in head walls and parapets clause 1108, (c) 900 mm dia	7.50	Rmt.	3850.00	Rupees Three Thousand Eight Hundred Fifty Only	Per Running Metre	28875.00
4	Providing and laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	54.33	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	249918.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	7.20	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	5061.00
6	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	21.00	Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	3570.00
0						Total:	376637.00

Amount Quoted by the Contractor In Percentage

RS.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD/Dhami

Schedule Of Quantity

Name of Work :- C/O Science Learning and Creativity Centre at village Bhog Anandpur
Shoghi (SH:- C/O Boundary wall a/w Planetorium. (balance work) Job No -1

Estimated Cost:- 4,94,244.00

Earnest Money:- 9,900.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	57.40	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	20463
2	Centring, Shuttering i/c sturting, propping etc and removal of form work i/c carraig of materials in all leads & lifts complete.	93.24	Sqm	470.50	Rupees Four Hundred Seventy and Paise Fifty Only	Per square metre	43869
3	Providing and laying concrete 1:2:4 (1 cement 2 sand 4 Graded stone aggregate) (20mm nominal size) excluding cost of form work in foundation and plinth and curing complete mechanically mixed and within all leads and lifts.	68.24	Cum	6300.00	Rupees Six Thousand Three Hundred Only	Per cubic metre	429912
	Total Rs.						494244
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharti

City of Works: C/O Two Nos Type-II Quarter at Suni Tehsil Suni Dist Shimla HP.
(SI: Providing and Fixing Pre-painted Sheet Roofing)

Schedule of Quantity

S.No										Estimated Cost:		Earnest Money:		Time :- One month									
Description of Work										Nos of Qty		In figure		Rate		In word		Unit		Amount			
										3		4		5		6		7		8			
1	Providing and fixing 0.60 mm thick plain pre-painted steel sheet roofing, with hot dipped metallic zinc coated sheet with top coat of regular modified polyester (RNP) organic coating of 20 microns over 5 microns primer coating to back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with pre-painted iron J or L hooks, bolts and nuts 6mm dia metric with pre-painted limpet and rubber washers complete with all accessories as required as per the direction of Engineer-in-charge.									142.69	Sqm	1284.00	Rupees One Thousand Two Hundred Eighty Four only		Sqm	181214.00							
2	Providing and fixing ridges or hips 60 cm overall with 0.60mm thick pre-painted steel sheets in roofing with hot dipped metallic zinc coated sheets with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating + back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with pre-painted iron J or L hooks, bolts & nuts 6mm dia & pre-painted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer in Charges.									34.20	Rmt	705.00	Rupees Seven Hundred Five only		Rmt	21111.00							
3	Providing and fixing valley 90cm overall 0.60mm thick pre-painted steel sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with pre-painted iron J or L hooks, bolts and nuts 6mm dia with pre-painted G.I. limpet and bitumen washers complete with all accessories as required as per the direction of Engineer-in-charge.									8.40	Rmt	1031.00	Rupees One Thousand Thirty One only		Rmt	86660.00							
4	Providing and fixing flushing 38cm overall with 0.60mm thick pre-painted sheet in roofing with hot dipped metallic zinc coated sheet with top coat of regular modified polyester organic coating of 20 microns over 5 microns primer coating - back coat of polyester of 5 microns over 5 microns primer coating i/c fixing with pre-painted iron J or L hooks, bolts and nuts 6mm dia meter & pre-painted G.I. limpet & bitumen washers complete with all accessories as required as per the direction of Engineer-in-Charge.									24.50	Rmt	851.00	Rupees Eight Hundred Fifty One only		Rmt	20679.00							
5	Providing and fixing M.S. BP Sheet 1.66mm to 2.00 mm thick in eaves board/facia/soffits/ceiling including cutting, fixing and welding to steel roof members and applying a coat of red lead primer complete as per the instruction of Engineer-in-charge (Base members of steel work shall be measured & paid separately) F M.S BP sheet 1.66mm to 2.00mm thick in eaves board/ Facia/ Soffits/ Ceiling including cutting fixing and welding to steel roof member and applying a coat of Red lead primer complete.									75.86	Sqm	1660.00	Rupees One Thousand Six Hundred Sixty only		Sqm	125928.00							
6	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc, as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works									535.00	Kg	114.00	Rupees One Hundred Fourteen only		Kg	603900.00							
Amount Quoted by the Contractor in Percentage										Total (Rates excluding GST)								423582.00					
Note :- All the material will be procured by the contractor himself																							

Estimated Cost: 423582.00 only/-
Earnest Money: 100000.00 only/-
Time: - One month

Executive Engineer
Shimla Rural Division
HP, P.W.D. Division

Name of Work: C/O Two Nos Type-II Quarter at Suni Tehsil Suni Dist Shimla HP.
(Slt:- Providing and fixing Structural Steel, Painting and finishing work.)

Schedule of Quantity

(SII- Providing and fixing Structural Steel, Painting and finishing work)										Estimated Cost: 422592.00 only /-	
										Earnest Money 10000.00 only /-	
										Time: - One month	
S. No	Description of Work	Nos of Qty		Rate		Unit	Amount				
		3	4	In Figure 5	In word 6			7	8		
1	2 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete in stringers, beams, landings etc. of stair cases, including use of chequered plate wherever required, all complete	1951.07	Kg	102.00	Rupees One Hundred Two only	Kg	199009.00				
2	Painting two coats (excluding priming coat) on new steel and other metal surface under coat with ready mixed paint brushing to give an even shade including cleaning the surface all dirt, dust and other foreign matter :- With ready mixed paint other than white including entire carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	104.51	Sqm	106.00	Rupees One Hundred Six only	Sqm	11078.00				
3	Applying priming coat over new wood and wood based surfaces after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter sand paper and knotting complete including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge	121.96	Sqm	54.00	Rupees Fifty Four only	Sqm	6586.00				
4	Painting two coats(excluding priming coat) on new wood and wood based surfaces with enamel paint to give an even shade including cleaning the surface of dirt,dust and other foreign matter sand papering and stopping. (i) with enamel paint other than white including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	121.96	Sqm	96.00	Rupees Ninety Six only	Sqm	11708.00				
5	Applying priming coat on new concrete/masonry/lasbestos cement/plastered surfaces after and including etching the surface by thoroughly cleaning oil,grease,dirt and other foreign matter and sand papering as required with Ready mixed primer including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	391.48	Sqm	55.00	Rupees Fifty Five only	Sqm	21531.00				
6	Painting two Coats (Excluding priming coat) on new concrete / masonry / plastered surface with enamel paint of approved brand and manufacture use on to give even shade including cleaning all dirt, dust and other foreign matter and sand papering as required including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge	391.48	Sqm	118.00	Rupees One Hundred Eighteen only	Sqm	46195.00				
7	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade : New work (two or more coats) over and including water thinable priming coat with cement primer including carriage of materials upto all leads and lifts and as per the direction of Engineer-in-Charge.	114.90	Sqm	128.00	Rupees One Hundred Twenty Eight only	Sqm	14707.00				
8	Finishing walls with 100% Premium acrylic emulsion paint having VOC less than 50 gm/litre and UV resistance as per IS 15489:2004, Alkali & Fungal resistance, dirt resistance exterior paint of required shade (Company Depot Tinted) with silicon additives. New work (Two or more coats applied @ 1.43 litre/ 10 sqm. Over and including priming coat of exterior primer applied @ 0.90 litre/10 sqm.	239.20	Sqm	134.00	Rupees One Hundred Thirty Four only	Sqm	32053.00				
9	Kota stone slabs 20 mm thick in risers of steps, skirting, dado and pillars laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing and polishing complete.	32.66	Sqm	1462.00	Rupees One Thousand Four Hundred Sixty Two only	Sqm	47749.00				

19	Construction of chamber 300x300x500 inside size for stop cock with CT surface box 100x100x75mm (INSIDE) with hinged cover fixed in cement concrete slab 1:2:4 mix (cement: 2 sand: 4 crushed stone aggregate 20mm nominal size) and inside plastering with C.M 1:3 (One cement: five sand: ten crushed stone aggregate 40mm nominal size) and inside plastering with C.M 1:3 (One cement: three sand) finished with floating coat of neat cement including curing complete with 100mm thick wall of brick masonry in cement mortar 1:5 (1 cement: 5 sand) with 100mm thick wall of brick masonry (2nd class) in cement mortar 1:5 (1 cement: 5 sand including cartage of materials through all modes of transportation with in all leads and lifts and as per direction of Engineer-in-charge.	3.00	Nos.	1942.00	Rupees Five Thousand Nine Hundred Forty Two only	Nos.	5876.00
11	Providing and fixing high pressure uPVC spigot and socket waste and ventilating pipes including fixing with approved adhesive etc. complete 150 mm dia	50.00	Rmt	523.00	Rupees Five Hundred Twenty Three only	Rmt	26150.00
				Total (Rates excluding GST)			422592.00
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor himself						


 Executive Engineer
 Shri Ram Prasad
 H.P. P.W.D. Dharwad

SCHEDULE OF QUANTITY
Name of Work:- Restoration of Rain damages on Airport Road Km. 0/000 to 1/150 (Sh: Construction of B-Wall at Rd. 0/690 to 0/690)

S. No.	Sub head and items of work	Qty.	Estimated Cost - Rs. 204972/- only. Earliest Money :- Rs. 4000/- only Time :-		Unit	Amount
			Rate Figures	One Month		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	18.00 Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	3560.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	18.80 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	5680.00
3	Providing and Laying cement concrete for plain / reinforced conc. in open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	49.50 Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	192966.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	19.20 Rmt.	144.07	Rupees One Hundred Forty Four and Paise Seven Only	Per Running Metre	2796.00
0					Total:	204972.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Schedule of Quantity

NAME OF WORK :- RR Damages on Badmain Basantpur road km 0/000 to 7/000.
(Sh: C/O R/wall at Rd 0/720 to 0/735.50).

S. No	Description of Work	Nos of Qty		Rate		Unit	Estimated Cost:	
							Earnest Money	only /-
							Time :- One month	only /-
1	2	3	4	In Figure	In word	7	8	Amount
				5	6			
1	Earth work in excavation for structures as per drawing and technical specifications clause No. 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of side and bottom and backfilling in trenches with excavated suitable materials as per MORCD Specification directed by Engineer -in- Charge.	36.43	Per Cum	356.50	Three hundred fifty six rupees fifty paisa only	Per Cum	12987.00	
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803, 1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction -in- Charge.	79.40	Per Cum	4800.00	Forty eight Hundred rupees only	Per Cum	381120.00	
3	Back filling behind Abutment , wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	10.85	Per Cum	841.80	Eight Hundred forty one rupees eighty paisa only	Per Cum	9134.00	
4	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	32.00	Per Nos	180.00	One hundred eighty rupees only	Per Nos	5760.00	
Amount Quoted by the Contractor in Percentage					Total			409001.00
Note :- All the material will procured by the contractor himself								

Executive Engineer
Sumter-Rural Division
HP, P.W.D. Dharami

Schedule of Quantity

NAME OF WORK :- RR Damages on Badmain Basantpur road km 0/000 to 7/000.
(SH: C/O R/wall at Rd 0/870 to 0/885.50).

(SH: C/O R/wall at Rd 0/870 to 0/885.50).									
Basantpur road km 0/000 to 7/000.									
S. No	Description of Work	Nos of Qty		Rate		Unit	Estimated Cost:		only /-
		3	4	In Figure	In word		Earnest Money	10000.00	
1	2	3	4	5	6	7	8		
1	Earth work in excavation for structures as per drawing and technical specifications clause No. 205.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of side and bottom and backfilling in trenches with excavated suitable materials as per MORID Specification directed by Engineer-in-Charge.	36.43	Per Cum	356.50	Three hundred fifty six rupees fifty paise only	Per Cum	12987.00		
2	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803.1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including cartage of material up to all leads and lifts as per the direction -in-Charge.	79.40	Per Cum	1800.00	Forty eight Hundred rupees only	Per Cum	281126.00		
3	Back filling behind Abutment . wing wall and return wall complete as per drawings and technical specification clause 1204.3.8.	10.85	Per Cum	841.80	Eight Hundred forty one rupees eighty paise only	Per Cum	9124.00		
4	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	32.00	Per Nos	180.00	One hundred eighty rupees only	Per Nos	5760.00		
Amount Quoted by the Contractor in Percentage				Total		409001.00			
Note :- All the material will procured by the contractor himself									

Engineer
Shimla Rural Division
HP PWD, Shimla

Schedule Of Quantity

Name of Work :- RRD on Badmain to Basantpur road km 0/000 to 7/000 (SH:- C/O R/wall at Rd. 5/285 to 5/293)

Estimated Cost:- 4,72,550.00

Earnest Money:- 10,000.00

Time:- One Month

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	5	6		
1	2					7	8
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	39.52	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	14089
3	Providing and Laying for plain / reinforced concrete. In open foundation & plinth complete as per drawing and technical specification clause-802, 803, 1202 & 1203 including carriage of materials as per the directions of Engineer-in-Charge 1:4:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal size)	92.32	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	443136
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	36.00	No	190.00	Rupees One Hundred Ninety Only	Each	6840
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	10.08	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	8485
	Total Rs.						472550
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharti

SCHEDULE OF QUANTITY
Name of Work:- Restoration of rain damages on Bangora Kalihatti Bastighunana Road (Sh: Construction of Retaining wall between Rd. 11/420 to 11/430)

Estimated Cost: - Rs 418573 /- only
 Earnest Money : - Rs. 8000 /-only
 Time - One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount	
			4	5			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORO specification directed by Engineer-in-Charge.	19.21	Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	3800.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORO specification directed by Engineer-in-Charge.	23.52	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	7106.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	101.82	Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	396926.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.78	Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per cubic metre	7690.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	20.00	Rmt.	152.54	Rupees One Hundred Fifty Two and Paise Fifty Four Only	Per Running Metre	3051.00
0						Total:	418573.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
 Shimla Rural Division
 HPPWD, Dhani

Estimated Cost :- Rs 418634 /- only
Earnest Money :- Rs. 8000 /- only
Time :- One Month

S. No.	Sub head and items of work	Qty.	Rate		One Month	
			Rate figures	Unit	Amount	
1	2 Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORO specification directed by Engineer-in-Charge.	3 19.21 Cum	4 197.80	5 Rupees One Hundred Ninety Seven and Paise Eighty Only	6 Per cubic metre	7 3800.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORO specification directed by Engineer-in-Charge.	23.52 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	7106.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	101.82 Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	396926.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.78 Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per cubic metre	7690.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge. -	20.40 Rmt.	152.54	Rupees One Hundred Fifty Two and Paise Fifty Four Only	Per Running Metre	3112.00
0					Total:	418634.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Bangora Kalihatti Bastigunana Road Km. 0/000 to 11/675 (Sh: Construction of R-Wall at Rd. 11/240 to 11/254)

Estimated Cost :- Rs 422742 /- only
Earnest Money :- Rs. 8000 /-only
Time :-

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures				
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	18.08	Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	3576.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	20.69	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	6251.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	100.15	Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	390416.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	25.48	Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per cubic metre	18177.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.00	Rmt	144.07	Rupees One Hundred Forty Four and Paise Seven Only	Per Running Metre	4322.00
0						Total:	422742.00

Time: -

One Month

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD,Dhami

Name of Work:- Restoration of rain damages on Banuti Pahal Road via Nehwal in Km. 0/00 to 17/105 (Sh: Construction R-wall at Rd. 1/753 to 1/770)

Schedule of Quantity

Estimated Cost - Rs 483149 /- only
Earnest Money - Rs. 100000 /-only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			Figures	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	27.54 Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6428.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	32.98 Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	11757.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	96.56 Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	444176.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.73 Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	9874.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification - Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	64.20 Rmt.	170.00	Rupees One Hundred Seventy Only	Per Running Metre	10914.00
0					Total:	483149.00

Amount Quoted by the Contractor In Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharm

Schedule Of Quantity

Name Of Work :- R/R Damages on Chauri ki Ghatti to Yan via Bhad road Km. 0/00 to 9/600. (SH:- C/O R/wall at Rd 2/900 to 2/905 & removal of slips in various Rds)

Estimated Cost:- 3,20,009.00

Earnest Money:- 6,400.00

Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	Excluding GST	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	9.75	Cum	197.8	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per Cubic metre	1929
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads upto 50m, dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	1.55	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per Cubic metre	467
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	22.05	Cum	4067.80	Rupees Four Thousand Sixty Seven and Paise Eighty Only	Per Cubic metre	89695
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	8.00	Nos	161.00	Rupees One Hundred Sixty One Only	Each	1288
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	6.00	Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per Cubic metre	4280
6	Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slips and disposal of cut materialm as per technical specification	789.90	Cum	199.16	Rupees One Hundred Ninety Nine and Paise Sixteen Only	Per Cubic metre	157316
Total Rs.							254976
Note :- The Rates are excluding GST							

Amount Quoted by the Contractor in Percentage

Note :- All the material will procured by the contractor him self

--	--	--	--	--	--	--	--	--	--

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm

Schedule Of Quantity

Name of Work :- R/R damages on Chauri ki Ghati to Yaan Via Bhad road km 0/00 to 9/600 (SH:- C/O R/wall at km 9/345 to 9/360)

Estimated Cost:- 4,16,484.00
Earnest Money:- 8,300.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate excluding GST	In words	Unit	Amount
		3	4				
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per Technical Specification Clause 1603.1	27.99	Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	5536
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	27.12	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	8193
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand, 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	95.27	Cum	4067.80	Rupees Four Thousand Sixty Seven and Paise Eighty Only	Per cubic metre	387539
4	Providing weap holes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clause 614,709,1204.3.7	17.40	Nos	161.02	Rupees One Hundred Sixty One and Paise Two Only	Each	2802
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (1) Granular material	17.40	Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per cubic metre	12413
Total Rs.							416484
Note :- The Rates are excluding GST							
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharni.

Schedule Of Quantity

Name Of Work :- R/R Damages on Chauri-ki-Ghatti to Yan, Bhad road Km. 0/00 to 9/600. (SH:- C/O R/wall at Rd 2/830 to 2/840 and C/O B/wall at 2/980 to 2/995)

Estimated Cost:- 4,08,600.00

Earnest Money:- 8,200.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		In words	Unit	Amount
		3	4	Excluding GST	5			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	16.70	Cum	197.8		Rupees One Hundred Ninety Seven and Paise Eighty Only	Per Cubic metre	3303
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	17.50	Cum	302.12		Rupees Three Hundred Two and Paise Twelve Only	Per Cubic metre	5287
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	94.20	Cum	4067.80		Rupees Four Thousand Sixty Seven and Paise Eighty Only	Per Cubic metre	383187
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614, 709, 1204.3.7. including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	46.00	Nos	161.00		Rupees One Hundred Sixty One Only	Each	7406
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	13.20	Cum	713.39		Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per Cubic metre	9417
Total Rs.								408600
Note :- The Rates are excluding GST								
Amount Quoted by the Contractor in Percentage								
Note :- All the material will procured by the contractor him self								

Executive Engineer,
Shirala Rural Division,
HP, PWD, Dharm,

Name of Work:- Restoration of rain damages on Badheri Section under Jutogh Sub Division (Sh. Hiring of JCB for removal of snow / Slips)

SCHEDULE OF QUANTITY

Hiring of JCB for removal of Snow / Slips)									
Estimated Cost - Rs 399675 /- only									
Earnest Money - Rs 8000 /-only									
Time - One Month									
S. No.	Sub head and items of work		Qty.	Rate figures		Unit	Amount		
1	2	3	4	5	6	7			
1	Hiring of JCB/Excavator-cum-loder for removal of snow/slips including the cost of fuel oil, lubricants, wages of operational staff any repair during operational will be carried out at his risk and cost including carriage of machinery from one place to another at required location, actual working hour will be accounted for payment and proper disposal of snow/slips debres by the contractor will be ensured and including all lift and I work shall be executed as per direction of Engineer-in-Charge.	365.00	Hour	1095.00	Rupess One Thousand Ninety Five Only	Per Hour	399675.00		
0	Total:						399675.00		

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharmi

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Dhami Bainsih Road Km. 0/000 to 6/000 (Sh: Construction of PCC R/Wall at Rd. 5/015 to 5/045)

Estimated Cost - Rs 499219 / only
Earnest Money - Rs 10000 / only
Time - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount	
			figures	5			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	13.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	3081.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	43.20	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	15401.00
3	Providing and Laying cement concrete for plain / reinforced conc. in open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	100.80	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	463680.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge	11.70	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	9849.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	42.40	Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Metre	7208.00
0						Total:	499219.00

Amount Quoted by the Contractor in Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD Dhami

Schedule of Quantity

Name of Work: RRD on Gallu to Palged road Km 0/000 to 9/600 (SH: C/O PCC R/Wall at RD 2/355 to 2/362, 2/395 to 2/405 & 2/840 to 2/850.90)

Estimated Cost:- 4,99,848.00 Only.
Earnest Money: 10,000.00 Only.

Time: - One month

S. No.	Description of Work	Nos of Qty.		Rate		Unit	Amount
				In Figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1	3	4	5	6	7	8
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1	26.19	cum	199.00	Rupees One hundred Ninety Nine Only	per cum	5,212.00
2	Earthwork in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps & other deleterious material & disposal upto ahead of 50m, dressing of sides & bottom and backfilling in trenches with excavated suitable material.	27.31	cum	356.50	Rupees Three hundred Fifty-Six and Fifty paise only	per cum	9,736.00
3	P/L concrete for plain/reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 for plain/ reinforcement including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:4:8 nominal mix (1 Cement : 4 sand : 8 graded crushed stone aggregate 20mm nominal size).	91.65	cum	5000.00	Rupees Five Thousand only	per cum	4,58,250.00
4	Providing weep holes in brick masonry/ stone masonry/ plain or reinforced concrete abutment, wing wall, return wall, with 100mm dia PVC pipe extending through the full width of the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7	70.00	Nos.	190.00	Rupees One hundred Ninety Only	Per each	13,300.00
5	Backfilling behind abutment, wing wall, and return wall complete as per drawing & technical specification clause 1204.3.8, including carriage of materials as per the directions of Engineer-in-charge.	13.35	cum	1000.00	Rupees One thousand Only	per cum	13,350.00
					Total		4,99,848.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer

Shimla Rural Division

HPPWD Dhamu

Schedule of Quantity

Name of Work: RRD on Gallu to Palged road Km 0/000 to 9/600 (SH: C/O R/Wall at RD 1/505 to 1/512.90, 1/535 to 1/545, 1/890 to 1/898 & 2/235 to 2/245)

Estimated Cost:- 4,99,848.00 Only.
Earnest Money: 10,000.00 Only.
Time: - One month

S. No.	Description of Work	Nos of Qty.		Rate		Unit	Amount
				In Figure	In word		
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1	3	4	5	6	7	8
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1	26.19	cum	199.00	Rupees One hundred Ninety Nine Only	per cum	5,212.00
2	Earthwork in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps & other deleterious material & disposal upto ahead of 50m, dressing of sides & bottom and backfilling in trenches with excavated suitable material.	27.31	cum	356.50	Rupees Three hundred Fifty-Six and Fifty paise only	per cum	9,736.00
3	P/L concrete for plain/reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 for plain/ reinforcement including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:4:8 nominal mix (1 Cement : 4 sand : 8 graded crushed stone aggregate 20mm nominal size).	91.65	cum	5000.00	Rupees Five Thousand only	per cum	4,58,250.00
4	Providing weep holes in brick masonry/ stone masonry/ plain or reinforced concrete abutment, wing wall, return wall, with 100mm dia PVC pipe extending through the full width of the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7	70.00	Nos.	190.00	Rupees One hundred Ninety Only	Per each	13,300.00
5	Backfilling behind abutment, wing wall, and return wall complete as per drawing & technical specification clause 1204.3.8, including carriage of materials as per the directions of Engineer-in-charge.	13.35	cum	1000.00	Rupees One thousand Only	per cum	13,350.00
					Total		4,99,848.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machines/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
 Shimla Rural Division
 HPPWD District

Schedule of Quantity

Name of Work: RRD on Gallu to Palged road Km 0/000 to 9/600 (SH: C/O R/Wall at RD 3/470 to 3/482, 3/665 to 3/675 & 3/705 to 3/715)

Estimated Cost:- 4,97,343.00 Only.

Earnest Money: 10,000.00 Only.

Time: - One month

S. No.		Description of Work		Nos of Qty.		Rate		Unit	Amount		
1		2		3	4	In Figure		5	6	7	8
1		2		3	4	In Figure		5	6	7	8
1		Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1		26.12	cum	199.00			Rupees One hundred Ninety Nine Only	per cum	5,198.00
2		Earthwork in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps & other deleterious material & disposal upto ahead of 50m, dressing of sides & bottom and backfilling in trenches with excavated suitable material.		27.56	cum	356.50			Rupees Three hundred Fifty-Six and Fifty paise only	per cum	9,825.00
3		P/L concrete for plain/reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 for plain/ reinforcement including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:4:8 nominal mix (1 Cement : 4 sand : 8 graded crushed stone aggregate 20mm nominal size).		90.56	cum	5000.00			Rupees Five Thousand only	per cum	4,52,800.00
4		Providing weep holes in brick masonry/ stone masonry/ plain or reinforced concrete abutment, wing wall, return wall, with 100mm dia PVC pipe extending through the full width of the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7		84.00	Nos.	190.00			Rupees One hundred Ninety Only	Per each	15,960.00
5		Backfilling behind abutment, wing wall, and return wall complete as per drawing & technical specification clause 1204.3.8, including carriage of materials as per the directions of Engineer-in-charge.		13.56	cum	1000.00			Rupees One thousand Only	per cum	13,560.00
									Total		4,97,343.00
		Amount procured by the contractor in percentage		Rs.							
		Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted									


Executive Engineer
 Shimla Rural Division
 HPPWD Dhara

Schedule of Quantity

Name of Work: RRD on Gallu to Palged road Km 0/000 to 9/600 (SH: C/O Wire Crate R/Wall at RD 2/605 to 2/634)

Estimated Cost:- 4,93,433.00 Only.
Earnest Money:- 10,000.00 Only.
Time:- One month

S. No.	Description of Work	Nos of Qty.		In Figure	Rate		Unit	Amount
		3	4		In word	6		
1	Earthwork in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps & other deleterious material & disposal upto alead of 50m, dressing of sides & bottom and backfilling in trenches with excavated suitable material.	48.72	cum	356.50	Rupees Three hundred Fifty-Six and Fifty paise only		per cum	17369.00
2	Providing and laying of boulder apron laid in wire crate with 4 mm dia G.I wire conforming to IS:280 and IS: 4826 in 100x100mm mesh (woven diaonally) including 10 percent extra for laps and joints laid with stone boulders not less than 25kg each as per drawing and HPPWD technical specification including carriage of all labour, material and equipments to various location through all modes of transportation as per HPPWD specification 1990 Vol-I and as per direction of Engineer in Charge at site in all leads and lifts.	125.28	cum	3800.00	Rupees Three Thousand Eight hundred only		per cum	476064.00
					Total			4,93,433.00
	Amount procured by the contractor in percentage	Rs.						
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted							


Executive Engineer
 Shimla Rural Division
 HPPWD Dhami

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Sangti Nerl Road Km. 0/000 to 6/465 (Sh: Construction of P.C.C. R-wall at Rd. 1/020 to 1/030)

Estimated Cost : - Rs 330941 /- only

Earnest Money : - Rs. 7000 /-only

Time: - One Month

S. No.	Sub head and Items of work	Qty.	Rate			Unit	Amount
			3	4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	14.40	Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	2848.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	19.52	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	5897.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	79.55	Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	310111.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.40	Rmt.	144.07	Rupees One Hundred Forty Four and Paise Seven Only	Per Running Metre	4380.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material, including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	10.80	Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per cubic metre	7705.00
0						Total:	330941.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will be procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharami

Name of Work:- Restoration of rain damages on Hiranagar Jutogh Road Km. 0/000 to 1/200 (Sh: Construction of R-wall at Rd. 0/845 to 0/855)

SCHEDULE OF QUANTITY

Estimated Cost : Rs 255975/- only

Earnest Money : Rs 5000/-only

Time : One Month

S. No.	Sub head and items of work	Qty.	Rate figures	Unit	Amount
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	14.40 Cum	197.80	Per cubic metre	2848.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	16.80 Cum	302.12	Per cubic metre	5075.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	80.75 Cum	3898.31	Per cubic metre	226422.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.40 Rmtl.	144.07	Per Running Metre	4380.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	9.60 Cum	713.39	Per cubic metre	6849.00
0				Total:	255975.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharami

Name of Work:- Restoration of rain damages on Hiranagar Sharog Road Km. 0/000 to 5/000 (Sh: Construction of Retaining wall between Rd. 1/580 to 1/591)

SCHEDULE OF QUANTITY

Estimated Cost :- Rs. 283294 /- only
Earnest Money :- Rs. 6000 /- only
Time :- One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			Figures	5	5	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	15.84 Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	3133.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	18.48 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	5583.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	66.83 Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	260524.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	30.40 Rmt.	152.54	Rupees One Hundred Fifty Two and Paise Fifty Four Only	Per Running Metre	4637.00
5	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	13.20 Cum	713.39	Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per cubic metre	9417.00
0					Total:	283294.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Hiranagar Sharog Road Km. 0/000 to 5/00 (Sh: Construction of B-Wall at Rd. 0/211 to 0/236)

Estimated Cost:- Rs 316981 /- only
Earnest Money :- Rs. 6000 /- only
Time:- One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			figures			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	17.88 Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	3537.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	26.00 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	7855.00
3	Providing and Laying cement concrete for plain / reinforced conc. in open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	71.25 Cum	4200.00	Rupees Four Thousand Two Hundred Only	Per cubic metre	299250.00
4	Providing weapholes in brick masonry / stone masonry (plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(V):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	44.00 Rmt	144.07	Rupees One Hundred Forty Four and Paise Seven Only	Per Running Metre	6339.00
0					Total:	316981.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharm

Schedule of Quantity
Name of Work-RRD on Jalog Himri Naltu Reog road km 0/00 to 2/150 (SH: P/L Kharanja Stone Soling at Rd
00/250 to 00/600 & 1/330 to 1/505)

Estimated Cost:- 499807.00 Only.
Earnest Money: 10000.00 Only.
Time: - One month

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Preparation of sub grade by dressing to camber (Earth work for the cutting involved for sub grade to be paid for separately depending upon the classification of soil completed as per HP PWD specification.	1837.50	per sqm	₹ 2.00	One hundred ninety nine rupees and zero paisa only.	per sqm	3675.00
2	Consolidation of sub grade with road roller including making good the undulation etc. with earth or quarry soil etc. and rerolling the sub-grade completed as per HP.PWD specifications	1837.50	per sqm	₹ 1.90	Three hundred fifty six rupees and fifty paisa only.	per sqm	3491.00
3	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with power road roller to the requested gradient and comber including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP.PWD specification. 100 mm spread thickness (finished work including materials and labour)	183.75	per cum	₹ 2,041.30	Five thousand rupees and zero paisa only.	per cum	375089.00
4	Making up loss of material irregularities on shoulder to the designed level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000m as per technical specification Clause 1903.	1896.00	per sqm	₹ 62.00	One hundred ninety rupees and zero paisa only	per sqm	117552.00
					Total		499807.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted						


Executive Engineer
Shimla Rural Division
HPPWD Dharni

Schedule of Quantity

Name of Work :- RRD on Jalog to Gadheri road km 0/00 to 10/500 (SH: Removal of Land slide / Slips at various Rds between Km 0/000 to 4/00)

Estimated Cost: 4,98,501/- only
Earnest Money: 10,000/-only.

Time: - One month

Sr. No.	Description of Work	Qty .		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in all kind of soil/ ordinary rock by mechanical means including cutting and trimming of slopes and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads and lifts and work will be executed as per the direction of Engineer in charge.	2121.28	Per Cum.	₹ 235.00	Two hundred thirty five rupees and zero paisa only.	Per Cum.	₹ 4,98,501.00
					Total		₹ 4,98,501.00
	Amount procured by the contractor in percentage						
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HP.PWD, Dharhi

Schedule of Quantity

Name of Work :- RRD on Jalog to Gadheri road km 0/00 to 10/500 of Land slide / Slips at various Rds between Km 04/00 to 10/500)

(SH: Removal

Estimated Cost: 4,85,247/- only

Earnest Money: 10,000/-only.

Time: - One month

Sr. No.	Description of Work	Qty .		Rate		Unit	Amount
		3	4	In Figure	In word	7	8
1	2			5	6		
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in all kind of soil/ ordinary rock by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611 including all leads and lifts and work will be executed as per the direction of Engineer in charge.	2064.88	Per Cum.	₹ 235.00	Two hundred thirty five rupees and zero paisa only.	Per Cum.	₹ 4,85,247.00
					Total		₹ 4,85,247.00
	Amount procured by the contractor in percentage						
	Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
 Shimla Rural Division
 HP.PWD, Dhami

Name of Work :-RRD on Kadharghat to Palag Serikedi Road km 0/00 to 7/030 (SH: C/O B/wall at Km 4/353 to 4/380) (PCC)

Schedule of Quantity

Estimated Cost:- 490087.00 Only.
Earnest Money: 10000.00 Only.
Time: - One month

S.No		Description of Work		Nos of Qty		Rate		Unit	Amount
				3	4	In Figure	In word	7	8
1	2 Excavation in soil in hilly area by mechanical means including cutting and trimming of side slopes and disposing of excavated earth with the lift upto 1.5 mtr. and a lead upto 20 mtr. As per technical specification clause 1603.1	23.76	per cum	₹ 199.00	One hundred ninety nine rupees and zero paisa only.			per cum	4728.00
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 l/c setting out,construction of shoring and bracing removal of stumps and other deleterious materials and disposal upto a lead of 50 metre, dressing of sides and bottom and back filling in trenches with excavated suitable material.	7.29	per cum	₹ 356.50	Three hundred fifty six rupees and fifty paisa only.			per cum	2599.00
3	Providing concrete for plain/reinforced concrete 1:4:8 (in 20 mm aggregate) in open foundation complete as per drawing and technical specification clauses 802, 803, 1202 & 1203.	94.50	per cum	₹ 5,000.00	Five thousand rupees and zero paisa only.			per cum	472500.00
4	Providing weepholes in brick masonry/stone masonry/plain reinforced concrete abutment,wing wall, return wall with 100 mm dia. PVC pipe extending through the full width of the structures with slope of 1(v) : 20 (H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204,3.7.	54.00	Nos.	₹ 190.00	One hundred ninety rupees and zero paisa only			Nos.	10260.00
Amount procured by the contractor in percentage		Rs.		Total					490087.00
Conditions:- All the Machineries/materials will be procured by the contractor himself and bills will be submitted									

Executive Engineer
Shimla Rural Division
HPPWD Dhary

Name of Work:- Restoration of rain damages on Khel Ka Chaura Baggi Road Km. 0/000 to 10/000 (Sfr: Construction of R-wall at Rd. 8/340 to 8/362) Under PDNA

SCHEDULE OF QUANTITY

Estimated Cost :- Rs. 415847 /- only

Earnest Money :- Rs. 8000 /- only

Time :- One Month

S. No.	Sub head and Items of work	Qty.	Rate		Unit	Amount
			Figures			
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	52.80 Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	10444.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	17.82 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	5384.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand : 8 graded stone in-Charge	100.98 Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	389831.00
4	Providing weepholes in brick masonry / stone masonry / plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slope of 1(V) 20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge	44.20 Rmt.	144.07	Rupees One Hundred Forty Four and Paise Seven Only	Per Running Metre	6368.00
0					Total	415847.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will be procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharam

Schedule of Quantity

Name of Work: RRD on link road Bag to Kayalu Km 0/000 to 10/500 (SH: C/O R/Wall in between Km 7/445 to 7/487.5) *cunder PDNR 2025*

Estimated Cost:- 4,99,931.00 Only.
Earnest Money: 10,000.00 Only.

Time: - One month

Sr. No.	Description of Work	Nos of Qty.		Rate		Unit	Amount
				In Figure	In word		
1	2	3	4	5	6	7	8
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1	31.88	cum	199.00	Rupees One hundred Ninety Nine Only	per cum	6344.00
2	Earthwork in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps & other deleterious material & disposal upto ahead of 50m, dressing of sides & bottom and backfilling in trenches with excavated suitable material.	26.78	cum	356.50	Rupees Three hundred Fifty-Six and Fifty paise only	per cum	9547.00
3	P/L concrete for plain/reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 for plain/ reinforcement including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:4:8 nominal mix (1 Cement : 4 sand : 8 graded crushed stone aggregate 20mm nominal size).	95.63	cum	5000.00	Rupees Five Thousand only	per cum	478150.00
4	Providing weep holes in brick masonry/ stone masonry/ plain or reinforced concrete abutment, wing wall, return wall, with 100mm dia PVC pipe extending through the full width of the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7	31.00	Rmt	190.00	Rupees One hundred Ninety Only	Per Rmt	5890.00
					Total		499931.00
	Amount procured by the contractor in percentage	Rs.					
	Conditions:- All the Machinerics/materials will be procured by the contractor himself and bills will be submitted						

Executive Engineer
Shimla Rural Division
HPPWD Dharni

Schedule Of Quantity

Name Of Work :- R/R Damages on Link road from Hiranagar Petrol Pump to Jablog in Km 0/00 to 0/760 (SH:- C/O R/wall at Rd. 0/363 to 0/391)

Estimated Cost:- 4,84,308.00

Earnest Money:- 10,000.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Excavation in Soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	14.56	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic metre	3398.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	33.32	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic metre	11879.00
3	Providing and Laying cement concrete for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand; 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	96.32	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic metre	443072.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (1) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	21.00	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Cubic metre	17678.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	48.70	Rmt	170.00	Rupees One Hundred Seventy Only	Per running metre	8279.00
Total Rs.							484308.00
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharmi

Schedule of Quantity

NAME OF WORK :- RRD on Link road from Khatnol to Dandbag Km 0/000 to 6/150.
(SH : C/O B/Wall at RD 5.327 to 5.354).

Estimated Cost:	497345.00	only /-
Earliest Money	10000.00	only /-
Time :- One month		

S. No	Description of Work	Nos of Qty		Rate		Unit	Amount
		3	4	In Figure	In word		
				5	6		
1	Excavation in soil in hilly area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 metre and a lead upto 20mtr as per drawing and technical specification clause 1603.1 and other deleterious material and disposal upto all leads and lifts as per MORD Specification directed by Engineer-in-Charge.	57.51	Per Cum	233.40	Two hundred thirty three rupee forty Paise only	Per Cum	13423.00
2	Earth work in excavation for structures as per drawing and technical specifications clause No. 305.1 including setting out construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all lead and lifts dressing of side and bottom and backfilling in trenches with excavated suitable materials as per MORD Specification directed by Engineer-in-Charge.	10.53	Per Cum	356.50	Three hundred fifty six rupees fifty paise only	Per Cum	3754.00
3	Providing and laying concrete for plain reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803.1202 & 1203 in cement concrete 1:1.8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of material up to all leads and lifts as per the direction-in-Charge.	98.01	Per Cum	4800.00	Forty eight Hundred rupees only	Per Cum	470448.00
4	Providing and laying 100 mm dia meter pipe for weep holes complete of approved quality including carries of material within all leads and lift.	54.00	Per Nos	180.00	One hundred eighty rupees only	Per Nos	9720.00
					Total		497345.00
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Engineer
Shrinilesh Kural
H.P. P.W.D. Division

Schedule of Quantity

Name of Work: RRD on link road Bag to Kayalu Km 0/000 to 10/500 (under PDNA 2025)
SH: C/O R/Wall in between Km 7/795 to 7/804.3

Estimated Cost:- 4,99,935.00 Only.
Earnest Money: 10,000.00 Only.

Time: - One month

Description of Work		Nos of Qty.		Rate		Unit	Amount
Sr. No.				In Figure	In word		
Time: - One month							
1	2	3	4	5	6	7	8
1	Excavation in soil in hilly area by mechanical means i/c cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20m as per technical specifications clause 1603.1.1	31.43	cum	199.00	Rupees One hundred Ninety Nine Only	per cum	6255.00
2	Earthwork in excavation for structure as per drawing and technical specification clause 305.1 including setting out, construction of shoring and bracing, removal of stumps & other deleterious material & disposal upto ahead of 50m, dressing of sides & bottom and backfilling in trenches with excavated suitable material.	19.72	cum	356.50	Rupees Three hundred Fifty-Six and Fifty paise only	per cum	7030.00
3	P/L concrete for plain/reinforcement concrete in open foundation & plinth complete as per drawing and technical specification clause 802, 803, 1202 & 1203 for plain/ reinforcement including carriage of materials as per the directions of Engineer-in-charge. (i) Cement Concrete 1:4:8 nominal mix (1 Cement : 4 sand : 8 graded crushed stone aggregate 20mm nominal size).	94.49	cum	5000.00	Rupees Five Thousand only	per cum	472450.00
4	Providing weep holes in brick masonry/ stone masonry/ plain or reinforced concrete abutment, wing wall, return wall, with 100mm dia PVC pipe extending through the full width of the structure with slope of 1(V):20(H) towards drawing face complete as per drawing and technical specifications clause 614, 709, 1204.3.7	16.00	Nos.	190.00	Rupees One hundred Ninety Only	Per each	3040.00
5	Backfilling behind abutment, wing wall, and return wall complete as per drawing & technical specification clause 1204.3.8, including carriage of materials as per the directions of Engineer-in-charge.	11.16	cum	1000.00	Rupees One thousand Only	per cum	11160.00
Amount procured by the contractor in percentage		Rs.		Total		499935.00	
Conditions:- All the Machineres/materials will be procured by the contractor himself and bills will be submitted							

Executive Engineer
Shirur Rural Division
HPPWD Dhani

SCHEDULE OF QUANTITY
000 to 5/450 (Sh: Constr

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	14.41	Cum	197.80	Per cubic metre	2850.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of slumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	22.36	Cum	302.12	Per cubic metre	6755.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement 4 sand 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	100.41	Cum	3890.31	Per cubic metre	390626.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (i) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	15.48	Cum	713.39	Per cubic metre	11043.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall /return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(V) 20(H) towards drawing face complete as per drawing and technical specification Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	43.90	Rmt	152.54	Per Running Metre	6697.00
0					Total:	417971.00

Note : (i) All the material will procured by the contractor him self.

~~Executive Engineer~~
~~Shimla Rural Division~~
~~HPPWD, Dhamsi~~

Schedule Of Quantity

Name Of Work :- R/R Damages on NH-22 to Judicial complex via Chakker road Km. 0/00 to 1/790. **Estimated Cost:- 3,82,830.00**

(SH:- C/O U-shaped drain b/w 1/630 to 1/730 & P/F RCC. Drain covers km.1/630 to 1/730) **Earnest Money:- 7,700.00**

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				Excluding GST	In words		
1	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	32.50	Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per Cubic metre	9819
2	Stone soling properly hand-packed filling interstices with Kharanja stone and consolidating with spalls to the requested gradient including spreading watering and rolling of binding materials moorum or earth etc. complete as per HP PWD specification. 100 mm spread thickness (finished work including materials and labour) including carriage of all material with all leads and lift	5.00	Cum	1289.83	Rupees One Thousand Two Hundred Eighty Nine and Paise Eighty Three Only	Per Cubic metre	6449
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:3:6 (1 Cement 3 sand 6 graded stone Aggregate 20 mm nominal mix) including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	14.00	Cum	4491.52	Rupees Four Thousand Four Hundred Ninety One and Paise Fifty Two Only	Per Cubic metre	62881
4	Providing and Fixing in Position pre-cast RCC Manhole cover of reqired shape and approved quality rectangular shape 900mm x600mm size. Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	33.00	Nos	9202.46	Rupees Nine Thousand Two Hundred Two and Paise Forty Six Only	Each	303681
Total Rs.							382830
Note :- The Rates are excluding GST							
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dharti.

Name of Work:- Restoration of Rain damages on Okhroo Nehra via Keru Road Km. 0/00 to 2/00 (Sh: Construction of B-Wall at R.D. 1/400 to 1/420)

SCHEDULE OF QUANTITY

Estimated Cost:- Rs 215467 /- only
Earnest Money :- Rs. 4000 /-only
Time:- One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	7.80 Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	1543.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	11.40 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	3444.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	52.40 Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	204271.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(h) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	43.10 Rmt.	144.07	Rupees One Hundred Forty Four and Paise Seven Only	Per Running Metre	6209.00
0					Total:	215467.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharm


SCHEDULE OF QUANTITY
ah Sedan Road Km. 0/00 to 5/700 (Sh: C/o Retaining
55.50)

Time: -	One Month
---------	-----------

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
			4	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in Charge.	3	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	2311.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	11.33	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	4039.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	54.83	4600.00	Rupees Four Thousand Six Hundred Only	Per cubic metre	252218.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8. (i) Granular material. Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	13.95	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	11743.00
5	Providing weapholes in brick masonry / stone masonry/plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(V)/20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	28.30	170.00	Rupees One Hundred Seventy Only	Per Running Metre	4811.00
0						
					Total:	275122.00

Amount Quoted by the Contractor In Percentage

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dharm

Name of Work:- Restoration of rain damages on Shal Chanog Road Km. 0/00 to 7/330 (Sh: Construction of R-wall at Rd. 3/820 to 3/825)

One Month

Amount Quoted by the Contractor in Percentage

Executive Engineer
Shimla, Rural Division
HPPWD, Dharm

Name of Work: - Restoration of rain damages on Shaltu Nehra Dargot Road Km. 0/000 to 5/450 (SH:- Construction of PCC R/
Wall at RD. 3 /895 to 3/905.50)

SCHEDULE OF QUANTITY

Estimated Cost: - Rs 498531 /- only
Earnest Money : - Rs. 10000 /-only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount.
			Figures	5		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge	12.97	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per Cubic Meter 3027.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge	54.81	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per Cubic Meter 19540.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement :4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	99.88	Cum	4600.00	Rupees Four Thousand Six Hundred Only	Per Cubic Meter 459448.00
4	Backfilling behind abutment, wing wall and return wall complete as per drawings & technical specification Clause 1204.3.8, (1) Granular material, Including carriage of material within all leads upto leads as per the direction of Engineer-in-Charge.	11.34	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per Running Meter 9546.00
5	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	41.00	Rmt	170.00	Rupees One Hundred Seventy Only	Per Running Meter 6970.00
0						Total: 498531.00

Note : (i) All the material will procured by the contractor him self.

Amount Quoted by the Contractor in Percentage

Rs.

Executive Engineer
Shimla Rural Division
HPPWD, Dhani

NAME OF WORK :- RR Damages on Shimla Mandi road km 22/000 to 33/200.
(SH:-Removal of slips on various Rd's of road).

**Executive Engineer,
Shimla Rural Division,
HPPWD, Dharam.**

Name of work: RR Damages on Shimla Mandi road Km 39/200 a 52/300.
(Sit : C/O R/W all at RD 46/400 to 46/405.80).

Schedule of Quantity

S. No										Estimated Cost:		Earnest Money		only /-	
Description of Work										Time: - One month		10000.00		only /-	
		Nos of Qty		Rate		Unit		Amount							
				In Figure		In word									

Executive Engineer
Shimla Rural Division
H.P. P.W.D. D.D.

Schedule Of Quantity

Name of Work :- R/R damages on Shoghi Mehli road km 0/000 to 12/375 (SH:- C/O R/wall at RD 4/080 to 4/097)

Estimated Cost:- 4,96,994.00

Earnest Money:-9,900.00

Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	26.69	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	6229
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	5.27	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1879
3	Providing and Laying for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 for Plain / reinforcement including carriage of materials as per the directions of materials as per the directions of Engineer-in-Charge (i) Cement Concrete 1:4:8 (1 Cement 4 sand: 8 graded stone Aggregate 40 mm nominal mix)	97.07	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	465938
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full width of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614.709,1204.3.7.	53.00	No	190.00	Rupees One Hundred Ninety Only	Each	10070
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material	15.30	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	12860
	Total Rs.						496994
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dharm

Schedule Of Quantity

Name of Work :- R/R damages on Shoghi Mehli road km 0/000 to 12/375 (SH:- C/O R/wall at RD 11/995 to 12/009)

Estimated Cost:- 4,90,608.00
Earnest Money:-9,800.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				In figures	In words		
1	2	3	4	5	6	7	8
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	37.80	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	8823
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	5.60	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	1996
3	Providing and Laying for plain / reinforced concrete. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 including carriage of materials upto all leads and lifts 1:4:8 (1 Cement 4 sand: 8 graded stone Aggregate 40 mm nominal mix)	95.20	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	456960
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614.709.1204.3.7.	42.00	No	190.00	Rupees One Hundred Ninety Only	Each	7980
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	17.64	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	14849
	Total Rs.						490608
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhari

Schedule Of Quantity

Name of Work :- R/R damages on Totu Tara Devi road km 0/00 to 4/105 (SH:- C/O R/wall b/w km 2/940 to 2/953)

Estimated Cost:- 4,04,690.00

Earnest Money:- 8,100.00

Time:- One Month.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
				Excluding GST	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1.1	20.54	Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	4063
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	20.54	Cum	302.11	Rupees Three Hundred Two and Paise Eleven Only	Per cubic metre	6205
3	Providing and laying concrete for plain/reinforced concrete in open foundations complete as per drawings and technical specifications Clause 802.803.1202 & 1203 in cement concrete 1:4:8 (1 Cement 4 Sand 8 graded stone aggregate 20 mm nominal mix) including carriage of all material with all leads and lift as per directed by Engineer -in- Charge.	91.91	Cum	4067.80	Rupees Four Thousand Sixty Seven and Paise Eighty Only	Per cubic metre	373871
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614.709.1204.3.7.	42.00	No	161.00	Rupees One Hundred Sixty One Only	Each	5752
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	16.38	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	13789
Total Rs.							404690
Note :- The Rates are excluding GST							
Amount Quoted by the Contractor in Percentage							
Note :- All the material will procured by the contractor him self							

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dhangra

Draft Schedule Of Quantity

Name of Work :- R/R Damades on Totu Tara Devi road Portion km 0/00 to 4/105 (SH:- C/O R/Wall in between km 2/900 to 2/912)

Estimated Cost:- 4,70,719.00
Earnest Money:- 9,400.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		Unit	Amount
		3	4	In figures	In words		
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1	25.20	Cum	233.40	Rupees Two Hundred Thirty Three and Paise Forty Only	Per cubic metre	5882
2	Earth work in excavation for structures as per drawing and technical specification clauses 305.1 including setting out, construction of shoring bracing removal of stumps and other deleterious material and disposal up to lead of 50m dressing of sides and bottom and backfilling in trenches with excavated suitable material	21.36	Cum	356.50	Rupees Three Hundred Fifty Six and Paise Fifty Only	Per cubic metre	7615
3	Providing and Laying for plain / reinforced concrete. In open foundation & plinth complete as per drawing and technical specification clause-802, 803, 1202 & 1203 including cartage of materials as per the directions of Engineer-In-Charge 1:4:8 (1 Cement 4 sand 8 graded stone Aggregate 20 mm nominal size)	90.72	Cum	4800.00	Rupees Four Thousand Eight Hundred Only	Per cubic metre	435456
4	Providing wearholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with stop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3.7.	38.00	No	190.00	Rupees One Hundred Ninety Only	Each	7220
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3.8 granular material.	17.28	Cum	841.80	Rupees Eight Hundred Forty One and Paise Eighty Only	Per cubic metre	14546
	Total Rs.						470719
	Amount Quoted by the Contractor in Percentage						
	Note :- All the material will procured by the contractor him self						

Executive Engineer,
 Shimla Rural Division,
 HP, PWD, Dhara

Schedule Of Quantity

Name Of Work :- R/R Damages on tukandi Shilgaon via Kiari road , Portion Km. 0/000 to 3/870.
(SH:- C/O R/wall at Rd 3/595 to 3/607.50)

Estimated Cost:- 4,12,538.00

Earnest Money:- 8,200.00
Time:- One Months.

S.No	Description of Work	No. of Qty.		Rate		In words	Unit	Amount
		3	4	Excluding GST	5			
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	36.63	Cum	197.80		Rupees One Hundred Ninety Seven and Paise Eighty Only	Per Cubic metre	7245
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	6.38	Cum	302.11		Rupees Three Hundred Two and Paise Eleven Only	Per Cubic metre	1927
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 14:8 (1 Cement 4 sand: 8 graded stone Aggregate 20 mm nominal mix) Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge	94.50	Cum	4067.80		Rupees Four Thousand Sixty Seven and Paise Eighty Only	Per Cubic metre	384407
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v) 20(H) towards drawing face complete as per drawing and technical specification clauses 614,709,1204.3,7. Including carriage of material upto all leads and lifts as per the direction of Engineer-in-Charge.	38.00	No	161.00		Rupees One Hundred Sixty One Only	Each	6118
5	Back filling filling behind abutment wing wall and retaining wall complete as per drawing and technical specification clause 1204.3,8 granular material.	18.00	Cum	713.39		Rupees Seven Hundred Thirteen and Paise Thirty Nine Only	Per Cubic metre	12841
Total Rs.								412538
Note :- The Rates are excluding GST								
Amount Quoted by the Contractor in Percentage								
Note :- All the material will procured by the contractor him self								

Executive Engineer,
Shimla Rural Division,
HP, PWD, Dharm

SCHEDULE OF QUANTITY

N.O.W :- RRD on Various roads under Thaila section under Sunni Sub-Division.(SH:- Removal of slips/Debris/Cut material at various Rds)

SCHEDULE OF QUANTITY						
N.O.W :- RRD on Various roads under Thaila section under Sunni Sub-Division.(SH:- Removal of slips/Debris/Cut material etc. at various Rds)					Estimated cost:-	498,087.00
					Earnest money:-	9962.00
					Time:-	One Month
Sr. No.	Description	Qty.	Unit	Rate in figure.	Rate in word.	Amount.
1	Removal of landslides /slip clearance. Removal of land slide in hilly area in all kind of soil/ ordinary rock by mechanical means including cutting and trimming of slops and disposal of cut material with in a left up to 1.5 metre and land upto 1000 meter as per technical specification 302.3.5 and 1611	2119.52	Per Sqm	235.00	Rupees Two Hundred Thirty Five only	498087.00
					Total:-	498087.00
Amount Quoted by the Contractor in Percentage						
Note :- All the material will procured by the contractor him self						


 Executive Engineer,
 Shimla Rural Division,
 HPPWD, Dharm

SCHEDULE OF QUANTITY

Name of Work:- Restoration of rain damages on Shimla Nalagarh Road Km. 6/910 to 22/00 (Sh: Construction of B-Wall at Rd 8.525 to 8.545)

Estimated Cost: - Rs 420627 /- only
Earnest Money : - Rs. 8000 /- only
Time: - One Month

S. No.	Sub head and items of work	Qty.	Rate		Unit	Amount
			figures			
1	2	3	4	5	6	7
1	Excavation in soil in Hilly Area by manual means including cutting and trimming of side slopes and disposing of excavated earth with a lift upto 1.5 m and a lead upto 20 m as per drawing and Technical Specification Clause 1603.1 and other deleterious materials and disposal upto all leads and lifts as per MORD specification directed by Engineer-in-Charge.	90.00 Cum	197.80	Rupees One Hundred Ninety Seven and Paise Eighty Only	Per cubic metre	17802.00
2	Earthwork in excavation for structures as per drawing and technical specifications Clause 305.1 including setting out, construction of shoring and bracing, removal of stumps and other deleterious material and disposal upto all leads and lifts dressing of sides and bottom and backfilling in trenches with excavated suitable material as per MORD specification directed by Engineer-in-Charge.	37.60 Cum	302.12	Rupees Three Hundred Two and Paise Twelve Only	Per cubic metre	11360.00
3	Providing and Laying cement concrete for plain / reinforced conc. In open foundation complete as per drawing and technical specification clause-802, 803, 1202 & 1203 in Cement Concrete 1:4:8 (1 Cement : 4 sand: 8 graded stone Aggregate 20 mm nominal mix). Including carriage of material upto all leads and lifts as per the directions of Engineer-in-Charge.	99.00 Cum	3898.31	Rupees Three Thousand Eight Hundred Ninety Eight and Paise Thirty One Only	Per cubic metre	385933.00
4	Providing weapholes in brick masonry / stone masonry /plain reinforced concrete abutment, wing wall, return wall with 100 mm dia PVC pipe extending through the full with of the structures with slop of 1(v):20(H) towards drawing face complete as per drawing and technical specification . Including carriage of material upto all leads and lifts as per the direction of Engineer -in-Charge.	38.40 Rmt.	144.07	Rupees One Hundred Forty Four and Paise Seven Only	Per Running Metre	5532.00
0					Total:	420627.00

Amount Quoted by the Contractor in Percentage excluding GST

Rs.

Note : (i) All the material will procured by the contractor him self.

Executive Engineer
Shimla Rural Division
HPPWD, Dhami