

Himachal Pradesh
Public Works Department

No:-PW/GHR/C.B-E- Tender/offline/ 2026-27-
To

5650-56

Dated: 07/10/2026

✓ The Chief Engineer(MZ)
HPPWD, Mandi.

Subject: - Publication of "Notice Inviting Tender".

Enclosed please find herewith the Tender Notice of works as given in the Notice Inviting Tender for uploading on department website as per notification Principal Secretary (PW) to the Govt. of H.P letter No. PBW(B)A(3)1/2024 dated Shimla-2 the 03.01.2024 and No. PBW(B)A(3)8/2025-300858 dated 13th Nov., 2025 as the work mentioned in the tender notice are urgent in nature and in public interest.

DA:-Notice Inviting Tender.

OW
Executive Engineer,
Gohar Division,
H.P.P.W.D. Gohar.

Copy alongwith copy of NIT is forwarded to the Superintending Engineer, 1st Circle HPPWD Mandi for information please.

Copy alongwith copy of NIT is forwarded to all the Assistant Engineers working under Gohar Division for information please.

Copy to Accounts Branch/Drawing Branch alongwith copy of NIT for information.

Copy to Notice Board in this office.

Executive Engineer,
Gohar Division,
H.P.P.W.D. Gohar.

Himachal Pradesh
Public works Department
Notice inviting Tender

Sealed percentage rate tenders on form 6 & 8 are invited by the Executive Engineer, Gohar Division, H.P.PWD Gohar for the following works from the approved and eligible contractors enlisted in H.P.PWD so as to reach in his office on or before **19-10-2026 up to 11.00 A.M.** and will be opened on the same day at 11.30 A.M. in the presence of intending contractors or their authorized representatives. The D.N.I.T. tender documents can be had from this office against cash payment (Non-refundable) up to 5.00 P.M. **on 17-10-2026**. The applications for issue of tender forms will be received **up to 2.00 P.M. on 16-10-2026**.

The earnest money in the shape of National Saving Certificate/ Time deposit accounts/Saving account/F.D. Rs. in any of the Post Office/Nationalized Banks in Himachal Pradesh duly pledged in favour of the Executive Engineer must accompany the request for issue of tender form for each work. Conditional tenders and the tenders received without earnest money will summarily be rejected. The Executive Engineer reserves the right to reject the tenders without assigning any reason. It is further added that the rates be quoted both in words and figures for proper checking to avoid any complications. If the date of opening will be holiday, the tenders will be opened on the next working day at the same time.

Sr. No.	Name of road/work	Estimated Cost	Earnest Money	Time limit
1	RR Damages on Kot Devidarh road km. 0/00 to 22/500 (SH:- C/o PCC R/wall with Parapets at RD 13/350 to 13/360 and 14/850 to 14/865) Under PDNA	4,38,090	8800	Two Months
2	RR Damages on Tunna Bhurla road km. 0/00 to 6/500 (SH:- C/o PCC R/wall with Toe wall at RD 3/705 to 3/719.50) Under PDNA	4,86,530	9800	Two Months
3	SDF/2026/27 RRD on chailli to Shilno road km. 0/00 to 10/500 (SH:- Maintenance of earthen shoulders, Bush cutting, Removal of slips and clearing of drain.)	1,48,311	3000	Two Months
4	RR Damages on Chail Moviseri road km. 0/00 to 11/200 (SH:- C/o PCC R/wall with Parapets at RD 5/630 to 5/634 and R/wall with toe wall at RD 7/120 to 7/126) Under PDNA	3,99,350	8000	Two Months
5	RR Damages on Syanh Dhaban Bhiyarta Road km. 0/00 to 6/200 (SH:- C/o Wire crate R/wall at RD 4/400 to 4/410) Under PDNA	4,27,861	8600	Two Months
6	SDF/2026/21 RRD on Hafvana Panyas road km. 0/00 to 17/500 (SH:- Maintenance of earthen shoulders, Bush cutting, Removal of slips and clearing of drain Between Km. 6/00 to 12/00)	97,347	2000	Two Months
7	SDF/2025/328 R/O RRD on Chambi to Kangar road km. 0/00 to 5/500 (SH:- Maintenance of earthen shoulders, Bush cutting, Removal of slips and clearing of drain)	1,72,739	3500	Two Months
8	SDF/2026/25 RRD on BBMB Colony to Sushan Jawala road km. 0/00 to 3/500 (SH:- Maintenance of earthen Shoulders, Bush Cutting, Removal of slips and clearing of drain.	98,881	2000	Two Months

9	SDF/2026/29 Restoration of Rain Damages on Jachh to Gawata. Sandyar Via Dharwar GP Jhungi km. 0/00 to 9/00 (SH:- Hiring of JCB for removal of minor slips/debris. dressing of berms Clearance of drain etc. in km. 4/500 to 9/00) Job-II	99000	2000	Two Months
10	SDF/2026/29 Restoration of Rain Damages on Jachh to Gawata. Sandyar Via Dharwar GP Jhungi km. 0/00 to 9/00 (SH:- Hiring of Tipper carriage of Muck/Debris)	99,200	2000	Two Months
11	SDF/2025/1407 R/O of road from Ghyam to Upper Fangot Km. 0/00 to 2/500 (SH:- C/o unlined surface drain, Removal of slip, P/L 600 mm dia RCC Pipe at various RDs, Surface dressing and widening at various km.)	1,26,311	2600	Two Months
12	SDF/2025/1406 R/o of road Karsog road to House of Kashmir singh km. 0/00 to 3/00 (SH:- C/o Unlined surface drain, Removal of slip, surface dressing, Widening at various km. and extension of 600 mm dia hume pipe culvert at RD 0/250)	1,94,063	3900	Two Months
13	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- C/o PCC U-Shape drain at RD 0/225 to 0/234 and 0/755 to 0/785)	97,231	2000	Two Months
14	RRD on Dhanotu to Rohangaloo road km. 0/00 to 32/400 (SH:- C/o PCC B/wall at RD 28/395 to 28/401.50)	98,586	2000	Two Months
15	RRD on various roads under Dhanotu Sub-Division (SH:- Hiring of JCB for removal of minor slips/debris.dressing of berms clearance of drain etc. in various roads under Dhanotu section)	99000	2000	Two Months
16	RRD on various roads under Dhanotu Sub-Division (SH:- Hiring of JCB for removal of minor slips/debris.dressing of berms clearance of drain etc. in various roads under Bharjwanoo section)	97,900	2000	Two Months
17	RRD on various roads under Dhanotu Sub-Division (SH:- Hiring of JCB for removal of minor slips/debris.dressing of berms clearance of drain etc. in various roads under Baggi section)	99000	2000	Two Months
18	RRD on Nalsar Chunahan road km. 0/00 to 3/750 (SH:- Construction of Steel railing both side of bridge at RD 1/070)	80,700	1700	Two Months

Certified that tender of above works are being called for emergent nature in exigency of public interest.

GENERAL CONDITIONS:-

1. The Contractors are required to submit the valid Enlistment/GST registration and latest ITR alongwith application form.
2. The Contractors should quote the percentage rates in the tenders both in figures and words.
3. The tender forms will not be issued to those contractors whose performance is not found satisfactory.
4. An undertaking will have to be given by the contractor that he has not more than two works in hand at the time of opening of this tender.
5. Contractors will have to submit appropriate Earnest Money in the shape of F.D.R along with the application form for getting issued the tender forms. Applications with out EMD shall be summarily rejected.
6. As per Govt. Notification No.PBW(B)A(3)1/2020-I dated 07-10-2021 the tenders above 5% of estimated cost will be summarily rejected. The tender offered below 30 % will also be accepted as per the office letter No. Engineer-in- Chief office letter No. PW-CTR/32-20/Genl Inst. CPWD-2020-37996-38096 dated 13.03.2023 and further ex- post-facto approval has been granted by the Principal Secretary (PW) to the Govt. of H.P. letter No. PBW (B) A(3)1/2020-I dated 10.05.2023. Beside this the

additional performance security will have to borne by the bidders as per the said notifications.

7. Conditional and incomplete tenders shall be rejected.
8. The Executive Engineer reserves the right to accept or reject the tender without any reason.


Executive Engineer,
Gdhar Division (B&R),
HPPWD Gdhar.

BILL OF QUANTITY

Name of work :- RR Damages on Kot Devidarh road km 0/000 to 22/500 (SH:- C/O PCC R/Wall with Parapets at RD 13/350 to 13/360 and 14/850 to 14/865) Under PDNA

Estimated cost Rs. - 4,38,090/-

Earnest Money cost Rs.8800/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	33.38	Per Cubic meter	₹ 230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	92.56	Per Cubic meter	₹ 4,350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	17.00	Per Cubic meter	₹ 1,050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	26.00	Each	₹ 380.70		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

Name of work :- RR Damages on Tunna Bhurla road km 0/000 to 6/500 (SH:- C/O PCC R/Wall with Toe wall at RD 3/705 to 3/719.50) Under PDNA

Estimated cost Rs. - 4,86,530/-

Earnest Money cost Rs.9800/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	49.01	Per Cubic meter	₹ 230.00	₹ 11,272.00	Rupees Eleven Thousand Two Hundred Seventy Two Only
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	104.40	Per Cubic meter	₹ 4,350.20	₹ 4,54,161.00	Rupees Four Lakh(s) Fifty Four Thousand One Hundred Sixty One Only
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	26.00	Each	₹ 380.70	₹ 9,898.00	Rupees Nine Thousand Eight Hundred Ninety Eight Only
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	10.66	Per Cubic meter	₹ 1,050.60	₹ 11,199.00	Rupees Eleven Thousand One Hundred Ninety Nine Only
Total:-					₹ 4,86,530.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

106

Bill of quantity approved for Rs 4,86,530/- only

Executive Engineer
Gohar Division (B&R)
HP,PWD Gohar.

BILL OF QUANTITY

Name of work :- SDF/2026/27 RRD on Chailli to Shilnoo road km 0/00 to 10/500 (SH:- Maintenance of earthen shoulders, Bush cutting, Removal of slips and clearing of drain)

Estimated cost Rs. - 1,48,311/-

Earnest Money cost Rs.3,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	747.00	per square metre	30.20	22,559.00	Rupees Twenty Two Thousand Five Hundred Fifty Nine Only
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals .	360.00	per square metre	15.10	5,436.00	Rupees Five Thousand Four Hundred Thirty Six Only
3	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1640.00	per Running metre	22.20	36,408.00	Rupees Thirty Six Thousand Four Hundred Eight Only
4	Cutting of branches of trees shrubs and trimming of grass and weeds cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914.as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	11970.00	per square metre	5.90	70,623.00	Rupees Seventy Thousand Six Hundred Twenty Three Only
5	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	126.41	per Cubic metre	105.10	13,286.00	Rupees Thirteen Thousand Two Hundred Eighty Six Only
Total:-					1,48,312.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

60

1 set of quantity approved for Rs 1,48,312/- only

BILL OF QUANTITY

Name of work :- RR Damages on Chail Moviseri road km 0/000 to 11/200 (SH:- C/O PCC R/Wall with Parapets at RD 5/630 to 5/634 and R/Wall with toe wall at RD 7/120 to 7/126) Under PDNA

Estimated cost Rs. - 3,99,350/-
Earnest Money cost Rs.8,000/-
Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.28	Per Cubic meter	₹ 230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	87.13	Per Cubic meter	₹ 4,350.20		
3	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	8.80	Per Cubic meter	₹ 1,050.60		
4	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	12.00	Each	₹ 380.70		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

04
Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

of work :- RR Damages on Syanh Dhaban Bhiyarta Road km 0/00 to 6/200 (SH:- C/O Wire crate /R/Wall at /400 to 4/410) Under PDNA

Estimated cost Rs. - 4,27,861/-

Earnest Money cost Rs.8600/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	26.75	Per Cubic meter	₹ 230.00		
2	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	15.00	Per Cubic meter	4820.10		
3	Providing and laying of boulder apron laid in wire crates with 4mm (four millimeter dia) G.I wire conforming to IS 280 and IS 4826 in 150 mm x 150 mm mesh (woven diagonally) including 10% of laps laid with boulders apron weighing not less than 25 kg (twenty five kilo gram) each as per drawing including all leads ,lifts of material and technical specification clause 1301. within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge complete in all respect.	109.38	Per Cubic meter	3078.30		
4	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	12.09	Per Cubic meter	₹ 1,050.60		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

04
Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar

BILL OF QUANTITY

Detail of work :- SDF/2026/21 RRD on Hafwana to Panyas road km 0/00 to 17/500 (SH:- Maintenance of earthen shoulders, Bush cutting, Removal of slips and clearing of drain Between KM 6/00 to 12/00)

Estimated cost Rs. - 97,347/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads, lifts and carriage of materials and other incidentals. as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	177.00	per square metre	30.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads, lifts and carriage of materials and other incidentals.	67.50	per square metre	15.10		
3	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metre as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1310.00	per Running metre	22.20		
4	Cutting of branches of trees shrubs and trimming of grass and weeds cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914.as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	9051.00	per square metre	5.90		
5	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slopes and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	80.88	per Cubic metre	105.10		
Total:-						
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

BILL OF QUANTITY

Name of work :- SDF/2025/328 R/O RRD on Chambhi to Kangar road km 0/00 to 5/500 (SH:- Maintenance of earthen shoulders, Bush cutting, Removal of slips and clearing of drain)

Estimated cost Rs. - 1,72,739/-

Earnest Money cost Rs.3500/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	3111.00	per square metre	30.20	93,952.00	Rupees Ninety Three Thousand Nine Hundred Fifty Two Only
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals .	513.00	per square metre	15.10	7,746.00	Rupees Seven Thousand Seven Hundred Forty Six Only
3	The maintenance of drains include erosion, repair, clearing, cleaning, reshaping, regrading, deepening of side drains as well as catch water drains as per technical specification Clause 1907 within all leads , lifts and carriage of materials and other incidentals .	3010.00	per Running metre	3.00	9,030.00	Rupees Nine Thousand Thirty Only
4	Cutting of branches of trees shrubs and trimming of grass and weeds cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914.as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	4244.00	per square metre	5.90	25,040.00	Rupees Twenty Five Thousand Forty Only
5	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	351.77	per Cubic metre	105.10	36,971.00	Rupees Thirty Six Thousand Nine Hundred Seventy One Only
Total:-					1,72,739.00	
Percentage rate Quoted in figure						
Percentage rate Quoted in words						

Bill of quantity approved for Rs 1,72,739/- only

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

Item of work :- SDF/2026/25 RRD on BBMB Colony to Sushan Jawala road km 0/00 to 3/500 (SH:-
Maintenance of earthen shoulders, Bush cutting, Removal of slips and clearing of drain)

Estimated cost Rs. - 98,881/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Maintenance of earthen shoulder (Filling with fresh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	256.50	per square metre	30.20		
2	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals .	97.20	per square metre	15.10		
3	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metre as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	790.00	per Running metre	22.20		
4	Cutting of branches of trees shrubs and trimming of grass and weeds cutting of branches of trees and shrubs from the road way or with in R.O.W including disposal of wood and leaves to suitable location as per technical specification Clause 1914.as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1086.50	per square metre	5.90		
5	Removal of landslide/slip clearance. Removal of land slide in hilly area in ordinary rock not requiring blasting by mechanical means including cutting and trimming of slops and disposal of cut material with in any lift and lead upto 1.5 m and land upto 1000 meter as per technical specification 302.3.5 and 1611 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	625.30	per Cubic metre	105.10		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

BILL OF QUANTITY

of work :- SDF/2026/29 Restrotation of Rain Damages on Jachh to Gawata,Sandyar Via
war GP Jhungi Km 0/00 to 9/00 (SH:- Hurring of JCB for removal of minor slips/debris ,
essing of berms Clearnace of drain etc. in in Km 4/500 to 9/00) Job-II

Estimated cost Rs. - 99,000/-
Earnest Money cost Rs.2,000/-
Time - Two Month

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. propority the owner is responsible.
- 3 Driver and POL will be provided by the owner.


Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar. ⑧

BILL OF QUANTITY

Name of work :- SDF/2026/29 Restrotation of Rain Damages on Jachh to Gawata,Sandyar Via Dharwar GP Jhungi Km 0/00 to 9/00 (SH:- Hiring of Tipper for carriage of Muck/Debris KM 0/00 TO 9/00)					Estimated cost Rs. - 99,200/-	
					Earnest Money cost Rs. 2,000/-	
					Time - Two Month	
SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of Tipper for carriage/ disposal of debris to dumping site of work with lift to suitable place with in all leads and lifts to the entire satisfaction of the Engineer-in Charge . The Tipper should work minimum 9.00 AM to 5.00 PM daily any loss to the public/ private property or any accident etc. happened during the course of hiring period shall be absolute responsibility of the Tipper owner which shall have to be fully compensated by him in all cases the fuel and Tipper driver and lodging & boarding of operational staff will be provided by the Tipper owner the repair and spare including watch and ward of Tipper also borne by the contractor /owner. The daily log book will be maintained at site which should be dully verified by the Engineer-in charge.	32.00	Days	3100.00		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.


 Executive Engineer
 Gohar Division (B&R)
 HP.PWD Gohar. 6

BILL OF QUANTITY

Name of work :- SDF/2025/1407 R/O of road from Ghyan to Upper Fangot km 0/00 to 2/500(SH:- C/o Unlined surface drain, Removal of slip, P/L 600 mm dia RCC Pipe at various RDs, Surface dressing and widening at various km)

Estimated cost Rs. - 1,26,311/-

Earnest Money cost Rs.2600/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer -in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and safety measures and incidentals necessary to complete the work by all means (if any required) recovery for 13.57 cubic metre @ Rs. 300.00 per cubic metre amount Rs.4071/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect	339.15	Per Cubic meter	182.80	61,997.00	Rupees Sixty One Thousand Nine Hundred Ninety Seven Only
2	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metere as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	350.00	per Running metre	22.20	7,770.00	Rupees Seven Thousand Seven Hundred Seventy Only
3	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	800.00	per square metre	30.20	24,160.00	Rupees Twenty Four Thousand One Hundred Sixty Only

	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads, lifts and carriage of materials and other incidentals.	820.00	per square metre	15.10	12,382.00	Rupees Twelve Thousand Three Hundred Eighty Two Only
5	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 600 mm dia. R.C.C. pipe as per direction of Engineer -in -Charge complete in all respect.	10.00	Per Running meter	2000.20	20,002.00	Rupees Twenty Thousand Two Only
	Percentage rate Quoted in figure	Total:-			1,26,311.00	
	Percentage rate Quoted in words					

Bill of Quantity approved for Rs 1,26,311.00 only

QV
Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

(90)

12

BILL OF QUANTITY

Name of work :- SDF/2025/1406 R/O of road Karsog road to House of Kashmir singh km 0/00 to 3/00 (SH:- C/o Unlined surface drain, Removal of slip, Surface dressing, Widening at various km and extension of 600 mm dia hume pipe culvert at RD 0/250)

Estimated cost Rs. - 1,94,063/-

Earnest Money cost Rs.3900/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Excavation in soil in hill area in all heights and depths in all kinds of soil including saturated soil comprising of pick, jumper blasting work both in soft and hard rock with chiseling / wedging out side of rock (where blasting is prohibited) and their intermediate classification of soil including dewatering where required setting out to the required line grades , side slopes trimming bottom and level as shown on drawings as directed by the Engineer -in charge at site according to technical clause 1603.1 and 1603.2 sorting useful / un-useful materials and stacking the same in all leads and lifts and transportation of the un-useful materials for filling in roads ways , embankments for grades improvements and leveling to the require grade and then disposing of surplus excavated earth in acquired width of road or on approved dumping sites through all modes of transportation including head load animal load or mechanical means along with its leveling fine dressing and all labour, machineries , materials , tools equipment's and sefety measures and incidentals necessary to complete the work by all means (if any required) recovery for 20.98 cubic metre @ Rs. 300.00 per cubic metre amount Rs.6294/- shall be done on prorata basis for the quantity of cutting in earth work effected . Any loss to the public and private property during the course of execution shall be the absolute responsibility of the contractor , which shall have to be duly compensated by him in all respect	524.21	Per Cubic meter	182.82	95,836.00	Rupees Ninety Five Thousand Eight Hundred Thirty Six Only
2	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	4.20	Per Cubic meter	230.00	966.00	Rupees Nine Hundred Sixty Six Only

	Providing and Laying concrete 1:4:8 (one cement : four sand : eight graded crushed stone aggregate 40mm (forty millimeter) nominal size for plain/reinforced concrete in open foundations complete as per drawing and technical specification clauses 802, 803, 1202 and 1203 within all leads , lifts and carriage of materials and other incidentals as directed by Engineer-incharge.	4.28	Per Cubic meter	4820.10	20,630.00	Rupees Twenty Thousand Six Hundred Thirty Only
4	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	4.42	Per Cubic meter	4350.20	19,228.00	Rupees Nineteen Thousand Two Hundred Twenty Eight Only
5	Back filling behind abutment, wing wall and return wall complete as per drawing and technical specification clause 1204.3.8 granular material within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge completer in all respect.	0.78	Per Cubic meter	1050.60	819.00	Rupees Eight Hundred Nineteen Only
6	Construction of unlined surface drains of average cross-sectional area 0.20sqm (zero point two zero square metre) in ordinary rock to specified lines, grades, levels and dimensions. excavated material to be used in embankment with a lift upto any metre and lead of any metre as per Technical Specification Clause 307 as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	300.00	per Running metre	22.20	6,660.00	Rupees Six Thousand Six Hundred Sixty Only
7	Maintenance of earthen shoulder (Filling with fesh selected soil) Making up loss of material/irregularities on shoulders to the design level by adding fresh approved selected soil and compacting it with appropriate equipment at OMC upto a lead of 1000 m as per technical specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer in charge with in all leads lifts and carriage of materials and other incidentals.	1000.00	per square metre	30.20	30,200.00	Rupees Thirty Thousand Two Hundred Only
8	Maintenance of earthen shoulder (stripping of excess soil) Stripping excess soil from the shoulder surface to achieve the approved level and compacting with plate compactor at OMC as per drawings and Technical Specification Clause 1903 within all leads , lifts and carriage of materials and other incidentals .	975.00	per square metre	15.10	14,723.00	Rupees Fourteen Thousand Seven Hundred Twenty Three Only
9	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete 600 mm dia. R.C.C. pipe as per direction of Engineer -in -Charge complete in all respect.	2.50	Per Running meter	2000.20	5,001.00	Rupees Five Thousand One Only
	Total:-				1,94,063.00	
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

(43)

Bill of quantity approved for Rs 1,94,063.00 only

BILL OF QUANTITY

Name of work :- RRD on Dhanotu to Rohangaloo road km 0/00 to 32/400 (SH:- C/o PCC U-Shape drain at rd 0/225 to 0/234 and 0/755 to 0/785)

Estimated cost Rs. - 97,231/-

Earnest Money cost Rs. 2,000/-

Time - Three Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	28.11	Per Cubic meter	230.00		
2	Providing concrete for plain/reinforced concrete in open foundations 1:3:6 (1 Cement : 3 coarse sand) : 6 graded stone aggregate 40 mm nominal size) mechanically mixed and vibrated and curing complete including cost of formwork complete as per drawings and technical specifications Clause 802, 803, 1202 & 1203 including carriage of material within all leads, lifts and other incidental charges.	15.54	Per Cubic Metre	5050.20		
3	Stone masonry in cement mortar for foundation complete as per drawing and technical specification clause 702, 704, 1202 and 1204 (random rubble masonry in cement mortar . 1:6(one cement : six sand) within all leads , lifts and carriage of materials and other incidentals .as per direction of Engineer -in -Charge complete in all respect.	2.34	Per Cubic Metre	5250.45		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					


 Executive Engineer
 Gohar Division
 H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on Dhanotu to Rohangaloo road km 0/000 to 32/400(SH:- Construction of PCC B/Wall at RD 28/395 to 28/401.50)

Estimated cost Rs. - 98,586/-

Earnest Money cost Rs.2,000/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Earth work in excavation for structure as per drawing and technical specification clause 305.1 i/c setting out construction of shoring and bracing removal of stumps and other deleterious material and disposal up to any lead dressing of sides and bottom and back filling in trenches with excavated suitable material ordinary soil including carriage of material with in all leads and lifts and other incidentals and as per the direction of the Engineer-in Charge.	7.28	Per Cubic meter	230.00		
2	Providing and laying cement concrete 1:5:10 (one cement : five sand ten graded crashed stone aggregate) 40mm (forty millimeter) size for plain / reinforced concrete in open foundation complete as per drawings and technical specification clause 802,803,1202 & 1203 within all leads , lifts and carriage of materials and other incidentals . as per direction of Engineer -in -Charge completer in all respect.	21.84	Per Cubic meter	4350.20		
3	Providing weep hole in brick masonry / stone masonry /plain reinforced concrete abutment wing wall return wall with 100 mm (one hundred millimetre) dia PVC pipe extended through the full width of the structures with slope of 1 (v) :20 (H) towards drawing face complete as per drawing and technical specification clause 614,709& 1204.3.7 with in all leads, lifts and other incidentals as per direction of Engineer -in -Charge complete in all respect.	5.00	Each	380.70		
	Total:-					
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Executive Engineer
Gohar Division
H.P.P.W.D. Gohar

BILL OF QUANTITY

Name of work :- RRD on various roads under Dhanotu Sub - Division (SH:- Hiring of JCB for removal of minor slips/debris , dressing of berms Clearnace of drain etc. in various roads under Dhanotu section)					Estimated cost Rs. - 99,000/-	
					Earnest Money cost Rs.2,000/-	
					Time - Two Month	
Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.


 Executive Engineer
 Gohar Division (B&R)
 HP.PWD Gohar.

BILL OF QUANTITY

of work :- RRD on various roads under Dhanotu Sub - Division (SH:- Hurring of JCB for removal of minor slips/debris , dressing of berms Clearnace of drain etc. in various roads under Bharjwanoo section)

Estimated cost Rs. - 97,900/-

Earnest Money cost Rs.2,000/-

Time - Two Month

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	89.00	Per Hour	1100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.


 Executive Engineer
 Gohar Division (B&R)
 HP.PWD Gohar. ⑤

BILL OF QUANTITY

Name of work :- RRD on various roads under Dhanotu Sub - Division (SH:- Herring of JCB for removal of minor slips/debris , dressing of berms Clearnace of drain etc. in various roads under Baggi section)

Estimated cost Rs. - 99,000/-

Earnest Money cost Rs.2,000/-

Time - Two Month

Sr. No.	Description of work	No.or Qty.	Unit	Estimated Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Hiring of JCB/Excavator for removal of slips/ debris in all kind of soil and saturated soil, dressing of road surface, filling of depressions and disposing of all excavated slips / earth or un-serviseable materials from the road surfaces up to any leads and lift as per direction and entire satisfaction of Engineer in Charge. Any loss to the public/private property or any accident etc. happened during the course of hiring period/execution shall be the absolute responsibility of JCB/excavator owner which shall have to be duly compensated by him in all cases.The fuel and operational staff for excavator will be provided by the owner, The repair and spare, watch and ward of excavator also be borne by the contractor/owner.The daily log book will be maintained at site which should be duly verified by the Engineer-in-Charge.	90.00	Per Hour	1100.00		
	Percentage rate Quoted in figure					
	Percentage rate Quoted in words					

Terms and conditions:-

- 1 The daily logbook will be maintained at site which should be daily verified by the Engineer-in-Charge
- 2 During working hours any type of accident or loss of private/Govt. property the owner is responsible.
- 3 Driver and POL will be provided by the owner.

Executive Engineer
Gohar Division (B&R)
HP.PWD Gohar.

BILL OF QUANTITY

Name of work :- RRD on Nalsar Chunahan road Km 0/00 to 3/750(SH:- Construction of Steel railing both side of bridge at RD 1/070)

Estimated cost Rs. - 80,700/-

Earnest Money cost Rs. 1700/-

Time - Two Month

SR. No.	Description of work	No.or Qty.	Unit	Estimate d Rate (in. Rs.)	Total amount with all taxes including GST in Rs. P	Total amount with all taxes including GST in words
1	Structure Steel work riveted, bolted or welded in built up sections, trusses and framed work including cutting hoisting fixing in postion and applying a priming coat of approved steel primer In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works as per direction of Engineer - in - charge .	743.46	Per Kilogramm	102.10		
2	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/10 sqm of approved brand and manufactureas per direction of Engineer -in -Charge complete in all respect.	50.40	Per Square meter	95.10		
	Total:-					
	Quoted rate in figure					
	Quoted rate in words					


 Executive Engineer
 Gohar Division (B&R)
 HP.PWD Gohar.